CITY OF HOUSTON
DEPARTMENT OF PUBLIC WORKS AND ENGINEERING
ENGINEERING AND CONSTRUCTION DIVISION

PROJECT MANUAL
LIFT STATION RENEWAL/REPLACEMENT PROJECT
WOODWAY #1 LIFT STATION REPLACEMENT
WBS No. R-000267-109B-4

VOLUME 1 of 1

Divisions 00 through 16

March 2015

ARCADIS
2929 Briarpark Drive Suite 300
Houston, Texas 77042
(713) 953-4800
TBPE Firm No. F-533

Document 00010

TABLE OF CONTENTS

NOTE: Bold capitalized Specification Sections are included in http://documents.publicworks.houstontx.gov/document-center/cat_view/88-engineering-and-construction/92-specifications.html; and are incorporated in Project Manuals by reference as if copied verbatim. Documents listed "for filing" are to be provided by Bidder and are not included in this Project Manual unless indicated for example only. The Document numbers and titles hold places for actual documents to be submitted by Contractor during Bid, post-bid, or construction phase of the Project. Specification Sections marked with an asterisk (*) are amended by a supplemental specification, printed on blue paper and placed in front of the Specification it amends. Documents in the 200, 300 and 400 series of Division 00, except for Document 00410B – Bid Form, Part B, are not part of the Contract.

Doc. No.	Document Title	Doc. Date
	INTRODUCTORY INFORMATION	
00010	Table of Contents	08-01-2013
00015	List of Drawings	02-01-2004
00041	List of Pre-qualified Asbestos & Lead Abatement Contractors	09-01-2004
	BIDDING REQUIREMENTS	
	INSTRUCTIONS TO BIDDERS	
00200	Instructions to Bidders	03-01-2013
00210	Supplementary Instructions to Bidders	07-01-2013
00220	Request for Bid Information	06-11-2004
	INFORMATION AVAILABLE TO BIDDERS	
00320	Geotechnical Information	09-02-2005
00330	Existing Conditions	04-30-2004
00340	Environmental Information	09-14-2005
	BID FORMS AND SUPPLEMENTS	
00410	Bid Form, Parts A & B	08-01-2013
00430	Bidder's Bond (For filing; Example Form)	02-01-2004
00450	Bidder's Statement of MWBE/PDBE/DBE/SBE Status	07-01-2013
00452	Contractor Submission List - Fair Campaign Ordinance	04-30-2004
00453	Bidder's Statement of Residency	02-01-2004
00454	Affidavit of Non-interest	02-01-2004
00455	Affidavit of Ownership or Control	09-04-2007
00457	Conflict of Interest Questionnaire	02-28-2006

Doc. No.	Document Title	Doc. Date
00459	Contractor's Statement Regarding Previous Contracts Subject to EEO	02-01-2004
00460	(POP-1)Pay or Play Acknowledgement Form	07-03-2012
00470	Bidder's MWSBE Participation Plan	08-01-2013
00471	Pre-Bid Good Faith Efforts	07-01-2013
00472	Bidder's Goal Deviation Request	07-01-2013

POST-BID PROCEDURES

00495	Post-bid Procedures	08-01-2013

CONTRACTING REQUIREMENTS

AGREEMENT

00500	Form of Business	02-01-2004
00501	Resolution of Contractor	02-01-2010
00520	Agreement	08-01-2013
00570	Contractor's Revised MWSBE Participation Plan	08-01-2013
00571	Record of Post-Bid Good Faith Efforts	08-01-2013
00572	Contractor's Request for Plan Deviation Request	08-01-2013

BONDS AND CERTIFICATES

00600	List of Proposed Subcontractors and Suppliers	07-01-2013
00601	Drug Policy Compliance Agreement	02-01-2004
00602	Contractor's Drug Free Workplace Policy (For filing)	
00603	Checklist for Drug Policy Submittal	02-09-2012
00604	History of OSHA Actions and List of On-the-job Injuries	02-01-2004
00605	List of Safety Impact Positions	02-01-2004
00606	Contractor's Certification of No Safety Impact Positions	02-01-2004
00606	Contractor's Certification of No Safety Impact Positions	02-01-2004
00607	Certification Regarding Debarment, Suspension, and Other Responsibility Matters	02-01-2004
00610	Performance Bond	05-17-2005
00611	Statutory Payment Bond	05-17-2005
00612	One-year Maintenance Bond	05-17-2005
00613	One-year Surface Correction Bond	05-17-2005
00620	Affidavit of Insurance (with attached Certificates of Insurance)	02-01-2004
00622	Name and Qualifications of Proposed Superintendent (For filing)	
00624	Affidavit of Compliance with Affirmative Action Program	02-01-2004
00630	(POP2) Certification of compliance with Pay or Play Program	07-03-2012
00631	(POP3) City of Houston Pay or Play Program – List of	

Doc. No.	Document Title	Doc. Date
	Subcontractors	07-03-2012
00633	Equal Employment Opportunity–Certification By Material Suppliers	02-01-2010
00642	Monthly Subcontractor Payment Reporting Form	02-01-2010
00646	Payment Notification Explanation of Withholding	02-01-2010
GENERAL CONDITIONS		
00700	General Conditions	08-01-2013
SUPPLEMENTARY CONDITIONS		
00800	Supplementary Conditions	08-01-2013
00805	Equal Employment Opportunity Program Requirements	05-01-2012
00808	Requirements for the City of Houston Program for Minority, Women, and Small Business Enterprises (MWSBE), and Persons with Disabilities Business Enterprises (PDBE) Program	08-01-2013
00809	CDBG Requirements	04-01-2005
00820	Wage Scale for Engineering Construction	02-01-2013
00821	Wage Scale for Building Construction	02-01-2013
00830	Trench Safety Geotechnical Information	02-01-2004
00840	Pay or Play Program Requirements	07-03-2012
ADDENDA AND MODIFICATIONS		
00910	Addendum	02-01-2004
00911	Notice of Addendum	02-01-2004
00931	Request for Information	02-01-2004

Doc. No.	Document Title	Doc. Date

SPECIFICATIONS

DIVISION 1 - GENERAL REQUIREMENTS

01110	Summary of Work	06-27-2005
01145	Use of Premises	01-01-2011
01255	Change Order Procedures	08-01-2003
01270	Measurement and Payment	08-01-2003
01292	Schedule of Values	08-01-2003
01312	Coordination and Meetings	08-01-2003
01321	Construction Photographs	08-01-2003
01325	Construction Schedule	08-01-2003
01326	Construction Schedule (Bar Chart)	08-01-2003
01330	Submittal Procedures	08-01-2003
01340	Shop Drawings, Product Data, and Samples	08-01-2003
01351	Environmental Safety and Worker Protection	01-01-2011
01410	TPDES Requirements (with Attachments)	02-01-2011
01422	Reference Standards	08-01-2003
01450	Contractor's Quality Control	08-01-2003
01452	Inspection Services	08-01-2003
01454	Testing Laboratory Services	08-01-2003
01502	Mobilization	08-01-2008
01504	Temporary Facilities and Controls	01-01-2011
*01506	Diversion Pumping	08-01-2003
01506S	*Diversion Pumping*	*03-22-2013*
01520	Temporary Field Office	02-08-2012
01554	Traffic Control and Street Signs	07-01-2012
*01555	Traffic Control and Regulation	01-01-2011
01555S	*Traffic Control and Regulation*	*10-04-2013*
01562	Tree and Plant Protection	01-01-2011
01570	Storm Water Pollution Control	01-26-2012
01575	Stabilized Construction Access	02-01-2011
01576	Waste Material Disposal	08-01-2003
01578	Control of Ground and Surface Water	01-01-2011
01580	Project Identification Signs	08-01-2003
01581	Excavation in Public Way Permit Signs	08-01-2003
01610	Basic Product Requirements	01-01-2011
01630	Product Substitution Procedures	08-01-2003
01725	Field Surveying	01-01-2011
01731	Cutting and Patching	01-01-2011
01732	Procedure for Water Valve Assistance (with Attachments)	08-01-2003
01740	Site Restoration	08-01-2003

Doc. No.	Document Title	Doc. Date
01755	Starting Systems	08-01-2003
01770	Closeout Procedures	08-01-2003
01782	Operations and Maintenance Data	08-01-2003
01785	Project Record Documents	08-01-2003
DIVISION 2 - SITE WORK		
02081	**CAST-IN-PLACE CONCRETE MANHOLES**	**01-01-2011**
02082	**PRECAST CONCRETE MANHOLES**	**01-01-2011**
02084	**FRAMES, GRATES, RINGS, AND COVERS**	**08-01-2008**
02085	**VALVE BOXES, METER BOXES, AND METER VAULTS**	**01-01-2011**
02086	**ADJUSTING MANHOLES, INLETS, AND VALVE BOXES TO GRADE**	**01-01-2011**
02105	Chemical Sampling and Analysis	03-18-2005
02120	Off-Site Transportation and Disposal	03-18-2005
02136	**WASTE MATERIAL HANDLING, TESTING AND DISPOSAL**	**01-01-2011**
02220	Demolition	03-18-2005
***02221**	**REMOVING EXISTING PAVEMENTS AND STRUCTURES**	**07-01-2009**
02221S	*Removing Existing Pavement, Structures, Wood, Demolition Debris*	*10-24-2012*
02222	**ABANDONMENT OF SEWERS**	**01-01-2011**
02260	**TRENCH SAFETY SYSTEM**	**02-01-2011**
02315	**ROADWAY EXCAVATION**	**07-01-2009**
02316	**EXCAVATION AND BACKFILL FOR STRUCTURES**	**01-01-2011**
02317	**EXCAVATION AND BACKFILL FOR UTILITIES**	**01-01-2011**
02318	**EXTRA UNIT PRICE WORK FOR EXCAVATION AND BACKFILL**	**01-01-2011**
02319	**BORROW**	**01-01-2011**
02320	**UTILITY BACKFILL MATERIALS**	**01-01-2011**
02321	**CEMENT STABILIZED SAND**	**01-01-2011**
02322	**FLOWABLE FILL**	**08-01-2008**
02330	**EMBANKMENT**	**10-01-2002**
02336	**LIME-STABILIZED SUBGRADE**	**10-01-2002**
02337	**LIME/FLY-ASH STABILIZED SUBGRADE**	**10-01-2002**
02338	**PORTLAND CEMENT STABILIZED SUBGRADE**	**10-01-2002**
02400	**TUNNEL SHAFTS**	**01-01-2011**
02425	**TUNNEL EXCAVATION AND PRIMARY LINER**	**10-01-2002**
02426	**SEWER LINE IN TUNNELS**	**10-01-2002**
02427	**PLASTIC LINER FOR LARGE-DIAMETER CONCRETE SEWERS AND STRUCTURES**	**10-01-2002**
02431	**TUNNEL GROUT**	**10-01-2002**
02441	**MICROTUNNELING AND PIPE-JACKED TUNNELS**	**01-01-2011**
02447	**AUGERING PIPE AND CONDUIT**	**10-01-2002**

Doc. No.	Document Title	Doc. Date
02448	PIPE AND CASING AUGERING FOR SEWERS	10-01-2002
02476	CAISSON FOR LIFT STATION	01-01-2011
02501	DUCTILE IRON PIPE AND FITTINGS	01-01-2011
02502	STEEL PIPE AND FITTINGS	01-01-2011
02503	COPPER TUBING	10-01-2002
02504	CENTRIFUGALLY CAST FIBERGLASS PIPE	02-01-2011
02506	POLYVINYL CHLORIDE PIPE	01-01-2011
02508	EXTRA STRENGTH CLAY PIPE	02-01-2011
*02511	WATER LINES	01-01-2011
02511S	*Water Lines*	*10-21-2013*
02512	WATER TAP AND SERVICE LINE INSTALLATION	01-01-2011
02513	WET CONNECTIONS	10-01-2002
02514	DISINFECTION OF WATER LINES	01-01-2011
02515	HYDROSTATIC TESTING OF PIPELINES	01-01-2011
02516	CUT, PLUG, AND ABANDONMENT OF WATER LINES	01-01-2011
02520	FIRE HYDRANTS	05-05-2011
*02524	AIR RELEASE AND VACUUM RELIEF VALVES	01-01-2011
02524S	*Air Release and Vacuum Valves*	*01-16-2014*
02526	WATER METERS	01-01-2011
02527	POLYURETHANE COATINGS ON STEEL OR DUCTILE IRON PIPE	10-01-2002
02528	POLYETHYLENE WRAP	01-01-2011
02531	GRAVITY SANITARY SEWERS	01-01-2011
02532	SANITARY SEWER FORCE MAINS	01-01-2011
02533	ACCEPTANCE TESTING FOR SANITARY SEWERS	01-01-2011
02534	SANITARY SEWER SERVICE STUBS OR RECONNECTIONS	01-01-2011
02558	CLEANING AND TELEVISION INSPECTION	01-01-2011
02581	STREET LIGHTING CONDUIT	10-01-2002
02611	REINFORCED CONCRETE PIPE	02-01-2011
02621	GEOTEXTILE	10-01-2002
02631	STORM SEWERS	01-01-2011
02632	CAST-IN-PLACE INLETS, HEADWALLS, AND WINGWALLS	10-01-2002
02633	PRECAST CONCRETE INLETS, HEADWALLS, AND WINGWALLS	10-01-2002
02711	HOT MIX ASPHALT BASE COURSE	07-01-2009
02712	CEMENT STABILIZED BASE COURSE	10-01-2002
02713	RECYCLED CRUSHED CONCRETE BASE COURSE	07-01-2009
02714	FLEXIBLE BASE COURSE FOR TEMPORARY DRIVEWAYS	07-01-2009
02716	Cement Stabilized Sand Base	10-06-1997

Doc. No.	Document Title	Doc. Date
02741	**ASPHALTIC CONCRETE PAVEMENT**	**07-01-2009**
02742	**PRIME COAT**	**10-01-2002**
02743	**TACK COAT**	**10-01-2002**
02751	**CONCRETE PAVING**	**07-01-2009**
***02752**	**CONCRETE PAVEMENT JOINTS**	**10-01-2002**
02752S	*CONCRETE PAVEMENT JOINTS*	*12-29-2009*
02753	**CONCRETE PAVEMENT CURING**	**10-01-2002**
02754	**CONCRETE DRIVEWAYS**	**09-01-2002**
02761	**COLORED CONCRETE FOR MEDIANS AND SIDEWALKS**	**09-01-2002**
02762	**BLAST CLEANING OF PAVEMENT**	**10-01-2002**
02764	**RAISED PAVEMENT MARKERS**	**10-01-2002**
02765	**TEMPORARY AND REMOVABLE REFLECTORIZED PAVEMENT MARKINGS**	**10-01-2002**
02767	**THERMOPLASTIC PAVEMENT MARKINGS**	**10-01-2002**
02771	**CURB, CURB AND GUTTER, AND HEADERS**	**10-01-2002**
02772	**CONCRETE MEDIANS AND DIRECTIONAL ISLANDS**	**10-01-2002**
02775	**CONCRETE SIDEWALKS**	**10-01-2002**
02811	**LANDSCAPE IRRIGATION**	**10-01-2002**
02830	Fences and Gates	12-12-2005
02911	**TOPSOIL**	**10-01-2002**
02912	**TREE, PLANT, AND HARDSCAPE PROTECTION**	**07-01-2009**
02915	**TREE PLANTING**	**01-01-2011**
02922	**SODDING**	**07-01-2009**
02951	**PAVEMENT REPAIR AND RESTORATION**	**07-01-2009**

DIVISION 3 - CONCRETE

03055	CONCRETE STRUCTURES	05-30-2007
03151	JOINTS IN CONCRETE STRUCTURES	06-28-2007
03211	REINFORCING STEEL	05-30-2007
03310	STRUCTURAL CONCRETE	05-30-2007
03315	**CONCRETE FOR UTILITY CONSTRUCTION**	**10-01-2002**
03341	CONCRETE: MISCELLANEOUS MATERIALS	05-30-2007
03350	CONCRETE FINISHING	05-30-2007
03390	CONCRETE CURING	05-30-2007
03600	STRUCTURAL GROUT	05-30-2007

DIVISION 5 – METALS

05120	STRUCTURAL STEEL	05-30-2007

Doc. No.	Document Title	Doc. Date
DIVISION 6 - WOOD AND PLASTICS		
06610	FIBERGLASS REINFORCED PLASTICS PULTRUDED GRATING	05-30-2007
DIVISION 9 - FINISHES		
09901	**PROTECTIVE COATINGS**	**01-01-2011**
09901S	*PROTECTIVE COATINGS*	*01-15-2014*
09904	PROTECTIVE COATINGS FOR WASTEWATER WET WELLS	01-01-2011
09917	CORROSION PROTECTIVE COATING SYSTEM	10-07-2010
DIVISION 10 - SPECIALTIES		
DIVISION 11 – EQUIPMENT		
11311	SUBMERSIBLE WASTEWATER PUMPS	09-04-2013
DIVISION 13 - SPECIAL CONSTRUCTION		
13440	PUMP STATION CONTROL SYSTEM	01-01-2010
13441	SCADA SOFTWARE ENGINEERING SECURITY AND QUALITY REQUIREMENTS	12-26-2013
13446	PRIMARY INSTRUMENTATION DEVICES	01-01-2010
13471	CONTROL CABINET ENCLOSURES	01-01-2010
DIVISION 15 – MECHANICAL		
15050	BASIC MECHANICAL MATERIALS AND METHODS	09-18-2011
15053	PUMP STATION PIPING	09-18-2011
15126	VALVES FOR SEWAGE SERVICE	05-30-2007
DIVISION 16 – ELECTRICAL		
16010	BASIC ELECTRICAL REQUIREMENTS	01-01-2010
16060	ELECTRICAL DEMOLITION	01-01-2010
16111	CONDUIT, FITTINGS, AND BODIES	01-01-2010
16120	600-VOLT BUILDING WIRE AND CABLE	01-01-2010
16121	600-VOLT CONTROL CABLE	01-01-2010
16122	600-VOLT POWER CABLE	01-01-2010
16123	MEDIUM VOLTAGE POWER CABLE	01-01-2010
16125	THERMOCOUPLE EXTENSION CABLE	01-01-2010
16126	INSTRUMENTATION CABLE	01-01-2010
16131	DEVICE, PULL AND JUNCTION BOXES	01-01-2010
16140	WIRING DEVICES	01-01-2010
16160	CABINETS AND ENCLOSURES	01-01-2010
16161	PANELBOARDS	01-01-2010

Doc. No.	Document Title	Doc. Date
16165	DISCONNECT SWITCHES	01-01-2010
16170	GROUNDING AND BONDING	01-01-2010
16195	ELECTRICAL IDENTIFICATION	01-01-2010
16290	SURGE PROTECTION DEVICES	01-01-2010
16402	UNDERGROUND DUCT BANKS	01-01-2010
16410	LOW VOLTAGE POWER FACTOR CORRECTION CAPACITORS	01-01-2010
16461	DRY-TYPE TRANSFORMERS	01-01-2010
16480	MOTOR CONTROL CENTER	01-01-2010
16481	MEDIUM VOLTAGE MOTOR CONTROL CENTER	01-01-2010
16510	LIGHTING LUMINAIRES	01-01-2010
16640	CATHODIC PROTECTION FOR PIPELINES	01-01-2010
16662	MOTOR MANAGEMENT RELAY	01-01-2010
16670	LIGHTNING PROTECTION SYSTEM	01-01-2010
16910	MANUAL TRANSFER SWITCH	01-01-2010

END OF DOCUMENT

Document 00015

LIST OF DRAWINGS

Sheet No.		Title
1	G1	COVER SHEET
2	G2	INDEX OF DRAWINGS (SHEET 1 OF 2)
3	G3	INDEX OF DRAWINGS (SHEET 2 OF 2)
4	G4	LEGEND AND ABBREVIATIONS
5	G5	GENERAL NOTES
~~6~~	~~G6~~	~~EXISTING LIFT STATIONS SITE PLANS~~ (NOT APPLICABLE)
7	G7	FIRM MAP
8	G8	SURVEY CONTROL MAP 1 OF 9
~~9~~	~~G9~~	~~SURVEY CONTROL MAP 2 OF 9~~ (NOT APPLICABLE)
~~10~~	~~G10~~	~~SURVEY CONTROL MAP 3 OF 9~~ (NOT APPLICABLE)
~~11~~	~~G11~~	~~SURVEY CONTROL MAP 4 OF 9~~ (NOT APPLICABLE)
12	G12	SURVEY CONTROL MAP 5 OF 9
13	G13	~~SURVEY CONTROL MAP 6 OF 9~~ (NOT APPLICABLE)
14	G14	~~SURVEY CONTROL MAP 7 OF 9~~ (NOT APPLICABLE)
15	G15	~~SURVEY CONTROL MAP 8 OF 9~~ (NOT APPLICABLE)
16	G16	SURVEY CONTROL MAP 9 OF 9
17	C104	WOODWAY LIFT STATION REPLACEMENT- EXISTING SITE LAYOUT
18	C105	WOODWAY LIFT STATION REPLACEMENT- PROPOSED DEMOLITION PLAN
19	C106	WOODWAY LIFT STATION REPLACEMENT- SECTIONS - DEMOLITIONS
20	C107	WOODWAY LIFT STATION REPLACEMENT- PROPOSED OVERALL IMPROVEMENTS
21	C108	WOODWAY LIFT STATION REPLACEMENT- PROPOSED SITE PLAN
22	C109	WOODWAY LIFT STATION REPLACEMENT - SITE GRADING & CONCRETE PAVEMENT PLAN
23	C110	WOODWAY LIFT STATION REPLACEMENT - SITE DRAINAGE PLAN
24	C111	WOODWAY LIFT STATION FORCEMAIN PLAN AND PROFILE
25	C112	WOODWAY LIFT STATION FENCING SITE PLAN
26	C113	WOODWAY LIFT STATION FENCE DETAILS (WOOD AND VINYL)
27	C114	WOODWAY LIFT STATION VINYL FENCE AND GATE DETAILS
28	M1	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - PROPOSED PLAN VIEW AT GRADE
29	M2	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - PROPOSED PLAN VIEW - SECTION A

Sheet No.		Title
30	M3	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - PROPOSED PLAN VIEW - SECTION B
31	M4	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - PROPOSED PUMP CURVE
32	M5	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - PIPE SUPPORT DETAILS
33	M6	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - TYPICAL DETAILS 1
34	M7	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - TYPICAL DETAILS 2
35	M8	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - TYPICAL DETAILS 3
36	M9	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - BYPASS FORCEMAIN MANHOLE
37	M10	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - WATERLINE DETAILS
38	M11	WOODWAY LIFT STATION REPLACEMENT - MECHANICAL - HATCH DETAIL
39	S1	WOODWAY LIFT STATION - STRUCTURAL - PROPOSED LIFT STATION PLAN VIEW AT GRADE
40	S2	WOODWAY LIFT STATION - STRUCTURAL - PROPOSED LIFT STATION PLAN VIEW AT VAULT FLOOR
41	S3	WOODWAY LIFT STATION - STRUCTURAL - PROPOSED LIFT STATION ELEVATION VIEW - SECTION A
42	S4	WOODWAY LIFT STATION - STRUCTURAL - PROPOSED LIFT STATION SECTION VIEWS
43	S5	WOODWAY LIFT STATION - STRUCTURAL - STANDARD DETAILS (1 OF 3)
44	S6	WOODWAY LIFT STATION - STRUCTURAL - STANDARD DETAILS (2 OF 3)
45	S7	WOODWAY LIFT STATION - STRUCTURAL - STANDARD DETAILS (3 OF 3)
46	A1	WOODWAY LIFT STATION REPLACEMENT - ARCHITECTURAL ABBREVIATIONS, LEGEND NOTES & CODE PLAN
47	A2	WOODWAY LIFT STATION REPLACEMENT - ARCHITECTURAL PLANS & ELEVATIONS
48	A3	WOODWAY LIFT STATION REPLACEMENT - ARCHITECTURAL DETAILS
49	A4	WOODWAY LIFT STATION REPLACEMENT - HVAC SYMBOLS, ABBREVIATIONS & GENERAL NOTES
50	A5	WOODWAY LIFT STATION REPLACEMENT - HVAC PLANS & EQUIPMENT SCHEDULES

Sheet No.		Title
51	E1	ELECTRICAL SYMBOLS, LEGEND AND ABBREVIATIONS
52	E2	ELECTRICAL DEMOLITION PLAN
53	E3	ELECTRICAL SITE PLAN
54	E4	ELECTRICALCONDUIT LAYOUT AND SECTIONS
55	E5	ELECTRICAL LIFT STATION SECTION
56	E6	ELECTRICAL CONDUIT SCHEDULE
57	E7	ELECTRICAL TYPICAL JUNCTION BOXES AND CONDUIT INSTALLATION DETAILS
58	E8	ELECTRICAL TYPICAL INSTALLATION DETAILS 1 OF 2
59	E9	ELECTRICAL TYPICAL INSTALLATION DETAILS 2 OF 2
60	E10	ELECTRICAL ONE-LINE DIAGRAM
61	E11	ELECTRICAL POWER WIRING DIAGRAM
62	E12	ELECTRICAL DEVICE RATING SCHEDULE
63	E13	ELECTRICAL PROCESS AND INSTRUMENTATION DIAGRAM 1 OF 2
64	E14	ELECTRICAL PROCESS AND INSTRUMENTATION DIAGRAM 2 OF 2
65	E15	ELECTRICAL OUTDOOR CONTROL CABINET ENCLOSURE
66	E16	ELECTRICAL OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT & SCHEDULE
67	E17	ELECTRICAL OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT 1 OF 3
68	E18	ELECTRICAL OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT 2 OF 3
69	E19	ELECTRICAL OUTDOOR CONTROL CABINET EQUIPMENT LAYOUT 3 OF 3
70	E20	ELECTRICAL OUTDOOR CONTROL CABINET CONTROL WIRING DIAGRAM 1 OF 6
71	E21	ELECTRICAL OUTDOOR CONTROL CABINET CONTROL WIRING DIAGRAM 2 OF 6
72	E22	ELECTRICAL OUTDOOR CONTROL CABINET CONTROL WIRING DIAGRAM 3 OF 6
73	E23	ELECTRICAL OUTDOOR CONTROL CABINET CONTROL WIRING DIAGRAM 4 OF 6
74	E24	ELECTRICAL OUTDOOR CONTROL CABINET CONTROL WIRING DIAGRAM 5 OF 6
75	E25	ELECTRICAL OUTDOOR CONTROL CABINET CONTROL WIRING DIAGRAM 6 OF 6
76	E26	ELECTRICAL SUBMERSIBLE TRANSDUCER WELL LEVEL GAUGING SYSTEM
77	E27	ELECTRICAL CATHODIC PROTECTION DETAILS
78	TCP1	TRAFFIC CONTROL PLAN GENERAL NOTES
~~79~~	~~TCP2~~	~~TRAFFIC CONTROL PLAN WOODWAY DRIVE AT SAGE ROAD~~

Sheet No.		Title
		(NOT APPLICABLE)
~~80~~	~~TCP3~~	~~TRAFFIC CONTROL PLAN MEMORIAL DRIVE AT N POST OAK LANE~~ (NOT APPLICABLE)
~~81~~	~~TCP4~~	~~TRAFFIC CONTROL PLAN WOODWAY DRIVE AT N POST OAK LANE~~
~~82~~	~~TCP5~~	~~TRAFFIC CONTROL PLAN WOODWAY DRIVE~~ (NOT APPLICABLE)
~~83~~	~~TCP6~~	~~TRAFFIC CONTROL PLAN TYPICAL DETAIL TWO-WAY FLAGGING OPERATION~~ (NOT APPLICABLE)
84	TCP7	TRAFFIC CONTROL PLAN TYPICAL DETAIL BOULEVARD OUTSIDE LANE CLOSURE
~~85~~	~~TCP8~~	~~TRAFFIC CONTROL PLAN TYPICAL DETAIL BOULEVARD INSIDE LANE CLOSURE~~ (NOT APPLICABLE)
86	TCP9	TRAFFIC CONTROL PLAN TYPICAL DETAIL BOULEVARD CLOSURE WOODWAY AND MEMORIAL
~~87~~	~~TCP10~~	~~TRAFFIC CONTROL PLAN TYPICAL DETAIL SANDRINGHAM AT BUCKINGHAM~~ (NOT APPLICABLE)
~~88~~	~~TCP11~~	~~TRAFFIC CONTROL PLAN TYPICAL DETAIL BAYOU TIMBER AT SAGE~~ (NOT APPLICABLE)
~~89~~	~~TCP12~~	~~TRAFFIC CONTROL PLAN TYPICAL DETAIL LEFT-TURN LANE CLOSURE MEMORIAL AT BUCKINGHAM~~ (NOT APPLICABLE)
90	TCP13	TYPICAL SIDEWALK CLOSURE AND PEDESTRIAN DETOUR
~~91~~	~~SP1~~	~~STORM WATER POLLUTION PREVENTION PLAN~~ (NOT APPLICABLE)
~~92~~	~~SP2~~	~~STORM WATER POLLUTION PREVENTION PLAN~~ (NOT APPLICABLE)
93	SP3	STORM WATER POLLUTION PREVENTION PLAN
~~94~~	~~SP4~~	~~STORM WATER POLLUTION PREVENTION PLAN~~ (NOT APPLICABLE)
~~95~~	~~TP1~~	~~TREE PROTECTION PLAN 1 OF 17~~ (NOT APPLICABLE)
~~96~~	~~TP2~~	~~TREE PROTECTION PLAN 2 OF 17~~ (NOT APPLICABLE)
~~97~~	~~TP3~~	~~TREE PROTECTION PLAN 3 OF 17~~ (NOT APPLICABLE)
~~98~~	~~TP4~~	~~TREE PROTECTION PLAN 4 OF 17~~ (NOT APPLICABLE)
~~99~~	~~TP5~~	~~TREE PROTECTION PLAN 5 OF 17~~ (NOT APPLICABLE)
~~100~~	~~TP6~~	~~TREE PROTECTION PLAN 6 OF 17~~ (NOT APPLICABLE)
~~101~~	~~TP7~~	~~TREE PROTECTION PLAN 7 OF 17~~ (NOT APPLICABLE)
~~102~~	~~TP8~~	~~TREE PROTECTION PLAN 8 OF 17~~ (NOT APPLICABLE)
~~103~~	~~TP9~~	~~TREE PROTECTION PLAN 9 OF 17~~ (NOT APPLICABLE)
~~104~~	~~TP10~~	~~TREE PROTECTION PLAN 10 OF 17~~ (NOT APPLICABLE)
~~105~~	~~TP11~~	~~TREE PROTECTION PLAN 11 OF 17~~ (NOT APPLICABLE)
~~106~~	~~TP12~~	~~TREE PROTECTION PLAN 12 OF 17~~ (NOT APPLICABLE)
~~107~~	~~TP13~~	~~TREE PROTECTION PLAN 13 OF 17~~ (NOT APPLICABLE)
108	TP14	TREE PROTECTION PLAN 14 OF 17
109	TP15	TREE PROTECTION PLAN 15 OF 17
110	TP16	TREE PROTECTION PLAN 16 OF 17

Sheet No.		Title
111	TP17	TREE PROTECTION PLAN 17 OF 17
112	D1	STORMWATER POLLUTION PREVENTION PLAN (SHEET 1 OF 2)
113	D2	STORMWATER POLLUTION PREVENTION PLAN (SHEET 2 OF 2)
114	D3	TRAFFIC CONTROL PLAN GENERAL NOTES
115	D4	TRAFFIC CONTROL PLAN STANDARDS
116	D5	BARRICADE STANDARD
117	D6	COH STANDARD WASTE WATER DETAILS (SHEET 1 OF 3)
118	D7	COH STANDARD WASTE WATER DETAILS (SHEET 2 OF 3)
119	D8	COH STANDARD WASTE WATER DETAILS (SHEET 3 OF 3)
120	D9	COH STANDARD STREET CUT PAVEMENT REPLACEMENT DETAILS
121	D10	CONCRETE PAVING DETAILS 1
122	D11	CONCRETE PAVING DETAILS 2
123	D12	CONCRETE PAVING DETAILS 3
124	D13	COH STANDARD STREET & SIDEWALK DETAILS
125	D14	COH STANDARD CONSTRUCTION SIGN DETAILS

END OF DOCUMENT

Document 00041

LIST OF PRE-QUALIFIED ASBESTOS/LEAD ABATEMENT, MOLD & SOIL REMEDIATION, DEMOLITION AND PETROLEUM STORAGE TANK REMOVAL CONTRACTORS

1.01 DOCUMENT INCLUDES

A. Authorization

B. List of Authorized Contractors.

2.0 RELATED DOCUMENTS

A. Section 13280 – Hazardous Materials Remediation

B. Section 13281&13282 – Abatement of Asbestos/Lead Containing Materials

3.0 AUTHORIZATION

A. The list of Contractors Pre-qualified for Asbestos/Lead Abatement, Mold & Soil Remediation, Demolition & Petroleum Storage Tank Removal ("List") was authorized on March 21, 2012, by City of Houston Council Motion No. 12-0180.

B. Only those firms on the List can be utilized by Bidder in subcontracting for asbestos & lead abatement, mold & soil remediation, demolition & petroleum storage tank removal included in the Work.

C. The List is administered by General Services Department. All inquiries should be directed to Gabriel Mussio (832-393-8079).

4.0 LIST OF AUTHORIZED CONTRACTORS

A. As of the date specified in paragraph 3.0.A., all contractors listed in paragraph 4.0.B were licensed in the State of Texas for the type of work. Authorized Contractors must maintain there license to be on the list.

B. Authorized Contractors:

1. AAR Incorporated, 6640 Signat Drive, Houston, Texas 77041
2. A & M Environmental, LLC, 6536 Supply Row, Houston, Texas 77011
3. ARC Abatement Inc., 6827 Signat Drive, Houston, Texas 77041
4. AIA General Contractors, Inc., 18331 Running Vine Lane, Spring, Texas 77379
5. Arrow Services, Inc., 10202 Airline Drive, Suite A, Houston, Texas 77037
6. Basic Environmental Group, LLC., 1839 Key Biscayne Court, Houston,

Texas 77065

7. Cherry Environmental Services, Inc., 4501 Cherry Lane, Santa Fe, Texas 77517

8. Clark-Tech Environmental Systems, Inc., 1515 Globe Street, Houston, Texas 77034

9. CRG Environmental Services, LLC., 2504 Avenue I, Rosenberg, Texas 77471

10. DNB Enterprises, Inc., 12969 West Hardy, Houston, Texas 77037

11. Dunphey Petroleum Services, Inc., 3505 Daphne, Houston, Texas 77021

12. EC Government Services, 5850 San Felipe, Suite 400, Houston, Texas 77057

13. Effective Environmental, Inc., 9950 Chemical Road, Pasadena, Texas 77507

14. GenTech Construction Company, LLC., 2211 West 34th Street, Houston, Texas 77018

15. Hazard Assessment Leaders, Inc., dba HAL, Inc., 5311 Petty Street, Houston, Texas 77007

16. Inland Environmental, Ltd., PO Box 6751, Kingwood, Texas 77325

17. J.T.B. Services, Inc., 9026 Lambright, Houston, Texas 77075

18. NCM, 16421 Aldine Westfield Road, Houston, Texas 77032

19. PfP Abatement Group, LLC., 3823 Shadow Trail Drive, Houston, Texas 77084

20. PEMCO, Inc., PO Box 2009, Pearland, Texas 77588-2009

21. RNDI Companies, Inc., 2255 Ridge Road, Suite 216, Rockwell, Texas 75807

22. Separation Systems Consultants, Inc., 17041 El Camino Real, Suite 200 Houston, Texas 77058

23. Texas Environmental Control, Inc., 4623 Steffani Lane, Houston, Texas 77041

24. Weston Solutions, Inc., 5599 San Felipe, Suite 700, Houston, Texas 77056

25. 1 Priority Environmental Services, Inc., 2573 Gravel Drive, Fort Worth, Texas 76118

END OF DOCUMENT

Document 00042

DESIGNATED SUBCONTRACTORS AND SUPPLIERS

A. Subcontract work for the following Sections to firm(s) listed and for reason(s) stated below:

****

Edit following list. Ensure individual Sections include names of designated firms and the reason is stated here. Use the following sample format.

****

1. [Section 12610- Open Office Furniture; procurement and installation of Open Office Furniture. The City has an existing procurement/installation contract with the firm stated in Section 12610.]

END OF DOCUMENT

****

List of Changes:

04-30-2004: Added List of Changes, Notice to Bidders Section. Defined new term (Code). Provided information on how errors in extending unit prices and totaling alternates would be handled. Changed document number for Notice of Intent to Award.

12-10-2004: Corrected paragraph references in Paragraphs 6.0.B, 11.0.B.2 and 11.0.C.3.

02-28-2006: Deleted Paragraphs 9.0.D and 9.0.J. Guidance on how to handle math errors in Bid Form is provided in tabular form in Document 00210 – Supplementary Instructions to Bidders.

08-10-2006: Added Small Business Enterprise (SBE) title and DBE to Paragraph 12.0 B.

04-12-2013: Added required no-contact/quiet period language as Paragraph 3.0 C., drawn from the City Procurement Manual.

02-26-2014: Add the updated no-contact/quiet period language as Paragraph 3.0 C., again drawn from the City Procurement Manual.

****

Document 00200

TABLE OF CONTENTS

INSTRUCTIONS TO BIDDERS

PARA	TITLE	PAGE
1.0	*RELATED DOCUMENTS*	1
2.0	*DEFINITIONS*	1
3.0	*NOTICE TO BIDDERS*	2
4.0	*BID DOCUMENTS*	2
5.0	*EXAMINATION OF DOCUMENTS, SITE, AND LOCAL CONDITIONS*	2
6.0	*INTERPRETATIONS DURING BIDDING*	2
7.0	*ADDENDA*	3
8.0	*SUBSTITUTION OF PRODUCTS*	3
9.0	*PREPARATION OF BIDS*	3
10.0	*BID SUBMISSION*	3
11.0	*BID SECURITY*	4
12.0	*SUBCONTRACTORS AND SUPPLIERS*	4
13.0	*MODIFICATION OR WITHDRAWAL OF BID*	4
14.0	*BID DISQUALIFICATION*	4
15.0	*PREBID MEETING*	5
16.0	*OPENING OF BIDS*	5
17.0	*EVALUATION AND CONSIDERATION OF BIDS*	5
18.0	*ACCEPTANCE OF THE BID*	5

Document 00200

INSTRUCTIONS TO BIDDERS

1.0 *RELATED DOCUMENTS*

A. Document 00210 – Supplementary Instructions to Bidders.

B. Document 00320 – Geotechnical Information.

C. Document 00330 – Existing Conditions.

D. Document 00410 – Bid Form, Parts A & B.

E. Document 00495 – Post-Bid Procedures.

F. Document 00520 – Agreement.

G. Document 00700 – General Conditions.

H. Document 00800 – Supplementary Conditions.

2.0 *DEFINITIONS*

A. Definitions set forth in Document 00700 – General Conditions and in other documents of Project Manual, are applicable to Bid Documents.

B. *Addendum:* Written or graphic instrument issued prior to Bid opening, which clarifies, modifies, corrects, or changes Bid Documents.

C. *Alternate:* The total amount bid for additions to work, as described in Section 01110 – Summary of Work. Each Alternate includes cost of effects on adjacent or related components, and Bidder's overhead and profit.

D. *Bid:* A complete and properly signed offer to perform the Work in accordance with this Document and Document 00210 – Supplementary Instructions to Bidders.

E. *Bid Date:* Date and time set for receipt of Bids as stated in Document 00210 – Supplementary Instructions to Bidders, or as modified by Addenda.

F. *Bid Documents:* Project Manual, Drawings, and Addenda.

G. *Bid Supplement: A* Bid submittal that is required in Document 00410 – Bid Form.

H. *Bidder:* Person or firm, identified in Document 00410B – Bid Form – Part B, including its successors, and its authorized representative.

I. *Code:* Code of Ordinances, Houston, Texas.

J. *Low Bidder:* Apparent successful Bidder that qualifies as a responsible Bidder and that submits Bid with lowest Total Bid Price.

K. *Project Manager:* Person designated in Document 00100 – Advertisement for Bids and Document 00220 – Request for Bid Information to represent the City during bidding and post-bid periods.

L. *Project Manual:* Volume assembled for the Work that includes the bidding requirements, sample forms, Conditions of the Contract, and Specifications.

M. *Security Deposit:* A certified check, cashier's check, or bid bond in the amount of 10 percent of the Total Bid Price.

N. *Total Bid Price:* Total amount bid for performing the Work as identified by Bidder in Document 00410B – Bid Form – Part B, which amount includes:

1. Stipulated Price;

2. Total Base Unit Prices;

3. Total Extra Unit Prices;

4. Total Cash Allowances; and

5. Total Alternates.

3.0 *NOTICE TO BIDDERS*

A. The City of Houston Fair Campaign Ordinance makes it unlawful for a Contractor to offer any contribution to a candidate for City elective office (including elected officers and officers-elect) during a certain period of time prior to and following the award of the Contract by the City Council. The term "Contractor" includes proprietors of proprietorships, all partners of partnerships, and all officers, directors, and holders of 10 percent or more of the outstanding shares of corporations. A statement disclosing the names and business addresses of each of those persons will be required to be submitted with each bid or proposal; for a City Contract. Bidder shall complete and submit Document 00452 – Form A, Contractor Submission List, City of Houston Fair Campaign Ordinance, with its Bid to comply with this requirement. See Chapter 18 of the Code for further information.

B. Chapter 15, Article VIII, of the City's Code provides that no contract shall be let, nor any other business transaction entered into, by the City with any person indebted to the City or a qualifying entity, if the contractor or transaction comes within the provisions of Section 15-1 (c) of the Code. Exceptions are provided in Section 15-126 of the Code. Bidder shall complete and submit Document 00455 – Affidavit of Ownership or Control, with its Bid to comply with this requirement.

C. Neither bidder(s) nor any person acting on bidder(s)'s behalf shall attempt to influence the outcome of the award by the offer, presentation or promise of gratuities, favors, or anything of value to any appointed or elected official or employee of the City of Houston, their families or staff members. All inquiries regarding the solicitation are to be directed to the designated City Representative identified on the first page of the solicitation. Upon issuance of the solicitation through the pre-award phase and up to the date the City Secretary publicly posts notice of any City Council agenda containing the applicable award, aside from bidder's formal response to the solicitation, through the pre-award phase, written requests for clarification during the period officially designated for such purpose by the City Representative, neither bidder(s) nor persons acting on their behalf shall communicate with any appointed or elected official or employee of the City of Houston, their families or staff through written or oral means in an attempt to persuade or influence the outcome of the award or to obtain or deliver information intended to or which could reasonably result in an advantage to any bidder. However, nothing in this paragraph shall prevent a bidder from making public statements to the City Council convened for a regularly scheduled session after the official selection has been made and placed on the City Council agenda for action, or to a City Council committee convened to discuss a recommendation regarding the solicitation.

4.0 *BID DOCUMENTS*

A. The Bid Documents may be obtained at location specified in Document 00210 – Supplementary Instructions to Bidders.

B. The Bid Documents are made available only for the purpose of bidding on the Work. Receipt of Bid Documents does not grant a license for other purposes.

C. On receipt of Bid Documents, Bidder shall verify that documents are legible and complete, compare contents of Project Manual with Document 00010 – Table of Contents, and compare Index of Drawings with Document 00015 – List of Drawings. Bidder shall notify Project Manager if Bid Documents are incomplete.

D. If City of Houston Standard Specifications or Standard Details are required by the Project Manual, Bidder shall refer to Document 00210 – Supplementary Instructions to Bidders for purchase information.

5.0 *EXAMINATION OF DOCUMENTS, SITE, AND LOCAL CONDITIONS*

A. Bidder shall examine Project site, become familiar with local conditions under which the Work shall be performed, conduct appropriate investigations, and correlate personal observations with requirements of the Bid Documents before submitting a Bid.

B. Bidder shall make site investigations to the extent Bidder deems necessary to ascertain extent of subsurface conditions.

C. Failure of Bidder to perform the investigations prior to submitting a Bid does not relieve Bidder of responsibility for investigations, interpretations and proper use of available information in the preparation of its Bid.

D. Bidder shall observe limitations of access to occupied or restricted site as stated in Document 00210 – Supplementary Instructions to Bidders.

6.0 *INTERPRETATIONS DURING BIDDING*

A. Bidder shall immediately submit Document 00220 – Request for Bid Information to Project Manager upon finding errors, discrepancies, or omissions in Bid Documents. Confirmation of receipt of questions by the City is the responsibility of Bidder. Verbal discussions and answers are not binding.

B. Document 00220 – Request for Bid Information must be received at least 10 days before the Bid Date to allow issuance of Addenda in accordance with Paragraph 7.O.D. Replies, if issued, are by Addenda.

7.0 *ADDENDA*

A. Addenda that affect bidding requirements are applicable only during applicable only through issuance of the Notice to Proceed. Addenda that affect the Contract are a part of the Contract.

B. BIDDERS WHO SUBMIT A BID ON THIS PROJECT SHALL BE PRESUMED TO HAVE RECEIVED ALL ADDENDA AND TO HAVE INCLUDED ANY COST THEREOF IN THEIR BIDS, REGARDLESS OF WHETHER THEY ACKNOWLEDGE THE ADDENDA OR NOT.

C. The City will make Addenda available at same location where the Bid Documents may be obtained. The City will notify plan holders of record when Addenda are available. Bidders are responsible for obtaining Addenda after notification.

D. No Addendum will be issued later than noon on Monday before Bid Date, except Addenda with minor clarifications, withdrawing request for Bids, or postponing Bid Date.

8.0 *SUBSTITUTION OF PRODUCTS*

A. No substitutions of Products will be considered during the bidding period.

9.0 *PREPARATION OF BIDS*

A. Bidder shall fill in applicable blanks in Document 00410A&B – Bid Form – Parts A & B and Bid Supplements. In addition, Bidder shall bid all Alternates. Bidder shall properly sign Document 00410B -Bid Form.

B. Bidder shall initial all pages, except signature page, of Document 00410B – Bid Form – Part B.

C. Bidder is responsible for all costs incurred by the Bidder, associated with preparation of its Bid and compliance with Post-bid Procedures.

D. Bidder may not adjust preprinted price on line items stating "Fixed Unit Price" in the description on the Bid Form.

E. Bidder may increase preprinted price on line items stating "Minimum Bid Price" in the description on the Bid Form by crossing out the minimum and inserting revised price on the line above.

F. Bidder may decrease preprinted price on line items stating "Maximum Bid Price" in the description on the Bid Form by crossing out the maximum and inserting revised price on the line above.

G. Bidder shall insert a price no greater than the maximum preprinted range and no less than the preprinted range for line items stating "Fixed Range Unit Price" in the description on the Bid Form by crossing out prices noted and inserting revised price on the line above.

H. Bidder may not adjust Cash Allowance amounts.

10.0 *BID SUBMISSION*

A. City Secretary will receive Bids on Bid Date at location specified in Document 00210 – Supplementary Instructions to Bidders.

B. Bids submitted after Bid Date will be returned to Bidder unopened.

C. Verbal, facsimile, or electronic Bids are invalid and will not be considered.

D. Bidder shall submit in person or by mail one copy of the signed Document 00410 – Bid Form, Parts A and B, along with required Security Deposit, and required Bid Supplements, in a sealed, opaque envelope. In addition, Bidder shall clearly identify Project, Bid Date and Bidder's name on outside of envelope. If forwarded by mail, the sealed envelope containing the Bid must be enclosed in another envelope addressed for postal delivery.

11.0 *BID SECURITY*

A. Bidder shall submit a Security Deposit with its Bid.

B. Certified Check or Cashier's Check

1. Bidder shall make check payable to the City of Houston.

2. A check is submitted on the condition that if Bidder is named Low Bidder and fails either to timely and properly submit documents required in Document 00495 – Post-Bid Procedures, the City will cash the check in accordance with Paragraph 11.0.E.

C. Bid Bond

1. The bid bond must be a valid and enforceable bond, signed by a surety that complies with other requirements set out by law.

2. The bid bond must name the City of Houston as obligee, and be signed by the Bidder as principal and signed and sealed by the surety.

3. The bid bond must be conditioned such that if Bidder is named Low Bidder and then fails to timely and properly submit documents required in Document 00495 – Post-Bid Procedures, surety will be obligated to pay to the City an amount in accordance with Paragraph 11.0.E.

D. Security Deposits will be retained until after the Contract is awarded or all Bids are rejected.

E. Low Bidder forfeits Security Deposit if it fails to timely and properly submit documents required in Document 00495 – Post-Bid Procedures. The City may claim an amount equal to the difference between the Total Bid

Price of the defaulting Bidder and the Total Bid Price of the Bidder awarded the Contract. If Security Deposit is a check, the City will reimburse any remaining balance to the defaulting Bidder.

12.0 *SUBCONTRACTORS AND SUPPLIERS*

A. The City may reject proposed Subcontractors or Suppliers.

B. Refer to Document 00800 – Supplementary Conditions, for MWBEPDBE, DBE and SBE goals.

13.0 *MODIFICATION OR WITHDRAWAL OF BID*

A. A Bidder may modify or withdraw a Bid submitted before the Bid Date by written notice to the City Secretary. The notice may not reveal the amount of the original Bid and must be signed by the Bidder.

B. Bidder may not modify or withdraw its Bid by verbal, facsimile, or electronic means.

C. A withdrawn Bid may be resubmitted up to the time designated for receipt of Bids.

14.0 *BID DISQUALIFICATION*

A. The City may disqualify a Bid if the Bidder:

1. fails to provide required Security Deposit in the proper amount;
2. improperly or illegibly completes information required by the Bid Documents;
3. fails to sign Bid or improperly signs Bid;
4. qualifies its Bid; or
5. improperly submits its Bid.

B. When requested, Low Bidder shall present satisfactory evidence that Bidder has regularly engaged in performing construction work as proposed, and has the capital, labor, equipment, and material to perform the Work.

15.0 *PREBID MEETING*

A. A prebid meeting is scheduled to be held at the place, time, and date listed in Document 00210 – Supplementary Instructions to Bidders.

B. All Bidders, subcontractors, and suppliers are invited to attend.

C. Representatives of City Engineer will attend.

16.0 *OPENING OF BIDS*

A. Bids are opened by the City Secretary and publicly read in City Council Chambers on the Public Level in City Hall Annex at 11:00 a.m. on Bid Date.

B. Place and date of Bid opening may be changed in accordance with Sections 15-3(b)(5) and 15-3(b)(6) of the City Code.

17.0 *EVALUATION AND CONSIDERATION OF BIDS*

A. Project Manager will tabulate, record and evaluate Bids.

B. The City may reject all Bids or may reject any defective Bid.

18.0 *ACCEPTANCE OF THE BID*

A. The City will send to Low Bidder Document 00498 – Notice of Intent to Award. Acceptance by the City is conditioned upon Bidder's timely and proper submittal of documents required in Document 00495 – Post-Bid Procedures.

B. The Bid remains open to acceptance and is irrevocable for the period of time stated in Document 00410A – Bid Form – Part A.

END OF DOCUMENT

Document 00210

SUPPLEMENTARY INSTRUCTIONS TO BIDDERS

The following Paragraphs modify Document 00200 - Instructions to Bidders. Where a portion of the Instructions to Bidders is modified or deleted by these Supplementary Instructions, the unaltered portions of the Instructions to Bidders remains in effect.

2.0 – DEFINITIONS: Add the following Paragraphs to this Section:

O. *Office of Business Opportunity (OBO):* All references to Affirmative Action Contract Compliance Division (AACC) set forth in Document 00700 – General Conditions and in other documents of the Project Manual, shall refer to, and include, the Office of Business Opportunity.

3.0 - NOTICE TO BIDDERS: Add the following Paragraph to this Section:

C. The City will award this contract to a "Local Business", as that term is defined in Section 15-176 of the City of Houston Code of Ordinances ("the Code"):

- If the bid of the Local Business is less than $100,000 and is the lowest responsible bid or is within 5% of the lowest bid received, or
- If the bid of the Local Business is more than $100,000 and is the lowest responsible bid or is within 3% of the lowest bid received, and
- Unless the Director determines that such an award would unduly interfere with contract needs, as provided in Section 15-181 of the Code.

If there is no bid of a Local Business that meets these criteria, the City will award the contract to the lowest responsible bidder.

4.0 – BID DOCUMENTS: Add the following Paragraphs to this Section:

A. Add the following Paragraph A.1:

1. Bid documents may only be obtained electronically at the City's website: http://bidsets.publicworks.houstontx.gov/.

D. Add the following Paragraph D.1:

1. Copies of the City Standard Specifications and Details may be acquired at no cost on the City's website **http://documents.publicworks.houstontx.gov/document-center/cat_view/88-engineering-and-construction/92-specifications/208-division-02-16-standard-specifications.html**

E. The following plan rooms, whose names, addresses, phone and fax numbers were last updated on April 9, 2007, have been authorized by the City to display Bid Documents for examination:
(Note: The Bid Documents furnished to the plan rooms for examination can be in electronic format, in hard copies, or in any other formats pertaining to each City Contracting Division's discretion.)

1. AMTEK Information Services, Inc., 4001 Sherwood Lane, Houston, TX 77092, 713-956-0100, Fax 713-956-5340, Email: planroom@amtekusa.com

2. Associated Builders & Contractors, Inc., (ABC), 3910 Kirby, Suite 131, Houston, TX 77098-4151, 713-523-6222, Fax 713-874-0747. Email: lori@abchouston.org

3. Associated General Contractors (AGC-BB) Building Branch, 3825 Dacoma, Houston, TX 77092-8717, 713-843-3700, Fax 713-843-3701. Email: karla.s@agchouston.org

4. Associated General Contractors, (AGC-HHUI), Highway, Heavy Utilities and Industrial Branch, 2400 Augusta St., Suite 180, Houston, TX 77057, 713-334-7100, Fax 713-334-7130. Email: houston@agctx.org (Attention: Mel Keyser)

5. Construction Information Network, 1225 North Loop West, Suite 550, Houston, TX 77008, 713-868-2233 ext. 329, Fax 866-852-2713. Email: paul.tilford@cnsx.com

6. F. W. Dodge Corporation, 4101 Greenbriar, Suite 320, Houston, TX 77098, 713-529-4895, Fax 713-524-7639. Email: terrie_harris@mcgraw-hill.com

7. Hispanic Contractors Association of Houston (HCA-GHA), 11 Parker Road, Suite 7, Houston, TX 77241, 713-699-2732 or 832-754-3705, Fax 713-695-1556, Email: hispanicontractorsassociation@yahoo.com; or Randymagdaleno@yahoo.com

8. Houston Minority Business Development Center, 2900 Woodridge, Suite 124, Houston, TX 77087, 713-644-0821, Fax 713-644-3523. Email: gtamez@gacompanies.com

9. Reed Construction Data, 30 Technology Parkway South, Suite 100, Norcross, GA – 30092-8629. Tel. 1-800-424-3996 or 1-800-699-8640; Fax 1-800-317-0870 or 1-800-508-5370.

10. The Builders' Exchange of Texas, Inc., 3910 Kirby, Suite 131, Houston, TX 77098, 210-564-6900, Fax: 210-564-6921, Email: houston@bxtx.com

F. Add the following Paragraph F.1:

1. **Designation as a City Business or Local Business**

To be designated as a City or Local Business for the purpose of the Hire Houston First Program, as set out in Article XI of Chapter 15 of the Houston City Code, a bidder or proposer must submit the Hire Houston First Application and Affidavit to the Director of the Mayor's Office of Business Opportunity (OBO) and receive notice that the designation has been approved prior to submission of a bid or proposal. Submit with your bid a valid official letter from OBO with your designation as a City or Local Business.

5.0 - EXAMINATION OF DOCUMENTS, SITE, AND LOCAL CONDITIONS: Insert the following paragraph:

A. Add the following Paragraph D.1:

1. The site, or part of it, is currently occupied and access is limited. Premises will be open for examination by appointment, under admission by attending at Prebid Meeting for information.

9.0 – PREPARATION OF BIDS: Add the following Paragraph I to this Paragraph:

I. For math errors the City encounters in analyzing Bids, the following guidance will be used:

In the event of a conflict between:	The Bid Price is:
1. Individual Unit Price and Extension of that Unit Price	Individual Unit Price times Estimated Quantity
2. A Unit Price extension and total of Unit Price Extensions	Sum of all Individual Unit Price Extensions
3. Individual Alternate and total of Alternates	Sum of all Individual Alternates
4. Individual subtotals for Stipulated Price, Base Unit Prices, Extra Unit Prices, Contractor Bonus, Cash Allowances, and Alternates; and the Total Bid Price	Sum of Individual subtotals for Stipulated Price, Base Unit Prices, Extra Unit Prices, Contractor Bonus, Cash Allowances and Alternates

10.0 – BID SUBMISSION: Add the following Paragraph A.1 to this Section:

A. Add the following Paragraph A.1:

1. City Secretary will receive Bids at 900 Bagby, Room P101, Houston, Texas until 10:30 a.m., local time on April 23, 2015.

15.0 – PREBID MEETING: Add the following Paragraph A.1 to this Section:

A. Add the following Paragraph A.1:

1. A Prebid Meeting will be held at 11:30 A.M. on Tuesday, April 7, 2015, in 16th Floor, Conference Room No. 16-A at 611 Walker Street, Houston, Texas 77002.

END OF DOCUMENT

Document 00220

REQUEST FOR BID INFORMATION

PROJECT: Lift Station Renewal/Replacement - Woodway #1 Lift Station Replacement

PROJECT No.: WBS No. R-000267-109B-4

TO: Akhter Hussain, P.E.
15th Floor
611 Walker, Houston, Texas 77002

Phone No. (832) 395-2294
Fax No. (832) 395-2344
Email Addr. akhter.hussain@houstontx.gov

(Type or Print question legibly; use back if more space is needed)

This request relates to _____ (Drawing / Detail No.) and/or _____ (Specification Section No.)

Attachments to this request: _____

_____
Signature

_____
Date

_____
(Type or Print Name)

_____
(Type or Print Company Name)

END OF DOCUMENT

Document 00320

GEOTECHNICAL INFORMATION

1. DOCUMENT INCLUDES

A. Soils investigation reports.
B. Bidder's responsibilities.

2. RELATED DOCUMENTS

A. Document 00340 – Environmental Information
B. Section 02260 - Trench Safety Systems

3. SITE INVESTIGATION REPORTS

A. In the design and preparation of Contract documents for this Project, the City and Design Consultant have used information in geotechnical reports for the investigation and analysis of soils and subsurface conditions at the Project site.

B. An electronic copy of the report for this project is included in a CD-Rom affixed to the inside front cover of the project manual.

C. Neither the City nor Design Consultant is responsible for accuracy or completeness of any information or data.

4. GEOTECHNICAL REPORTS

A. Report No.: 12-344E Prepared by (Firm Name): Geotech Engineering and Testing; Title: Geotechnical Study Proposed Pump and Lift Station Renewal/ Rehabilitation Post Oak Lane, Stablewood, Bayou Timber and Buckingham; Report Date: June 16, 2014 ; No. of Pages: 154

5. BIDDER RESPONSIBILITIES

A. Bidder shall take full responsibility for interpretation and use of information contained in above listed reports for its bidding and construction purposes.

B. Bidder may perform additional soils investigations as Bidder deems appropriate.

END OF DOCUMENT

Document 00340

ENVIRONMENTAL INFORMATION

1.0 DOCUMENT INCLUDES

A. Environmental Site Assessment, if applicable.

B. Asbestos and Lead Surveys, if applicable.

C. Bidder's responsibilities.

2.0 RELATED DOCUMENTS

A. Document 00320 - Geotechnical Information

3.0 SITE INVESTIGATION REPORTS

A. In the design and preparation of Contract documents for this Project, the City and Design Consultant have used information in environmental site assessment reports for the investigation and analysis of soils and subsurface conditions at the Project site.

B. In the design and preparation of Contract documents for this Project, the City and Design Consultant have relied upon information in surveys taken for Asbestos-containing Materials (ACMs) and lead at the Project site.

C. An electronic copy of each report for this project is included in a CD-Rom affixed to the inside front cover of the project manual.

D. Neither the City nor Design Consultant is responsible for accuracy or completeness of any information or data.

4.0 REPORTS

A. Environmental Assessment Surveys

Report No.: 1130018301 Prepared by (Firm Name):ARCADIS U.S, Inc.; Title: Phase II Environmental Site Assessment Lift Station Renewal/ Replacement Galleria Area Lift Stations; Report Date: July 23, 2014; No. of Pages 95

5.0 BIDDER RESPONSIBILITIES

A. Bidder shall take full responsibility for interpretation and use of information contained in above listed reports for bidding and construction purposes.

B. Bidder may perform additional investigations as Bidder deems appropriate.

END OF DOCUMENT

Document 00410A

BID FORM – PART A

To: **The Honorable Mayor and City Council of the City of Houston**
City Hall Annex
900 Bagby Street
Houston, Texas 77002

Project: Lift Station Renewal/Replacement - Woodway #1 Lift Station Replacement

Project No.: WBS No. R-000267-109B-4

Bidder: _____

(Print or type full name of business entity, such as corporation, LLC, etc)

OFFER

A. Total Bid Price: Having examined the Project location and all matters referred to in Bid Documents for the Project, we, the undersigned, offer to enter into a Contract to perform the Work for the Total Bid Price shown on the signature page of this Document

B. Security Deposit: Included with the Bid is a Security Deposit in the amount of 10 percent of the Total Bid Price subject to terms described in Document 00200 – Instructions to Bidders.

C. Period for Bid Acceptance: This offer is open to acceptance and is irrevocable for 90 days from Bid Date. That period may be extended by mutual written agreement of the City and Bidder.

D. Addenda: All Addenda have been received. Modifications to Bid Documents have been considered and all related costs are included in the Total Bid Price.

E. Bid Supplements: The following documents are attached:

[X] Security Deposit *(as defined in Document 00200 – Instructions to Bidders)*
[X] Document 00450 - Bidder's Statement of MWSBE Status
[X] Document 00452 - Contractor's Submission List - Fair Campaign Ordinance Form A
[X] Document 00453 – Bidder's Statement of Residency *(not required for AIP funded project)*
[X] Document 00454 - Affidavit of Non-interest
[X] Document 00455 - Affidavit of Ownership or Control
[ ] Document 00456 - Bidder's Certificate of Compliance with Buy American Program *(required for AIP funded project)*
[X] Document 00457 – Conflicts of Interest Questionnaire (CIQ)
[ ] Document 00458 - Bidder's Certificate Regarding Foreign Trade Restriction *(required for AIP funded project)*
[ ] Document 00459 - Contractor's Statement Regarding Previous Contracts Subject to EEO *(required for AIP funded project)*
[X] Document 00460 – (POP 1) Pay or Play Acknowledgement Form

[X] Document 00470 – Bidder's MWSBE Participation Plan *(required unless no MWSBE participation goal is provided in Document 00800* (the "Goal")*).*

[X] Document 00471 – Pre-bid Good Faith Efforts *(required if the goal in Bidder's Participation Plan–Document 00470 is lower than the Goal).*

[X] Document 00472 – Bidder's Goal Deviation Request *(required if the goal in Bidder's Participation Plan–Document 00470 is lower than the Goal).*

[X] Others as listed: Valid official letter from OBO with your designation as a City or Local Business *(Bidder's Participation Hire Houston First)*

CONTRACT TIME

A. If offer is accepted, Contractor shall achieve Date of Substantial Completion within 301 days after Date of Commencement of the Work, subject to adjustments of Contract Time as provided in the Contract.

Document 00410B

BID FORM – PART B

1.0 TOTAL BID PRICE HAS BEEN CALCULATED BY BIDDER, USING THE FOLLOWING COMPONENT PRICES AND PROCESS (PRINT OR TYPE NUMERICAL AMOUNTS):

A. STIPULATED PRICE: $ "N/A"

(Total Bid Price; minus Base Unit Prices, Extra Unit Prices, Cash Allowances and All Alternates, if any)

B. BASE UNIT PRICE TABLE:

Item No.	Spec Ref.	Base Unit Short Title	Unit of Measure	Estimated Quantity	Unit Price (this column controls)	Total in figures
1	01502	Mobilization See Footnote (1)	LS	1	$44,000.00(1)	$44,000.00(1)
2	01506 01506S	Diversion/By-pass Pumping	LS	1	$_____ (20,000.00)(2)	$_____ (20,000.00)(2)
3	01506S	Long Term Diversion/By-pass Pumping	Month	18	$_____ (7,500.00)(3)	$_____ (135,000.00)(3)
4	01555	Traffic Control and Regulation See Footnote (2)	LS	1	$_____ (18,000.00)(2)	$_____ (18,000.00)(2)
5	01555	Flagmen See Footnote (2)	LS	1	$_____ (10,000.00)(2)	$_____ (10,000.00)(2)
6	01562	Tree and Plant Protection	LS	1	$_____ (15,000.00)(2)	$_____ (15,000.00)(2)
7	01570	Inlet Protection Barrier	LF	300		
8	01570	Sandbag Barrier	LF	750		
9	01570	Filter Fabric Fence	LF	1,800		
10	01575	Stabilized Construction Exit	SY	50		
11	01740	Site Restoration	LF	441		
12	02082	6-ft diameter precast concrete force main bypass manhole	LS	1		
13	02082	6-ft diameter precast corrosion resistant sanitary sewer manhole	LS	1		

Bidder's Initials [ ]

Item No.	Spec Ref.	Base Unit Short Title	Unit of Measure	Estimated Quantity	Unit Price (this column controls)	Total in figures
14	02220, Div 01, 02, 16	Woodway LS – Salvage & Demolition of Existing Pumps, Piping, Valves, Electrical and Instrumentation Devices; Also includes demolition of existing lift station structures (as needed per plans), includes but not limited to wet well, and valve vault, existing bypass manholes, electrical panels. Also includes cut, fill and abandonment of existing 6" Force Main and excavation and removal of existing storm water culvert & safety end treatments; as well as, cutting and removing of trees, plants and shrubs.	LS	1		
15	02221	Remove and dispose of pavement, pavers, bricks, and/or other concrete surfacing (all thicknesses, including base & subgrade, w/ or w/o curb, all depth)	SY	1,500		
16	02260	Trench Safety System for trench excavations	LF	30		
17	02511	3/4-inch diameter water supply line by open cut (to connect to hose bibb) from existing water meter	LF	27		
18	02526	3/4-inch hose bib per plans	EA	1		
19	02526	3/4-inch RPZ Backflow Preventer with lockable metal cage cover.	EA	1		
20	02531 02533	8-inch diameter vitrified clay pipe (condensate line from Control Bldg), by open cut	LF	18		
21	02531 02533 02534	18-inch diameter sanitary sewer (i.e., stub out from Wet Well with temporary end cap for future service connection), by open cut	LF	20		

Item No.	Spec Ref.	Base Unit Short Title	Unit of Measure	Estimated Quantity	Unit Price (this column controls)	Total in figures
22	02532 02533	12-inch diameter sanitary sewer force main, by open cut	LF	276		
23	02631	24-inch diameter RCP storm sewer by open cut method with all connections and collars.	LF	356		
24	02632 02633	Stormwater Inlets (Type A) in place includes adjustments frame and cover to new pavement	LS	4		
25	02713	Recycled Crushed Concrete Base Course, 9-inch, Compacted and In-place	TON	212		
26	02751	Reinforced Concrete Pavement, 7-inch thick	SY	663		
27	02754	20-ft wide, Concrete Driveway, 7-inch thick	SF	298		
28	02775	4 ½ inch thick – 5-ft wide concrete sidewalk	SF	75		
29	02830	8-foot High Vinyl Fence & Posts	LF	150		
30	02830	12-foot High Hardwood Fence & Posts	LF	320		
31	02830	4-foot Wide – 8-foot high Vinyl Personnel Gate	EA	1		
32	02830	20' wide double swing gates with steel Padlock assembly	EA	1		
33	02922	Sodding for Lift Station Sites	SY	200		

Item No.	Spec Ref.	Base Unit Short Title	Unit of Measure	Estimated Quantity	Unit Price (this column controls)	Total in figures
34	02316 02320 03055, 03151, 03211, 03310, 03315, 03341, 03350, 03390, 03600 13440, 13441, 13446, 13471, DIV 16	New Electrical Controls including Electrical Building	LS	1		
35	02316 02317 02320 02465 03055, 03310, 03151, 03211, 03310, 03315, 03341, 03350, 03390, 03600, 05120, 06610,	Lift Station Structure (By Caisson): Concrete structure and associated items for wet well and valve vault including but not limited to excavation and backfill, wet well hatches with safety grating, fiberglass grating, force main and drain line connections; wet well ventilation piping with bird screen, including miscellaneous accessories and appurtenances.	LS	1		
36	09901, 09904, 09917	Concrete Corrosion Protection System: Complete installed concrete corrosion protection system (liner or spray-on system) for all interior surfaces with Wet Well Structure (except wet well floor), inclusive of all surface cleaning and preparation, installation and final application.	LS	1		

Item No.	Spec Ref.	Base Unit Short Title	Unit of Measure	Estimated Quantity	Unit Price (this column controls)	Total in figures
37	05120, 11311, 13440, 13441, 13446, 13471, 15050, 15053, 15126	Lift Station Piping and Mechanical: Installation of wet-well submersible pumps, cooling jackets, discharge piping; wet well piping brackets and supports, air release valves, isolation and check valves; bypass piping and valves, force main and drain line connections; influent line connections, including miscellaneous accessories and appurtenances.	LS	1		
TOTAL BASE UNIT PRICES						$_____

C. EXTRA UNIT PRICE TABLE:

Item No.	Spec Ref.	Extra Unit Short Title	Unit of Measure	Estimated Quantity	Unit Price (this column controls)	Total in figures
38	02318	Extra cement stabilized sand backfill	CY	50	$ (28.00)[2]	$ (1,400.00)[2]
39	02318	Extra excavations around obstructions	CY	100	$ (30.00)[2]	$ (3,000.00)[2]
40	02318	Extra machine excavation	CY	50	$ (30.00)[2]	$ (1,500.00)[2]
41	02318	Extra replacement of backfill material	CY	50	$ (6.00)[2]	$ (300.00)[2]
42	02318	Extra hand excavation around obstructions	CY	50	$ (17.00)[2]	$ (850.00)[2]
43	02318	Extra Class "A" Concrete installed in place for Structures	CY	50	$ (400.00)[2]	$ (20,000.00)[2]
44	02318	Extra Grade 60 reinforcing steel in place	LB	2,000	$ (1.00)[2]	$ (2,000.00)[2]
45	02105	Preparatory Work for sampling and analysis in PPCA	LS	1	$ (7,500.00)[3]	$ (7,500.00)[3]
46	02120	Transportation and Disposal of Contaminated Ground Water From PPCA	Gal	10,000	$ (1.00)[2]	$ (10,000.00)[2]
47	02120	Transportation and Disposal of soil from PPCA, Category 1 and Category II Soils	CY	650	$ (75.00)[2]	$ (48,750.00)[2]
TOTAL EXTRA UNIT PRICES						$ 95,300.00

REST OF PAGE INTENTIONALLY LEFT BLANK

D. CASH ALLOWANCE TABLE:

Item No.	Spec Ref.	Cash Allowance Short Title	Cash Allowance in figures (1)
48	01110	Building Permit Allowance	$50,000.00
49	01110	Lane Closure Permit Fee	$3,000.00
50	01110	Street Cut Permit	$2,500.00
51	01110	Utility Reimbursement	$25,000.00
52	01110	Demolition Permit	$1,000.00
53	01110	Flood Plain Fees	$3,500.00
TOTAL CASH ALLOWANCES			$85,000.00

REST OF PAGE INTENTIONALLY LEFT BLANK

E. ALTERNATES TABLE:

Item No.	Spec Ref.	Alternate Short Title	Unit of Measure	Estimated Quantity	Unit Price (this column controls)	Total Price for Alternate in figures
N/A	N/A	N/A	N/A	N/A	N/A	N/A
TOTAL ALTERNATES						$ N/A

REST OF PAGE INTENTIONALLY LEFT BLANK

F. TOTAL BID PRICE: $_____
(Add Totals for Items A., B., C., D., and E. above)

2.0 SIGNATURES: By signing this Document, I agree that I have received and reviewed all Addenda and considered all costs associated with the Addenda in calculating the Total Bid Price.

Bidder: _____
(Print or type full name of your proprietorship, partnership, corporation, or joint venture.*)

**By: _____
Signature Date

Name: _____
(Print or type name) Title

Address: _____
(Mailing)

_____
(Street, if different)

Telephone and Fax Number: _____
(Print or type numbers)

* If Bid is a joint venture, add additional Bid Form signature sheets for each member of the joint venture.

** Bidder certifies that the only person or parties interested in this offer as principals are those named above. Bidder has not directly or indirectly entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding.

Note: This document constitutes a government record, as defined by § 37.01 of the Texas Penal Code. Submission of a false government record is punishable as provided in § 37.10 of the Texas Penal Code.

Footnotes for Tables B through E:
(1) Fixed Unit Price determined prior to Bid. Cannot be adjusted by the Bidder.
(2) Minimum Bid Price determined prior to Bid. Can be increased by the Bidder by crossing out the Minimum and noting revised price on the line above.
(3) Maximum Bid Price determined prior to Bid. Can be decreased but not increased by Bidder by crossing out the Maximum and noting revised price on the line above. A Bid that increases the Maximum Bid Price may be found non-conforming and non-responsive.
(4) Fixed Range Bid Price determined prior to Bid. Unit Price can be adjusted by Bidder to any amount within the range defined by crossing out prices noted and noting revised price on the line above.

Document 00430

BIDDER'S BOND

THAT WE, _____, as Principal,
(Bidder)
("Bidder"), and the other subscriber hereto, _____, as Surety, do hereby acknowledge ourselves to be held and firmly bound to the City of Houston, a municipal corporation, in the sum of _____ Dollars ($_____) (an amount equal to 10 percent of the Total Bid Price, including Cash Allowances and Alternates, if any, for the payment of which sum, well and truly to be made to the City of Houston and its successors, the Bidder and Surety do bind themselves, their heirs, executors, administrators, successors, and assigns, jointly and severally.

THE CONDITIONS OF THIS OBLIGATION ARE SUCH THAT:

WHEREAS, the Bidder has submitted on or about this day a proposal offering to perform the following:

_____
(Project Name, Location and Number)
in accordance with the Drawings, Specifications, and terms and conditions related thereto to which reference is hereby made.

NOW, THEREFORE, if the Bidder's offer as stated in the Document 00410 – Bid Form is accepted by the City, and the Bidder executes and returns to the City Document 00520 – Agreement, required by the City, on the forms prepared by the City, for the Work and also executes and returns the same number of the Performance, Payment and Maintenance Bonds (such bonds to be executed by a Corporate Surety authorized by the State Board of Insurance to conduct insurance business in the State of Texas, and having an underwriting limitation in at least the amount of the bond) and other submittals as required by Document 00495 - Post-Bid Procedures, in connection with the Work, within the Contract Time, then this obligation shall become null and void; otherwise it is to remain in full force and effect.

If Bidder is unable to or fails to perform the obligations undertaken herein, the undersigned Bidder and Surety shall be liable to the City for the full amount of this obligation which is hereby acknowledged as the amount of damages which will be suffered by the City on account of the failure of such Bidder to perform such obligations, the actual amount of such damages being difficult to ascertain.

Notices required or permitted hereunder shall be in writing and shall be deemed delivered when actually received or, if earlier, on the third day following deposit in a United States Postal Service post office or receptacle, with proper postage affixed (certified mail, return receipt requested), addressed to the respective other Party at the address prescribed in the Contract documents, or at such other address as the receiving Party may hereafter prescribe by written notice to the sending Party.

IN WITNESS THEREOF, the Bidder and Surety have signed and sealed this instrument on the respective dates written below their signatures and have attached current Power of Attorney.

ATTEST, SEAL: (if a corporation)
WITNESS: (if not a corporation)

By: _____
Name:
Title:

ATTEST/SURETY WITNESS: (SEAL)

By: _____
Name:
Title:
Date:

_____
(Name of Bidder)

By: _____
Name:
Title:
Date:

_____
(Full Name of Surety)

_____
(Address of Surety for Notice)

_____
(Telephone Number of Surety)

By: _____
Name:
Title:
Date:

END OF DOCUMENT

Document 00450

BIDDER'S STATEMENT OF MWBE/PDBE/DBE/SBE STATUS

This certifies that the status of the Bidder, _____, in
(Bidder's Name)
regard to the City of Houston Code of Ordinances, Chapter 15, Article V, relating to City-wide percentage goals for contracting with Minority and Women-owned Business Enterprises (MWBE) and Disadvantaged Business Enterprises (DBE), Chapter 15, Article VI, relating to City-wide percentage goals for contracting with Persons with Disabilities Business Enterprises (PDBE) and Chapter 15, Article IX, relating to City-wide percentage goals for contracting with a Small Business Enterprise (SBE) is as follows:

1. Bidder (individual, partnership, corporation) is [__] is not [__] a Minority Business Enterprise as certified by the Office of Business Opportunity.

2. Bidder (individual, partnership, corporation) is [__] is not [__] a Women-owned Business Enterprise as certified by the Office of Business Opportunity

3. Bidder (individual, partnership, corporation) does [__] does not [__] declare itself to be a Persons with Disabilities Business Enterprise as defined above.

4. Bidder (individual, partnership, corporation) does [__] does not [__] declare itself to be a Disadvantaged Business Enterprise as defined above.

5. Bidder (individual, partnership, corporation) does [__] does not [__] declare itself to be a Small Business Enterprise as defined above.

Signature: _____

Title: _____

Date: _____

END OF DOCUMENT

Document 00452
Form A
CONTRACTOR SUBMISSION LIST
CITY OF HOUSTON FAIR CAMPAIGN ORDINANCE

The City of Houston Fair Campaign Ordinance makes it unlawful for a Contractor to offer any contribution to a candidate for City elective office (including elected officers-elect) during a certain period of time prior to and following the award of the Contract by the City Council. The term "Contractor" includes proprietors of proprietorships, partners or joint venturers having an equity interest of 10 percent or more for the partnership or joint venture, and officers, directors and holders of 10 percent or more of the outstanding shares of corporations. Submission of a statement disclosing the names and business addresses of each of those persons is required with each Bid/Proposal for a City Contract. See Chapter 18 of the City of Houston Code of Ordinances for further information.

This list is submitted under the provisions of Section 18-36(b) of the City of Houston Code of Ordinances in connection with the attached Bid/Proposal of:

Firm or Company Name: _____
Firm or Company Address: _____
_____

The firm/company is organized as indicated below. Check one as applicable and attach additional pages if needed to supply the required names and addresses.

[ ] SOLE PROPRIETOR

Name _____ _____
Proprietor Address

[ ] A PARTNERSHIP

LIST EACH PARTNER HAVING EQUITY INTEREST OF 10% OR MORE OF PARTNERSHIP (IF NONE STATE "NONE")

Name _____ _____
Partner Address

Name _____ _____
Partner Address

[ ] A CORPORATION

LIST ALL DIRECTORS OF THE CORPORATION (IF NONE STATE "NONE")

Name _____ _____
Director Address

Name _____ (Director) _____ (Address)

Name _____ (Director) _____ (Address)

LIST ALL OFFICERS OF THE CORPORATION (IF NONE STATE "NONE")

Name _____ (Officer) _____ (Address)

Name _____ (Officer) _____ (Address)

Name _____ (Officer) _____ (Address)

LIST ALL INDIVIDUALS OWNING 10% OR MORE OF OUTSTANDING SHARES OF STOCK OF THE CORPORATION (IF NONE STATE "NONE")

Name _____ (Owner) _____ (Address)

Name _____ (Owner) _____ (Address)

Name _____ (Owner) _____ (Address)

I certify that I am duly authorized to submit this list on behalf of the firm, that I am associated with the firm in the capacity noted below, and that I have knowledge of the accuracy of the information provided herein.

_____
Signature

_____
Printed Name

_____
Title

Note: This list constitutes a government record as defined by § 37.01 of the Texas Penal Code.

END OF DOCUMENT

Document 00453

BIDDER'S STATEMENT OF RESIDENCY

The City may not award a contract for general construction, services, or purchases to a Nonresident Bidder unless Nonresident's Bid is lower than the lowest Bid submitted by a responsible Texas Resident Bidder by the same amount that a Texas Resident bidder would be required to underbid the Nonresident Bidder to obtain a comparable contract in the state in which Nonresident's principle place of business is located.

1. This certifies that the Bidder, _____, is a State of Texas Resident Bidder as defined in TEX. GOVT. CODE ANN. § 2252.001(4) (Vernon 1994).

_____ _____
Signature Title

"Texas Resident Bidder" means a bidder whose principal place of business is in this State, and includes a Contractor whose ultimate parent company or majority owner has its principal place of business in this State. *When bidder cannot sign 1, above, proceed to 2.*

2. a. _____ is a resident of _____ and is a Nonresident Bidder as defined in TEX. GOVT. CODE ANN. § 2252.001(3) (Vernon 1994).

_____ _____
Signature Title

"Nonresident Bidder" means a bidder whose principal place of business is not in this State, but excludes a contractor whose ultimate parent company or majority owner has its principal place of business in this State.

b. The State of _____ _____ have a state statute giving
Bidder's resident state Does or Does Not
preference to resident bidders.

_____ _____
Signature Title

If the answer to 2.b is that your state does have a statute giving preference to resident bidders, then you must provide a copy and proceed to 3.

3. A copy of the State of _____ statute is attached.

_____ _____
Signature Title

_____
Date

END OF DOCUMENT

Document 00454

AFFIDAVIT OF NON-INTEREST

BEFORE ME, the undersigned authority, a Notary Public in and for the State of Texas, on this day personally appeared _____, who
Affiant

being by me duly sworn on his oath stated that he is _____, of
Title

_____,
Name of Firm

the firm named and referred to and in the foregoing; and that he knows of no officer, agent, or employee of the City of Houston being in any manner interested either directly or indirectly in such Contract.

_____
Affiant's Signature

SWORN AND SUBSCRIBED before me on _____.
Date

_____
Notary Public in and for the State of TEXAS

_____
Print or type name

My Commission Expires: _____
Expiration Date

END OF DOCUMENT

Document 00455

AFFIDAVIT OF OWNERSHIP OR CONTROL

ORIG. DEPT.: DEPARTMENT OF PUBLIC WORKS AND ENGINEERING **FILE/I.D. NO.:** R-000267-109B-4

INSTRUCTION: ENTITIES USING AN ASSUMED NAME SHOULD DISCLOSE SUCH FACT TO AVOID REJECTION OF THE AFFIDAVIT. THE FOLLOWING FORMAT IS RECOMMENDED: CORPORATE/LEGAL NAME DBA ASSUMED NAME.

STATE OF _____ §
§ **AFFIDAVIT OF OWNERSHIP OR CONTROL**
COUNTY OF _____ §

BEFORE ME, the undersigned authority, on this day personally appeared _____ [*FULL NAME*] (hereafter "Affiant"), _____ [*STATE TITLE/CAPACITY WITH CONTRACTING ENTITY*] of _____ [*CONTRACTING ENTITY'S CORPORATE/LEGAL NAME*] ("Contracting Entity"), who being by me duly sworn on oath stated as follows:

1. Affiant is authorized to give this affidavit and has personal knowledge of the facts and matters herein stated.

2. Contracting Entity seeks to do business with the City in connection with _____ [*DESCRIBE PROJECT OR MATTER*] which is expected to be in an amount that exceeds $50,000.

3. The following information is submitted in connection with the proposal, submission or bid of Contracting Entity in connection with the above described project or matter.

4. Contracting Entity is organized as a business entity as noted below (check box as applicable).

FOR PROFIT ENTITY:

[ ] SOLE PROPRIETORSHIP
[ ] CORPORATION
[ ] PARTNERSHIP
[ ] LIMITED PARTNERSHIP
[ ] JOINT VENTURE
[ ] LIMITED LIABILITY COMPANY
[ ] OTHER (Specify type in space below)

_____

_____

_____

NON-PROFIT ENTITY:

[ ] NON-PROFIT CORPORATION
[ ] UNINCORPORATED ASSOCIATION

5. The information shown below is true and correct for the Contracting Entity and all owners of 5% or more of the Contracting Entity and, where the Contracting Entity is a non-profit entity, the required information has been shown for each officer, *i.e.*, president, vice-president, secretary, treasurer, etc. ***[NOTE: IN ALL CASES, USE FULL NAMES, LOCAL BUSINESS AND RESIDENCE ADDRESSES AND TELEPHONE NUMBERS. DO NOT USE POST OFFICE BOXES FOR ANY ADDRESS. INCLUSION OF E-MAIL ADDRESSES IS OPTIONAL, BUT RECOMMENDED. ATTACH ADDITIONAL SHEETS AS NEEDED.]***

Contracting Entity

Name: _____

Business Address *[NO./STREET]* _____

[CITY/STATE/ZIP CODE] _____

Telephone Number (_____)_____

Email Address *[OPTIONAL]* _____

Residence Address *[NO./STREET]* _____

[CITY/STATE/ZIP CODE] _____

Telephone Number (_____)_____

Email Address *[OPTIONAL]* _____

5% Owner(s) or More (IF NONE, STATE "NONE.")

Name: _____

Business Address *[NO./STREET]* _____

[CITY/STATE/ZIP CODE] _____

Telephone Number (_____)_____

Email Address *[OPTIONAL]* _____

Residence Address *[NO./STREET]* _____

[CITY/STATE/ZIP CODE] _____

Telephone Number (_____)_____

Email Address *[OPTIONAL]* _____

6. *Optional Information*

Contracting Entity and/or _____ [***NAME OF OWNER OR NON-PROFIT OFFICER***] is actively protesting, challenging or appealing the accuracy and/or amount of taxes levied against _____ [***CONTRACTING ENTITY, OWNER OR NON-PROFIT OFFICER***] as follows:

Name of Debtor: _____

Tax Account Nos. _____

Case or File Nos. _____

Attorney/Agent Name _____

Attorney/Agent Phone No. (_____)_____

Tax Years _____

Status of Appeal *[**DESCRIBE**]* _____

_____

_____

_____

Affiant certifies that he or she is duly authorized to submit the above information on behalf of the Contracting Entity, that Affiant is associated with the Contracting Entity in the capacity noted above and has personal knowledge of the accuracy of the information provided herein, and that the information provided herein is true and correct to the best of Affiant's knowledge and belief.

_____
Affiant

SWORN TO AND SUBSCRIBED before me this _____ day of _____, 20_____.

(Seal)

_____
Notary Public

NOTE:
This affidavit constitutes a **government record** as defined by Section 37.01 of the Texas Penal Code. Submission of a false government record is punishable as provided in Section 37.10 of the Texas Penal Code. Attach additional pages if needed to supply the required names and addresses.

Document 00457

Conflict of Interest Questionnaire

****

Print out latest version of CIQ form from website listed below:

****

Local Government Code Chapter 176 requires Bidders with the City of Houston ("City") to file a Conflict of Interest Questionnaire with the City Secretary of the City of Houston.

The Conflict of Interest Questionnaire is available for downloading on the Texas Ethics Commission's website at: http://www.ethics.state.tx.us/forms/CIQ.pdf. The completed Conflict of Interest Questionnaire will be posted on the City Secretary's website. Also you will find a list of the City Local Government Officers on the City Secretary's website.

For your convenience the CIQ form is attached as part of this document. Although the City has provided this document for the Bidders convenience, it is the Bidders responsibility to submit the latest version of the CIQ form as promulgated by the Texas Ethics Commission.

The Failure of any Bidder to comply with this law is a Class C misdemeanor.

END OF DOCUMENT

Document 00459

CONTRACTOR'S STATEMENT REGARDING PREVIOUS CONTRACTS SUBJECT TO EQUAL EMPLOYMENT OPPORTUNITY

Section 60-1.7(b) of the Regulations of the Secretary of Labor requires each bidder or prospective prime contractor and proposed subcontractor, where appropriate, to state in the bid or at the outset of negotiations for the contract whether it has participated in any previous contract or subcontract subject to the equal opportunity clause; and if so, whether it has filed with the Joint Reporting Committee, the Director, an agency, or the former President's Committee on Equal Employment Opportunity all reports due under the applicable filing requirements. In any case in which a bidder or prospective prime contractor or proposed subcontractor which participated in a previous contract subject to Executive Order 10925, 11114. or 11246 has not filed a report due under the applicable filing documents, no contract or subcontract shall be awarded unless such contractor submits a report covering the delinquent period or such other period specified by the FAA or the Director, OFCCP.

Contractor has __ has not __ participated in a previous contract subject to the equal opportunity clause prescribed by Executive Order 10925, or Executive Order 11114, or Executive Order 11246.

Contractor has __ has not __ submitted all compliance reports in connection with any such contract due under the applicable filing requirements; and that representations indicating submission of required compliance reports signed by proposed subcontractors will be obtained prior to award of subcontracts.

If Contractor has participated in a previous contract subject to the equal opportunity clause and has not submitted compliance reports due under applicable filing requirements, Contractor (Proposer) shall submit a compliance report on Standard Form 100, "Employee Information Report EEO-1" prior to the award of the Contract.

Standard Form 100 is normally furnished to contractors annually, based on a mailing list currently maintained by the Joint Reporting Committee. In the event Contractor has not received the form, Contractor may obtain it by writing to the following address:

Joint Reporting Committee
1800 G Street
Washington, DC 20506

_____
(Printed or typed Name of Signatory)

_____ _____
Signature Date

_____
Title

_____
Contractor's Firm Name

NOTE: The penalty for making false statements in offers is prescribed in 18 U.S.C. 1001.

END OF DOCUMENT

Document 00460
(POP -1)
City of Houston
Pay or Play Program
Acknowledgement Form

It has been determined that the project currently open for bidding meets the criteria of the City of Houston Pay or Play program. This form acknowledges your awareness of the Pay or Play program which is authorized by Ordinance 2007-534. Your signature below affirms that you will comply with the requirements of the program if you are the successful bidder/proposer, and ensure the same on behalf of subcontracts subject to the Pay or Play Program.

I declare under penalty of perjury under the laws of the State of Texas that if awarded this contract which meets the criteria for the City of Houston's Pay or Play Program, I will comply with all requirements of the Pay or Play Program in accordance with Executive Order 1-7.

***Fill out all information below and submit this form with your bid/proposal packet.**

_____
Solicitation Number

_____ _____
Signature Date

_____ _____
Print Name City Vendor ID

_____ _____
Company Name Phone Number

_____
Email Address

Note: For more information contact your POP Liaison or the POP Contract Administrator. All contact information can be found on www.houstontx.gov →Departments→Office of Business Opportunity→Pay or Play.

Document 00470

BIDDER'S MWSBE PARTICIPATION PLAN

The Bidder or Proposer shall submit this completed form with the bid, to demonstrate the Bidder/Proposer's plan to meet the contract-specific MWSBE goal ("contract goal"). If the Bidder or Proposer cannot meet the contract goal, the Bidder/Proposer has the burden to demonstrate "Good Faith Efforts", which shall include correctly and accurately preparing and submitting this form, a Record of Good Faith Efforts (Document 00471), and a Request for Deviation from the Goal (Document 00472), the documentation evidencing their "Good Faith Efforts", as required by the City of Houston's Good Faith Efforts Policy (Document 00808). The City will review the Participation Plan and Good Faith Efforts at the time of bid opening. Visit http://www.houstontx.gov/obo for more information.

Contract Goal	MBEGoal %	WBEGoal %
	11%	7%

Bidder's Participation Plan Percentage	SBE	MBE	WBE	Total

NAICS Code (6 digit)	Description of Work (Plan Sheet #, Unit Price #, Scope of Work #, as applicable)	% of Total Bid Price (2 decimal places)	Cert. Type for Goal MBE, WBE, SBE)	Certified Firm Name Firm Address Contact Name Phone No. and E-Mail (if available)

Signature for Company: _____ Date: _____
Print Name: _____ Phone: _____
Bidder: _____
(Print or type full name of business entity, such as corporation, LLC, etc)

I understand that supplying inaccurate information may violate Texas Penal Code Section 37.10 and lead to City sanctions.

DOCUMENT 00470

CONTINUATION PAGE

NAICS Code (6 digit)	Description of Work (Plan Sheet #, Unit Price #, Scope of Work #, as applicable)	% of Total Bid Price (2 decimal places)	Cert. Type for Goal MBE, WBE, SBE)	Certified Firm Name Firm Address Contact Name Phone No. and E-Mail (if available)

Signature for Company: _____ Date: _____
Print Name: _____ Phone: _____
Bidder: _____
(Print or type full name of business entity, such as corporation, LLC, etc)

I understand that supplying inaccurate information may violate Texas Penal Code Section 37.10 and lead to City sanctions.

Document 00471

PRE-BID GOOD FAITH EFFORTS

Bidder or Proposer Name: _____ **Project Name**_____

A Bidder or Proposer that may be unable to complete or follow a Participation Plan (Document CCD-00470) to meet the Contract Goal in the Supplemental Conditions (Document 00800), must submit this completed form as well as a Goal Deviation Request Form (Document 00472), and any other documentation of "Good Faith Efforts" with the bid (see Document 00808). The Bidder or Prime Contractor has the burden to demonstrate "Good Faith Efforts" to meet the MWSBE goal, which includes correctly and accurately preparing and submitting this form and other efforts described in the City's Good Faith Efforts Policy (Document 00808). The Office of Business Opportunity will review Good Faith Efforts and Participation Plan after selection of an apparent low bidder.

UNLESS THE BIDDER'S/PROPOSER'S PARTICIPATION PLAN MEETS THE CONTRACT GOAL, FAILURE TO SUBMIT THIS FORM MAY RESULT IN THE BID BEING FOUND NON-RESPONSIVE.

NAICS Code	Plan Item No.	MWSBE Type for Goal	Certified Firm Name Address, Phone No. and E-Mail	Certified Firm Contact Person	Method of Contact	Prime Contact Date	Certified Firm Response	Results of Contact (why suitable or not suitable for work)
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			

Authorized Signature: _____ Date: _____ Phone: _____

Print Name: _____ Email Address: _____

CONTINUATION PAGE

NAICS Code	Plan Item No.	MWSBE Type for Goal	Certified Firm Name Address, Phone No. and E-Mail	Certified Firm Contact Person	Method of Contact	Prime Contact Date	Certified Firm Response	Results of Contact (why suitable or not suitable for work)
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			

Authorized Signature: _____ Date: _____ Phone: _____

Print Name: _____ Email Address: _____

Document 00472

BIDDER'S MWSBE GOAL DEVIATION REQUEST

Bidder or Proposer Name:_____

Project Name & Bid/Contract #:_____

	MBE	WBE	SBE	Total
Department Approved MWSBE Goals	%	%	%	%
Bidder's Proposed MWSBE Goals	%	%	%	%

Justification: Please provide the reason the Bidder is unable to meet the Contract Goal in Form 00800.

_____

_____

_____

Good Faith Efforts: Please list any efforts not listed in the Bidder's Good Faith Effort Report (Form 00471).

_____

_____

_____

_____

Date: _____ Bidder: _____

Email: _____ By: _____

Phone Number: _____ Title: _____

FOR OFFICIAL USE ONLY: Approved ☐ Not Approved ☐

OBO Representative Date: _____

_____ Title: _____

Document 00495

POST-BID PROCEDURES

1.0 DOCUMENT ADDRESSES

A. Notice of Intent to Award

B. Monitoring Authority/Contracting Department

C. Requirements of Bidder

D. Failure of Bidder to comply with requirements

E. Notice to Proceed

2.0 NOTICE OF INTENT TO AWARD

A. The City will provide written Notice of Intent to Award to Low Bidder.

3.0 DEFINITIONS

A. The "Monitoring Authority" or "OBO" for this Project is:

Director, Office of Business Opportunity Division
City of Houston
611 Walker Street, 7th Floor
Houston, Texas 77002

B. The "Contracting Department" for this Project is:
Director, Department of DEPARTMENT OF PUBLIC WORKS AND ENGINEERING
City of Houston
611 Walker Street
Houston, Texas 77002
ATTN: **Akhter Hussain, P.E.,**

4.0 REQUIREMENTS OF BIDDER

A. Within10 days of receipt of Notice of Intent to Award, Low Bidder shall execute and deliver to Akhter Hussain, P.E., Project Manager and Monitoring Authority, for the City's approval, documents indicated by an "X" below:
[ ] Document 00570 – Revised MWSBE Participation Plan *(Do not submit if OBO Director approved Bidder's Plan – Document 00470)*

[X] Executed Subcontract(s), Letter(s) of Intent, or documentation of good faith efforts to meet the MWSBE goals

B. Within 10 days of receipt of Notice of Intent to Award, Low Bidder shall execute and deliver to Akhter Hussain, P.E., Project Manager for the City's approval, documents indicated by an "X" below:

[ ] Document 00500 - Form of Business
[X] Document 00501 - Resolution of Contractor
[X] Document 00520 - Agreement
[X] Document 00600 - List of Proposed Subcontractors and Suppliers
[X] Document 00601 - Drug Policy Compliance Agreement
[X] Document 00602 - Contractor's Drug-free Workplace Policy *(Contractor creates this document.)*
[X] Document 00604 - History of OSHA Actions and List of On-the-job Injuries
[X] Document 00605 - List of Safety Impact Positions *(Contractor completes this list. Do not submit if submitting Document 00606.)*
[ ] Document 00606 - Contractor's Certification of No Safety Impact Positions *(Do not submit if submitting Document 00605.)*
[ ] Document 00607 - Certification Regarding Debarment, Suspension, and Other Responsibility Matters
[ ] Document 00608 - Contractor's Certification Regarding Non-segregated Facilities for Project Funded by AIP Grant
[X] Document 00610 - Performance Bond
[X] Document 00611 - Statutory Payment Bond
[X] Document 00612 - One-year Maintenance Bond
[ ] Document 00613 - One-year Surface Correction Bond
[X] Document 00620 - Affidavit of Insurance *(with Certificate of Insurance attached)*
[X] Document 00622 - Name and Qualifications of Proposed Superintendent *(Contractor creates this document.)*
[ ] Document 00623 - Contractor's Act of Assurance (SRF Form ED-103)
[X] Document 00624 - Affidavit of Compliance with S/WMBE Program
[ ] Document 00625 - SRF Participation Summary
[ ] Document 00626 - SRF Affirmative Steps Solicitation Report
[ ] Document 00627 - SRF Prime Contractor Affirmative Steps Certification and Goals
[ ] Document 00629 - Affidavit for FAA Form 7460-1
[X] Document 00630 - Certification of Compliance with Pay or Play Program
[X] Document 00631 - City of Houston Pay or Play Program – List of Subcontractors
[ ] Document 00809 – CDBG Requirements for Federally Funded Projects

C. Within 10 days of receipt of Notice of Intent to Award, Low Bidder shall execute the following forms and deliver them directly to the Monitoring Authority.

1. Original forms contained in Document 00805 – Equal Employment Opportunity Program Requirements:
   [X] Pages 00805-3 to 00805-5, Certification by Bidder Regarding Equal

Employment Opportunity

[X] Page 00805-6, Total Work Force Composition of the Company, or copy of latest EEO-1 form (required only if Contractor has a work force of 50 or more people and the Original Contract Price is $50,000 or more)

[X] Page 00805-7, Equal Employment Opportunity Compliance Program

[X] Page 00805-26, Certification by Proposed Subcontractor Regarding Equal Employment Opportunity

[X] Page 00805-29, Certification by Proposed Material Supplier, Lessor, and Professional Service Providers Regarding Equal Employment Opportunity

2. Original completed form Document 00633 - Certification by Proposed Material Suppliers, Lessors, and Professional Service Providers Regarding Equal Employment Opportunity, for each proposed material supplier and equipment supplier.

3. Original forms contained in Document 00820 – Wage Scale for Engineering Construction.

[X] *Certificate from Contractor Appointing Officer or Employee to Supervise Payment of Employees*

[ ] *Certificate from SubContractor Appointing Officer or Employee to Supervise Payment of Employees*

[ ] Document 00812, Exhibit "A" – Certificate from Contractor Appointing Officer or Employee to Supervise Payment of Employees

D. Designations of Subcontractors and Suppliers, who have been selected by Bidder in Document 00600 - List of Proposed Subcontractors and Suppliers, and accepted by the City, may be changed only with prior notice and acceptance by Project Manager as provided in Conditions of the Contract. For each Product Supplier subsequently added or substituted, provide an original completed form, Document 00633 - Certification by Proposed Material Suppliers, Lessors, and Professional Service Providers Regarding Equal Employment Opportunity, directly to the Monitoring Authority.

E. On Bidder's written request, Akhter Hussain, P.E., Project Manager may grant an extension of time, not to exceed 5 days, to furnish documents specified in Paragraphs 4.0.A and 4.0.B. If Bidder is required to resubmit documents specified in Paragraph 4.0.A or 4.0.B, Bidder shall do so within time limits provided in the request for resubmission.

F. Designations of Subcontractors and Suppliers, who have been selected by Bidder in its Participation Plan, and accepted by the City, may be changed only with prior notice and acceptance by the Monitoring Authority as provided in Document 00808 – Bidder/Contractor Requirements for the City of Houston Minority, Women, and Small Business Enterprise (MWSBE), and Persons with Disabilities Business Enterprise (PDBE).

5.0 FAILURE OF BIDDER TO COMPLY WITH REQUIREMENTS

A. Should Bidder, on receipt of Notice of Intent to Award, fail to comply with requirements of this Document 00495 within stated time, the City may declare award in default and require forfeiture of the Security Deposit.

B. After the City's written notice of default to Low Bidder, the City may award the Contract to Bidder whose offer is the next lowest bid, and Security Deposit of Bidder in default shall be forfeited to the City in accordance with provisions of Document 00200 - Instructions to Bidders.

6.0 NOTICE TO PROCEED

A. Upon the City's execution of the Agreement and delivery to Contractor, City Engineer will give Document 00551 - Notice to Proceed to Contractor, which establishes Date of Commencement of the Work.

END OF DOCUMENT

Document 00500

FORM OF BUSINESS

Please mark the box describing your firm's form of business, fill in the requested information, and include the relevant attachments.

[ ] **Corporation**
Corporate Name: _____
State of Incorporation: _____
Mailing Address: _____, _____
Type of Corporation: _____

Certificate of Assumed Name, if operating under a name different than that on the corporate charter (the Certificate must have been issued within the past 10 years to be valid)

*Certificate of Good Standing

*Certificate of Existence (if non-Texas corporation, Certificate of Authority)

[ ] **Partnership/Joint Venture**
Partnership/Joint Venture Name: _____
Mailing Address: _____, _____
Type of Partnership/Joint Venture: _____

Copy of the Partnership or Joint Venture Agreement, **or**
Affidavit with the name of the partnership or joint venture, the names of the individual partners or participants in the joint venture, and a statement that the partnership or joint venture is in existence

Certificate of Assumed Name, (the Certificate must have been issued within the past 10 years to be valid)

If firm is a limited partnership, the Certificate of Limited Partnership

If any partner or joint venturer is a corporation, the above information relating to corporation must be included as to each sum partner or joint venturer.

[ ] **Sole Proprietorship**

Name: _____
Mailing Address: _____

Certificate of Assumed Name, if operating under a name different than that of the sole proprietor (the Certificate must have been issued within the past 10 years to be valid)

** Must be furnished upon request of the Director and must be less than 90 days old.*

END OF DOCUMENT

****

Instructions:

Contractor must execute and deliver to the Project Manager a Resolution of Contractor for each individual authorized to sign Contract Documents related to this Contract. Contractor may rescind Resolutions of Contractor through a written document in similar form.

****

Document 00501

RESOLUTION OF CONTRACTOR

_____ ("Contractor"),
(Name of Contractor, e.g., "Biz. Inc.", "Biz LLP")

is a _____,
(Type of Organization, e.g.: Corporation, Limited Partnership, Limited Liability Partnership, Limited Liability Company, etc.)

which is bound by acts of _____,
(Name and Form of Governing Entity, e.g., "Biz Inc. Board of Directors", "Bill Smith, GP", etc.)

("Governing Entity").

On the _____ day of _____, 20___, the Governing Entity resolved, in accordance with all documents, rules, and laws applicable to the Contractor, that

_____, is authorized to act as the
(Contractor's Representative)

Contractor's Representative in all business transactions (initial one) ____ conducted in the State of Texas OR ____ related to this Contract; and

The Governing Entity warrants that the above resolution (a) was entered into without dissent or reservation by the Governing Entity, (b) has not been rescinded or amended, and (c) is now in full force and effect; and

In authentication of the adoption of this resolution, I subscribe my name on this day of _____, 20___.

_____ _____
(Authorized Signature for Governing Entity) (Print or Type Name and Title of Authorized Signatory)

SWORN AND SUBSCRIBED before me on _____
Date

_____
Notary Public in and for the State of Texas

My Commission Expires: _____ _____
Expiration Date Print or Type Name of Notary Public

Document 00520

AGREEMENT

Project: Lift Station Renewal/Replacement - Woodway #1 Lift Station Replacement

Project Location: 4750 Woodway Drive, Houston Texas(Key Map No. 491M, 491L)

Project No: WBS No. R-000267-109B-4

The City: THE CITY OF HOUSTON, 900 Bagby Street, Houston, Texas 77002 (the "City")

and

Contractor: _____

(Address for Written Notice) _____

_____

Fax Number: _____ **Phone Number:** _____

City Engineer, with respect to Sections 4.3 thru 4.5 of the General Conditions, is:

J. Timothy Lincoln, P.E. (or his successor)

P. O. Box 1562, Houston, Texas 77251-1562 (Address for Written Notice)

City Engineer, with respect to all other terms of the General Conditions, is:

Joseph T. Myers, P.E. (or his successor)

Fax Number: (832) 395-2410

THE CITY AND CONTRACTOR AGREE AS FOLLOWS:

ARTICLE 1
THE WORK OF THE CONTRACT

1.1 Contractor shall perform the Work in accordance with the Contract.

ARTICLE 2
CONTRACT TIME

2.1 Contractor shall achieve Date of Substantial Completion within **301** days after Date of Commencement of the Work, subject to adjustments of Contract Time as provided in the Contract.

2.2 The Parties recognize that time is of the essence for this Agreement and that the City will suffer financial loss if the Work is not completed within the Contract Time. Parties also recognize delays, expense, and difficulties involved in proving in a legal or arbitration proceeding actual loss suffered by the City if the Work is not completed on time. Accordingly, instead of requiring any such proof, the Parties agree that as liquidated damages for delay (but not as a penalty), Contractor shall pay the City the amount stipulated in Document 00800 – Supplementary Conditions, for each day beyond Contract Time.

ARTICLE 3
CONTRACT PRICE

3.1 Subject to terms of the Contract, the City will pay Contractor in current funds for Contractor's performance of the Contract, Contract Price of $ which includes Alternates, if any, accepted below.

3.2 The City accepts Alternates as follows:

****
Delete or add lines below to indicate all Alternates that were included in Request for competative sealed proposals. Remove brackets and instructions when done. Change color of remaining text to black.
****

Alternate No. 1 [*Accepted or Not Accepted*]
Alternate No. 2 [*Accepted or Not Accepted*]
Alternate No. 3 [*Accepted or Not Accepted*]
Alternate No. 4 [*Accepted or Not Accepted*]

ARTICLE 4
PAYMENTS

4.1 The City will make progress payments to Contractor as provided below and in Conditions of the Contract.

4.2 The Period covered by each progress payment is one calendar month ending on the [___] 15th or [___] last day of the month.

4.3 The City will issue Certificates for Payment and will make progress payments on the basis of such Certificates as provided in Conditions of the Contract.

4.4 Final payment, constituting entire unpaid balance of Contract Price, will be made by the City to Contractor as provided in Conditions of the Contract.

ARTICLE 5
CONTRACTOR REPRESENTATIONS

5.1 Contractor represents:

5.1.1 Contractor has examined and carefully studied Contract documents and other related data identified in Request For or Competitive Sealed Proposals or Competitive Sealed Bids.

5.1.2 Contractor has visited the site and become familiar with and is satisfied as to general, local, and site conditions that may affect cost, progress, and performance of the Work.

5.1.3 Contractor is familiar with and is satisfied as to all federal, state, and local laws and regulations that may affect cost, progress, and performance of the Work.

5.1.4 Contractor has carefully studied all: (1) reports of explorations and tests of subsurface conditions at or contiguous to the site and all drawings of physical conditions in or relating to existing surface or subsurface structures at or contiguous to the site (except Underground Facilities) which have been identified in Contract

documents and (2) reports and drawings of a hazardous environmental condition, if any, at the site which has been identified in Contract documents.

5.1.5 Contractor has obtained and carefully studied (or assumes responsibility for having done so) all additional or supplementary examinations, investigations, explorations, tests, studies, and data concerning conditions (surface, subsurface, and Underground Facilities) at or contiguous to the site which may affect cost, progress, or performance of the Work or which relate to any aspect of the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor, including applying specific means, methods, techniques, sequences, and procedures of construction, if any, expressly required by the Contract to be employed by Contractor, and safety precautions and programs incident thereto

5.1.6 Contractor does not consider that any further examinations, investigations, explorations, tests, studies, or data are necessary for performance of the Work at Contract Price, within Contract Time, and in accordance with the Contract.

5.1.7 Contractor is aware of general nature of work to be performed by the City and others at the site that relates to the Work as indicated in Contract documents.

5.1.8 Contractor has correlated information known to Contractor, information and observations obtained from visits to the site, reports and drawings identified in the Contract, and all additional examinations, investigations, explorations, tests, studies, and data with the Contract.

5.1.9 Contractor has given City Engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Contractor has discovered in the Contract, and written resolution thereof by City Engineer is acceptable to Contractor.

5.1.10 Contract documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance and furnishing of the Work.

ARTICLE 6
MISCELLANEOUS PROVISIONS

6.1 The Contract may be terminated by either Party as provided in Conditions of the Contract.

6.2 The Work may be suspended by the City as provided in Conditions of the Contract.

ARTICLE 7
ENUMERATION OF CONTRACT DOCUMENTS

7.1 The following documents are incorporated into this Agreement:

7.1.1 Document 00700 - General Conditions.

7.1.2 Document 00800 - Supplementary Conditions.

7.1.3 Division 01 - General Requirements.

7.1.4 Divisions 02 through 16 of Specifications.

7.1.5 Drawings listed in Document 00015 - List of Drawings. Drawing No. _____and bound separately.

7.1.6 Addenda [and Riders] which apply to the Contract, are as follows:

Addendum No. 1, dated None

Addendum No. 2, dated None

Addendum No. 3, dated None

Rider No. [___], dated None

7.1.7 Other documents:

	Document No.	Title
[X]	00410B	Bid Form – Part B
[X]	00470	Standard Pre-Bid Participation Plan Document
[ ]	00471	Pre-Bid Good Faith Efforts Report
[ ]	00472	Goal Deviation Request
[ ]	00500	Form of Business
[X]	00501	Resolution of Contractor (if a corporation)
[ ]	00570	Amended S/MWBE Participation Plan
[ ]	00571	Contractor's Good Faith Efforts Report
[ ]	00572	Plan Deviation Request
[ ]	00608	Contractor's Certification Regarding Non-Segregated Facilities for Project Funded by AIP Grant
[X]	00610	Performance Bond
[X]	00611	Statutory Payment Bond
[X]	00612	One-year Maintenance Bond
[ ]	00613	One-year Surface Correction Bond
[X]	00620	Affidavit of Insurance (with the Certificate of Insurance attached)
[ ]	00623	Contractor's Act of Assurance (SRF Form ED-103)
[X]	00624	Affidavit of Compliance with Affirmative Action Program
[ ]	00628	Affidavit of Compliance with Disadvantaged Business Enterprise (DBE) Program for Project Funded By AIP Grant
[X]	00630	(POP-2) Certification of Compliance with Pay or Play Program
[X]	00631	(POP-3) City of Houston Pay or Play Program – List of Subcontractors
[X]	00800	Supplementary Conditions for Project CIP or AIP Funded
[ ]	00801	Supplementary Conditions for Project AIP Funded
[ ]	00802	SRF Supplementary Conditions
[X]	00805	Equal Employment Opportunity Program Requirements
[ ]	00806	EPA DBE and Wage Rate Requirements (SRF only)
[ ]	00807	Bidder/Contractor Requirements for DBE Program
[X]	00808	Minority and Women-owned Business Enterprise (MWBE) & Persons with Disabilities Business Enterprise (PDBE) Program
[ ]	00810	Federal Wage Rate - Highway
[ ]	00811	Federal Wage Rate - Building
[ ]	00812	Federal Wage Rate - Heavy
[X]	00820	Wage Rate for Engineering Construction
[ ]	00821	Wage Rate for Building Construction
[X]	00830	Trench Safety Geotechnical Information
[X]	00840	Pay or Play Program
[ ]	00912	Rider

ARTICLE 8
SIGNATURES

8.1 This Agreement is executed in two original copies and is effective as of the date of countersignature by City Controller.

CONTRACTOR:

By: _____
Name: _____
Title: _____
Date: _____
Tax Identification Number: _____

(If Joint Venture)

By: _____
Name: _____
Title: _____
Date: _____
Tax Identification Number: _____

CITY OF HOUSTON, TEXAS

APPROVED:

By: _____
Director,
Department of Public Works and Engineering

SIGNED:

By: _____
Mayor

COUNTERSIGNED:

By: _____
City Controller

Date Countersigned:

ATTEST/SEAL:

By: _____
City Secretary

8.2 This Contract and Ordinance have been reviewed as to form by the undersigned legal assistant and have been found to meet established Legal Department criteria. Legal Department has not reviewed the content of these documents.

_____ _____
Legal Assistant Date

END OF DOCUMENT

Document 00570

CONTRACTOR'S REVISED MWSBE PARTICIPATION PLAN

As soon as the Contractor becomes aware that the Contractor may not abide by the most current approved Plan, the Contractor shall submit this completed form with a Record of Post-Bid Good Faith Efforts (Document 00571), a Request for Plan Deviation (Document 00572), and any other document evidencing "Good Faith Efforts", as required by the Good Faith Efforts Policy (Document 00808). The City will review this Revised Participation Plan and may approve this Revised Plan if the Contractor has made Good Faith Efforts. For more information, visit http://www.houstontx.gov/obo.

Original Participation Plan Percentage	MBE	WBE	SBE	Revised Participation Plan Percentage	MBE	WBE	SBE

NAICS Code (6 digit)	Description of Work (Plan Sheet #, Unit Price #, Scope of Work #, as applicable)	% of Total Bid Price (2 decimal places)	Cert. Type for Goal (MBE, WBE, SBE)	Certified Firm Name Firm Address Contact Name Phone No. and E-Mail (if available)

Signature for Company: _____* Date: _____
Print Name: _____ Phone: _____

*I understand that supplying inaccurate information may violate Texas Penal Code Section 37.10 and lead to City sanctions.

Document 00570

CONTINUATION PAGE

NAICS Code (6 digit)	Plan Item Number (if applicable)/ Description of Work	% of Total Bid Price (2 decimal places)	Cert. Type for Goal (MBE, WBE, SBE)	Certified Firm Name Firm Address Contact Name Phone No. and E-Mail (if available)

Signature for Company: _____* Date: _____
Print Name: _____ Phone: _____

understand that supplying inaccurate information may violate Texas Penal Code Section 37.10 and lead to City sanctions.

Document 00571

RECORD OF POST-AWARD GOOD FAITH EFFORTS

Contractor Name: _____ **Project Name:** _____

A Contractor that may be unable to follow an agreed Participation Plan (Document 00470 or 00570) must submit this completed form, a Plan Deviation Request Form (Document 00572), and any other documentation of "Good Faith Efforts" (see Document 00808) that the OBO Representative may require. The Contractor shall submit one completed Document 00571 (Part A) for each Certified Firm that is no longer performing part or all of its work duties under the Approved Plan. The Contractor has the burden to demonstrate "Good Faith Efforts" to meet the MWSBE goal, which includes correctly and accurately preparing and submitting this form and other efforts described in the Good Faith Efforts Policy (Document 00808). The Office of Business Opportunity may review Participation Plan and Good Faith Efforts from time to time and may request that the Contractor submit this form and other information.

UNLESS THE CONTRACTOR MEETS THE GOALS IN THE AGREED PARTICIPATION PLAN, FAILURE TO SUBMIT THIS FORM MAY RESULT IN A DEFAULT OF THE CONTRACT.

PART A (REASON FOR NON-USE OF CERTIFIED FIRM IN AGREED PLAN)

NAICS Code	Plan Item No.	MWSBE Type for Goal	Certified Firm Name, Address, Phone No. and E-mail	Plan Goal & Actual Use (in % of total)	Method of Contact	Reason for Non-Use (why the Contractor was not able to use the Certified Firm in accordance with the Agreed Plan)
				Plan %: ____ Actual %: ____	Phone € E-mail € Fax €	

PART B (REASON FOR NONUSE OF REPLACEMENT CERTIFIED FIRMS—IF APPLICABLE)

NAICS Code	Plan Item No.	MWSBE Type for Goal	Certified Firm Name Address, Phone No. and E-Mail	Certified Firm Contact Person	Method of Contact	Prime Contact Date	Certified Firm Response	Results of Contact (why Certified Firm was unsuitable or unusable)
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			

Authorized Signature: _____ Date: _____ Phone: _____

Print Name: _____ Email Address: _____

RECORD OF POST-AWARD GOOD FAITH EFFORTS

Document 00571

PART B CONTINUATION (REASON FOR NONUSE OF REPLACEMENT CERTIFIED FIRMS)

NAICS Code	Plan Item No.	MWSBE Type for Goal	Certified Firm Name Address, Phone No. and E-Mail	Certified Firm Contact Person	Method of Contact	Prime Contact Date	Certified Firm Response	Results of Contact (why Certified Firm was unsuitable or unusable)
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			
					Phone € E-mail € Fax €			

Authorized Signature: _____ Date: _____ Phone: _____

Print Name: _____ Email Address: _____

Document 00572

CONTRACTOR'S REQUEST FOR PLAN DEVIATION

Contractor Name:_____

Project Name:_____

	MBE	WBE	SBE	Total
Approved Participation Plan Percentages	%	%	%	%

	MBE	WBE	SBE	Total
Contractor's Requested Participation Plan	%	%	%	%

Justification: Please provide the reason the Contractor is unable to meet the MWSBE goal in the Approved Plan.

_____

_____

_____

Good Faith Efforts: Please list any efforts not listed in Contractor's Record of Good Faith Effort (Document 00571).

_____

_____

_____

_____

Please attach additional pages if the space for Justification or Good Faith Efforts is insufficient.

Date:_____ *Contractor:_____

E-mail: _____ *By:_____

Phone Number: _____ Title:_____

*I understand that the approval of this deviation request does not constitute a final decision by OBO that Contractor has used Good Faith Efforts in meeting the Contracting Goal.

FOR OFFICIAL USE ONLY: Approved ☐ Not Approved ☐

OBO Representative Date:_____

_____ Title: _____

Document 00600

LIST OF PROPOSED SUBCONTRACTORS AND SUPPLIERS

PROJECT NAME: Lift Station Renewal/Replacement - Woodway #1 Lift Station Replacement
TOTAL DBE AWARD: $ _____
ORIG. CONTRACT PRICE: $_____ TOTAL MWSBE AWARD: $ _____
PROJECT NO.: WBS No. R-000267-109B-4 TOTAL HUB AWARD: $ _____
DATE OF REPORT: _____ TOTAL PDBE AWARD: $ _____

NAICS (6 digits)	**SUBCONTRACTOR OR SUPPLIER (INCLUDE "MWSBE", "PDBE", "DBE", OR "HUB" DESIGNATION)[2]**	**ADDRESS**	**SCOPE OF WORK[3]**

NOTES:
1. RETURN FOR ALL PROJECTS AS REQUIRED IN DOCUMENT 00800 – SUPPLEMENTARY CONDITIONS. RETURN WITHIN THE SPECIFIED NUMBER OF DAYS AFTER RECEIPT OF NOTICE OF INTENT TO AWARD
2. DESIGNATE FIRMS CERTIFIED BY THE CITY OFFICE OF BUSINESS OPPORTUNITY ON THIS FORM.
3. DESCRIBE THE WORK TO BE PERFORMED, FOR WHICH THE FIRM IS CERTIFIED, SUCH AS "PAVING", "ELECTRICAL", ETC.
4. **CONTRACTOR SHALL EXECUTE CONTRACTS WITH APPROVED SUBCONTRACTORS AND SUPPLIERS WITHIN 30 DAYS AFTER THE DATE OF THE NOTICE TO PROCEED. COPIES OF CONTRACTS WITH DESIGNNATED FIRMS MUST BE SENT TO THE OFFICE OF BUSINESS OPPORTUNITY.**

SIGNATURE: _____ COMPANY NAME: _____

NAME: _____ TITLE: _____
(Type or Print)

LIST OF PROPOSED SUBCONTRACTORS AND SUPPLIERS

Document 00600

Continuation Page

PROJECT NAME: Lift Station Renewal/Replacement - Woodway #1 Lift Station Replacement
DATE OF REPORT: _____
PROJECT NO.: WBS No. R-000267-109B-4

NAICS (6 digits)	SUBCONTRACTOR OR SUPPLIER (INCLUDE "MWSBE", "PDBE", "DBE", OR "HUB" DESIGNATION)[2]	ADDRESS	SCOPE OF WORK[3]

SIGNATURE: _____ COMPANY NAME: _____

NAME: _____ TITLE: _____
(Type or Print)

END OF DOCUMENT

Document 00601

DRUG POLICY COMPLIANCE AGREEMENT

I, _____ _____
Name Title

of _____
Contractor

have authority to bind Contractor with respect to its Bid, Proposal, or performance of any and all contracts it may enter into with the City of Houston; and that by making this Agreement, I affirm that Contractor is aware of and by the time the Contract is awarded will be bound by and agree to designate appropriate safety impact positions for company employee positions, and to comply with the following requirements before the City issues a Notice to Proceed:

1. Develop and implement a written Drug Free Workplace Policy and related drug testing procedures for Contractor that meet the criteria and requirements established by the Mayor's Amended Policy on Drug Detection and Deterrence (Mayor's Drug Policy) and the Mayor's Drug Detection and Deterrence Procedures for Contractors (Executive Order No. 1-31).

2. Obtain a facility to collect urine samples consistent with Health and Human Services (HHS) guidelines and an HHS-certified drug-testing laboratory to perform drug tests.

3. Monitor and keep records of drug tests given and results; and upon request from the City of Houston, provide confirmation of such testing and results.

4. Submit semi-annual Drug Policy Compliance Declarations.

I affirm on behalf of Contractor that full compliance with the Mayor's Drug Policy and Executive Order No. 1-31 is a material condition of the Contract with the City of Houston,

I further acknowledge that falsification, failure to comply with or failure to timely submit declarations or documentation in compliance with the Mayor's Drug Policy or Executive Order No. 1-31 will be considered a breach of the Contract with the City and may result in non-award or termination of the Contract by the City.

_____ _____
Contractor Title

_____ _____
Signature Date

END OF DOCUMENT

Document 00604

HISTORY OF OSHA ACTIONS AND LIST OF ON-THE-JOB INJURIES

Prior to award of the Contract, Low Bidder will be required to file the following with the City:

1. A history of all OSHA actions, advisories, etc., Contractor has received on all jobs worked in any capacity, prime or subcontractor. The history shall be for the two-year period preceding the Bid Date of the Project.

2. A list of all on-the-job injuries, accidents, and fatalities suffered by any present or former employees of Contractor during the same two-year period.

3. If less than the two-year period, give the date Contractor started doing business.

This information must be submitted to the City within the time period stated in Document 00498 - Notice of Intent to Award. An officer of the company must certify in a notarized statement that the information submitted is true and correct.

END OF DOCUMENT

Document 00605

LIST OF SAFETY IMPACT POSITIONS

****

Contractor is to provide a complete List of Employee Classifications that are considered in a "Safety Impact Position" and the number of employees in each of those classifications.

****

Employee Classification	**Number of Employees**

END OF DOCUMENT

Document 00606

CONTRACTOR'S CERTIFICATION OF NO SAFETY IMPACT POSITIONS IN PERFORMANCE OF A CITY CONTRACT

BEFORE ME, the undersigned authority, on this day personally appeared

_____,
Affiant

who being by me duly sworn on his oath stated that he is _____
Title

of _____
Contractor

and that no employee safety impact positions, as defined in §5.17 of Executive Order No. 1-31, will be involved in performing _____.
Project

Contractor agrees and covenants that it shall immediately notify the City of Houston Director of Personnel if any safety impact positions are established to provide services in performing this City Contract.

_____
Affiant's Signature

SWORN AND SUBSCRIBED before me on this day of _____, 20___.

_____
Notary Public in and for the State of TEXAS

_____
Print or Type Notary Public Name

My Commission Expires: _____
Expiration Date

END OF DOCUMENT

Document 00607

CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS

Contractor certifies to the best of its knowledge and belief that it and its principals:

1. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal, State, or local department or agency;

2. Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State, or local) transaction or contract under a public transaction: violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

3. Are not presently indicted for or otherwise criminally or civilly charged by a government entity (Federal, State, or local) with commission of any of the offenses enumerated in paragraph 2 of this certification; and

4. Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State, or local) terminated for cause or default.

I understand that a false statement on this certification may be grounds for rejection of this proposal or termination of the award. In addition, under 18 USC Section 1001, a false statement may result in a fine of up to $10,000 or imprisonment for up to five years, or both.

Company:

_____
Typed Name & Title of Authorized Representative

_____ _____
Signature of Authorized Representative Date

☐ I am unable to certify the above statements. My explanation is attached.

END OF DOCUMENT

Document 00610

PERFORMANCE BOND

THAT WE, _____, as Principal, (the "Contractor"), and the other subscriber hereto, _____, as Surety, do hereby acknowledge ourselves to be held and firmly bound to the City of Houston (the "City"), a municipal corporation, in the penal sum of $_____ for the payment of which sum, well and truly to be made to the City, its successors and assigns, Contractor and Surety do bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally.

THE CONDITIONS OF THIS OBLIGATION ARE SUCH THAT:

WHEREAS, the Contractor has on or about this day executed a Contract in writing with the City for _____

_____,

all of such work to be done as set out in full in said Contract documents therein referred to and adopted by the City Council, all of which are made a part of this instrument as fully and completely as if set out in full herein.

NOW THEREFORE, if the said Contractor shall faithfully and strictly perform the Contract in all its terms, provisions, and stipulations in accordance with its true meaning and effect, and in accordance with the Contract documents referred to therein and shall comply strictly with each and every provision of the Contract and with this Bond, then this obligation shall become null and void and shall have no further force and effect; otherwise the same is to remain in full force and effect. Should the Contractor fail to faithfully and strictly perform the Contract in all its terms, including but not limited to the indemnifications thereunder, the Surety shall be liable for all damages, losses, expenses and liabilities that the City may suffer in consequence thereof, as more fully set forth herein.

It is further understood and agreed that the Surety does hereby relieve the City or its representatives from the exercise of any diligence whatever in securing compliance on the part of the Contractor with the terms of the Contract, and the Surety agrees that it shall be bound to take notice of and shall be held to have knowledge of all acts or omissions of the Contractor in all matters pertaining to the Contract. The Surety understands and agrees that the provision in the Contract that the City will retain certain amounts due the Contractor until the expiration of 30 days from the acceptance of the Work is intended for the City's benefit, and the City will have the right to pay or withhold such retained amounts or any other amount owing under the Contract without changing or affecting the liability of the Surety hereon in any degree.

It is further expressly agreed by Surety that the City or its representatives are at liberty at any time, without notice to the Surety, to make any change in the Contract documents and in the Work to be done thereunder, as provided in the Contract, and in the terms and conditions thereof, or to make any change in, addition to, or deduction from the Work to be done thereunder; and that such changes, if made, shall not in any way vitiate the obligation in this Bond and undertaking or release the Surety therefrom.

It is further expressly agreed and understood that the Contractor and Surety will fully indemnify and save harmless the City from any liability, loss, cost, expense, or damage arising out of Contractor's performance of the Contract.

If the City gives Surety notice of Contractor's default, Surety shall, within 45 days, take one of the following actions:

1. Arrange for Contractor, with consent of the City, to perform and complete the Contract; or

2. Take over and assume completion of the Contract itself, through its agents or through independent contractors, and become entitled to the payment of the balance of the Contract Price.

If the Surety fails to take either of the actions set out above, it shall be deemed to have waived its right to perform and complete the Contract and receive payment of the balance of the Contract Price and the City shall be entitled to enforce any remedies available at law, including but not limited to completing the Contract itself and recovering any cost in excess of the Original Contract Price from the Surety.

This Bond and all obligations created hereunder shall be performable in Harris County, Texas. This Bond is given in compliance with the provisions of Chapter 2253, Texas Government Code, as amended, which is incorporated herein by this reference.

Notices required or permitted hereunder shall be in writing and shall be deemed delivered when actually received or, if earlier, on the third day following deposit in a United States Postal Service post office or receptacle, with proper postage affixed (certified mail, return receipt requested), addressed to the respective other Party at the address prescribed in the Contract documents, or at such other address as the receiving party may hereafter prescribe by written notice to the sending party.

IN WITNESS THEREOF, the said Contractor and Surety have signed and sealed this instrument on the respective dates written below their signatures and have attached current Power of Attorney.

ATTEST, SEAL: (if a corporation)
WITNESS: (if not a corporation)

_____
Name of Contractor

By: _____
Name:
Title:

By: _____
Name:
Title:
Date:

ATTEST/SURETY WITNESS:

(SEAL)

_____
Full Name of Surety

_____
Address of Surety for Notice

_____

_____
Telephone Number of Surety

By: _____
Name:
Title:
Date:

By: _____
Name:
Title: Attorney-in-Fact
Date:

This Ordinance or Contract has been reviewed as to form by the undersigned legal assistant and have been found to meet established Legal Department criteria. The Legal Department has not reviewed the content of these documents.

_____
Legal Assistant

_____
Date

END OF DOCUMENT

Document 00611

STATUTORY PAYMENT BOND

THAT WE, _____, as Principal, hereinafter called Contractor and the other subscriber hereto, _____, as Surety, do hereby acknowledge ourselves to be held and firmly bound unto the City of Houston, a municipal corporation, in the sum of $_____ for the payment of which sum, well and truly to be made to the City of Houston, and its successors, the said Contractor and Surety do bind themselves, their heirs, executors, administrators, successors, jointly and severally.

THE CONDITIONS OF THIS OBLIGATION ARE SUCH THAT:

WHEREAS, the Contractor has on or about this day executed a contract in writing with the City of Houston for _____

_____,

all of such work to be done as set out in full in said Contract documents therein referred to and adopted by the City Council, all of which are made a part of this instrument as fully and completely as if set out in full herein;

NOW, THEREFORE, if the said Contractor shall pay all claimants supplying labor and materials to him or a Subcontractor in the prosecution of the Work provided for in the Contract, then, this obligation shall be void; otherwise the same is to remain in full force and effect;

PROVIDED HOWEVER, that this Bond is executed pursuant to the provisions of Chapter 2253, Texas Government Code, as amended, and all liabilities on this Bond shall be determined in accordance with the provisions of said Article to the same extent as if it were copied at length herein.

IN WITNESS THEREOF, the said Contractor and Surety have signed and sealed this instrument on the respective dates written below their signatures and have attached current Power of Attorney.

ATTEST, SEAL: (if a corporation)
WITNESS: (if not a corporation)

_____
Name of Contractor

By: _____
Name:
Title:

By: _____
Name:
Title:
Date:

ATTEST/SURETY WITNESS:

(SEAL)

_____
Full Name of Surety

_____
Address of Surety for Notice

_____

_____
Telephone Number of Surety

By: _____
Name:
Title:
Date:

By: _____
Name:
Title: Attorney-in-Fact
Date:

This Ordinance or Contract has been reviewed as to form by the undersigned legal assistant and have been found to meet established Legal Department criteria. The Legal Department has not reviewed the content of these documents.

_____ _____
Legal Assistant Date

END OF DOCUMENT

Document 00612

ONE-YEAR MAINTENANCE BOND

THAT WE, _____, as Principal, hereinafter called Contractor, and the other subscriber hereto, _____, as Surety, do hereby acknowledge ourselves to be held and firmly bound to the City of Houston, a municipal corporation, in the sum of $_____, for the payment of which sum well and truly to be made to the City of Houston and its successors, the said Contractor and Surety do bind themselves, their heirs, executors, administrators, successors, jointly and severally.

THE CONDITIONS OF THIS OBLIGATION ARE SUCH THAT:

WHEREAS, the Contractor has on or about this day executed a Contract in writing with the City of Houston for _____

_____,

all of such work to be done as set out in full in said Contract documents therein referred to and adopted by the City Council, all of which are made a part of this instrument as fully and completely as if set out in full herein.

NOW THEREFORE, if the said Contractor shall comply with the provisions of Paragraph 11.5.1 of the General Conditions, and correct work not in accordance with the Contract documents discovered within the established one-year period, then this obligation shall become null and void, and shall be of no further force and effect; otherwise, the same is to remain in full force and effect.

Notices required or permitted hereunder shall be in writing and shall be deemed delivered when actually received or, if earlier, on the third day following deposit in a United States Postal Service post office or receptacle, with proper postage affixed (certified mail, return receipt requested), addressed to the respective other party at the address prescribed in the Contract documents, or at such other address as the receiving party may hereafter prescribe by written notice to the sending party.

IN WITNESS THEREOF, the said Contractor and Surety have signed and sealed this instrument on the respective dates written below their signatures and have attached current Power of Attorney.

ATTEST, SEAL: (if a corporation)
WITNESS: (if not a corporation)

_____
Name of Contractor

By: _____
Name:
Title:

By: _____
Name:
Title:
Date:

ATTEST/SURETY WITNESS:

(SEAL)

_____
Full Name of Surety

_____
Address of Surety for Notice

_____

_____
Telephone Number of Surety

By: _____
Name:
Title:
Date:

By: _____
Name:
Title: Attorney-in-Fact
Date:

This Ordinance or Contract has been reviewed as to form by the undersigned legal assistant and have been found to meet established Legal Department criteria. The Legal Department has not reviewed the content of these documents.

_____
Legal Assistant

_____
Date

END OF DOCUMENT

Document 00620

AFFIDAVIT OF INSURANCE

BEFORE ME, the undersigned authority, on this day personally appeared

_____, who
Affiant

being by me duly sworn on his oath stated that he is _____, of
Title

_____,
Contractor's Company Name

the Contractor named and referred to within the Contract documents; that he is fully competent and authorized to give this affidavit and that the attached original insurance certificate truly and accurately reflects the insurance coverage that is now available and will be available during the term of the Contract.

_____
Affiant's Signature

SWORN AND SUBSCRIBED before me on _____.
Date

_____
Notary Public in and for the State of TEXAS

_____
Print or type Notary Public name

My Commission Expires: _____
Expiration Date

END OF DOCUMENT

Document 00624

AFFIDAVIT OF COMPLIANCE WITH AFFIRMATIVE ACTION PROGRAM

BEFORE ME, the undersigned authority, on this day personally appeared _____, who
Affiant

being by me duly sworn on his oath stated that he is _____,
Title

of _____,
Contractor

the Contractor named and referred to within the Contract documents; that he is fully competent and authorized to give this affidavit and that the Contract is in compliance with the Affirmative Action Program of the City and has done all that is required by the Contract documents, the Affirmative Action Program, and pursuant to Chapter 15, Code of Ordinances, City of Houston, §15.16 et seq.

_____
Affiant's Signature

SWORN AND SUBSCRIBED before me on this day of _____, 20__.

_____
Notary Public in and for the State of TEXAS

_____
Print or Type Notary Public Name

My Commission Expires: _____
Expiratio

END OF DOCUMENT

Document 00630
(POP-2)
City of Houston
Certification of Compliance with
Pay or Play Program

Contractor Name: _____ $ _____
(Contractor/Subcontractor) *(Amount of Contract)*

Contractor Address: _____

Project No.: «WBSNo» _____

Project Name: «LegalPrjName» _____

POP Liaison Name: _____

In accordance with the City of Houston Pay or Play Program authorized by Ordinance 2007-534 and Executive Order 1-7, Contractor/Subcontractor agrees to abide by the terms of this Program. This certification is required of all contractors for contracts subject to the program. You must agree EITHER to PAY or to PLAY for all covered employees. The Contractor/Subcontractor may also Pay on behalf of some covered employees and Play on behalf of other covered employees.

The Contractor/Subcontractor will comply with all provisions of the Pay or Play Program and will furnish all information and reports requested to determine compliance with program requirements of the Pay or Play Program (See Executive Order 1-7 for the terms of the Pay or Play program) The criteria of the program is as follows:

The Contractor/Subcontractor agrees to **"Pay"** $1.00 per hour for work performed by covered employees under the contract with the City. If independent contract labor is utilized the Contractor/Subcontractor agrees to report hours worked by the independent contract laborer and pay $1.00 per hour for work performed.

Otherwise the Contractor/Subcontractor agrees to **"Play"** by providing health benefits to each covered employee. The health benefits must meet the following criteria:

1. The employer will contribute no less than $150 per employee per month toward the total premium cost for single coverage only; and
2. The employee contribution, if any amount, will be no greater than 50% of the total premium cost and no more than $150 per month.
3. Pursuant to E.O. 1-7 section 4.04 a contractor is deemed to have complied with respect to a covered employee who is not provided health benefits if the employee refuses the benefits and the employee's contribution to the premium is no more than $40 per month.

Please select whether you choose to:	Pay	Play	Both

The Contractor/Subcontractor will file compliance reports with the City, which will include activity for covered employees subject to the program, in the form and to the extent requested by the administering department. Compliance reports shall contain information including, but not limited to, documentation showing employee health coverage and employee work records.
Note: The Contractor is responsible to the City for the compliance of covered employees of covered subcontractors and only forms that are accurate and complete will be accepted.

*Estimated Number of:	Prime Contractor	Sub-Contractor
Total Employees on City Job		
Covered Employees		
Non-Covered Employees		
Exempt Employees		

***Required**

I hereby certify that the above information is true and correct.

_____ _____
Contractor ***(Signature)*** Date

_____
Name and Title ***(Print or type)***

Document 00631
(POP-3)
City of Houston
Pay or Play Program
List of Subcontractors

Prime Contractor: _____
Project Number/Description: _____
_____

POP Contact Person: _____
Address: _____
_____
Email: _____
Phone: _____

Note: Include ALL subcontractors (use additional form if necessary)

Subcontractor Name	Supplier Y/N?	Amount of Subcontract	Check One: Pay	Play	Both (Pay and Play)	N/A	Contact Person	Phone	Email Address	Mailing Address

*If the above information is found to be submitted fraudulently with the intent to bypass or deceive the purpose of the Pay or Play Program the contractor will be held liable for all compliance requirements from the inception of the contract. All subcontracts that surpass the $200,000.00 threshold will be responsible for Pay or Play compliance from the inception of the contract.

Affidavit

I hereby solemnly affirm, certify and confirm that the total sub-contract value stated above is the final value of the contract (*) including all material costs, fuel, payroll, taxes, fees, profit sharing, labor or any payments in relation to the contracted work and no separate payment or contract has been made for the sub-contract under contract no._____. The above sub-contract value includes all the costs related to work under the contract. The contractor and sub-contractor(s) agree to inform The Mayor's Office of Business Opportunity of any related cost(s) added to the contracted work and re-submit POP-3 with the current value of the sub-contract. I understand that compliance with "Pay or Play" program is mandatory and nothing has been hidden to circumvent the program requirements.

_____
Contractor Authorized Representative & Title Date
Name & Signature

EQUAL EMPLOYMENT OPPORTUNITY CERTIFICATION BY MATERIAL SUPPLIERS

Document 00633

CERTIFICATION BY PROPOSED MATERIAL SUPPLIERS,
LESSORS, AND PROFESSIONAL SERVICE PROVIDERS
REGARDING EQUAL EMPLOYMENT OPPORTUNITY

Company Name: _____ $_____
(Supplier, Lessor, Professional Service Provider) (Amount of Contract)

Company Address: _____

Company Telephone Number:_____ Fax:_____

E-mail Address: _____

Web Page/URL Address:_____

Company Tax Identification Number: _____

Project No.: [*WBS/CIP/AIP/File No.*] _____

Project Name: [*Legal Project Name*] _____

In accordance with the City of Houston Ordinance 78-1538, Supplier/Lessor/Professional Service Provider represents to be an equal opportunity employer and agrees to abide by the terms of the Ordinance. This certification is required of all Suppliers/Lessors/Professional Service Providers (herein Supplier) with contracts in the amount of $10,000.00 or more.

[ ] Yes [ ] No Supplier agrees not to discriminate against any employee or applicant for employment because of race, religion, color, sex, national origin, or age.

[ ] Yes [ ] No Supplier agrees that all qualified applicants will receive consideration for employment without regard to race, religion, color, sex, national origin, or age.

[ ] Yes [ ] No Supplier will comply with all provisions of Executive Order No. 11246 and rules, regulations and applicable orders of the Department of Labor or other Federal Agency responsible for enforcement of applicable equal opportunity and affirmative action provisions and will likewise furnish all information and reports required by the Mayor or Contract Compliance Officers for the purpose of investigation to ascertain and effect compliance with the City of Houston's Office of Affirmative Action and Contract Compliance.

[ ] Yes [ ] No The Supplier shall file and cause their sub-tier contractors to file compliance reports with the City in the form and to the extent as may be prescribed by the Mayor or Contract Compliance Officers. Compliance reports filed at such times as directed shall contain information including, but not limited to, the practices, policies, programs, and employment policies.

I hereby certify that the above information is true and correct.

_____ _____
COMPANY OFFICER (Signature) DATE

_____
NAME AND TITLE (Print or type)

END OF DOCUMENT

CITY OF HOUSTON
STANDARD DOCUMENT

MONTHLY SUBCONTRACTOR PAYMENT REPORTING FORM

****

Instructions:

Before submitting this document, Contractor shall provide

1. *Payment Notifications (00646) to each subcontractor on each contract;*
2. *A copy to the City Monitoring Authority of all applicable Payment Notifications;*
3. *A list to the City Monitoring Authority containing the information requested in this document for each subcontractor from which Contractor has withheld payment; and*
4. *The notarized signature of Contractor's Representative.*

****

Document 00642

MONTHLY SUBCONTRACTOR PAYMENT REPORTING FORM

Legal Project Name:_____

Outline Agreement No.:_____ WBS No.:_____

Contractor's Company Name: _____

Address: _____

CERTIFICATION

_____, Contractor's Representative for the above referenced Contract, hereby certifies that (1) Contractor has paid all subcontractors, except those noted below, (2) Contractor made such payments (a) in proportion to the amount City paid Contractor and (b) in accordance and compliance with all applicable Contract Documents and laws; and (3) Contractor withheld no sums from any subcontractor for allegations of deficiency in Work. The term "subcontractor", as used herein, includes all persons or firms furnishing work, materials, services or equipment Contractor ordered incorporated into Work or placed near the Project for which the City made partial payment.

EXCEPTION: Contractor sent Payment Notifications to the following subcontractors explaining why Contractor withheld payment. Copies are attached.

Subcontractor Name:_____	Subcontractor Name: _____
Street Address:_____	Street Address: _____
City, State, and Zip Code: _____	City, State, and Zip Code: _____
Amount of Payment Withheld:_____	Amount of Payment Withheld: _____
Date Payment First Withheld: _____	Date Payment First Withheld: _____
Description of Good Faith Reason:_____	Description of Good Faith Reason:_____
_____	_____

_____ _____
(Signature of Contractor's Representative) (Print or Type Name of Contractor's Representative)

SWORN TO AND SUBSCRIBED before me on: _____
Date

_____
Notary Public in and for the State of Texas

My Commission Expires: _____ _____
Expiration Date Print or Type Name of Notary Public

****

Instructions:

If Contractor withholds any amount of a payment to a Subcontractor for any reason, the Contractor shall send Payment Notifications to the Subcontractor explaining why the payment was withheld.

Contractor shall provide the City Monitoring Authority with Payment Notifications for each subcontractor from which Contractor has withheld payment. Contractor shall submit all necessary Payment Notifications (Document 00646), Payment Reporting Forms (Document 00642), and other documentation at the same time Contractor submits the Application and Certification for Payment or the Estimate for Payment.

****

Document 00646

PAYMENT NOTIFICATION – EXPLANATION OF WITHHOLDING

Legal Project Name:_____

Outline Agreement No.:_____ WBS No.:_____

Contractor's Company Name: _____

Address: _____

Date: _____

SUBCONTRACTOR PAYMENT INFORMATION:

Subcontractor Name:_____

Street Address: _____

City, State, and Zip Code: _____

Business Phone Number: _____

Amount of Subcontractor Invoice: _____

Amount of Payment Made: _____

Amount of Payment Withheld:_____

Date Payment First Withheld: _____

DETAILED EXPLANATION OF WITHHOLDING: _____

_____

_____

_____

_____

_____ _____

(Signature of Contractor's Representative) (Print or Type Name of Contractor's Representative)

****

List of Changes:

02-04-2005: Added new Paragraph 3.25.1.3 concerning strict liability. Edited Paragraph 3.25.1.1 accordingly. Edited Paragraph 9.6.1.4 to remove the words "retainage of".

08-15-2006: Revised many references to Section(s) to read Paragraph(s). Added Small Business Enterprise (SBE) requirement to Paragraphs 3.5.3, 3.5.3.1, 3.5.3.2 and 3.5.3.3.

08-17-2006: Added new Paragraphs 5.2.4, 5.2.5, 9.2.1 and 9.4.2 concerning prompt payment provisions.

10-10-2006: Added new Paragraphs 9.7.1.8, 9.7.1.9 concerning prompt payment provisions. Changed 9.8.1 to "20 days", and added language to 9.8.2 concerning "7 calendar days" and payment disputes.

03-10-2008: Revised Table 1 after 11.2.11 (Installation Floater), and expanded Paragraph 11.5.1 on Maintenance Bonds.

09-10-2008: Revised 5.2.5[sic] on page 17 to read 5.2.4.

10-24-2008: Revised many sections to include or amend numbering.

08-01-2009: Amended 1.1.6., definition of City Engineer. Amended 2.2 to say "Duties" and added 2.2.2 stating that the contract imposes no implied duty on City. Added 3.5.4 concerning Contractor Participation in the Pay or Play Program. Added 3.28 pertaining to Contractor Debt. Amended 4.1.2 to prohibit the City Engineer from delegating signature authority under 4.4. Amended 4.1.11 stating that City owes no duty to Contractor not stated in contract. Amended 4.3.2 to delete second sentence concerning City Engineers decision as a condition precedent to litigation. Amended 4.6 to require both parties to wave claims, attorney fees, and interest. Amended 11.2.6 to require Contractor to notify the City of any Insurance Policy cancelation or modification. Amended 11.2.8 to exempt Workers' Compensation coverage from certain documentation requirements. Amended Table 1 after 11.2.11 to specify automobile coverage requirements. Added 11.3.3 to address content requirements on Certificates of Insurance. Added 13.3.2 to extend joint and several liability to any series, affiliate, subsidiary, or successor to which Contractor assigns or transfers assets. Amended throughout to standardize references to Sections (x.x), Paragraphs (x.x.x), and Subparagraphs (x.x.x.x and below).

01-15-2010: Amended Sections 4.4 and 4.6 concerning written decisions, findings of fact, and hearings by the City engineer, precedent to litigation, and interest under Chapter 2251 of the Texas Local Government Code. Removed Section 4.5 NON-BONDING MEDIATION and renumbered and renamed Section 4.6 as 4.5 CONDITION PRECEDENT TO SUIT; WAIVER OF ATTORNEY FEES AND INTEREST.

05-01-2010: Amended Subsection 1.1.5 to change "municipal corporation" to "home rule municipality". Amended Subsection 3.9.1.1 to reflect change from Low Sulfur Deisel Fuel (500 ppm) to Ultra Low Sulfur Fuel (15 ppm).

12-07-2010: Amended Section 14.1.1.5 to mirror change in Section 3.9.1.1; Low Sulfur Diesel Fuel was changed to Ultra Low Sulfur Fuel.

12-09-2010: Amended Section 4.5 (and Table of Contents) by adding "Interim Payment Waiver & Release" language from Document 00850. Amended Subsection 11.3 to include new insurance requirements.

12-10-2010: Inserted phrase into definition of Claim (§1.1.7) defining what a Claim can constitute

****

List of Changes:

02-04-2005: Added new Paragraph 3.25.1.3 concerning strict liability. Edited Paragraph 3.25.1.1 accordingly. Edited Paragraph 9.6.1.4 to remove the words "retainage of".

08-15-2006: Revised many references to Section(s) to read Paragraph(s). Added Small Business Enterprise (SBE) requirement to Paragraphs 3.5.3, 3.5.3.1, 3.5.3.2 and 3.5.3.3.

08-17-2006: Added new Paragraphs 5.2.4, 5.2.5, 9.2.1 and 9.4.2 concerning prompt payment provisions.

10-10-2006: Added new Paragraphs 9.7.1.8, 9.7.1.9 concerning prompt payment provisions. Changed 9.8.1 to "20 days", and added language to 9.8.2 concerning "7 calendar days" and payment disputes.

03-10-2008: Revised Table 1 after 11.2.11 (Installation Floater), and expanded Paragraph 11.5.1 on Maintenance Bonds.

09-10-2008: Revised 5.2.5[sic] on page 17 to read 5.2.4.

10-24-2008: Revised many sections to include or amend numbering.

08-01-2009: Amended 1.1.6., definition of City Engineer. Amended 2.2 to say "Duties" and added 2.2.2 stating that the contract imposes no implied duty on City. Added 3.5.4 concerning Contractor Participation in the Pay or Play Program. Added 3.28 pertaining to Contractor Debt. Amended 4.1.2 to prohibit the City Engineer from delegating signature authority under 4.4. Amended 4.1.11 stating that City owes no duty to Contractor not stated in contract. Amended 4.3.2 to delete second sentence concerning City Engineers decision as a condition precedent to litigation. Amended 4.6 to require both parties to wave claims, attorney fees, and interest. Amended 11.2.6 to require Contractor to notify the City of any Insurance Policy cancelation or modification. Amended 11.2.8 to exempt Workers' Compensation coverage from certain documentation requirements. Amended Table 1 after 11.2.11 to specify automobile coverage requirements. Added 11.3.3 to address content requirements on Certificates of Insurance. Added 13.3.2 to extend joint and several liability to any series, affiliate, subsidiary, or successor to which Contractor assigns or transfers assets. Amended throughout to standardize references to Sections (x.x), Paragraphs (x.x.x), and Subparagraphs (x.x.x.x and below).

01-15-2010: Amended Sections 4.4 and 4.6 concerning written decisions, findings of fact, and hearings by the City engineer, precedent to litigation, and interest under Chapter 2251 of the Texas Local Government Code. Removed Section 4.5 NON-BONDING MEDIATION and renumbered and renamed Section 4.6 as 4.5 CONDITION PRECEDENT TO SUIT; WAIVER OF ATTORNEY FEES AND INTEREST.

05-01-2010: Amended Subsection 1.1.5 to change "municipal corporation" to "home rule municipality". Amended Subsection 3.9.1.1 to reflect change from Low Sulfur Deisel Fuel (500 ppm) to Ultra Low Sulfur Fuel (15 ppm).

12-07-2010: Amended Section 14.1.1.5 to mirror change in Section 3.9.1.1; Low Sulfur Diesel Fuel was changed to Ultra Low Sulfur Fuel.

12-09-2010: Amended Section 4.5 (and Table of Contents) by adding "Interim Payment Waiver & Release" language from Document 00850. Amended Subsection 11.3 to include new insurance requirements.

12-10-2010: Inserted phrase into definition of Claim (§1.1.7) defining what a Claim can constitute

01-14-2011: Insertion of terms "Business Enterprise" and "Business Enterprise Policy" into definition section (§1.1) and insertion of those terms in §3.5, as appropriate, and deletion of old §3.5.3

01-18-2011: Renaming of §4.5; renumbering of Table of Contents due to introduction of "Interim Payment Waiver & Release" as a separate section (§4.6)

01-31-2011: Edit of Section 4.6, Interim Payment Waiver & Release" to reflect language suggestions of Litigation Division of Legal Dept.

02-09-2011: Edit of language in definitions of "Business Enterprise" and "Business Enterprise Policy"

10-12-2011: Amended Section 8.2, related to delays and extensions of time, to strengthen language suggested in 2011 Construction Law CLE.

10-19-2011: General reformatting of entire document for consistency; updating of header re: date; insertion of "Mayor's Office of Business Opportunity", as appropriate, to refect name change

10-27-2011: Added a definition for "Mayor's Office of Business Opportunity"; amended Section 8.2.2 to refer to Section 4.3.6.2; replaced MWBE with "Business Enterprise", where appropriate; added "persons, or entities" to Section 5.1 to broaden applicable provisions; updated issue date to proposed Issue date of November 1, 2011.

10-31-2011: edited definition of "Business Enterprise"

07-01-2013: Edited Section 3.5.3 to remove the binding arbitration requirement for contractor and subcontractor claims, per change in Office of Business Opportunity policy.

07-25-2013: Removed Section 4.5.1, regarding conditions precedent to suit.

11-01-2014: Changed Section 3.5.2 to reflect a move away from arbitration to mediation to resolve subcontractor disputes; removed requirement for City Engineer's decision before a suit may be brought from Section 4.5.2; included language in Section 5.1.3 requiring submission of written contracts with Subcontractors within 30 days of Notice to Proceed issuance; changed Section 11.2 to reflect required insurance coverages updated for new fiscal year; added more explicit language regarding the City's Additional Insured status in Section 11.2.4 ("Insured Parties") and the City's waiver of subrogation requirement in Section11.2.7 ("Subrogation").

01-01-2015: Changed the Automobile Insurance requirement from $2,000,000 to $1,000,000.

****

Document 00700

GENERAL CONDITIONS

January 1, 2015 EDITION

TABLE OF ARTICLES

1. GENERAL PROVISIONS
2. THE CITY
3. CONTRACTOR
4. ADMINISTRATION OF THE CONTRACT
5. SUBCONTRACTORS AND SUPPLIERS
6. CONSTRUCTION BY THE CITY OR BY SEPARATE CONTRACTORS
7. CHANGES IN THE WORK
8. TIME
9. PAYMENTS AND COMPLETION
10. SAFETY PRECAUTIONS
11. INSURANCE AND BONDS
12. UNCOVERING AND CORRECTION OF THE WORK
13. MISCELLANEOUS PROVISIONS
14. TERMINATION OR SUSPENSION OF THE CONTRACT

ARTICLE 1 - GENERAL PROVISIONS 3

1.1 DEFINITIONS 3
1.2 EXECUTION, CORRELATION, AND INTENT 5
1.3 OWNERSHIP AND USE OF DOCUMENTS 6
1.4 INTERPRETATION 6

ARTICLE 2 - THE CITY 6

2.1 LIMITATIONS OF THE CITY'S OFFICERS AND EMPLOYEES 6
2.2 DUTIES OF THE CITY 6
2.3 AVAILABILITY OF LAND AND USE OF SITE 6
2.4 THE CITY'S RIGHT TO STOP THE WORK 7
2.5 THE CITY'S RIGHT TO CARRY OUT WORK 7

ARTICLE 3 - CONTRACTOR 7

3.1 RESPONSIBILITIES 7
3.2 REVIEW OF CONTRACT AND FIELD CONDITIONS BY CONTRACTOR 7
3.3 SUPERVISION AND CONSTRUCTION PROCEDURES 7
3.4 SUPERINTENDENT 8
3.5 LABOR 8
3.6 PREVAILING WAGE RATES 9
3.7 LABOR CONDITIONS 9
3.8 DRUG DETECTION AND DETERRENCE 9
3.9 MATERIALS & EQUIPMENT 10
3.10 PRODUCT OPTIONS AND SUBSTITUTIONS 10
3.11 CASH ALLOWANCES 11
3.12 WARRANTY 11
3.13 TAXES 12
3.14 PERMITS, FEES, AND NOTICES 12
3.15 CONSTRUCTION SCHEDULES 12
3.16 DOCUMENTS AND SAMPLES AT THE SITE 12
3.17 MANUFACTURER'S SPECIFICATIONS 12
3.18 SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES 13
3.19 CULTURAL RESOURCES AND ENDANGERED SPECIES 13
3.20 CUTTING AND PATCHING 14
3.21 CLEANING 14
3.22 SANITATION 14
3.23 ACCESS TO WORK AND TO INFORMATION 14
3.24 TRADE SECRETS 14
3.25 INDEMNIFICATION 14
3.26 RELEASE AND INDEMNIFICATION – PATENT, COPYRIGHT, TRADEMARK, AND TRADE SECRET INFRINGEMENT 15
3.27 INDEMNIFICATION PROCEDURES 15
3.28 CONTRACTOR DEBT 15

ARTICLE 4 - ADMINISTRATION OF THE CONTRACT 16

4.1 CONTRACT ADMINISTRATION 16
4.2 COMMUNICATIONS IN ADMINISTRATION OF THE CONTRACT 17
4.3 CLAIMS AND DISPUTES 17
4.4 RESOLUTION OF CLAIMS AND DISPUTES 18
4.5 CONDITION PRECEDENT TO SUIT; WAIVER OF ATTORNEYFEES AND INTEREST .....
4.6 INTERIM PAYMENT WAIVER & RELEASE 18

ARTICLE 5 - SUBCONTRACTORS AND SUPPLIERS 19

5.1 AWARD OF SUBCONTRACTS OTHER CONTRACTS FOR PORTIONS OF THE WORK 19
5.2 CONTRACTOR RESPONSIBILITY FOR SUBCONTRACTORS 19

ARTICLE 6 - CONSTRUCTION BY THE CITY OR BY SEPARATE CONTRACTORS 19

6.1 THE CITY'S RIGHT TO PERFORM CONSTRUCTION AND TO AWARD SEPARATE CONTRACTS 19
6.2 COORDINATION 19
6.3 MUTUAL RESPONSIBILITY 20
6.4 THE CITY'S RIGHT TO CLEAN UP 20

ARTICLE 7 - CHANGES IN THE WORK 20

7.1 CHANGES 20
7.2 WORK CHANGE DIRECTIVES 20
7.3 ADJUSTMENTS IN CONTRACT PRICE 21
7.4 MINOR CHANGES IN THE WORK 22

ARTICLE 8 - TIME 22

8.1 PROGRESS AND COMPLETION 22
8.2 DELAYS AND EXTENSIONS OF TIME 22

ARTICLE 9 - PAYMENTS AND COMPLETION 23

9.1 UNIT PRICE WORK 23
9.2 ESTIMATES FOR PAYMENT, UNIT PRICE WORK 23
9.3 STIPULATED PRICE WORK 24
9.4 APPLICATIONS FOR PAYMENT, STIPULATED PRICE WORK 24
9.5 CERTIFICATES FOR PAYMENT 24
9.6 COMPUTATIONS OF CERTIFICATES FOR PAYMENT 24
9.7 DECISIONS TO WITHHOLD CERTIFICATION 24
9.8 PROGRESS PAYMENTS 25
9.9 DATE OF SUBSTANTIAL COMPLETION 25
9.10 PARTIAL OCCUPANCY OR USE 26
9.11 FINAL COMPLETION AND FINAL PAYMENT 26

9.12 LIQUIDATED DAMAGES 27

ARTICLE 10 - SAFETY PRECAUTIONS 27

10.1 SAFETY PROGRAMS 27
10.2 POLLUTANTS AND POLLUTANT FACILITIES 27
10.3 SAFETY OF THE ENVIRONMENT, PERSONS, AND PROPERTY 28
10.4 EMERGENCIES 28

ARTICLE 11 - INSURANCE AND BONDS 28

11.1 GENERAL INSURANCE REQUIREMENTS 28
11.2 INSURANCE TO BE PROVIDED BY CONTRACTOR 29
11.3 PROOF OF INSURANCE 32
11.4 PERFORMANCE AND PAYMENT BONDS 33
11.5 MAINTENANCE BONDS 33
11.6 SURETY 33
11.7 DELIVERY OF BONDS 34

ARTICLE 12 - UNCOVERING AND CORRECTION OF THE WORK 34

12.1 UNCOVERING OF THE WORK 34
12.2 CORRECTION OF THE WORK 34
12.3 ACCEPTANCE OF NONCONFORMING WORK 34

ARTICLE 13 - MISCELLANEOUS PROVISIONS 34

13.1 GOVERNING LAWS 34
13.2 SUCCESSORS 35
13.3 BUSINESS STRUCTURE AND ASSIGNMENTS 35
13.4 WRITTEN NOTICE 35
13.5 RIGHTS AND REMEDIES 35
13.6 TESTS AND INSPECTIONS 35
13.7 INTEREST 35
13.8 PARTIES IN INTEREST 36
13.9 ENTIRE CONTRACT 36
13.10 WRITTEN AMENDMENT 36
13.11 COMPLIANCE WITH LAWS 36
13.12 SEVERABILITY 35

ARTICLE 14 - TERMINATION OR SUSPENSION OF THE CONTRACT 36

14.1 TERMINATION BY THE CITY FOR CAUSE 36
14.2 TERMINATION BY THE CITY FOR CONVENIENCE 37
14.3 SUSPENSION BY THE CITY FOR CONVENIENCE 37
14.4 TERMINATION BY CONTRACTOR 38

ARTICLE 1 - GENERAL PROVISIONS

1.1 DEFINITIONS

1.1.1 Agreement: Document signed by the Parties and binding the Parties, containing the name of Contractor, title and location of the Project, Original Contract Time, Original Contract Price, enumeration of documents included in the Contract, and other provisions.

1.1.2 Bonds: Performance Bond, Payment Bond, Maintenance Bond, and other Surety instruments executed by Surety. When in singular form, refers to individual instrument.

1.1.3 Business Enterprise: Any business entity registered in a program authorized by 49 C.F.R. § 26 (where applicable) or City Code of Ordinances, Chapter 15, Article II, relating to Equal Opportunity Employment and taking affirmative action to ensure that applicants are employed and employees are treated without regard to race, religion, color, sex, national origin, or age. The term "Business Enterprise" may include any Disadvantaged Business Enterprise ("DBE"), Minority Business Enterprise ("MBE"), Woman Business Enterprise ("WBE"), Small Business Enterprise ("SBE"), Person with Disability Enterprise ("PDBE"), and any Historically Underutilized Business ("HUB").

1.1.4 Business Enterprise Policy: Contract documents and applicable policies relating to Business Enterprises and authorized under 49 C.F.R. § 26 or City Code of Ordinances, Chapter 15, Article II.

1.1.5 Cash Allowance: An estimated sum of money to be used only for a limited class of expenditures such as utility relocation costs, fees for special licenses or permits, or other "pass-through" costs that would be the same for any contractor. Cash Allowances may not be used to purchase goods or services that are not specified in the Contract. The unspecified items must be purchased according to the terms of Article 7.

1.1.6 Change Order: Written instrument prepared by the City and signed by City Engineer and Contractor, specifying the following:

.1 a change in the Work;
.2 a change in Contract Price, if any; and
.3 a change in Contract Time, if any.

The value of a Change Order is the net amount after offsetting all deductions against all additions effected by the Change Order.

1.1.7 City: The City of Houston, a home rule municipality located principally within Harris County, Texas, including its successors and its authorized representatives.

1.1.8 City Engineer: The City Engineer, or the City employee representing the City Engineer, designated in the Agreement and authorized to represent the City, or successors.

1.1.9 Claim: Written demand or written assertion by one Party seeking adjustment of the Contract, payment of money, extension of time, or other relief under the Contract and includes, but is not limited to, claims for materials, labor, equipment, delay, changes, adjustments, substitutions, fees and third party claims. The Party making the Claim has the responsibility to substantiate the Claim.

1.1.10 Conditions of the Contract: General Conditions and Supplementary Conditions.

1.1.11 Construction Manager: Person or firm under contract with the City as its authorized representative to oversee and administer construction of the Work, and who may perform the role of Project Manager and Inspector, as designated by City Engineer in writing.

1.1.12 Contract: The Agreement; documents enumerated in and incorporated into the Agreement, Modifications, and amendments.

1.1.13 Contract Price: The monetary amount stated in the Agreement adjusted by Change Order, and increases or decreases in Unit Price Quantities, if any.

1.1.14 Contract Time: The number of days stated in the Agreement to substantially complete the Work, plus days authorized by Change Order.

1.1.15 Contractor: Person or firm identified as such in the Agreement including its successors and its authorized representatives.

1.1.16 Date of Commencement of the Work: Date established in Notice to Proceed on which Contract Time will commence. This date will not be changed by failure of Contractor, or persons or entities for whom Contractor is responsible, to act.

1.1.17 Date of Substantial Completion: Date that construction, or portion thereof designated by City Engineer, is certified by City Engineer to be substantially complete.

1.1.18 Design Consultant: Person or firm, under contract with the City, to provide professional services during construction and its authorized representatives. If a Design Consultant is not employed for services during construction, Project Manager will perform duties of Design Consultant designated in the Contract in addition to usual duties of Project Manager.

1.1.19 Drawings: Graphic and pictorial portions of the Contract that define the character and scope of the Work.

1.1.20 Extra Unit Price: Unit Prices, which may be required for completion of the Work. These Unit Prices and Unit Price Quantities are in the Contract and are included in Original Contract Price.

1.1.21 Furnish: To supply, pay for, deliver to the site, and unload.

1.1.22 General Requirements: The sections of Division 01 Specifications that specify administrative and procedural requirements and temporary facilities required for the Work.

1.1.23 Inspector: City's employee or agent authorized to assist with inspection of the Work.

1.1.24 Install: Unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, clean, protect, and similar operations.

1.1.25 Legal Holiday: Day established by the City Council as a holiday.

1.1.26 Major Unit Price Work: An individual Unit Price item,

.1 whose value is greater than five percent of Original Contract Price,

.2 whose value becomes greater than five percent of Original Contract Price as the result of an increase in quantity, or

.3 whose value is $100,000, whichever is least.

1.1.27 Mayor's Office of Business Opportunity: any reference to, or use of, the "Office of Affirmative Action" shall mean the Mayor's Office of Business Opportunity, or any such future name to which it is changed.

1.1.28 Minor Change in the Work: A written change in the Work, ordered by City Engineer, that does not change Contract Price or Contract Time, and that is consistent with the general scope of the Contract.

1.1.29 Modification: Change Order, Work Change Directive, or Minor Change in the Work.

1.1.30 Notice of Noncompliance: A written notice by City Engineer to Contractor regarding defective or nonconforming work that does not meet the Contract requirements, and that establishes a time by which Contractor shall correct the defective or nonconforming work.

1.1.31 Notice to Proceed: A written notice by City Engineer to Contractor establishing Date of Commencement of the Work.

1.1.32 Original Contract Price: The monetary amount originally stated in the Agreement.

1.1.33 Parties: Contractor and the City. When in singular form, refers to Contractor or the City.

1.1.34 Pollutant: Any materials subject to the Texas Solid Waste Disposal Act.

1.1.35 Pollutant Facility: Any facility regulated by the State of Texas to protect the health and environment from contamination by Pollutants, including without limitation, landfills, oil and gas production and storage facilities, wastewater facilities, waste injection wells, and storage tanks (including drums).

1.1.36 Product: Materials, equipment, or systems incorporated into the Work or to be incorporated into the Work.

1.1.37 Product Data: Illustrations, standard schedules, performance charts, instructions, brochures, diagrams, and other information furnished by Contractor to illustrate a Product.

1.1.38 Project: Total construction, of which the Work performed under the Contract may be the whole or a part, and which may include construction by the City or by separate contractors.

1.1.39 Project Manager: City Engineer's authorized representative for administration of the Work. Titles used within the City's departments may be different than those used in this definition.

1.1.40 Provide: Furnish and Install, complete, ready for intended use.

1.1.41 Samples: Physical examples that illustrate Products, or workmanship, and establish standards by which the Work is judged.

1.1.42 Shop Drawings: Drawings, diagrams, schedules, and other data specially prepared for the Work by Contractor, Subcontractor or Supplier, to illustrate a portion of the Work.

1.1.43 Specifications: Divisions 01 through 16 of the documents that are incorporated into the Agreement, consisting of written General Requirements and requirements for Products, standards, and workmanship for the Work, and performance of related services.

1.1.44 Stipulated Price: Single lump sum amount stated in the Contract for completion of the Work, or for designated portion of the Work.

1.1.45 Subcontractor: Person or firm that has direct or indirect contract with Contractor or with another Subcontractor to perform a portion of the Work and its authorized representatives.

1.1.46 Superintendent: Employee of Contractor having authority and responsibility to act for and represent Contractor.

1.1.47 Supplementary Conditions: Part of Conditions of the Contract that amends or supplements General Conditions.

1.1.48 Supplier: Manufacturer, distributor, materialman, or vendor having a direct agreement with Contractor or Subcontractor for Products, or services and its authorized representatives.

1.1.49 Surety: Corporate entity that is bound by one or more Bonds, and is responsible for completion of the Work, including the correction period, and for payment of debts incurred in fulfilling the Contract. Surety shall include co-surety or reinsurer, as applicable.

1.1.50 Underground Facilities: Pipes, conduits, ducts, cables, wires, manholes, vaults, tanks, tunnels, or other such facilities or attachments and encasements containing such facilities that exist below ground level.

1.1.51 Unit Price: An amount stated in the Contract for an individual, measurable item of work, which, when multiplied by actual quantity incorporated into the Work, amounts to full compensation for completion of the item, including work incidental to it.

1.1.52 Unit Price Quantities: Quantities indicated in the Contract that are approximations made by the City for contracting purposes.

1.1.53 Work: Entire construction required by the Contract, including all labor, Products, and services provided by Contractor to fulfill Contractor's obligations. The Work may constitute the whole or a portion of the Project.

1.1.54 Work Change Directive: A written change in the Work, ordered by City Engineer, that is within the general scope of the Contract and consisting of additions, deletions, or other revisions. A Work Change Directive will state proposed basis for adjustment, if any, in Contract Price or Contract Time, or both.

1.2 EXECUTION, CORRELATION, AND INTENT

1.2.1 Execution of the Contract by Contractor is conclusive that Contractor has visited the Work site, become familiar with local conditions under which the Work will be performed, and fully informed itself as to conditions and matters which can affect the Work or costs. Contractor further agrees that it has carefully correlated personal observations with requirements of the Contract.

1.2.2 The Contract and Modifications have been read and carefully considered by Contractor, who understands and agrees to their sufficiency for the Work. The Contract may not be more strongly construed against the City than against Contractor and Surety.

1.2.3 Contractor shall include all items necessary for proper execution and completion of the Work.

1.2.4 Reference to standard specifications, manuals, or codes of a technical society, organization, or association, or to laws or regulations of a governmental authority, whether specific or implied, mean the latest edition in effect as of date of receipt of bids, except as may be otherwise specifically stated in the Contract.

1.2.5 No provision of any referenced standard, specification, or manual changes the duties and responsibilities of the City, City Engineer, Contractor, or Design Consultant from those set forth in the Contract. Nor do these provisions assign to Design Consultant any duty or authority to supervise or direct performance of the Work or any duty or

authority to undertake any actions contrary to provisions of the Contract.

1.2.6 Organization of Specifications into divisions, sections, and articles and arrangement of Drawings does not control Contractor in dividing the Work among Subcontractors or in establishing the extent of work to be performed by any trade.

1.2.7 Unless otherwise defined in the Contract, words which have well-known construction industry technical meanings are used in the Contract in accordance with these recognized meanings.

1.3 OWNERSHIP AND USE OF DOCUMENTS

1.3.1 Drawings, Specifications, and other documents prepared by the City or by Design Consultant are instruments of service through which the Work to be executed by Contractor is described. Contractor may retain one Contract record set.

1.3.2 Neither Contractor, Subcontractor, nor Supplier will own or claim a copyright to documents contained in the Contract or any part of the Contract.

1.3.3 Documents contained in the Contract, prepared by the City or by Design Consultant, and copies furnished to Contractor, are for use solely with respect to the Work. They may not be used by Contractor, Subcontractor or Supplier on other projects or for additions to the Work, outside the scope of the Work, without the specific written consent of City Engineer, and Design Consultant, when applicable.

1.3.4 Contractor, Subcontractors, and Suppliers are granted a limited license to use and reproduce applicable portions of the Contract appropriate to and for use in execution of their work under the Contract.

1.4 *INTERPRETATION*

1.4.1 Specifications are written in an imperative streamlined form and are directed to Contractor, unless noted otherwise. When written in this form, words "shall be" are included by inference where a colon (:) is used within sentences or phrases.

1.4.2 In the interest of brevity, the Contract frequently omits modifying words such as "all" and "any" and articles such as "the" and "an", but an absent modifier or article is not intended to affect interpretation of a statement.

ARTICLE 2 - THE CITY

2.1 *LIMITATIONS OF THE CITY'S OFFICERS AND EMPLOYEES*

2.1.1 No officer or employee of the City may authorize Contractor to perform an act or work contrary to the Contract, except as otherwise provided in the Contract.

2.2 *DUTIES OF THE CITY*

2.2.1 If a building permit is required, the City will process an application for, and Contractor shall purchase the building permit before Date of Commencement of the Work.

2.2.2 The City will make available to Contractor a reproducible set of Drawings. Additional copies will be furnished, on Contractor's request, at the cost of reproduction.

2.2.3 When necessary for performance of the Work, the City will provide surveys describing physical characteristics, legal limitations, legal description of site, and horizontal and vertical control adequate to lay out the Work.

2.2.4 Information or services that the City is required to provide under the Contract will be provided by the City with reasonable promptness to avoid delay in orderly progress of the Work.

2.2.5 The Contract imposes no implied duty on the City. The City does not warrant any plans or specifications associated with the Contract.

2.2.6 Except as expressly stated in this Article, the City owes no duty to the Contractor or any subcontractor.

2.3 *AVAILABILITY OF LAND AND USE OF SITE*

2.3.1 The City will furnish, as indicated in the Contract, rights-of-way, land on which the Work is to be performed, and other land designated in the Contract for use by Contractor unless otherwise provided in the Contract.

2.3.2 Contractor shall confine operations at site to those areas permitted by law, ordinances, permits, and the Contract, and may not unreasonably encumber site with materials or equipment.

2.3.3 In addition to land provided by the City under Section 2.3, Contractor shall provide all land and access to land that may be required for use by Contractor for temporary construction facilities or for storage of materials and equipment, and shall indemnify the City during its use of the land as stated in Section 3.25.

2.4 *THE CITY'S RIGHT TO STOP THE WORK*

2.4.1 If Contractor fails to carry out the Work in accordance with the Contract, or fails to correct work which is not in accordance with requirements of the Contract as required in Sections 12.1 and 12.2, the City may, by Notice of Noncompliance, order Contractor to stop the Work or any portion of the Work until the cause for the order has been eliminated. However, the right of the City to stop the Work will not give rise to a Claim for delay or to a duty on the part of the City to exercise this right for the benefit of Contractor or any other person or entity, except to the extent required by Section 6.2. If Contractor corrects the defective or nonconforming work within the time established in Notice of Noncompliance, City Engineer will give written notice to Contractor to resume performance of the Work.

2.5 *THE CITY'S RIGHT TO CARRY OUT WORK*

2.5.1 If Contractor fails to carry out work in accordance with the Contract, and fails within the period established in a Notice of Noncompliance to correct the nonconforming work, the City may, after expiration of the required period, correct the deficiencies without prejudice to other remedies the City may have, including rights of the City under Section 14.1.

2.5.1.1 When the City corrects deficiencies, City Engineer will issue an appropriate Change Order and deduct from payments then or thereafter due Contractor the cost of correcting the deficiencies, including compensation for Design Consultant's and Construction Manager's additional services and expenses made necessary by such default, neglect, or failure. This action by the City and amounts charged to Contractor are both subject to prior approval of City Engineer. If payments, then or thereafter due Contractor, are not sufficient to cover these amounts, Contractor shall pay the difference to the City.

2.5.2 Notwithstanding the City's right to carry out work, maintenance and protection of the Work remains Contractor's responsibility, as provided in the Contract.

ARTICLE 3 - CONTRACTOR

3.1 *RESPONSIBILITIES*

3.1.1 Contractor shall maintain office with agent in the greater City of Houston area during the Contractor's performance under the Contract. Contractor shall file its street address with City Engineer.

3.1.2 Contractor and Contractor's employees shall not give or lend money or anything of value to an officer or employee of the City. Should this Paragraph 3.1.2 be violated, City Engineer may terminate the Contract under Section 14.1.

3.2 *REVIEW OF CONTRACT AND FIELD CONDITIONS BY CONTRACTOR*

3.2.1 Contractor shall carefully study and compare documents contained in the Contract with each other and with information furnished by the City pursuant to Section 2.2 and shall immediately report, in writing, any errors, inconsistencies, or omissions to City Engineer. If work is affected, Contractor shall obtain a written interpretation or clarification from City Engineer before proceeding with the affected work. However, Contractor will not be liable to the City for failure to report an error, inconsistency, or omission in the Contract unless Contractor had actual knowledge or should have had knowledge of the error, inconsistency, or omission.

3.2.2 Contractor shall take field measurements and verify field conditions, and shall carefully compare the conditions and other information known to Contractor with the Contract, before commencing activities. Contractor shall immediately report, in writing, to City Engineer for interpretation or clarification of discrepancies, inconsistencies, or omissions discovered during this process.

3.2.3 Contractor shall make a reasonable attempt to understand the Contract before requesting interpretation from City Engineer.

3.3 *SUPERVISION AND CONSTRUCTION PROCEDURES*

3.3.1 Contractor shall supervise, direct, and inspect the Work competently and efficiently, devoting the attention and applying the skills and

expertise as necessary to perform the Work in accordance with the Contract. Contractor is solely responsible and has control over construction means, methods, techniques, sequences, and procedures of construction; for safety precautions and programs in connection with the Work; and for coordinating all work under the Contract.

3.3.2 Regardless of observations or inspections by the City or City's consultants, Contractor shall perform and complete the Work in accordance with the Contract and submittals approved pursuant to Section 3.18. The City is not liable or responsible to Contractor or Surety for work performed by Contractor that is not in accordance with the Contract regardless of whether discovered during construction or after acceptance of the Work.

3.4 *SUPERINTENDENT*

3.4.1 Contractor shall employ a competent Superintendent and necessary assistants who shall be present at the site during performance of the Work. Communications given to Superintendent are binding on the Contractor.

3.4.2 Contractor shall notify City Engineer in writing of its intent to replace the Superintendent. Contractor may not replace the Superintendent if City Engineer makes a reasonable objection in writing.

3.5 *LABOR*

3.5.1 Contractor shall provide competent, qualified personnel to survey and lay out the Work and perform construction as required by the Contract. The City may, by written notice, require Contractor to remove from the Work any employee of Contractor or Subcontractors to whom City Engineer makes reasonable objection.

3.5.2 Contractor shall comply with the applicable Business Enterprise Policy set out in this Agreement and in the Supplementary Conditions, as set out in Chapter 15, Article V of the City of Houston Code of Ordinances.

3.5.3 When Original Contract Price is greater than $1,000,000, Contractor shall make Good Faith Efforts to award subcontracts or supply agreements in at least the percentages set out in the Supplementary Conditions for Business Enterprise Policy. Contractor acknowledges that it has reviewed the requirements for Good Faith Efforts on file with the City's Office of Business Opportunity and shall comply with them.

3.5.3.1 Contractor shall require written subcontracts with Business Enterprises and shall submit all disputes with Business Enterprises to voluntary mediation. Business Enterprise subcontracts complying with City Code of Ordinances Chapter 15, Article II must contain the terms set out in Subparagraph 3.5.3.2. If Contractor is an individual person, as distinguished from a corporation, partnership, or other legal entity, and the amount of the subcontract is $50,000 or less, the subcontract must also be signed by the attorneys of the respective parties.

3.5.3.2 Contractor shall ensure that subcontracts with Business Enterprise firms are clearly labeled **"THIS CONTRACT MAY BE SUBJECT TO MEDIATION ACCORDING TO THE TEXAS ALTERNATIVE DISPUTE RESOLUTION ACT"** and contain the following terms:

.1 (Business Enterprise) may not delegate or subcontract more than 50 percent of work under this subcontract to any other subcontractor without the express written consent of the City's OBO Director (the "Director").

.2 (Business Enterprise) shall permit representatives of the City of Houston, at all reasonable times, to perform (1) audits of the books and records of the Subcontractors and Suppliers, and (2) inspections of all places where work is to be undertaken in connection with this subcontract. (Business Enterprise) shall keep the books and records available for this purpose for at least four years after the end of its performance under this subcontract. Nothing in this provision shall affect the time for bringing a cause of action nor the applicable statute of limitations.

.3 Within five business days of execution of this subcontract, Contractor and (Business Enterprise) shall designate in writing to the Director an agent for receiving any notice required or permitted to be given pursuant to Chapter 15 of the Houston City Code of Ordinances, along with the street and mailing address and phone number of the agent.

3.5.4 The requirements and terms of the City of Houston Pay or Play Program, as set out in Executive Order 1-7 and Ordinance 2007-0534, are incorporated into the Contract for all purposes. Contractor shall comply with the terms and conditions of the Pay or Play Program as they are set out at the time of City Council approval of this

agreement. IF CONTRACTOR DOES NOT PAY IN ACCORDANCE WITH THE PAY OR PLAY PROGRAM WITHIN 30 DAYS OF THE DATE CITY ENGINEEER SENDS CONTRACTOR WRITTEN NOTIFICATION, CITY CONTROLLER MAY DEDUCT FUNDS UP TO THE AMOUNT OWED FROM ANY PAYMENTS OWED TO CONTRACTOR UNDER THIS AGREEMENT, AND CONTRACTOR WAIVES ANY RECOURSE.

3.6 *PREVAILING WAGE RATES*

3.6.1 Contractor shall comply with governing statutes providing for labor classification of wage scales for each craft or type of laborer, worker, or mechanic.

3.6.2 Prevailing wage rates applicable to the Work may be one or a combination of the following wage rates identified in Division 00:

.1 Federal Wage Rate General Decisions
- .1 Highway Rates
- .2 Building Rates
- .3 Heavy Construction Rates
- .4 Residential Rates

.2 City Prevailing Wage Rates
- .1 Building Construction Rates
- .2 Engineering Construction Rates
- .3 Asbestos Worker Rates

3.6.3 Each week Contractor shall submit to the City's Mayor's Office of Business Opportunity certified copies of payrolls showing classifications and wages paid by Contractor, Subcontractors, and Suppliers for each employee under the Contract, for any day included in the Contract.

3.7 *LABOR CONDITIONS*

3.7.1 In the event of labor disputes affecting Contractor or Contractor's employees, Contractor shall utilize all possible means to resolve disputes in order that the Work not be delayed to any extent. These means will include seeking injunctive relief and filing unfair labor practice charges, and any other action available to Contractor.

3.7.2 When Contractor has knowledge that any actual or potential labor dispute is delaying or is threatening to delay timely performance of the Work, Contractor shall immediately notify City Engineer in writing. No Claims will be accepted by City Engineer for costs incurred as a result of jurisdictional or labor disputes.

3.8 *DRUG DETECTION AND DETERRENCE*

3.8.1 It is the policy of the City to achieve a drug-free work force and to provide a workplace that is free from the use of illegal drugs and alcohol. It is also the policy of the City that manufacture, distribution, dispensation, possession, sale, or use of illegal drugs or alcohol by contractors while on the City's premises is prohibited. By executing the Contract, Contractor represents and certifies that it meets and will comply with all requirements and procedures set forth in the Mayor's Policy on Drug Detection and Deterrence, City Council Motion No. 92-1971 ("Mayor's Policy") and the Mayor's Drug Detection and Deterrence Procedures for Contractors, Executive Order No. 1-31, (Revised) ("Executive Order"). Mayor's Policy is on file in the office of the City Secretary. Copies of Executive Order may be obtained at the location specified in the Advertisement for Bids.

3.8.1.1 The Executive Order applies to the City's contracts for labor or services except the following:

- .1 contracts authorized by Emergency Purchase Orders,
- .2 contracts in which imposition of requirements of the Executive Order would exclude all potential bidders or proposers, or would eliminate meaningful competition for the Contract,
- .3 contracts with companies that have fewer than 15 employees during any 20-week period during a calendar year and no safety impact positions,
- .4 contracts with non-profit organizations providing services at no cost or reduced cost to the public, and
- .5 contracts with federal, state, or local governmental entities.

3.8.1.2 Prior to execution of the Contract, Contractor shall have filed with the City:

- .1 a Drug Policy Compliance Agreement form (Attachment "A" to the Executive Order), and
- .2 a copy of Contractor's drug free workplace policy, and
- .3 a written designation of all safety impact positions, if applicable, or a Contractor's Certification of a No Safety Impact Positions form (Attachment "C" to the Executive Order).

3.8.1.3 Every six months during performance of the Contract and upon completion of the Contract, Contractor shall file a Drug Policy Compliance Declaration form (Attachment "B" to the Executive Order). The Contractor shall submit the Drug Policy Compliance Declaration within 30 days of expiration of each six-month period of performance and within 30 days of completion of the Contract. The first six-month period shall begin on Date of Commencement of the Work.

3.8.1.4 Contractor shall have a continuing obligation to file updated designation of safety impact positions when additional safety impact positions are added to Contractor's employee workforce during performance of the Work.

3.8.1.5 Contractor shall require its Subcontractors and Suppliers to comply with the Mayor's Policy and Executive Order. Contractor is responsible for securing and maintaining required documents from Subcontractors and Suppliers for the City inspection throughout the term of the Contract.

3.8.1.6 Failure of Contractor to comply with requirements will be a material breach of the Contract entitling the City to terminate in accordance with Section 14.1.

3.9 *MATERIALS & EQUIPMENT*

3.9.1 Unless otherwise provided in the Contract, Contractor shall provide and assume full responsibility for Products, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, transportation, temporary facilities, supplies, and other facilities and incidentals necessary for Furnishing, performing, testing, starting-up, and completing the Work.

3.9.1.1 Contractor, Subcontractors, and Suppliers shall use Ultra Low Sulfur Diesel Fuel in all diesel operating vehicles and motorized equipment utilized in performing the Work. Ultra Low Sulfur Diesel Fuel is defined as diesel fuel having 15 ppm or the applicable standard set by state or federal law or rules and regulations of the Texas Commission on Environmental Quality, or the Environmental Protection Agency, whichever is less in sulfur content. Off-road Ultra Low Sulfur Diesel Fuel may be used in lieu of on-road Ultra Low Sulfur Diesel Fuel. Contractor shall provide, upon request by City Engineer, proof that Contractor, Subcontractors, and Suppliers are using Ultra Low Sulfur Diesel Fuel.

3.9.2 Contractor shall provide Products that are:

.1 new, unless otherwise required or permitted by the Contract, and
.2 of specified quality.

If required by City Engineer, Contractor shall furnish satisfactory evidence, including reports of required tests, as to kind and quality of Products.

3.9.3 Contractor shall store Products in a safe, neat, compact, and protected manner. Contractor shall also store Products delivered during the work, along the right-of-way:

.1 so as to cause the least inconvenience to property owners, tenants, and general public; and
.2 so as not to block access to, or be closer than, three feet to any fire hydrant.

Contractor shall protect trees, lawns, walks, drives, streets, and other improvements that are to remain, from damage. If private or public property is damaged by Contractor, Contractor shall, at its sole expense, restore the damaged property to at least its original condition.

3.9.3.1 Contractor shall obtain City Engineer's approval for storage areas used for Products for which payment has been requested under Paragraph 9.6.1. Contractor shall provide the City access to the storage areas for inspection purposes. Products, once paid for by the City, become the property of the City and may not be removed from place of storage, without City Engineer's written permission except for a movement to the site. Contractor's Installation Floater, required under Section 11.2, shall cover all perils, including loss or damage to Products during storage, loading, unloading, and transit to the site.

3.10 *PRODUCT OPTIONS AND SUBSTITUTIONS*

3.10.1 For Products specified by reference standards or by description only, Contractor may provide any Product meeting those standards or description.

3.10.2 For Products specified by naming one or more manufacturers with provision for substitutions or equal, Contractor may submit a request for substitution for any manufacturer not named.

3.10.3 City Engineer will consider requests for substitutions only within the first 15 percent of Contract Time, or first 90 days after date of Notice to Proceed, whichever is less.

3.10.4 Contractor shall document each request for substitution with complete data

substantiating compliance of proposed substitution with the Contract.

3.10.5 A request for substitution constitutes a representation that Contractor:

.1 has investigated the proposed Product and determined that it meets or exceeds the quality level of the specified Product;

.2 shall provide the same warranty for the substitution as for the specified Product;

.3 shall coordinate installation of the proposed substitution and make changes to other work which may be required for the Work to be completed, with no additional cost or increase in time to the City;

.4 confirms that cost data is complete and includes all related costs under the Contract;

.5 waives Claim for additional costs or time extensions that may subsequently become apparent; and

.6 shall provide review or redesign services by a design consultant with appropriate professional license and shall obtain re-approval and permits from authorities.

3.10.6 City Engineer will not consider and will not approve substitutions when:

.1 they are indicated or implied on Shop Drawing or Product Data submittals without separate written request; or

.2 acceptance will require revision to the Contract.

3.10.7 City Engineer may reject requests for substitution, and his decision will be final and binding on the Parties.

3.11 *CASH ALLOWANCES*

3.11.1 Contract Price includes Cash Allowances as identified in the Contract.

3.11.2 The City will pay the actual costs of Cash Allowance item exclusive of profit, overhead or administrative costs. If actual costs exceed the Cash Allowance, City Engineer must approve a Change Order for the additional costs.

3.12 *WARRANTY*

3.12.1 Contractor warrants to the City that Products furnished under the Contract are:

.1 free of defects in title;

.2 of good quality; and

.3 new, unless otherwise required or permitted by the Contract.

If required by the City Engineer, Contractor shall furnish satisfactory evidence as to kind, quality and title of Products, and that Products conform to requirements of the Contract.

3.12.2 In the event of a defect in a Product, either during construction or warranty period, Contractor shall take appropriate action with manufacturer of Product to assure correction or replacement of defective Product with minimum delay.

3.12.3 Contractor warrants that the Work is free of defects not inherent in the quality required or permitted, and that the Work does conform with the requirements of the Contract. Contractor further warrants that the Work has been performed in a thorough and workmanlike manner.

3.12.4 Contractor warrants that the Work is free of concentrations on polychlorinated biphenyl (PCB) and other substances defined as hazardous by the Comprehensive Environmental Response Compensation and Liability Act (CERCLA) or any other applicable law or regulation.

3.12.5 Work not conforming to requirements of Section 3.12, including substitutions not properly approved and authorized, may be considered nonconforming work.

3.12.6 Contractor's warranty excludes remedy for damage or defect caused by:

.1 improper or insufficient maintenance by the City;

.2 normal wear and tear under normal usage; or

.3 claim that hazardous material was incorporated into the Work, if that material was specified in the Contract.

3.12.7 Contractor warrants that title to all work covered by Contractor's request for payment passes to the City upon incorporation into the Work or upon Contractor's receipt of payment, whichever occurs first. The Contractor further warrants that the title is free of all liens, claims, security interests or other interests ("Encumbrances"). If not, upon written demand from City Engineer, Contractor shall immediately take legal action necessary to remove Encumbrances.

3.13 *TAXES*

3.13.1 Contractor shall pay all sales, consumer, use, and similar taxes, which are in effect or scheduled to go into effect on or before bids are received, related to work provided by Contractor.

3.13.2 Contractor shall obtain, and require Subcontractors and Suppliers to obtain, necessary permits from the state and local taxing authorities to perform contractual obligations under the Contract, including sales tax permits.

3.13.3 The City is exempt from the Federal Transportation and Excise Tax. Contractor shall comply with federal regulations governing the exemptions.

3.13.4 Products incorporated into the Work are exempt from state sales tax according to provisions of the TEX. TAX CODE ANN. CH. 151, Subsection H.

3.14 *PERMITS, FEES, AND NOTICES*

3.14.1 Unless otherwise provided in the Contract, Contractor shall secure and pay for all construction permits, licenses, and inspections:

.1 necessary for proper execution and completion of the Work; and

.2 legally required at time bids are received.

3.15 *CONSTRUCTION SCHEDULES*

3.15.1 On receipt of Notice to Proceed, Contractor shall promptly prepare and submit construction schedule for the Work for City Engineer's review. The schedule must reflect the minimum time required to complete the Work not to exceed Contract Time.

3.15.2 Contractor shall give 24-hour written notice to City Engineer before commencing work or resuming work where work has been stopped. Contractor shall also give the same notice to inspectors.

3.15.3 Contractor shall incorporate milestones specified in Summary of Work Specification into the construction schedule. Contractor's failure to meet a milestone, as determined by City Engineer, may be considered a material breach of the Contract.

3.15.4 Each month, Contractor shall submit to City Engineer a copy of an updated construction schedule indicating actual progress, incorporating applicable changes, and indicating courses of action required to assure completion of the Work within Contract Time.

3.15.5 Contractor shall keep a current schedule of submittals that coordinates with the construction schedule, and shall submit the initial schedule of submittals to City Engineer for approval.

3.16 *DOCUMENTS AND SAMPLES AT THE SITE*

3.16.1 Contractor shall maintain at the site, and make available to City Engineer, one record copy of Drawings, Specifications, and Modifications. Contractor shall maintain the documents in good order and marked currently to record changes and selections made during construction. In addition, Contractor shall maintain at the site, approved Shop Drawings, Product Data, Samples, and similar submittals, which will be delivered to City Engineer prior to final inspection as required in Paragraph 9.11.4.

3.16.2 Contractor shall maintain all books, documents, papers, accounting records, and other relevant documentation pursuant to the Work and shall make the books, documents, papers, and accounting records available to representatives of the City for review and audits during the Contract term and for the greater of three years following Date of Substantial Completion or until all litigation or audits are fully resolved.

3.16.3 Contractor shall provide to City Attorney all documents and records that City Attorney deems necessary to assist in determining Contractor's compliance with the Contract, with the exception of those documents made confidential by federal or state law or regulation.

3.17 *MANUFACTURER'S SPECIFICATIONS*

3.17.1 Contractor shall handle, store, and Install Products and perform all work in the manner required by Product manufacturer. Should the Contract and manufacturer's instructions conflict, Contractor shall report conflict to City Engineer for resolution prior to proceeding with the affected work.

3.17.2 References in the Contract to the manufacturer's specifications, directions, or recommendations, mean manufacturer's current published documents in effect as of date of receipt of bids, or in the case of a Modification, as of date of Modification.

3.18 SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES

3.18.1 Shop Drawings, Product Data, and Samples are not part of the Contract. The purpose of Contractor submittals is to demonstrate, for those portions of the Work for which submittals are required, the way Contractor proposes to conform to information given and design concept expressed in the Contract.

3.18.2 Contractor shall submit to Project Manager for review the Shop Drawings, Product Data, and Samples, which are required by the Contract. Review by Project Manager is subject to limitations of Paragraph 4.1.4. Contractor shall transmit the submittals to the Project Manager with reasonable promptness and in a sequence, so as to cause no delay in the Work or in activities of the City or of separate contractors. Contractor shall transmit submittals in time to allow a minimum of 30 days for Project Manager's review prior to date Contractor needs reviewed submittals returned. This time may be shortened for a particular job requirement if approved by Project Manager in advance of submittal.

3.18.3 Contractor shall certify that the content of submittals conforms to the Contract without exception by affixing Contractor's approval stamp and signature. By certifying and submitting Shop Drawings, Product Data, and Samples, Contractor represents, and Contractor's stamp of approval shall state, that Contractor has determined and verified materials, quantities, field measurements, and field construction criteria related to the submittal, and has checked and coordinated information contained within the submittals with requirements of the Contract.

3.18.4 Contractor may not perform any work requiring submittal and review of Shop Drawings, Product Data, or Samples until the submittal has been returned with appropriate review decision by the Project Manager. Contractor shall perform work in accordance with the review.

3.18.5 If Contractor performs any work requiring submittals prior to review and acceptance of the submittals by Project Manager, such work is at Contractor's risk and the City is not obligated to accept work if the submittals are later found to be unacceptable.

3.18.6 If, in the opinion of Project Manager, the submittals are incomplete, or demonstrate an inadequate understanding of the Work or lack of review by the Contractor, then submittals may be returned to the Contractor for correction and resubmittal.

3.18.7 Contractor shall direct specific attention in writing and on the resubmitted Shop Drawings, Product Data, or Samples to any additional proposed revisions, other than those revisions requested by Project Manager on previous submittals.

3.18.8 Contractor is not relieved of responsibility for deviations from requirements of the Contract by Project Manager's review of Shop Drawings, Product Data, or Samples unless Contractor has specifically informed Project Manager in writing of the deviation at the time of the submittal, and Project Manager has given written approval of the deviation.

3.18.9 When professional certification of performance criteria of Products is required by the Contract, the City may rely upon accuracy and completeness of the calculations and certifications.

3.18.10 For Product colors or textures to be selected by the City, Contractor shall submit all samples together to allow preparation of a complete selection schedule.

3.18.11 Contractor shall submit informational submittals, on which Project Manager is not expected to take responsive action, as required by the Contract.

3.18.12 Submittals made by Contractor which are not required by the Contract may be returned to Contractor without action.

3.19 CULTURAL RESOURCES AND ENDANGERED SPECIES

3.19.1 Contractor may not remove or disturb, or cause to be removed or disturbed, any historical, archaeological, architectural, or other cultural artifacts, relics, vestiges, remains, or objects of antiquity. If Contractor discovers one of these items, Contractor shall immediately notify City Engineer and further comply with the requirements of 13 Tex. Admin. Code Chs. 25 and 26 (2002), or successor regulation. Contractor shall protect site and cultural resources from further disturbance until professional examination can be made or until clearance to proceed is authorized in writing by City Engineer.

3.19.2 Should either threatened or endangered plant or animal species be encountered,

Contractor shall cease work immediately in the area of encounter and notify City Engineer.

3.20 *CUTTING AND PATCHING*

3.20.1 Contractor is responsible for necessary cutting, fitting, and patching to accomplish the Work and shall suitably support, anchor, attach, match, and trim or seal materials to work of other contractors. Contractor shall coordinate the Work with work of other contractors to minimize conflicts, as provided in Article 6.

3.20.2 Contractor may not endanger work by cutting, digging, or other action, and may not cut or alter work of other contractors except by written consent of City Engineer and affected contractor.

3.21 *CLEANING*

3.21.1 Contractor shall perform daily cleanup of all dirt, debris, scrap materials and other disposable items resulting from Contractor's operations, whether on-site or off-site. Unless otherwise authorized in writing by City Engineer, Contractor shall keep all streets, access streets, driveways, areas of public access, walkways, and other designated areas clean and open at all times.

3.21.2 Failure of Contractor to maintain a clean site, including access streets, is the basis for City Engineer to issue a Notice of Noncompliance. Should compliance not be attained within the time period in the Notice of Noncompliance, City Engineer may authorize necessary cleanup to be performed by others and the cost of the cleanup will be deducted from monies due Contractor.

Contractor shall legally dispose off-site, all waste materials and other excess materials resulting from Contractor's operations.

3.22 *SANITATION*

3.22.1 Contractor shall provide and maintain sanitary facilities at site for use of all construction forces under the Contract. Newly-constructed or existing sanitary facilities may not be used by Contractor.

3.23 *ACCESS TO WORK AND TO INFORMATION*

3.23.1 Contractor shall provide the City, Design Consultant, testing laboratories, and governmental agencies which have jurisdictional interests, access to the Work in preparation and in progress wherever located. Contractor shall provide proper and safe conditions for the access.

3.23.2 If required by City Engineer, Contractor shall furnish information concerning character of Products and progress and manner of the Work, including information necessary to determine cost of the Work, such as number of employees, pay of employees, and time employees worked on various classes of the Work.

3.24 *TRADE SECRETS*

3.24.1 Contractor will not make any claim of ownership of trade secrets as to products used in the Work, or preparation of any mixture for the Work. City Engineer will at all times have the right to demand and Contractor shall furnish information concerning materials or samples of ingredients of any materials used, or proposed to be used, in preparation of concrete placed or other work to be done. Mixtures, once agreed on, shall not be changed in any manner without knowledge and consent of City Engineer. The City will make its best efforts to protect confidentiality of proprietary information.

3.25 *INDEMNIFICATION*

3.25.1 CONTRACTOR AGREES TO AND SHALL DEFEND, INDEMNIFY, AND HOLD THE CITY, ITS AGENTS, EMPLOYEES, OFFICERS, AND LEGAL REPRESENTATIVES (COLLECTIVELY THE "CITY") HARMLESS FOR ALL CLAIMS, CAUSES OF ACTION, LIABILITIES, FINES, AND EXPENSES (INCLUDING, WITHOUT LIMITATION, ATTORNEYS' FEES, COURT COSTS, AND ALL OTHER DEFENSE COSTS AND INTEREST) FOR INJURY, DEATH, DAMAGE, OR LOSS TO PERSONS OR PROPERTY SUSTAINED IN CONNECTION WITH OR INCIDENTAL TO PERFORMANCE UNDER THE CONTRACT INCLUDING, WITHOUT LIMITATION, THOSE CAUSED BY:

.1 CONTRACTOR'S AND/OR ITS AGENTS', EMPLOYEES', OFFICERS', DIRECTORS', CONTRACTORS', OR SUBCONTRACTORS' (COLLECTIVELY IN NUMBERED SUBPARAGRAPHS .1 through .3, "CONTRACTOR") ACTUAL OR ALLEGED NEGLIGENCE OR INTENTIONAL ACTS OR OMISSIONS;

.2 THE CITY'S AND CONTRACTOR'S ACTUAL OR ALLEGED CONCURRENT NEGLIGENCE, WHETHER CONTRACTOR IS IMMUNE FROM LIABILITY OR NOT;

.3 THE CITY'S AND CONTRACTOR'S ACTUAL OR ALLEGED STRICT PRODUCTS LIABILITY OR STRICT STATUTORY LIABILITY, WHETHER CONTRACTOR IS IMMUNE FROM LIABILITY OR NOT.

CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD THE CITY HARMLESS DURING THE TERM OF THE CONTRACT AND FOR FOUR YEARS AFTER THE CONTRACT TERMINATES. CONTRACTOR SHALL NOT INDEMNIFY THE CITY FOR THE CITY'S SOLE NEGLIGENCE.

3.25.2 NOTWITHSTANDING ANYTHING TO THE CONTRARY, THE LIABILITY OF CONTRACTOR FOR THE CITY'S CONCURRENT NEGLIGENCE SHALL NOT EXCEED $1,000,000.

3.26 *RELEASE AND INDEMNIFICATION – PATENT, COPYRIGHT, TRADEMARK, AND TRADE SECRET INFRINGEMENT*

3.26.1 UNLESS OTHERWISE SPECIFICALLY REQUIRED BY THE CONTRACT, CONTRACTOR AGREES TO AND SHALL RELEASE AND DEFEND, INDEMNIFY, AND HOLD HARMLESS THE CITY, ITS AGENTS, EMPLOYEES, OFFICERS, AND LEGAL REPRESENTATIVES (COLLECTIVELY THE "CITY") FROM ALL CLAIMS OR CAUSES OF ACTION BROUGHT AGAINST THE CITY BY ANY PARTY, INCLUDING CONTRACTOR, ALLEGING THAT THE CITY'S USE OF ANY EQUIPMENT, SOFTWARE, PROCESS, OR DOCUMENTS CONTRACTOR FURNISHES DURING THE TERM OF THE CONTRACT INFRINGES ON A PATENT, COPYRIGHT, OR TRADEMARK, OR MISAPPROPRIATES A TRADE SECRET. CONTRACTOR SHALL PAY ALL COSTS (INCLUDING, WITHOUT LIMITATION, ATTORNEYS' FEES, COURT COSTS, AND ALL OTHER DEFENSE COSTS, AND INTEREST) AND DAMAGES AWARDED.

3.26.2 CONTRACTOR SHALL NOT SETTLE ANY CLAIM ON TERMS WHICH PREVENT THE CITY FROM USING THE EQUIPMENT, SOFTWARE, PROCESS, OR PRODUCT WITHOUT THE CITY ENGINEER'S PRIOR WRITTEN CONSENT.

3.26.3 UNLESS OTHERWISE SPECIFICALLY REQUIRED BY THE CONTRACT, WITHIN 60 DAYS AFTER BEING NOTIFIED OF THE CLAIM, CONTRACTOR SHALL, AT ITS OWN EXPENSE, EITHER:

.1 OBTAIN FOR THE CITY THE RIGHT TO CONTINUE USING THE EQUIPMENT, SOFTWARE, PROCESS, OR PRODUCT, OR

.2 IF BOTH PARTIES AGREE, REPLACE OR MODIFY THEM WITH COMPATIBLE AND FUNCTIONALLY EQUIVALENT PRODUCTS.

IF NONE OF THESE ALTERNATIVES IS REASONABLY AVAILABLE, THE CITY MAY RETURN THE EQUIPMENT, SOFTWARE, OR PRODUCT, OR DISCONTINUE THE PROCESS, AND CONTRACTOR SHALL REFUND THE PURCHASE PRICE.

3.27 *INDEMNIFICATION PROCEDURES*

3.27.1 *Notice of Indemnification Claims:* If the City or Contractor receives notice of any claim or circumstances which could give rise to an indemnified loss, the receiving party shall give written notice to the other Party within 10 days. The notice must include the following:

.1 a description of the indemnification event in reasonable detail,

.2 the basis on which indemnification may be due, and

.3 the anticipated amount of the indemnified loss.

This notice does not estop or prevent the City from later asserting a different basis for indemnification or a different amount of indemnified loss than that indicated in the initial notice. If the City does not provide this notice within the 10-day period, it does not waive any right to indemnification except to the extent that Contractor is prejudiced, suffers loss, or incurs expense because of the delay.

3.27.2 *Defense of Indemnification Claims:*

.1 *Assumption of Defense:* Contractor may assume the defense of the claim at its own expense with counsel chosen by it that is reasonably satisfactory to the City. Contractor shall then control the defense and any negotiations to settle the claim. Within 10 days after receiving written notice of the indemnification request, Contractor must advise the City as to whether or not it will defend the claim. If Contractor does not assume the defense, the City shall assume and control the defense, and all defense expenses constitute an indemnified loss.

.2 *Continued Participation:* If Contractor elects to defend the claim, the City may

retain separate counsel to participate in, but not control, the defense and to participate in, but not control, any settlement negotiations. Contractor may settle the claim without the consent or agreement of the City, unless it:

.1 would result in injunctive relief or other equitable remedies or otherwise require the City to comply with restrictions or limitations that adversely affect the City;

.2 would require the City to pay amounts that Contractor does not fund in full; or

.3 would not result in the City's full and complete release from all liability to the plaintiffs or claimants who are parties to or otherwise bound by the settlement.

3.28 *CONTRACTOR DEBT*

IF CONTRACTOR, AT ANY TIME DURING THE TERM OF THIS AGREEMENT, INCURS A DEBT, AS THE WORD IS DEFINED IN SECTION 15-122 OF THE HOUSTON CITY CODE OF ORDINANCES, IT SHALL IMMEDIATELY NOTIFY CITY CONTROLLER IN WRITING. IF CITY CONTROLLER BECOMES AWARE THAT CONTRACTOR HAS INCURRED A DEBT, IT SHALL IMMEDIATELY NOTIFY CONTRACTOR IN WRITING. IF CONTRACTOR DOES NOT PAY THE DEBT WITHIN 30 DAYS OF EITHER SUCH NOTIFICATION, CITY CONTROLLER MAY DEDUCT FUNDS IN AN AMOUNT EQUAL TO THE DEBT FROM ANY PAYMENTS OWED TO CONTRACTOR UNDER THIS AGREEMENT, AND CONTRACTOR WAIVES ANY RECOURSE THEREFOR. CONTRACTOR SHALL FILE A NEW AFFIDAVIT OF OWNERSHIP, USING THE FORM DESIGNATED BY CITY, BETWEEN FEBRUARY 1 AND MARCH 1 OF EVERY YEAR DURING THE TERM OF THE CONTRACT.

ARTICLE 4 - ADMINISTRATION OF THE CONTRACT

4.1 *CONTRACT ADMINISTRATION*

4.1.1 City Engineer will provide administration of the Contract and City Engineer is authorized to issue Change Orders, Work Change Directives, and Minor Changes in the Work.

4.1.2 City Engineer may act through Project Manager, Design Consultant, or Inspector. When the term "City Engineer" is used in the Contract, action by City Engineer is required unless City Engineer delegates his authority in writing. The City Engineer may not delegate authority to render decisions under Section 4.4.

The City does not have control over or charge of, and is not responsible for, supervision, construction, and safety procedures enumerated in Section 3.3. The City does not have control over or charge of and is not responsible for acts or omissions of Contractor, Subcontractors, or Suppliers.

4.1.3 The City and Design Consultant may attend project meetings and visit the site to observe progress and quality of the Work. The City and Design Consultant are not required to make exhaustive or continuous on-site inspections to check quality or quantity of the Work.

4.1.4 Project Manager will review and approve or take other appropriate action on Contractor's submittals, but only for limited purpose of checking for conformance with information given and design concept expressed in the Contract.

4.1.5 Project Manager's review of the submittals is not conducted for purpose of determining accuracy and completeness of other details, such as dimensions and quantities, or for substantiating instructions for installation or performance of Products, all of which remain the responsibility of Contractor.

4.1.6 Project Manager's review of submittals does not relieve Contractor of its obligations under Sections 3.3, 3.12, and 3.18. Review does not constitute approval of safety precautions or, unless otherwise specifically stated by Project Manager in writing, of construction means, methods, techniques, sequences, or procedures. Project Manager's review of a specific item does not indicate approval of an assembly of which the item is a component.

4.1.7 Based on field observations and evaluations, Project Manager will process Contractor's progress payments, certify amounts due Contractor, and issue Certificates for Payment in the amount certified.

4.1.8 Project Manager will receive and forward to City Engineer for his review and records, written warranties and related documents required by the Contract and assembled by Contractor.

4.1.9 Upon written request by Contractor or Project Manager, City Engineer will resolve matters

of interpretation of or performance of the Contract, which are not Claims. City Engineer's decisions are final and binding on the Parties.

4.1.10 City Engineer may reject work which does not conform to the Contract.

4.1.11 When City Engineer considers it necessary to implement the intent of the Contract, City Engineer may require additional inspection or testing of work in accordance with Paragraphs 13.6.3 and 13.6.4, whether such work is fabricated, Installed, or completed.

4.2 *COMMUNICATIONS IN ADMINISTRATION OF THE CONTRACT*

4.2.1 Except as otherwise provided in the Contract or when authorized by City Engineer in writing, Contractor shall communicate with Project Manager. Contractor shall communicate with Design Consultant, Design Consultant's subconsultants, and separate contractors through Project Manager. The City will communicate with Subcontractors and Suppliers through Contractor.

4.3 *CLAIMS AND DISPUTES*

4.3.1 *Documentation by Project Manager:* Contractor shall submit Claims, including those alleging an error or omission by Project Manager or Design Consultant, to Project Manager for documentation and recommendation to City Engineer.

4.3.2 *Decision of City Engineer:* Upon submission of Claim by Project Manager or Contractor, City Engineer will resolve Claims in accordance with Section 4.4.

4.3.3 *Time Limits on Claims:* Claims by Contractor must be made within 90 days after occurrence of event giving rise to the Claim.

4.3.4 *Continuing the Contract Performance:* Pending final resolution of a Claim including referral to non-binding mediation, unless otherwise agreed in writing, Contractor shall proceed diligently with the performance of the Contract and the City will continue to make payments in accordance with the Contract.

4.3.4.1 Pending final resolution of a Claim including referral to non-binding mediation, Contractor is responsible for safety and protection of physical properties and conditions at site.

4.3.5 *Claims for Concealed or Unknown Conditions:* Concealed or unknown physical conditions include utility lines, other man-made structures, storage facilities, Pollutants and Pollutant Facilities, and the like, but do not include conditions arising from Contractor operations, or failure of Contractor to properly protect and safeguard subsurface facilities. Concealed conditions also include naturally-occurring soil conditions outside the range of soil conditions identified through geotechnical investigations, but do not include conditions arising from groundwater, rain, or flood.

4.3.5.1 If conditions are encountered at the site which are Underground Facilities or otherwise concealed or unknown conditions which differ materially from:

.1 those indicated by the Contract; or

.2 conditions which Contractor could have discovered through site inspection, geotechnical testing, or otherwise;

then Contractor will give written notice to City Engineer no later than five days after Contractor's first observation of the condition and before condition is disturbed. Contractor's failure to provide notice constitutes a waiver of a Claim.

4.3.5.2 City Engineer will promptly investigate concealed or unknown conditions. If City Engineer determines that conditions at the site are not materially different and that no change in Contract Price or Contract Time is justified, City Engineer will notify Contractor in writing, stating reasons. If City Engineer determines the conditions differ materially and cause increase or decrease in Contractor's cost or time required for performance of part of the Work, City Engineer will recommend an adjustment in Contract Price or Contract Time, or both, as provided in Article 7. Opposition by a Party to the City Engineer's determination must be made within 21 days after City Engineer has given notice of the decision. If the Parties cannot agree on adjustment to Contract Price or Contract Time, adjustment is subject to further proceedings pursuant to Section 4.4.

4.3.6 *Claims for Additional Cost:* If Contractor wishes to make a Claim for increase in Contract Price, Contractor shall give written notice before proceeding with work for which Contractor intends to submit a Claim. Prior notice is not required for Claims relating to an emergency endangering life or property arising under Section 10.4.

4.3.6.1 Contractor may file a Claim in accordance with Section 4.4 if Contractor believes it has incurred additional costs, for the following reasons:

.1 written interpretation of City Engineer;
.2 order by City Engineer to stop the Work when Contractor is not at fault;
.3 suspension of the Work by City Engineer;
.4 termination of the Contract by City Engineer; or
.5 The City's non-compliance with another provision of the Contract.

4.3.6.2 No increase in Contract Price is allowed for delays or hindrances to the Work, except for direct and unavoidable extra costs to Contractor caused by failure of the City to provide information and services, or to make land and materials available, when required of the City under the Contract. Any increase claimed is subject to the provisions of Section 4.4 and Article 7.

4.3.6.3 The City is not liable for Claims for delay when Date of Substantial Completion occurs prior to expiration of Contract Time.

4.3.7 *Claims for Additional Time:* If Contractor wishes to make a Claim for an increase in Contract Time, Contractor shall give written notice as provided in Section 8.2. In case of continuing delay, only one Claim is necessary.

4.4 *RESOLUTION OF CLAIMS AND DISPUTES*

4.4.1 City Engineer will review Claims and take one or more of the following preliminary actions within 30 days of receipt of Claim:

.1 submit a suggested time to meet and discuss the Claim with City Engineer;
.2 reject Claim, in whole or in part, stating reasons for rejection;
.3 recommend approval of the Claim by the other Party;
.4 suggest a compromise; or
.5 take other actions as City Engineer deems appropriate to resolve the Claim.

4.4.2 City Engineer may request additional supporting data from claimant. Party making Claim shall, within 10 days after receipt of City Engineer's request, submit additional supporting data requested by City Engineer.

4.4.3 At any time prior to rendering a written decision regarding a Claim, City Engineer may refer Claim to non-binding mediation. If Claim is resolved, City Engineer will prepare and obtain all appropriate documentation. If Claim is not resolved, City Engineer will take receipt of Claim and begin a new review under Section 4.4.

4.4.4 If Claim is not referred to or settled in non-binding mediation, City Engineer may conduct a hearing and will render a written decision, including findings of fact, within 75 days of receipt of Claim, or a time mutually agreed upon by the Parties in writing. City Engineer may notify Surety and request Surety's assistance in resolving Claim. City Engineer's decision is final and binding on the Parties.

4.5 *CONDITION PRECEDENT TO SUIT; WAIVER OF ATTORNEY FEES AND INTEREST*

4.5.1 Neither the City nor Contractor may recover attorney fees for any claim brought in connection with this Contract.

4.5.2 Neither the City nor the Contractor may recover interest for any damages claim brought in connection with this Contract except as allowed by TEXAS LOCAL GOVERNMENT CODE Chapter 2251.

4.6 *INTERIM PAYMENT WAIVER & RELEASE*

4.6.1 In accordance with section 4.3, the Contractor shall use due diligence in the discovery and submission of any Claim against the City related to the Contractor's work.

4.6.2 The Contractor shall submit any Claim to the City not later than the 90th day after the occurrence of the event giving rise to the Claim.

4.6.3 Any failure to timely comply with the requirements of section 4.6.2 waives and releases any Claim when the Contractor submits an application for payment after the 90th day.

4.6.4 This waiver does not cover any retainage. In case of any conflict of law, this language shall be revised to the minimum extent necessary to avoid legal conflict. This waiver is made specifically for the benefit of the City.

ARTICLE 5 - SUBCONTRACTORS AND SUPPLIERS

5.1 *AWARD OF SUBCONTRACTS OTHER CONTRACTS FOR PORTIONS OF THE WORK*

5.1.1 Contractor may not contract with a Subcontractor, Supplier, person, or entity that City Engineer has made a reasonable and timely objection to.

5.1.2 If City Engineer has a reasonable objection to person or entity proposed by Contractor, Contractor shall propose another with whom City Engineer has no reasonable objection.

5.1.3 Contractor shall execute contracts with approved Subcontractors, Suppliers, persons, or entities before the Subcontractors or Suppliers begin work under the Contract. All such contracts must be executed and sent to the OBO Director and Contracting Department within 30 days after the date of the Notice to Proceed and must include provisions set forth in Articles 3 and 5 of this Document.

5.1.4 Contractor shall notify City Engineer in writing of any proposed change of Subcontractor, Supplier, person, or entity previously accepted by the City.

5.1.5 Contractor shall make timely payments to Subcontractors and Suppliers for performance of the Contract. Contractor shall protect, defend, and indemnify the City from any claim or liability arising out of Contractor's failure to make the payments. Disputes relating to payment of Business Enterprise Subcontractors or Suppliers will be submitted to arbitration in same manner as other disputes under Business Enterprise subcontracts. Failure of Contractor to comply with decisions of arbitrator may be determined by City Engineer a material breach leading to termination of the Contract.

5.2 *CONTRACTOR RESPONSIBILITY FOR SUBCONTRACTORS*

5.2.1 Contractor is responsible to the City, as may be required by laws and regulations, for all acts and omissions of Subcontractors, Suppliers, and other persons and organizations performing or furnishing any of the Work under direct or indirect contract with Contractor.

5.2.2 Contractor shall make available to each proposed Subcontractor, prior to execution of subcontract, copies of the Contract to which Subcontractor is bound by this Section 5.2. Contractor shall notify Subcontractor of any terms of proposed subcontract which may be at variance with the Contract.

5.2.3 The City's approval of Subcontractor or Suppliers does not relieve Contractor of its obligation to perform, or to have performed to the full satisfaction of the City, the Work required by the Contract.

5.2.4 Unless there is a contractual relationship between Contractor and a Subcontractor or Supplier to the contrary, Contractor shall withhold no more retainage from Subcontractors or Suppliers than City withholds from Contractor under this Agreement. However, once a Subcontractor or Supplier completes performance, Contractor shall release all retainage to that Subcontractor or Supplier regardless if City continues to retain under this Agreement.

5.2.5 Prior to a Subcontractor or Supplier commencing performance for Contractor, Contractor shall meet with that Subcontractor or Supplier to provide instructions on invoicing procedures, dispute resolution procedures, and statutory rights, such as claim filing procedures under the McGregor Act. Subcontractors and Suppliers must certify to the City Engineer that Contractor has fulfilled the requirements of this Section.

ARTICLE 6 - CONSTRUCTION BY THE CITY OR BY SEPARATE CONTRACTORS

6.1 *THE CITY'S RIGHT TO PERFORM CONSTRUCTION AND TO AWARD SEPARATE CONTRACTS*

6.1.1 The City may perform on-site construction operations related to the Work and as part of the Project with the City's workforce or with separate contractors.

6.2 *COORDINATION*

6.2.1 The City will coordinate activities of the City's workforce and of each separate contractor with work of Contractor, and Contractor shall cooperate with the City and separate contractors.

6.2.1.1 Contractor shall participate with other separate contractors and the City in reviewing their construction schedules when directed to do so by the Project Manager. Contractor shall make revisions to construction schedule and Contract Price deemed

necessary after joint review and mutual agreement. Construction schedules shall then constitute schedules to be used by Contractor, separate contractors, and the City, until subsequently revised.

6.2.2 Contractor shall afford to the City and to separate contractors reasonable opportunity for introduction and storage of their materials and equipment, and for performance of their activities.

6.2.3 If part of Contractor's work depends on proper execution of construction or operations by the City or a separate contractor, Contractor shall, prior to proceeding with that portion of the Work, inspect the other work and promptly report to City Engineer apparent discrepancies or defects in the other construction that would render it unsuitable for the proper execution of the Work. Failure of Contractor to report apparent discrepancies or defects in the other construction shall constitute acknowledgment that the City's or separate contractor's completed or partially completed construction is fit and proper to receive Contractor's work, except as to discrepancies or defects not then reasonably discoverable.

6.3 *MUTUAL RESPONSIBILITY*

6.3.1 The responsible party bears the costs caused by delays, by improperly timed activities, or by nonconforming construction.

6.3.2 Contractor shall promptly remedy damage caused by Contractor to completed or partially completed construction or to property of the City or separate contractor.

6.3.3 Claims or disputes between Contractor and other City contractors, or subcontractors of other City contractors, working on the Project must be submitted to binding arbitration in accordance with Construction Industry Arbitration Rules of the American Arbitration Association upon demand by any party to the dispute or by the City.

6.4 *THE CITY'S RIGHT TO CLEAN UP*

6.4.1 If dispute arises among Contractor, separate contractors, and the City as to responsibility under their respective contracts for maintaining premises and surrounding area free from waste materials and rubbish as described in Section 3.21, the City may clean up and allocate cost among those responsible, as determined by City Engineer.

ARTICLE 7 - CHANGES IN THE WORK

7.1 *CHANGES*

7.1.1 Changes in scope of the Work, subject to limitations in Article 7 and elsewhere in the Contract, may be accomplished without invalidating the Contract, or without notifying Surety by:

.1 Change Order;
.2 Work Change Directive; or
.3 Minor Change in the Work.

7.1.2 The following types of Change Orders require City Council approval:

.1 a single Change Order that exceeds five percent of Original Contract Price,
.2 a Change Order which, when added to previous Change Orders, exceeds five percent of Original Contract Price,
.3 a Change Order, in which the total value of increases outside of the general scope of work approved by City Council, when added to increases outside the general scope of work approved by City Council in previous Change Orders, exceeds 40 percent of the Original Contract Price, even if the net increase to the Original Contract Price is five percent or less.
In this context, "increase" means an increase in quantity resulting from the addition of locations not within the scope of work approved by City Council, or the addition of types of goods or services not bid as unit price items.

Nothing in this Section is intended to permit an increase of the Contract Price in excess of the limit set out in TEX. LOC. GOV'T CODE ANN. §252.048 or its successor statute.

7.1.3 Contractor shall proceed promptly to execute changes in the Work provided in Modifications, unless otherwise stated in the Modification.

7.2 *WORK CHANGE DIRECTIVES*

7.2.1 A Work Change Directive cannot change Contract Price or Contract Time, but is evidence that the Parties agree that a change, ordered by directive, will be incorporated in a subsequently issued Change Order as to its effect, if any, on Contract Price or Contract Time.

7.2.2 Failure by Contractor to commence work identified in a Work Change Directive within the time specified by City Engineer, or to complete the

work in a reasonable period of time, may be determined by City Engineer to be a material breach of Contract.

7.2.3 A Work Change Directive is used in the absence of total agreement of the terms of a Change Order. Interim payments are made in accordance with Paragraph 9.6.1.

7.2.4 If Contractor signs a Work Change Directive, then Contractor agrees to its terms including adjustment in Contract Price and Contract Time or method for determining them. Agreement by the Parties to adjustments in Contract Price and Contract Time are immediately recorded as a Change Order.

7.2.5 City Engineer, by Work Change Directive, may direct Contractor to take measures as necessary to expedite construction to achieve Date of Substantial Completion on or before expiration of Contract Time. When the Work is expedited solely for convenience of the City and not due to Contractor's failure to prosecute timely completion of the Work, then Contractor is entitled to an adjustment in Contract Price equal to actual costs determined in accordance with Article 7.

7.3 *ADJUSTMENTS IN CONTRACT PRICE*

7.3.1 Adjustments in Contract Price are accomplished by Change Order and are based on one of the following methods:

.1 mutual acceptance of fixed price, properly itemized and supported by sufficient data to permit evaluation;

.2 unit prices stated in the Contract or subsequently agreed upon;

.3 cost to be determined in a manner agreed upon by the Parties and mutually acceptable fixed or percentage fee; or

.4 as provided in Paragraph 7.3.2.

7.3.2 If Contractor does not agree with a change in Contract Price or Contract Time or the method for adjusting them specified in the Work Change Directive within 21 days from date of the Work Change Directive's issuance, method and adjustment are determined by City Engineer. If Project Manager or Contractor disagree with City Engineer's determination they then may file a Claim in accordance with Section 4.4.

7.3.2.1 If City Engineer determines a method and adjustment in Contract Price under Paragraph 7.3.2, Contractor shall provide, in a form as City Engineer may prescribe, appropriate supporting data for items submitted under Paragraph 7.3.2. Failure to submit the data within 21 days of request for the data by City Engineer shall constitute waiver of a Claim.

7.3.2.2 Unless otherwise provided in the Contract, costs for the purposes of this Paragraph 7.3.2 are limited to the following:

.1 costs of labor, including labor burden as stated below for social security, unemployment insurance, customary and usual fringe benefits required by agreement or custom, and Workers' Compensation insurance;

.1 the maximum labor burden applied to costs of labor for changes in the Work is 55 percent;

.2 costs of materials, supplies, and equipment, including cost of transportation, whether incorporated or consumed;

.3 rental costs of machinery and equipment, exclusive of hand tools, whether rented from Contractor or others, with prior approval of City Engineer;

.4 costs of premiums for Bonds and insurance and permit fees related to the change in the Work;

.5 additional costs of direct supervision of work and field office personnel directly attributable to the change; and

.6 allowances for overhead and profit as stated below.

.1 the maximum allowances for overhead and profit on increases due to Change Orders:

.2 for changes in the Work performed by Contractor and Subcontractors, allowance for overhead and profit are applied to an amount equal to cost of all additions less cost of all deletions to the Work. Allowance for overhead to Contractor and first tier Subcontractors on changes performed by Subcontractors are applied to an amount equal to the sum of all increases to the Work by applicable Subcontractors.

	Overhead	Profit
to Contractor for change in the Work performed by Subcontractors:	10 percent	0 percent
to first tier Subcontractors for change in the Work performed by its Subcontractors:	10 percent	0 percent
to Contractor and Subcontractor for change in the Work performed by their respective firms:	10 percent	5 percent

7.3.3 If the City deletes or makes a change, which results in a net decrease in Contract Price, the City is entitled to a credit calculated in accordance with Paragraphs 7.3.1 and 7.3.2 and Subparagraphs 7.3.2.1, and 7.3.2.2.1 through 7.3.2.2.5. When both additions and credits covering related work or substitutions are involved in a change, allowance for overhead and profit is figured on the basis of a net increase, if any, with respect to that change in accordance with Subparagraph 7.3.2.2.6.

7.3.4 When Contractor agrees with the determination made by City Engineer concerning adjustments in Contract Price and Contract Time, or the Parties otherwise reach agreement upon the adjustments, the agreement will be immediately recorded by Change Order.

7.4 *MINOR CHANGES IN THE WORK*

7.4.1 A Minor Change in Work is binding on the Parties. Contractor shall acknowledge, in a written form acceptable to City Engineer, that there is no change in Contract Time or Contract Price and shall carry out the written orders promptly.

ARTICLE 8 - TIME

8.1 *PROGRESS AND COMPLETION*

8.1.1 Time is of the essence in the Contract. By executing the Contract, Contractor agrees that Contract Time is a reasonable period for performing the Work.

8.1.2 *Computation of Time:* In computing any period of time prescribed or allowed by the General Conditions, the day of the act, event, or default after which designated period of time begins to run is not to be included. Last day of the period so computed is to be included, unless it is a Sunday or Legal Holiday, in which event the period runs until end of next day which is not a Sunday or Legal Holiday. Sundays and Legal Holidays are considered to be days and are to be included in all other time computations relative to Contract Time.

8.1.3 Contractor may not commence the Work prior to the effective date of insurance and Bonds required by Article 11.

8.1.4 Contractor shall proceed expeditiously and without interruption, with adequate forces, and shall achieve Date of Substantial Completion within Contract Time.

8.1.5 Should progress of the Work fall behind construction schedule, except for reasons stated in Paragraph 8.2.1, Contractor shall promptly submit at the request of Project Manager, updated construction schedule to City Engineer for approval. Contractor's failure to submit updated schedule may, at City Engineer's discretion, constitute a material breach of the Contract. Contractor shall take action necessary to restore progress by working the hours, including night shifts and lawful overtime operations as necessary, to achieve Date of Substantial Completion within Contract Time.

8.1.6 Except in connection with safety or protection of persons or the Work or property at the site or adjacent to the site, and except as otherwise indicated in the Contract, all the Work at the site will be performed Monday through Saturday between the hours of 7:00 a.m. and 7:00 p.m. Contractor may not perform work between 7:00 p.m. and 7:00 a.m., on a Sunday, or on a Legal Holiday, without giving City Engineer 24-hour prior written notice and receiving written consent of City Engineer.

8.2 *DELAYS AND EXTENSIONS OF TIME*

8.2.1 Contractor may request extension of Contract Time for a delay in performance of work that arises from causes beyond control and without fault or negligence of Contractor. Examples of these causes are:

.1 acts of God or of the public enemy;
.2 acts of government in its sovereign capacity;
.3 fires;
.4 floods;
.5 epidemics;
.6 quarantine restrictions;
.7 strikes;
.8 freight embargoes;
.9 unusually severe weather; and
.10 discovery of Pollutants or Pollutant Facilities at the site.

8.2.2 For any reason other than those listed in Section 4.3.6.2, if the Contractor's work is delayed in any manner or respect, the Contractor shall have no claim for damages and shall have no right of additional compensation from the City by reason of any delay or increased expense to the Contractor's work, except for an extension of time as provided in this provision.

8.2.3 Contractor may request an extension of Contract Time for delay only if:

.1 delay is caused by failure of Subcontractor or Supplier to perform or make progress; and

.2 cause of failure is beyond control of both Contractor and Subcontractor or Supplier.

8.2.4 Claims relating to Contract Time must be made in accordance with Paragraph 4.3.7.

8.2.5 Claims for extending or shortening Contract Time are based on written notice promptly delivered by the Party making Claim to other Party. Claim must accurately describe occurrence generating Claim, and a statement of probable effect on progress of the Work.

8.2.6 Claims for extension of Contract Time are considered only when a Claim is filed within the time limits stated in Paragraph 4.3.3.

.1 Notwithstanding paragraph 4.3.3, an extension of time for delays under this paragraph may be granted only upon written application by the Contractor within 48 hours from the claimed delay.

8.2.7 Written notice of Claim must be accompanied by claimant's written statement that adjustment claimed is entire adjustment to which claimant is entitled as a result of the occurrence of the event. When the Parties cannot agree, Claims for adjustment in Contract Time are determined by City Engineer in accordance with Section 4.4.

8.2.8 Adjustments to Contract Time are accomplished by Change Order.

ARTICLE 9 - PAYMENTS AND COMPLETION

9.1 *UNIT PRICE WORK*

9.1.1 Where the Contract provides that all or part of the Work is based on Unit Prices, the Original Contract Price includes, for all Unit Price work, an amount equal to the sum of Unit Prices times Unit Price Quantities for each separately identified item of Unit Price work.

9.1.2 Each Unit Price includes an amount to cover Contractor's overhead and profit for each separately identified item.

9.1.3 The Contractor may not make a Claim against the City for excess or deficiency in Unit Price Quantities provided in the Contract, except as provided in Subparagraph 9.1.4. Payment at the prices stated in the Contract is in full for the completed work. Contractor is not entitled to additional payment for materials, supplies, labor, tools, machinery and all other expenditures incidental to satisfactory completion of the Work.

9.1.4 City Engineer may increase or decrease quantities of the Work within limitations stated in Paragraph 7.1.2. Contractor is entitled to payment for actual quantities of items provided at Unit Prices set forth in the Contract.

9.1.5 Where the final quantity of work performed by Contractor on Major Unit Price Work item differs by more than 25 percent from quantity of the item stated in the Contract, a Party may request an adjustment in Unit Price, for the portion that differs by more than 25 percent, by a Change Order under Section 7.3.

9.2 *ESTIMATES FOR PAYMENT, UNIT PRICE WORK*

9.2.1 Following the day of each month indicated in the Contract, Project Manager will prepare a Certificate for Payment for the preceding monthly period based on estimated units of work completed. Prior to preparing Certificate of Payment, Contractor shall have submitted to City Engineer on a form approved by the Director of the Mayor's Office of Business Opportunity, evidence satisfactory to the City Engineer of payments made to Subcontractors and Suppliers for the month preceding the month for which the Certificate for Payment is prepared.

9.2.2 Before final completion, City Engineer will review and confirm with Contractor the actual final installed Unit Price quantities. City Engineer's determination of actual final installed Unit Price quantities will be included in the final Certificate for Payment and any previous underpayments and overpayments will be reconciled with the actual final Unit Price quantities. Contractor shall file written notice of intent to appeal, if any, City Engineer's

determination within 10 days of receipt of final Certificate for Payment. Upon expiration of the 10-day period, City Engineer's decision is final and binding on the Parties. If Contractor submits notice within the 10-day period, Contractor shall submit a Claim in accordance with Section 4.4.

9.3 *STIPULATED PRICE WORK*

9.3.1 For work contracted on a Stipulated Price basis, 10 days before submittal of first Application for Payment, Contractor shall submit to City Engineer a Schedule of Values allocated to various portions of the Work, prepared in the form and supported by the data as City Engineer may require to substantiate its accuracy. This schedule, as approved by City Engineer, is used as a basis for approval of Contractor's Applications for Payment.

9.4 *APPLICATIONS FOR PAYMENT, STIPULATED PRICE WORK*

9.4.1 For work contracted on a Stipulated Price basis, Contractor shall submit Applications for Payment to City Engineer each month on a form acceptable to City Engineer in accordance with Schedule of Values. Application must indicate percentages of completion of each portion of the Work listed in Schedule of Values as of the end of the period covered by the Application for Payment.

9.4.2 Applications for Payment must be supported by substantiating data as City Engineer may require and must reflect retainages as provided below. Evidence satisfactory to the City Engineer of payments made to Subcontractors and Suppliers for the month preceding the month for which the Application for Payment is submitted must accompany each Application for Payment on a form approved by the Director of Mayor's Office of Business Opportunity. Application must be sworn and notarized.

9.5 *CERTIFICATES FOR PAYMENT*

9.5.1 City Engineer will, within 10 days after the date specified in the Contract for Unit Price work, or upon receipt of Contractor's Application for Payment for Stipulated Price work, issue a Certificate for Payment for work based on amount which City Engineer determines is properly due, with copy to Contractor.

9.5.2 Unless otherwise provided in the Contract, payment for completed work and for properly stored Products is conditioned upon compliance with procedures satisfactory to City Engineer to protect the City's interests. Procedures will include applicable insurance, storage, and transportation to site for materials and equipment stored off-site. Contractor is responsible for maintaining materials and equipment until Date of Substantial Completion.

9.5.3 Contractor shall document its use of Ultra Low Sulfur Diesel Fuel by providing invoices and receipts evidencing Contractor's use.

9.6 *COMPUTATIONS OF CERTIFICATES FOR PAYMENT*

9.6.1 Subject to the provisions of the Contract, the amount of each Certificate for Payment is calculated as follows:

.1 that portion of Contract Price allocated to completed work as determined by:
  .1 multiplying the percentage of completion of each portion of the Work listed in the Schedule of Values by the value of that portion of the Work, or
  .2 multiplying Unit Price quantities Installed times the Unit Prices listed in the Contract;
.2 plus progress payments for completed work that has been properly authorized by Modifications;
.3 less retainage of five percent;
.4 plus actual costs, properly substantiated by certified copies of invoices and freight bills, of non-perishable materials and equipment delivered and properly stored, if approved in advance by Project Manager, less 15 percent;
.5 less any previous payments by the City.

9.7 *DECISIONS TO WITHHOLD CERTIFICATION*

9.7.1 City Engineer may decline to certify payment and may withhold payment in whole or in part to the extent reasonably necessary to protect the City if, in City Engineer's opinion, there is reason to believe that:

.1 nonconforming work has not been remedied;
.2 the Work cannot be completed for unpaid balance of Contract Price;
.3 there is damage to the City or another contractor;
.4 the Work will not be completed within Contract Time and that unpaid balance will not be adequate to cover actual and liquidated damages;

.5 probable evidence that third party claims will be filed in court, in arbitration, or otherwise;

.6 Contractor has failed to make payments to Subcontractors or Suppliers for labor, material, or equipment; or

.7 Contractor has persistently failed to carry out work in accordance with the Contract.

.8 Contractor has not paid Subcontractors or Suppliers because of a payment dispute; or

.9 Contractor has failed to provide satisfactory evidence described in Paragraphs 9.2.1, 9.4.2, and 9.8.2.

9.7.2 When the above reasons for withholding certification are removed, certification will be made for amounts previously withheld.

9.7.3 City Engineer may decline to certify payment and may withhold request for payment in whole or in part upon failure of Contractor to submit initial construction schedule or monthly schedule updates, as required in Paragraphs 3.15.1 and 3.15.3.

9.8 *PROGRESS PAYMENTS*

9.8.1 The City will make payment, in an amount certified by City Engineer, within 20 days after City Engineer has issued a Certificate for Payment.

9.8.2 The City has no obligation to pay or to facilitate the payment to a Subcontractor or Supplier, except as may otherwise be required by law. Contractor shall comply with the prompt payment requirements of Chapter 2251 of the Government Code. State law requires payment of Subcontractors and Suppliers by Contractor within 7 calendar days of Contractor's receipt of payment from the City, unless there is a payment dispute between Contractor and a Subcontractor or Supplier evidenced on a form approved by the Director of Mayor's Office of Business Opportunity and submitted to the City Engineer each month with Application for Payment or Estimate for Payment. **CONTRACTOR SHALL DEFEND AND INDEMNIFY THE CITY FROM ANY CLAIMS OR LIABILITY ARISING OUT OF CONTRACTOR'S FAILURE TO MAKE THESE PAYMENTS.**

9.8.2.1 The City may, upon request and at the discretion of City Engineer, furnish to Subcontractor information regarding percentages of completion or the amounts applied for by Contractor, and action taken thereon by the City because of work done by the Subcontractor.

9.8.2.2 Contractor shall prepare and submit to City Engineer a Certification of Payment to Subcontractors and Suppliers form to be attached to each monthly Estimate for Payment or Application for Payment.

9.8.3 A Certificate for Payment, a progress payment, or partial or entire use or occupancy of the Work by the City, does not constitute acceptance of work which is not in accordance with the Contract.

9.9 *DATE OF SUBSTANTIAL COMPLETION*

9.9.1 When Contractor considers the Work, or a portion thereof designated by City Engineer, to be substantially complete, Contractor shall prepare and submit to Project Manager a comprehensive punch list of items to be completed or corrected. Failure to include an item on the punch list does not alter the responsibility of Contractor to comply with the Contract.

9.9.1.1 By submitting the punch list to Project Manager, Contractor represents that work on the punch list will be completed within the time provided for in Subparagraph 9.9.4.3.

9.9.2 Upon receipt of Contractor's punch list, Project Manager will inspect the Work, or designated portion thereof, to verify that the punch list contains all items needing completion or correction. If Project Manager's inspection discloses items not on Contractor's punch list, the items must be added to the punch list of items to be completed or corrected. If Project Manager's inspection reveals that Contractor is not yet substantially complete, Contractor shall complete or correct the deficiencies and request another inspection by Project Manager. The City may recover the costs of re-inspection from Contractor.

9.9.3 Prior to City Engineer's issuing a Certificate of Substantial Completion, Contractor shall also provide:

.1 Certificate of Occupancy for new construction, or Certificate of Compliance for remodeled work, as applicable, and

.2 compliance with Texas Accessibility Standards through state inspection of the Work, if required. If Contractor calls for inspection in a timely manner

and the inspection is delayed through no fault of Contractor, and City Engineer so confirms, City Engineer may, upon request by Contractor, add the inspection to the punch list in Paragraph 9.9.2 and issue a Certificate of Substantial Completion.

9.9.4 When the Work, or designated portion thereof, is determined by City Engineer to be sufficiently complete in accordance with the Contract so the City can occupy or utilize the Work, or designated portion thereof, for the purpose for which it is intended, City Engineer will prepare a Certificate of Substantial Completion that incorporates the punch list in Paragraph 9.9.2 and establishes:

.1 Date of Substantial Completion;

.2 responsibilities of the Parties for security, maintenance, heating, ventilating and air conditioning, utilities, damage to the Work, and insurance; and

.3 fixed time within which Contractor shall complete all items on punch list of items to be corrected accompanying the certificate.

9.9.5 Warranties required by the Contract shall commence on the Date of Substantial Completion unless otherwise provided by City Engineer in Certificate of Substantial Completion. Warranties may not commence on items not substantially completed.

9.9.6 After Date of Substantial Completion and upon application by Contractor and approval by City Engineer, the City may make payment, reflecting adjustment in retainage, if any, as follows:

.1 with the consent of Surety, the City may increase payment to Contractor to 96 percent of Contract Price, less value of items to be completed and accrued liquidated damages.

9.9.7 Contractor shall complete or correct the items in Paragraph 9.9.2 within the time period set out in the Certificate of Substantial Completion. If Contractor fails to do so, the City may issue a Notice of Noncompliance and proceed according to Section 2.5.

9.10 *PARTIAL OCCUPANCY OR USE*

9.10.1 The City may occupy or use any completed or partially completed portion of the Work at any stage, provided the occupancy or use is consented to by Contractor and Contractor's insurer and authorized by public authorities having jurisdiction over the Work. Consent of Contractor to partial occupancy or use may not be unreasonably withheld.

9.10.2 Immediately prior to the partial occupancy or use, Project Manager and Contractor shall jointly inspect the area to be occupied or portion of the Work to be used to determine and record condition of the Work.

9.10.3 Partial occupancy or use of a portion of the Work does not constitute acceptance of work not in compliance with requirements of the Contract.

9.11 *FINAL COMPLETION AND FINAL PAYMENT*

9.11.1 Contractor shall review the Contract and inspect the Work prior to Contractor notification to City Engineer that the Work is complete and ready for final inspection. Contractor shall submit affidavit that the Work has been inspected and that the Work is complete in accordance with requirements of the Contract.

9.11.2 Project Manager will make final inspection within 15 days after receipt of Contractor's written notice that the Work is ready for final inspection and acceptance. If Project Manager finds the Work has been completed in accordance with the Contract, Contractor shall submit items set out in Paragraph 9.11.4 and, for stipulated price contracts, a final Application for Payment. City Engineer will, within 10 days, issue Certificate of Final Completion stating that to the best of City Engineer's knowledge, information, and belief, the Work has been completed in accordance with the Contract, and will recommend acceptance of the Work by City Council.

9.11.3 Should work be found not in compliance with requirements of the Contract, City Engineer will notify Contractor in writing of items of noncompliance. Upon inspection and acceptance of the corrections by Project Manager, compliance with all procedures of Paragraph 9.11.2, and Contractor's submission of the items set out in Paragraph 9.11.4, the City Engineer will issue Certificate of Final Completion to Contractor as provided in Paragraph 9.11.2.

9.11.4 Contractor shall submit the following items to City Engineer before City Engineer will issue a Certificate of Final Completion:

.1 affidavit that payrolls, invoices for materials and equipment, and other indebtedness of Contractor connected with the Work, less amounts withheld by the City, have been paid or otherwise satisfied. If required by City Engineer, Contractor shall submit

further proof including waiver or release of lien or claims from laborers or Suppliers of Products;

.2 certificate evidencing that insurance required by the Contract to remain in force after final payment is currently in effect, will not be canceled or materially changed until at least 30 days written notice has been given to the City;

.3 written statement that Contractor knows of no substantial reason that insurance will not be renewable to cover correction and warranty period required by the Contract;

.4 consent of Surety to final payment; and

.5 copies of record documents, maintenance manuals, tests, inspections, and approvals.

Upon City Engineer's issuance of a Certificate of Final Completion, Contractor may request increase in payment to 99 percent of Contract Price, less accrued liquidated damages.

9.11.5 If Contractor fails to submit required items in Paragraph 9.11.4 within 10 days of Project Manager's inspection of the Work under Paragraph 9.11.2 or Paragraph 9.11.3, City Engineer may, but is not obligated to:

.1 deduct liquidated damages accrued from monies held;

.2 proceed to City Council for acceptance of the Work, minus some or all of the items Contractor fails to submit under Paragraph 9.11.4; and,

.3 upon acceptance by City Council of the portion of the Work completed, make final payment as set out in Paragraph 9.11.8.

9.11.6 If final completion is materially delayed through no fault of Contractor, or by issuance of Change Orders affecting date of final completion, and City Engineer so confirms, the City may, upon application by Contractor and certification by City Engineer, and without terminating the Contract, make payment of balance due for that portion of the Work fully completed and accepted.

9.11.7 If remaining balance due for work not corrected is less than retainage stipulated in the Contract, Contractor shall submit to City Engineer written consent of Surety to payment of balance due for that portion of the Work fully completed and accepted, prior to certification of the payment. The payment is made under terms governing final payment, except that it does not constitute waiver of Claims.

9.11.8 The City will make final payment to Contractor within 30 days after acceptance of the Work by City Council, subject to limitations, if any, as stated in the Contract.

9.11.9 Acceptance of final payment by Contractor shall constitute a waiver of all Claims, whether known or unknown, by Contractor, except those previously made in writing and identified by Contractor as unsettled at time of final Application for Payment.

9.12 *LIQUIDATED DAMAGES*

9.12.1 Contractor, Surety, and the City agree that failure to complete the Work within Contract Time will cause damages to the City and that actual damages from harm are difficult to estimate accurately. Therefore, Contractor, Surety, and the City agree that Contractor and Surety are liable for and shall pay to the City the amount stipulated in Supplementary Conditions as liquidated damages, and that the amount of damages fixed therein is a reasonable forecast of just compensation for harm to the City resulting from Contractor's failure to complete the Work within Contract Time. The amount stipulated will be paid for each day of delay beyond Contract Time until Date of Substantial Completion.

9.12.2 Contractor shall pay the City an amount equal to $1,200.00 per diesel operating vehicle or piece of motorized equipment per incident of high sulfur diesel fuel usage.

ARTICLE 10 - SAFETY PRECAUTIONS

10.1 *SAFETY PROGRAMS*

10.1.1 Contractor is responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with performance of the Contract. Contractor shall submit a safety program to City Engineer prior to mobilizing for the Work, and is solely responsible for safety, efficiency, and adequacy of ways, means, and methods, and for damage which might result from failure or improper construction, maintenance, or operation performed by Contractor.

10.2 *POLLUTANTS AND POLLUTANT FACILITIES*

10.2.1 If Contractor encounters material on-site which it reasonably believes to be a Pollutant or

facilities which it reasonably believes to be a Pollutant Facility, Contractor shall immediately stop work in affected area and immediately notify City Engineer, confirming the notice thereafter in writing.

10.2.2 If City Engineer determines that the material is a Pollutant or facility is a Pollutant Facility, work in affected area may not be resumed except by Modification, and only if the work would not violate applicable laws or regulations.

10.2.3 If City Engineer determines that the material is not a Pollutant or a facility is not a Pollutant Facility, work in affected area will be resumed upon issuance of a Modification.

10.2.4 Contractor is not required to perform, unless authorized by Change Order, work relating to Pollutants or Pollutant Facilities except for that work relating to Pollutants or Pollutant Facilities specified in the Contract.

10.3 *SAFETY OF THE ENVIRONMENT, PERSONS, AND PROPERTY*

10.3.1 Contractor shall take reasonable precautions for safety and shall provide reasonable protection to prevent damage, injury, or loss from all causes, to:

.1 employees performing work on-site, and other persons who may be affected thereby;

.2 work, including Products to be incorporated into the Work, whether in proper storage, under control of Contractor or Subcontractor; and

.3 other property at or adjacent to the site, such as trees, shrubs, lawns, walks, pavements, roadways, structures, utilities, and Underground Facilities not designated for removal or replacement in course of construction.

10.3.2 Contractor shall give notices and comply with applicable laws, ordinances, rules, regulations, and lawful orders of public authorities bearing on safety of persons, property, or environment.

10.3.2.1 Contractor shall comply with requirements of Underground Facility Damage Prevention and Safety Act TEX. UTIL. CODE ANN. Ch. 251 (Vernon Supp. 2002).

10.3.2.2 Contractor shall comply with all safety rules and regulations of the Federal Occupational Health and Safety Act of 1970 and subsequent amendments (OSHA).

10.3.3 Contractor shall erect and maintain, as required by existing conditions and performance of the Contract, reasonable safeguards for safety and protection of persons and property, including posting danger signs and other warnings against hazards, promulgating safety regulations, and notifying owners and users of adjacent sites and utilities.

10.3.4 Contractor shall designate responsible member of Contractor's organization at site whose duty is prevention of accidents. This person will be Contractor's Superintendent unless otherwise designated by Contractor in writing to City Engineer.

10.3.5 Contractor shall prevent windblown dust and may not burn or bury trash debris or waste products on-site. Contractor shall prevent environmental pollution, including but not limited to particulates, gases and noise, as a result of the Work.

10.3.6 When use or storage of hazardous materials or equipment, or unusual methods are necessary for execution of the Work, Contractor shall exercise utmost care and carry on the activities under supervision of properly qualified personnel.

10.3.7 Contractor shall promptly remedy damage and loss to property referred to in Subparagraphs 10.3.1.2 and 10.3.1.3, caused in whole or in part by Contractor, or Subcontractors, which is not covered by insurance required by the Contract. Contractor is not required to remedy damage or loss attributable to the City, Design Consultant, or other contractors.

10.4 *EMERGENCIES*

10.4.1 In emergencies affecting safety of persons or property, Contractor shall act at Contractor's discretion to prevent imminent damage, injury, or loss. Additional compensation or extension of time claimed by Contractor because of emergencies are determined as provided in Article 7.

ARTICLE 11 - INSURANCE AND BONDS

11.1 *GENERAL INSURANCE REQUIREMENTS*

11.1.1 With no intent to limit Contractor's liability under indemnification provisions set forth in Paragraphs 3.25 and 3.26, Contractor shall provide and maintain in full force and effect during term of the Contract and all extensions and amendments

thereto, at least the following insurance and available limits of liability.

11.1.2 If any of the following insurance is written as "claims made" coverage and the City is required to be carried as additional insured, then Contractor's insurance shall include a two-year extended discovery period after last date that Contractor provides any work under the Contract.

11.1.3 Aggregate amounts of coverage, for purposes of the Contract, are agreed to be amounts of coverage available during fixed 12-month policy period.

11.2 *INSURANCE TO BE PROVIDED BY CONTRACTOR*

11.2.1 *Risks and Limits of Liability:* Contractor shall provide at a minimum insurance coverage and limits of liability set out in Table 1.

11.2.1.1 If Limit of Liability for Excess Coverage is $2,000,000 or more, Limit of Liability for Employer's Liability may be reduced to $500,000.

11.2.2 *Form of Policies:* Insurance may be in one or more policies of insurance, form of which is subject to approval by City Engineer. It is agreed, however, that nothing City Engineer does or fails to do with regard to insurance policies relieves Contractor from its duties to provide required coverage and City Engineer's actions or inactions will never be construed as waiving the City's rights.

11.2.3 *Issuers of Policies:* Issuer of any policy shall have:

.1 a Certificate of Authority to transact business in Texas, or

.2 have a Best's rating of at least B+ and a Best's Financial Size Category of Class VI or better, according to the most current edition of Best's Key Rating Guide, and the issuer must be an eligible nonadmitted insurer in the State of Texas.

Each insurer is subject to approval by City Engineer in City Engineer's sole discretion as to conformance with these requirements, pursuant to Paragraph 11.2.2.

11.2.4 *Insured Parties:* The City shall be an Additional Insured under this Contract. Each policy, except those for Workers' Compensation and Owner's and Contractor's Protective Liability, must name the City, its officers, agents, and employees as Additional Insured parties on original policy and all renewals or replacements during term of the Contract. The City's status as Additional Insured under Contractor's insurance does not extend to instances of sole negligence of the City unmixed with any fault of Contractor.

11.2.5 *Deductibles:* Contractor assumes and bears any claims or losses to extent of deductible amounts and waives any claim it may ever have for same against the City, its officers, agents, or employees.

11.2.6 *Cancellation:* Contractor shall notify the Director in writing 30 days prior to any cancellation or material change to Contractor's insurance coverage. Within the 30 day period, Contractor shall provide other suitable policies in lieu of those about to be canceled or nonrenewed so as to maintain in effect the required coverage. If Contractor does not comply with this requirement, the City Engineer, at his or her sole discretion, may:

.1 immediately suspend Contractor from any further performance under this Contract and begin procedures to terminate for default, or

.2 purchase the required insurance with City funds and deduct the cost of the premiums from amounts due to Contractor under this Contract.

11.2.7 *Subrogation:* Contractor waives any claim or right of subrogation to recover against the City, its officers, agents, or employees. Each policy, except professional liability, must contain an endorsement waiving such claim.

11.2.8 *Endorsement of Primary Insurance:* Each policy, except Workers' Compensation policies, must contain an endorsement that the policy is primary insurance to any other insurance available to additional insured with respect to claims arising hereunder.

11.2.9 *Liability for Premium:* Contractor is solely responsible for payment of all insurance premium requirements hereunder and the City is not obligated to pay any premiums.

11.2.10 *Additional Requirements for Workers' Compensation Insurance Coverage:* Contractor shall, in addition to meeting the obligations set forth in Table 1, maintain throughout the term of the Contract Workers' Compensation coverage as required by statute, and Contractor shall specifically comply with requirements set forth in Paragraph 11.2.10. The definitions set out below shall apply only for purposes of this Paragraph 11.2.10.

11.2.10.1 Definitions:

.1 *Certificate of Coverage:* A copy of certificate of insurance, or coverage agreement (TWCC-81, TWCC-82, TWCC-83, or TWCC-84), showing statutory Workers' Compensation insurance coverage for Contractor's, Subcontractor's, or Supplier's employees providing services for the duration of the Contract.

.2 *Duration of the Work:* Includes the time from Date of Commencement of the Work until Contractor's work under the Contract has been completed and accepted by City Council.

.3 *Persons providing services for the Work (Subcontractor in Texas Labor Code § 406.096):* includes all persons or entities performing all or part of services Contractor has undertaken to perform on the Work, regardless of whether that person contracted directly with Contractor and regardless of whether that person has employees. This includes, without limitation, independent contractors, subcontractors, leasing companies, motor carriers, owner-operators, employees of the entity, or employees of entity which furnishes persons to provide services on the Work. Services include, without limitation, providing, hauling, or delivering equipment or materials, or providing labor, transportation, or other service related to the Work. Services do not include activities unrelated to the Work, such as food/beverage vendors, office supply deliveries, and delivery of portable toilets.

11.2.10.2 Contractor shall provide coverage, based on proper reporting of classification codes and payroll amounts and filing of coverage agreements, which meets the statutory requirements of TEX. LAB. CODE ANN., Section 401.011(44) for employees of Contractor providing services on the Work, for duration of the Work.

11.2.10.3 Contractor shall provide a Certificate of Coverage to the City prior to being awarded the Contract.

11.2.10.4 If coverage period shown on Contractor's original Certificate of Coverage ends during duration of the Work, Contractor shall file new Certificate of Coverage with the City showing that coverage has been extended.

11.2.10.5 Contractor shall obtain from each person providing services on the Work, and provide to City Engineer:

.1 Certificate of Coverage, prior to that person beginning work on the Work, so the City will have on file Certificates of Coverage showing coverage for all persons providing services on the Work; and

.2 no later than seven days after receipt by Contractor, new Certificate of Coverage showing extension of coverage, if coverage period shown on current Certificate of Coverage ends during the duration of the Work.

11.2.10.6 Contractor shall retain all required Certificates of Coverage for the duration of the Work and for one year thereafter.

11.2.10.7 Contractor shall notify City Engineer in writing by certified mail or personal delivery, within 10 days after Contractor knew or should have known, of any change that materially affects provision of coverage of any person providing services on the Work.

11.2.10.8 Contractor shall post on-site a notice, in text, form and manner prescribed by Texas Workers' Compensation Commission, informing all persons providing services on the Work that they are required to be covered, and stating how person may verify coverage and report lack of coverage.

11.2.10.9 Contractor shall contractually require each person with whom it contracts to provide services on the Work to:

.1 provide coverage, based on proper reporting of classification codes, payroll amounts and filing of any coverage agreements, which meets statutory requirements of TEX. LAB. CODE ANN., Section 401.011(44) for all its employees providing services on the Work, for the duration of the Work;

.2 provide to Contractor, prior to that person's beginning work on the Work, a Certificate of Coverage showing that coverage is being provided for all employees of the person providing services on the Work, for the duration of the Work;

.3 provide Contractor, prior to the end of the coverage period, a new Certificate of Coverage showing extension of coverage, if the coverage period shown on the current Certificate of Coverage ends during the duration of the Work;

.4 obtain from each other person with whom it contracts, and provide to Contractor: (1) Certificate of Coverage, prior to other person's beginning work on the Work; and (2) new Certificate of Coverage showing extension of coverage, prior to end of coverage period, if coverage period shown on the current Certificate of Coverage ends during duration of the Work.

.5 retain all required Certificates of Coverage on file for the duration of the Work and for one year thereafter;

.6 notify City Engineer in writing by certified mail or personal delivery within 10 days after person knew, or should have known, of change that materially affects provision of coverage of any person providing services on the Work; and

.7 contractually require each person with whom it contracts to perform as required by Paragraphs 11.2.10.1 through 11.2.10.7, with Certificates of Coverage to be provided to person for whom they are providing services.

11.2.10.10 By signing the Contract or providing or causing to be provided a Certificate of Coverage, Contractor is representing to the City that all employees of Contractor who will provide services on the Work will be covered by Workers' Compensation coverage for the duration of the Work, that coverage will be based on proper reporting of classification codes and payroll amounts, and that all coverage agreements will be filed with appropriate insurance carrier. Contractor is not allowed to self-insure Workers' Compensation. Contractor may be subject to administrative penalties, criminal penalties, civil penalties, or other civil actions for providing false or misleading information.

11.2.10.11 Contractor's failure to comply with Paragraph 11.2.10 is a breach of the Contract by Contractor, which entitles the City to declare the Contract void if Contractor does not remedy breach within 10 days after receipt of notice of breach from City Engineer.

11.2.11 *Subcontractor Insurance Requirements:* Contractor shall require Subcontractors and Suppliers to obtain Commercial General Liability, Workers' Compensation, Employer's Liability and Automobile Liability coverage that meets all the requirements of Paragraph 11.2. The amount must be commensurate with the amount of the subcontract, but not less than $500,000 per occurrence. Contractor shall require all Subcontractors with whom it contracts directly, whose subcontracts exceed $100,000, to provide proof of Commercial General Liability and Automobile Liability insurance coverage meeting the above requirements. Contractor shall comply with all requirements set out under Paragraph 11.2.10 as to Workers' Compensation Insurance for all Subcontractors and Suppliers.

TABLE 1
REQUIRED COVERAGE

(Coverage)	(Limit of Liability)
.1 Workers' Compensation	Statutory Limits for Workers' Compensation
.2 Employer's Liability	Bodily Injury by Accident $1,000,000 (each accident) Bodily Injury by Disease $1,000,000 (policy limit) Bodily Injury by Disease $1,000,000 (each employee)
.3 Commercial General Liability: Including Contractor's Protective, Broad Form Property Damage, Contractual Liability, Explosion, Underground and Collapse, Bodily Injury, Personal Injury, Products, and Completed Operations (for a period of one year following completion of the Work).	Combined single limit of $1,000,000 (each occurrence), subject to general aggregate of $1,000,000; Products and Completed Operations $1,000,000 aggregate.
.4 Owner's and Contractor's Protective Liability	$1,000,000 combined single limit each Occurrence/ aggregate
.5 Installation Floater (Unless alternative coverage approved by City Attorney)	Value of stored material or equipment, listed on Certificates of Payments, but not yet incorporated into the Work
.6 Automobile Liability Insurance: (For automobiles furnished by Contractor in course of his performance under the Contract, including Owned, Non-owned, and Hired Auto coverage)	$1,000,000 combined single limit each occurrence for (1) Any Auto or (2) All Owned, Hired, and Non-Owned Autos
.7 Excess Coverage	$1,000,000 each occurrence/combined aggregate in excess of limits specified for Employer's Liability, Commercial General Liability, and Automobile Liability
Aggregate Limits are per 12-month policy period unless otherwise indicated.	

11.3 *PROOF OF INSURANCE*

11.3.1 Prior to commencing services and at time during the term of the Contract, Contractor shall furnish City Engineer with Certificates of Insurance, along with Affidavit from Contractor confirming that Certificate accurately reflects insurance coverage that is available during term of the Contract. If requested in writing by City Engineer, Contractor shall furnish City Engineer with certified copies of Contractor's actual insurance policies. Failure of Contractor to provide certified copies, as requested, may be deemed, at City Engineer's or City Attorney's discretion, a material breach of the Contract.

11.3.2 Notwithstanding the proof of insurance requirements, Contractor shall continuously maintain in effect required insurance coverage set forth in Paragraph 11.2. Failure of Contractor to comply with this requirement does constitute a material breach by Contractor allowing the City, at its option, to immediately suspend or terminate work, or exercise any other remedy allowed under the Contract. Contractor agrees that the City has not waived or is not estopped to assert a material breach of the Contract because of any acts or omissions by the City regarding its review or non-review of insurance documents provided by Contractor, its agents, employees, or assigns.

11.3.3 Contractor shall provide updated certificates of insurance to the Director upon request. The Contractor shall be responsible for delivering a current certificate of insurance in the proper form to the Director as long as Contractor is required to furnish insurance coverage under Paragraph 11.2.

11.3.4 Every certificate of insurance Contractor delivers in connection with this Contract shall

.1 be less than 12 months old;

.2 include all pertinent identification information for the Insurer, including the company name and address, policy

number, NAIC number or AMB number, and authorized signature;

.3 include in the Certificate Holder Box the Project name and reference numbers, contractor's email address, and indicates the name and address of the Project Manager;

.4 include the Contractor's email address in the Certificate Holder Box;

.5 include the Project reference numbers on the City address so the Project reference number is visible in the envelope window; and

.6 be appropriately marked to accurately identify all coverages and limits of the policy, effective and expiration dates, and waivers of subrogation in favor of the City for Commercial General Liability, Automobile Liability, and Worker's Compensation/Employers' Liability.

11.4 *PERFORMANCE AND PAYMENT BONDS*

11.4.1 For Contracts over the value of $25,000, Contractor shall provide Bonds on the City's standard forms covering faithful performance of the Contract and payment of obligations arising thereunder as required in the Contract pursuant to Chapter 2253 of the Government Code. The Bonds must be for 100 percent of Original Contract Price and in accordance with conditions stated on standard City Performance and Payment Bond and Statutory Payment Bond forms. Bonds may be obtained from Contractor's usual source and cost for the Bonds are included in Contract Price.

11.5 *MAINTENANCE BONDS*

11.5.1 *One-year Maintenance Bond:* Contractor shall provide Bond on standard City One-year Maintenance Bond form, providing for Contractor's correction, replacement, or restoration of any portion of the Work which is found to be not in compliance with requirements of the Contract during one-year correction period required in Paragraph 12.2. The Maintenance Bond must be for 100 percent of the Original Contract Price.

11.6 *SURETY*

11.6.1 A Bond that is given or tendered to the City pursuant to the Contract must be executed by a surety company that is authorized and admitted to write surety Bonds in the State of Texas.

11.6.2 If a Bond is given or tendered to the City pursuant to the Contract in an amount greater than 10 percent of Surety's capital and surplus, Surety shall provide certification that Surety has reinsured that portion of the risk that exceeds 10 percent of Surety's capital and surplus. The reinsurance must be with one or more reinsurers who are duly authorized, accredited, or trusted to do business in the State of Texas. The amount reinsured by reinsurer may not exceed 10 percent of reinsurer's capital and surplus. The amount of allowed capital and surplus must be based on information received from State Board of Insurance.

11.6.3 If the amount of a Bond is greater than $100,000, Surety shall:

.1 also hold certificate of authority from the United States Secretary of Treasury to qualify as surety on obligations permitted or required under federal law; or,

.2 Surety may obtain reinsurance for any liability in excess of $100,000 from reinsurer that is authorized and admitted as a reinsurer in the State of Texas and is the holder of a certificate of authority from the United States Secretary of the Treasury to qualify as surety or reinsurer on obligations permitted or required under federal law.

11.6.4 Determination of whether Surety on the Bond or the reinsurer holds a certificate of authority from the United States Secretary of the Treasury is based on information published in Federal Register covering the date on which Bond was executed.

11.6.5 Each Bond given or tendered to the City pursuant to the Contract must be on City forms with no changes made by Contractor or Surety, and must be dated, executed, and accompanied by power of attorney stating that the attorney in fact executing such the bond has requisite authority to execute such Bond. The Bonds must be dated and must be no more than 30 days old.

11.6.6 Surety shall designate in its Bond, power of attorney, or written notice to the City, an agent resident in Harris County to whom any requisite notices may be delivered and on whom service of process may be had in matters arising out of the suretyship.

11.6.7 Contractor shall furnish information to a payment bond beneficiary as required by TEX. GOV'T CODE ANN. CH. 2253.

11.7 *DELIVERY OF BONDS*

11.7.1 Contractor shall deliver required Bonds to the City within time limits stated in Notice of Intent to Award and prior to Date of Commencement of the Work.

ARTICLE 12 - UNCOVERING AND CORRECTION OF THE WORK

12.1 *UNCOVERING OF THE WORK*

12.1.1 If a portion of the Work has been covered which City Engineer has not specifically requested to observe prior to its being covered, City Engineer may request to see such work and it must be uncovered by Contractor. If such work is in accordance with the Contract, the costs of uncovering and covering such work are charged to the City by Change Order. If such work is not in accordance with the Contract, Contractor shall pay for uncovering and shall correct the nonconforming Work promptly after receipt of Notice of Noncompliance to do so.

12.2 *CORRECTION OF THE WORK*

12.2.1 Contractor shall promptly correct or remove work rejected by City Engineer or work failing to conform to requirements of the Contract, whether observed before or after Date of Substantial Completion and whether fabricated, Installed, or completed.

12.2.2 Contractor bears costs of correcting the rejected or nonconforming work including additional testing and inspections, and compensation for Design Consultant's services and expenses made necessary thereby.

12.2.3 If within one year after Date of Substantial Completion, or after date for commencement of warranties established under Paragraph 9.9.5 or by other applicable special warranty required by the Contract, whichever is later in time, any of the Work is found not to be in accordance with the requirements of the Contract, Contractor shall correct such work promptly after receipt of Notice of Noncompliance to do so.

12.2.4 One-year correction period for portions of the Work completed after Date of Substantial Completion will begin on the date of acceptance of that portion of the Work. This obligation under this Paragraph survives acceptance of the Work under the Contract and termination of the Contract.

12.2.5 The one-year correction period does not establish a duration for the Contractor's general warranty under Paragraph 3.12. The City retains the right to recover damages from the Contractor as long as may be permitted by the applicable statute of limitations.

12.2.6 If Contractor does not proceed with correction of the nonconforming work within time fixed by Notice of Noncompliance, the City may correct nonconforming work or remove nonconforming work and store salvageable Products at Contractor's expense. Contractor shall pay the costs of correction of nonconforming work and removal and storage of salvageable Products to the City. If Contractor does not pay costs of the correction or removal and storage within 10 days after written notice, the City may sell the Products at auction or at private sale. The City will account for proceeds thereof after deducting costs and damages that would have been borne by Contractor, including compensation for services of Design Consultant and necessary expenses. If the proceeds of sale do not cover costs which Contractor should have borne, Contractor shall pay the value of the deficiency to the City.

12.2.7 Contractor bears cost of correcting work originally installed by Contractor, the City, or by separate contractors and damaged by Contractor's correction or removal of Contractor's work.

12.3 *ACCEPTANCE OF NONCONFORMING WORK*

12.3.1 If City Engineer prefers to accept work which is not in accordance with requirements of the Contract, City Engineer may do so only by issuance of Change Order, instead of requiring its removal and correction. City Engineer will determine Contract Price reduction. The reduction will become effective even if final payment has been made.

ARTICLE 13 - MISCELLANEOUS PROVISIONS

13.1 *GOVERNING LAWS*

13.1.1 The Contract is subject to the laws of the State of Texas, the City Charter and Ordinances, the laws of the federal government of the United States, and all rules and regulations of any regulatory body or officer having jurisdiction.

13.1.2 Venue for any litigation relating to the Contract is Harris County, Texas.

13.2 *SUCCESSORS*

13.2.1 The Contract binds and benefits the Parties and their legal successors and permitted assigns; however, this Paragraph 13.2.1 does not alter the restrictions on assignment and disposal of assets set out in Paragraph 13.3.1. The Contract does not create any personal liability on the part of any officer or agent of the City.

13.3 *BUSINESS STRUCTURE AND ASSIGNMENTS*

13.3.1 Contractor may not assign the Contract at law or otherwise, or dispose of all or substantially all of its assets without City Engineer's prior written consent. Nothing in this Section, however, prevents the assignment of accounts receivable or the creation of a security interest as described in §9.406 of the Texas Business & Commerce Code. In the case of such an assignment, Contractor shall immediately furnish the City with proof of the assignment and the name, telephone number, and address of the assignee and a clear identification of the fees to be paid to the assignee.

13.3.2 Any series, as defined by the TEX. BUS. ORG. CODE ANN., affiliate, subsidiary, or successor to which Contractor assigns or transfers assets shall join in privity and be jointly and severally liable under this Contract.

13.4 *WRITTEN NOTICE*

13.4.1 All notices required or permitted by the Contract must be in writing and must be effected by hand delivery; registered or certified mail, return receipt requested; or facsimile with confirmation copy mailed to receiving Party. Notice is sufficient if made or addressed with proper postage to the address stated in the Agreement for each Party ("Notice Address") or faxed to the facsimile number stated in the Agreement for each Party. The notice is deemed delivered on the earlier of:

.1 the date the Notice is actually received;
.2 the third day following deposit in a United States Postal Service post office or receptacle; or
.3 the date the facsimile is sent unless the facsimile is sent after 5:00 p.m. local time of the recipient and then it is deemed received on the following day.

Any Party may change its Notice Address or facsimile number at any time by giving written notice of the change to the other Party in the manner provided for in this Paragraph at least 15 days prior to the date the change is affected.

13.5 *RIGHTS AND REMEDIES*

13.5.1 Duties and obligations imposed by the Contract and rights and remedies available thereunder are in addition to and not a limitation of duties, obligations, rights, and remedies otherwise imposed or available by law.

13.5.2 No act or failure to act by the City or Contractor is a waiver of rights or duties afforded them under the Contract, nor is the act or failure to act constitute approval of or acquiescence in a breach of the Contract. No waiver, approval or acquiescence is binding unless in writing and, in the case of the City, signed by City Engineer.

13.6 *TESTS AND INSPECTIONS*

13.6.1 Contractor shall give City Engineer, Construction Manager, and Design Consultant timely notice of the time and place where tests and inspections are to be made. Contractor shall cooperate with inspection and testing personnel to facilitate required inspections or tests.

13.6.2 The City will employ and pay for services of an independent testing laboratory to perform inspections or acceptance tests required by the Contract except:

.1 inspections or tests covered by Paragraph 13.6.3;
.2 those otherwise specifically provided in the Contract; or
.3 costs incurred in connection with tests or inspections conducted pursuant to Paragraph 12.2.2.

13.6.3 Contractor is responsible for and shall pay all costs in connection with inspection or testing required in connection with City Engineer's acceptance of a Product to be incorporated into the Work, or of materials, mix designs, or equipment submitted for approval prior to Contractor's purchase thereof for incorporation into the Work.

13.6.4 Neither observations by the City, Construction Manager, or Design Consultant, nor inspections, tests, or approvals by others, relieves Contractor from Contractor's obligations to perform the Work in accordance with the Contract.

13.7 *INTEREST*

13.7.1 No interest will accrue on late payments by the City except as provided under Chapter 2251 of the Government Code.

13.8 *PARTIES IN INTEREST*

13.8.1 The Contract does not bestow any rights upon any third party, but binds and benefits the Parties only.

13.9 *ENTIRE CONTRACT*

13.9.1 The Contract merges the prior negotiations and understandings of the Parties and embodies the entire agreement of the Parties. No other agreements, assurances, conditions, covenants, express or implied, or other terms of any kind, exist between the Parties regarding the Contract.

13.10 *WRITTEN AMENDMENT*

13.10.1 Changes to the Contract that cannot be effected by Modifications, must be made by written amendment, which will not be effective until approved by City Council.

13.11 *COMPLIANCE WITH LAWS*

13.11.1 Contractor shall comply with the Americans with Disabilities Act of 1990 as amended (ADA) and Texas Architectural Barriers Act and all regulations relating to either statute.

13.11.2 Contractor shall comply with all applicable federal, state, and city laws, rules and regulations.

13.12 *SEVERABILITY*

13.12.1 If any part of the Contract is for any reason found to be unenforceable, all other parts remain enforceable to the extent permitted by law.

ARTICLE 14 - TERMINATION OR SUSPENSION OF THE CONTRACT

14.1 *TERMINATION BY THE CITY FOR CAUSE*

14.1.1 Each of the following acts or omissions of Contractor or occurrences shall constitute an "Event of Default" under the Contract:

.1 Contractor refuses or fails to supply enough properly skilled workers or proper Products;

.2 Contractor disregards laws, ordinances, rules, regulations, or orders of a public authority having jurisdiction;

.3 Contractor is guilty of material breach of any duty or obligation of Contractor under the Contract;

.4 Contractor has had any other contract with the City terminated for cause at any time subsequent to the effective date of the Contract as set out in the Agreement; or

.5 Contractor fails to utilize Ultra Low Sulfur Diesel Fuel, as required in Paragraph 3.9.1.1.

14.1.2 If an Event of Default occurs, City Engineer may, at his option and without prejudice to any other rights or remedies which the City may have, deliver a written notice to Contractor and Surety describing the Event of Default and giving the Contractor 10 days to cure the Event of Default. If after the cure period, Contractor has failed or refused to cure the Event of Default, then City Engineer may deliver a second written notice to Contractor giving notice of the termination of the Contract or of the termination of Contractor's performance under the Contract ("Notice of Termination"). If City Engineer issues a Notice of Termination, then City Engineer may, subject to any prior rights of Surety and any other rights of the City under the Contract or at law:

.1 request that Surety complete the Work; or

.2 take possession of the site and all materials, equipment, tools, and construction equipment and machinery on the site owned by Contractor; and

.3 finish the Work by whatever reasonable method City Engineer may deem expedient.

14.1.3 After Contractor's receipt of a Notice of Termination, and except as otherwise directed in writing by City Engineer, Contractor shall:

.1 stop the Work on the date and to the extent specified in the Notice of Termination;

.2 place no further orders or subcontracts for Products or services;

.3 terminate all orders and subcontracts to the extent that they relate to performance of work terminated;

.4 assign to the City, in the manner, at the times, and to the extent directed by City Engineer, all rights, title, and interest of Contractor, under the terminated supply orders and subcontracts. The City may settle or pay claims arising out of termination of the orders and subcontracts;

.5 settle all outstanding liabilities and all claims arising out of the termination of supply orders and subcontracts with approval of City Engineer;

.6 take action as may be necessary, or as City Engineer may direct, for protection and preservation of property related to the Work that is in possession of Contractor, and in which the City has or may acquire an interest; and

.7 secure the Work in a safe state before leaving the site, providing any necessary safety measures, shoring, or other devices.

14.1.4 If the City terminates the Contract or terminates Contractor's performance under the Contract for any one or more of the reasons stated in Paragraph 14.1.1, Contractor may not receive any further payment until the Work is complete, subject to Paragraph 14.1.5.

14.1.5 If the unpaid balance of Contract Price exceeds the costs of finishing the Work, including liquidated damages and other amounts due under the Contract, the balance will be paid to Contractor. If the costs of finishing the Work exceed the unpaid balance, Contractor shall, within 10 days of receipt of written notice setting out the amount of the excess costs, pay the difference to the City. The amount to be paid to Contractor or the City will be certified by City Engineer in writing, and this obligation for payment shall survive termination of the Contract or termination of Contractor's performance under the Contract. Termination of the Contractor for cause shall not relieve the Surety from its obligation to complete the project.

14.2 *TERMINATION BY THE CITY FOR CONVENIENCE*

14.2.1 City Engineer may, without cause and without prejudice to other rights or remedies of the City, give Contractor and Surety a Notice of Termination with a seven days written notice.

14.2.2 After receipt of the Notice of Termination, and except as otherwise approved by City Engineer, Contractor shall conform to requirements of Paragraph 14.1.3.

14.2.3 After receipt of the Notice of Termination, Contractor shall submit to the City its termination Claim, in forms required by City Engineer. The Claim will be submitted to the City promptly, but no later than six months from the effective date of termination, unless one or more extensions are granted by City Engineer in writing. If Contractor fails to submit its termination Claim within the time allowed, in accordance with Paragraph 14.2.4, City Engineer will determine, on the basis of available information, the amount, if any, due to Contractor because of termination, and City Engineer's determination is final and binding on the Parties. The City will then pay to Contractor the amount so determined.

14.2.4 City Engineer will determine, on the basis of information available to City Engineer, the amount due, if any, to Contractor for the termination as follows:

.1 Contract Price for all work performed in accordance with the Contract up to the date of termination determined in the manner prescribed for monthly payments in Article 9, except no retainage is withheld by the City either for payment determined by percentage of completion or for materials and equipment delivered to the site, in storage or in transit.

.2 Reasonable termination expenses, including costs for settling and paying Subcontractor and Supplier claims arising out of termination of the Work, reasonable cost of preservation and protection of the City's property after termination, if required, and the cost of Claim preparation. Termination expenses do not include field or central office overhead, salaries of employees of Contractor, or litigation costs, including attorneys' fees.

No amount is allowed for anticipated profit or central office overhead on uncompleted work, or any cost or lost profit for other business of Contractor alleged to be damaged by the termination.

14.2.5 Contractor shall promptly remove from the site any construction equipment, tools, and temporary facilities, except the temporary facilities which City Engineer may wish to purchase and retain.

14.2.6 Contractor shall cooperate with City Engineer during the transition period.

14.2.7 The City will take possession of the Work and materials delivered to the site, in storage, or in transit, as of date or dates specified in the Notice of Termination, and is responsible for maintenance, utilities, security, and insurance, as stated in Notice of Termination.

14.3 *SUSPENSION BY THE CITY FOR CONVENIENCE*

14.3.1 City Engineer may, without cause, after giving Contractor and Surety 24-hour prior written

notice, order Contractor to suspend, delay, or interrupt the Work in whole or in part for a period of time as City Engineer may determine.

14.3.2 An adjustment will be made in Contract Time equivalent to the time of suspension.

14.3.3 Adjustment will be made to Contract Price for increases in the cost of performance of the Work, including profit on increased cost of performance caused by suspension, delay, or interruption of the Work in accordance with Paragraph 7.3. No adjustment will be made to the extent that:

.1 performance was, or would have been, suspended, delayed, or interrupted by another cause for which Contractor is responsible; or

.2 adjustment is made or denied under another provision of the Contract.

14.4 *TERMINATION BY CONTRACTOR*

14.4.1 Contractor may terminate the Contract if the Work is stopped for a period of 30 days through no act or fault of Contractor, directly related to one of these events:

.1 issuance of an order of a court or other public authority having jurisdiction;

.2 act of government, such as a declaration of national emergency which makes material unavailable; or

.3 if repeated suspensions, delays, or interruptions by the City as described in Paragraph 14.3 constitute, in the aggregate, more than 100 percent of the total number of days scheduled for completion, or 120 days in any 365-day period, whichever is less;

No termination will be effective for the above reasons if Contractor delivers written notice to City Engineer describing the reason for termination, giving the proposed termination date, and granting the City a reasonable opportunity to respond and cure any City default before termination is effective.

14.4.2 If the Contract is terminated pursuant to this Paragraph 14.4, Contractor shall comply with the requirements of Paragraphs 14.2.2 through 14.2.7.

END OF DOCUMENT

Document 00800

SUPPLEMENTARY CONDITIONS

The following Paragraphs amend and supplement the January 1, 2015 edition of General Conditions. Unaltered portions of General Conditions remain in effect.

ARTICLE 1 - GENERAL PROVISIONS:

1.1 *DEFINITIONS*: *Insert the following Paragraph 1.1.23, and reorder the remaining definitions accordingly.*

1.1.23 *Good Faith Efforts.* Steps taken to achieve an MBE, WBE, SBE, or PDBE goal or other requirements which, by their scope, intensity, and usefulness, demonstrate the bidder's responsiveness to fulfill the business opportunity objective, as well as the Contractor's responsibility to put forth measures to meet or exceed the MBE, WBE, SBE, or PDBE goal (Contract Goal). These steps apply from before a contract's award, through its duration, and after its conclusion, in the event the Contractor has been unsuccessful in meeting the Contract Goal. These efforts are required whether a Goal Oriented Contract or a Regulated Contract, as defined in the Office of Business Opportunity's Policy & Procedures Manual, available at http://www.houstontx.gov/obo.

ARTICLE 3 - THE CONTRACTOR

3.5 *LABOR*: *Insert the following Paragraphs, 3.5.3.1.1, 3.5.3.1.2 and3.5.3.1.3.*

3.5.3.1.1 If the Original Contract Price is greater than One Million Dollars, Contractor shall make Good Faith Efforts to comply with the City ordinances regarding Minority Business Enterprises (MBE), Women Business Enterprises (WBE), Persons with Disabilities Business Enterprises (PDBE) and Small Business Enterprise (SBE) participation goals which are as follows:

.1 the MBE goal is 11% percent,

.2 the WBE goal is 7% percent, and

.3 the PDBE goal is 0% percent.

.4 The bidder may substitute SBE participation of no more than four percent of the MBE goal, the WBE goal, or portions of the MBE Goal and WBE Goal.

3.5.3.1.2 The MBE, WBE, PDBE, and SBE goals are specific to this Agreement. The Contractor shall make reasonable efforts to achieve these goals.

3.5.3.1.3 Failure by Contractor to comply with the goals for MBE, WBE, SBE, or PDBE is a material breach of the Agreement, which may result in termination of the Agreement, or such other remedy permitted as the City deems appropriate.

ARTICLE 8 - TIME

8.1 *PROGRESS AND COMPLETION: Add the following Paragraph 8.1.6.1.*

8.1.6.1 Contractor shall credit the City by Change Order for inspection services for overtime work or work performed on Sundays or Legal Holidays. The amount Contractor credits the City will be [$50.00 per hour] per inspector for inspection services.

ARTICLE 9 - PAYMENTS AND COMPLETION

9.12 *LIQUIDATED DAMAGES: Insert the following Paragraph 9.12.1.1.*

9.12.1.1 The amount of liquidated damages payable by Contractor or Surety for each and every day of delay beyond Contract Time, are $1,200.00 per day.

ARTICLE 11 - INSURANCE AND BONDS

11.2 INSURANCE TO BE PROVIDED BY CONTRACTOR: Insert the following Paragraph 11.2.1.2.

11.2.1.2 Contractor shall purchase for the duration of the Contract the insurance set out in Table 2 in addition to the minimum insurance coverage set out in section 11.2.1.

TABLE 2
ADDITIONAL REQUIRED COVERAGE
DEFENSE COSTS EXCLUDED FROM FACE AMOUNT OF POLICY.

(Coverage)	(Limit of Liability)
Property and Casualty Coverage: "All Causes of Loss" Builder's Risk Form for directing physical change to building or plant construction on the Work site and/or all land improvements including all work. (Including but not limited to earthquake, flood, boiler, and machinery including testing, damage to existing or adjoining property, time element coverage, collapse, soft costs	100% of Contract Price, including change orders

(management, architecture, financial costs, pre-opening costs, etc.), transit coverage, off-site storage).

END OF DOCUMENT

Document 00805

EQUAL EMPLOYMENT OPPORTUNITY PROGRAM REQUIREMENTS
(City of Houston Information Requirements
for the Successful Bidder on All Construction Contracts)

DOCUMENTS THAT MUST BE SIGNED AND RETURNED TO THE CITY OF HOUSTON PRIOR TO FINAL EXECUTION OF CONTRACT

Certification by Bidder Regarding Equal Employment Opportunity EEO-3

Total Work Force Composition of the Company,..... EEO-6
or in lieu thereof, a copy of the latest Equal Employment Opportunity Commission's EEO-1 form (This information is required only if the Contractor has a work force of 50 or more people and the Contract is $50,000 or more.)

Company's Equal Employment Opportunity Compliance Program EEO-7

INFORMATION THAT MUST BE SUPPLIED DURING THE COURSE OF THE WORK

Certification By Proposed Subcontractor Regarding
Equal Employment Opportunity EEO-26

Certification by Proposed Material Suppliers, Lessors,and
Professional Service Providers Regarding Equal Employment Opportunity..... EEO-29

PLEASE COMPLETE PAGES EEO-3 THROUGH EEO-7 AND MAIL TO:

City of Houston
Mayor's Office of Business Opportunity
Contract Compliance Section
611 Walker, 7th Floor
Houston, Texas 77002
Attention: Director

The remainder of the reports can be mailed at the appropriate time.

EQUAL EMPLOYMENT OPPORTUNITY PROGRAM REQUIREMENTS

The following are Equal Employment Opportunity requirements to be met and documents to be submitted to:

Mayor's Office of Business Opportunity
Contract Compliance Section
611 Walker, 7th Floor
Houston, Texas 77002

Under the conditions and terms of all City construction contracts, the prime contractor is responsible for all Equal Employment Opportunity compliance, including subcontractor compliance.

EQUAL EMPLOYMENT OPPORTUNITY FORMS (EEO Forms)

These forms are submitted by the prime contractors at the beginning of the Project and as requested:

- EEO Forms 3, 6, and 7, by prime contractors

This form is submitted by all subcontractors before they begin work on the project:

- EEO Form 26 by subcontractors

This form is submitted by all suppliers, lessors, or professional services providers before they begin work on the project:

- EEO Form 29

POSTING

The following poster should be clearly displayed on each job site, or in case of annual service agreements, in the Contractor's office:

Equal Employment Opportunity is the Law Poster

JOB SITE VISITS

Site visits will be made by a Contract Compliance Officer, who will make their presence known to the Project Manager, Supervisor, or Foreman, and will conduct interviews with employees on site.

PAYMENT AND EVALUATION

Upon completion of the Project, as part of the contract-awarding department's total clearance process, the Office of Business Opportunity's Contract Compliance Section must certify to the department that all EEO compliance requirements have been met.

CERTIFICATION BY BIDDER REGARDING
EQUAL EMPLOYMENT OPPORTUNITY

GENERAL

In accordance with Executive Order 11246 (30 F.R. 12319-25), the implementing rules and regulations thereof, and orders of the Secretary of Labor, a certification regarding Equal Opportunity is required of bidders or prospective contractors and their proposed subcontractors prior to the award of contracts or subcontracts.

CERTIFICATION OF BIDDER

Bidder's Name:_____

Address:_____

Telephone Number:_____ Fax :_____

Name of the Company's EEO Officer: _____

E-mail Address:_____

Web Page/URL Address:_____

IRS Employer Identification Number:_____

Work to be performed:_____

Project No:_____

1. Participation in a previous contract or subcontract.

   a. Bidder has participated in a previous contract or subcontract subject to the Equal Opportunity Clause. ☐ YES ☐ NO

   b. Compliance reports were required to be filed in connection with such contract or subcontract. ☐ YES ☐ NO

   c. Bidder has filed all compliance reports required by Executive Orders 10925, 11114, 11246, or by regulations of the Equal Employment Opportunity Commission issued pursuant to Title VII of the Civil Rights Act of 1964. ☐ YES ☐ NO

   d. If answer of item c. is "No", please explain in detail on reverse side of this certification.

2. Dollar amount of bid:$ _____

3. Anticipated performance period in days: _____

4. Expected total number of employees to perform the proposed construction: _____

5. Nonsegregated facilities.

a. Notice to prospective federally-assisted construction contractors

(1) A Certification of Nonsegregated Facilities, as required by the May 9, 1967, Order (32 F.R. 7439, May 19, 1967) on Elimination of Segregated Facilities, by the Secretary of Labor, must be submitted to the recipient prior to the award of a federally-assisted construction contract exceeding $10,000 which is not exempt from the provisions of the Equal Opportunity Clause.

(2) Contractors receiving federally-assisted construction contract awards exceeding $10,000 which are not exempt from the provisions of the Equal Opportunity Clause will be required to provide the forwarding of the following notice to prospective subcontractors for supplies and construction contracts where the subcontracts exceed $10,000 and are not exempt from the provisions of the Equal Opportunity Clause.

The federally-assisted construction Contractor certifies that he/she does not maintain or provide any segregated facilities at any of his/her establishments, and does not permit employees to perform their services at any location, under his/her control, where segregated facilities are maintained. The federally-assisted construction Contractor certifies further that he/she will not maintain or provide segregated facilities at any of his/her establishments, and will not permit employees to perform their services at any location, under his/her control, where segregated facilities are maintained. The federally-assisted construction Contractor agrees that a breach of this certification is a violation of the Equal Opportunity Clause in this Contract. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive or are in fact segregated on the basis of race, creed, color, or national origin because of habit, local custom, or otherwise. The federally-assisted construction Contractor agrees that (except where he/she has obtained identical certifications from proposed Subcontractors for specific time periods) he/she will obtain identical certifications in duplicate from proposed Subcontractors prior to the award of subcontracts exceeding $10,000 which are not exempt from the provisions of the Equal Opportunity Clause, and that he/she will retain the duplicate of such certifications in his/her files. The Subcontractor will include the original in his/her bid package.

6. Race or ethnic group designation of bidder. Enter race or ethnic group in appropriate box:

☐ White ☐ Black ☐ Hispanic

☐ Pacific Islander, Asian ☐ American Indian, Aleut.

7. Gender of Owner ☐ Male ☐ Female

REMARKS: _____

Certification - The information above is true and complete to the best of my knowledge and belief.

_____
Company Officer (Please Type)

_____ _____
Signature Date

NOTE: The penalty for making false statements in offers is prescribed in 18 U.S.C. 1001.

Total Work Force Composition of the Company

City of Houston, Affirmative Action Requirements for All Construction Contracts

	White		Black		Hispanic		Pacific Islander/ Asian		Alaska Native/ Amer Ind.		Total Persons		Total Minority		Total Female	
	M	F	M	F	M	F	M	F	M	F	M	F	M	F	M	F
Officials and Administrators																
Professionals																
Paraprofessionals																
Technicians																
Protective Service Workers																
Sales Workers																
Office and Clerical																
Skilled Craft Workers																
Operatives (Semi-skilled)																
Laborers (Unskilled)																
Service / Maintenance Workers																
Others																
Total																

This report includes all of the company's permanent work force. For description of job categories, see Pages CC-27 through CC-29.

Check One: [ ] Contractor [ ] Subcontractor DATE: _____

COMPANY: _____

EQUAL EMPLOYMENT OPPORTUNITY COMPLIANCE PROGRAM FOR

_____

Name of Company

The Company's Office of Business Opportunity Program shall consist of documented good faith efforts to comply with the goals, timetables, and objectives set forth in the following Affirmative Action steps:

A. City of Houston's Specific Equal Employment Opportunity Policy and Clause as contained in City Council Ordinance No. 78-1538, passed August 9, 1978.

B. Notice of Requirement for Office of Business Opportunity to ensure Equal Employment Opportunity (Executive Order 11246).

C. Standard Federal Equal Employment Opportunity Construction Contract Specifications (Executive Order 11246).

Project: _____

_____
Company Officer (Please Type)

_____ _____
Signature Date

NOTE: The penalty for making false statements in offers is prescribed in 18 U.S.C. 1001.

SPECIAL PROVISIONS

SPECIFIC EQUAL EMPLOYMENT OPPORTUNITY POLICY

1. GENERAL

   a. Equal employment opportunity requirements not to discriminate and to take affirmative action to assure equal employment opportunity are required by Executive Order 11246, as amended. The requirements set forth in these Special Provisions shall constitute the specific affirmative action requirements for Project activities under this Contract and shall supplement the notice of requirement for affirmative action to ensure equal employment opportunity and standard federal equal employment opportunity construction contract specifications.

   b. The Contractor shall work with the City and the Federal Government in carrying out equal employment opportunity obligations and in their review of his/her activities under the Contract.

   c. The prime Contractor and all Subcontractors holding subcontracts of $10,000 or more shall comply with the following minimum specific requirement activities of equal employment opportunity. The Contractor shall include these requirements in every subcontract of $10,000 or more with such modification of language as is necessary to make them binding on the Subcontractor.

2. EQUAL EMPLOYMENT OPPORTUNITY POLICY

   The Contractor shall accept as his/her operating policy the following statement which is designed to further the provision of equal employment opportunity to all persons without regard to their race, age, color, religion, sex, or national origin, and to promote the full realization of equal employment opportunity through a positive continuing program:

   It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, color, sex, or national origin. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship.

3. EQUAL EMPLOYMENT OPPORTUNITY OFFICER

   The Contractor shall designate and make known to the City contracting officers an equal employment opportunity officer (hereinafter referred to as the EEO Officer) who must be capable of effectively administering and promoting an active Contractor program of equal employment opportunity and who must be assigned adequate authority and responsibilities to do so.

4. DISSEMINATION OF POLICY

a. All members of the Contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement the Contractor's equal employment opportunity policy and contractual responsibilities to provide equal employment opportunity in each grade and classification of employment. To ensure that the above agreement will be met, the following actions shall be taken as a minimum:

(1) Periodic meetings of supervisory and personnel office employees shall be conducted before the start of work and then not less often than once every six months, at which time the Contractor's equal employment opportunity policy and its implementation will be reviewed and explained. The meetings shall be conducted by the EEO Officer or other knowledgeable company official.

(2) All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, or other knowledgeable company official, covering all major aspects of the Contractor's equal employment opportunity obligations, within 30 days following their reporting for duty with the Contractor.

(3) The EEO Officer or appropriate company official shall instruct all employees engaged in the direct recruitment of employees for the Project relative to the methods followed by the Contractor in locating and hiring minorities and females.

b. In order to make the Contractor's equal employment opportunity policy known to all employees, prospective employees, and potential sources of employees, i.e., schools, employment agencies, labor unions (where appropriate), college placement officers, etc., the Contractor shall take the following actions:

(1) Notices and posters setting forth the Contractor's equal employment opportunity policy shall be placed in areas readily accessible to employees, applicants for employment, and potential employees.

(2) The Contractor's equal employment opportunity policy and the procedures to implement such policy shall be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

5. RECRUITMENT

a. When advertising for employees, the Contractor shall include in all advertisements for employees the notation "An Equal Opportunity Employer". All such advertisements will be published in newspapers, or

other publications, having a large circulation among minority groups in the area from which the Project work force would normally be derived.

b. The Contractor shall, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee-referral sources likely to yield qualified minority-group applicants, including, but not limited to, State employment agencies, schools, colleges, minority-group organizations, and female recruitment agencies. To meet this requirement, the Contractor shall, through his/her EEO Officer, identify sources of potential minority and female employees, and establish with such identified sources procedures whereby such group applicants may be referred to the Contractor for employment consideration.

In the event the Contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he/she is expected to observe the provisions of that agreement to the extent that the system permits the Contractor's compliance with equal employment opportunity Contract provisions. (The U. S. Department of Labor has held that where implementation of such agreements has the effect of discriminating against minorities or women, or obligates the Contractor to do the same, such implementation violates Executive Order 11246 as amended).

c. The Contractor shall encourage his/her present employees to refer female or minority-group applicants for employment by posting appropriate notices or bulletins in areas accessible to all such employees. In addition, information and procedures with regard to referring such applicants will be discussed with employees.

6. PERSONNEL ACTIONS

a. Wage, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff and termination, shall be taken without regard to race, color, religion, sex, national origin, or age. The following procedures shall be followed:

(1) The Contractor shall conduct periodic inspections of Project sites to ensure that working conditions and employee facilities do not indicate discriminatory treatment of Project-site personnel.

(2) The Contractor shall periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.

(3) The Contractor shall periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the Contractor shall promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

(4) The Contractor shall promptly investigate all complaints of alleged discrimination made in connection with his/her obligations under this Contract, shall attempt to resolve such complaints, and shall take appropriate corrective action. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the Contractor shall inform every complainant of all avenues of appeal.

7. TRAINING AND PROMOTION

a. The Contractor shall assist in locating, qualifying, and increasing the skills of minority-group and women employees and applicants for employment.

b. Consistent with the Contractor's work force requirements and as permissible under Federal and State regulations, the Contractor shall make full use of training programs, i.e., apprenticeship and on-the-job training programs, for the geographical area of Contract performance.

c. The Contractor shall advise employees and applicants for employment of available training programs and entrance requirements for each.

d. The Contractor shall periodically review the training and promotion potential of minority-group and women employees and shall encourage eligible employees to apply for such training and promotion.

8. UNIONS

If the Contractor relies in whole or in part upon unions as a source of employees, he/she shall use his/her best efforts to obtain the cooperation of such unions to increase minority groups and women within the unions, and to effect referrals by such unions of minority and female employees. Actions by the Contractor, either directly or through a contractor's association acting as his/her agent, will include the procedures set forth below:

a. The Contractor shall use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority-group members and women for membership in the unions and increasing the skills of minority-group employees and women so that they may qualify for higher-paying employment.

b. The Contractor shall use best efforts to incorporate an equal employment opportunity clause into all union agreements to the end that such unions will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, or age.

c. The Contractor is to obtain information as to the referral practices and policies of the labor union, except that to the extent such information is within the exclusive possession of the labor union, and such labor union refuses to furnish such information to the Contractor, the Contractor shall so certify to the City and shall set forth what efforts have been made to obtain such information.

d. In the event the union is unable to provide the Contractor with a reasonable flow of minority and women referrals within the time limit set forth in the collective bargaining agreement, the Contractor shall, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, age, sex, or national origin, making full efforts to obtain qualified and/or qualifiable minority group persons and women. (The U. S. Department of Labor has held that it shall be no excuse that the union with which the Contractor has a collective bargaining agreement providing for exclusive referral failed to refer minority employees.) In the event the union referral practice prevents the Contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such Contractor shall immediately notify the City.

9. SUBCONTRACTING

a. The Contractor shall use his/her best efforts to solicit bids from and to utilize minority-group and female subcontractors or subcontractors with meaningful minority-group and/or female representation among their employees.

b. The Contractor shall use his/her best efforts to assure Subcontractors' compliance with their equal employment opportunity obligations.

10. RECORDS AND REPORTS

a. The Contractor shall keep such records as are necessary to determine compliance with the Contractor's equal employment opportunity obligations. The records kept by the Contractor will be designed to indicate:

(1) The number of minority and non-minority group members and women employed in each work classification on the Project.

(2) The progress and efforts being made in cooperation with unions to increase employment opportunities for minorities and women (applicable only to contractors who rely in whole or in part on unions as a source of their work force).

(3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees.

(4) The progress and efforts being made in securing the services of female and minority subcontractors.

b. All records, including payrolls, must be retained for a period of three years following completion of the Contract work and shall be available at reasonable times and places for inspection by authorized representatives of the City and/or the appropriate federal agency.

CITY OF HOUSTON, TEXAS

EQUAL EMPLOYMENT OPPORTUNITY CLAUSE

Pursuant to City Council Ordinance No. 78-1538, passed August 9, 1978, all contracts entered into by the City of Houston involving the expenditure of $10,000 or more, shall incorporate the following Equal Employment Opportunity Clause:

1. The Contractor, Subcontractor, vendor, Supplier, or lessee shall not discriminate against any employee or applicant for employment because of race, religion, color, sex, national origin, or age. The Contractor, Subcontractor, vendor, Supplier, or lessee shall take affirmative action to ensure that applicants are employed and that employees are treated during employment without regard to their race, religion, color, sex, national origin, or age. Such action will include, but not be limited to, the following: employment; upgrading; demotion or transfer; recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor, Subcontractor, vendor, Supplier, or lessee agrees to post in conspicuous places available to employees, and applicants for employment, notices to be provided by the City setting forth the provisions of this Equal Employment Opportunity Clause.

2. The Contractor, Subcontractor, vendor, Supplier, or lessee states that all qualified applicants will receive consideration for employment without regard to race, religion, color, sex, national origin, or age.

3. The Contractor, Subcontractor, vendor, Supplier, or lessee shall send to each labor union or representatives of workers with which it has a collective bargaining agreement or other contract or understanding, a notice to be provided by the agency contracting officer advising the said labor union or workers' representative of the Contractor's and Subcontractor's commitments under Section 202 of Executive Order No. 11246, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.

4. The Contractor, Subcontractor, vendor, Supplier, or lessee will comply with all provisions of Executive Order No. 11246 and the rules, regulations, and relevant orders of the Secretary of Labor or other Federal Agency responsible for enforcement of the equal opportunity and affirmative action provisions applicable, and shall likewise furnish all information and reports required by the Mayor and/or Contractor Compliance Officers for purposes of investigation to ascertain and effect compliance with this program.

5. The Contractor, Subcontractor, vendor, Supplier, or lessee shall furnish all information and reports required by Executive Order No. 11246, and by the rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and shall permit access to all books, records, and accounts by the appropriate City and Federal officials for purposes of investigation to ascertain compliance with such rules, regulations, and orders. Compliance reports filed at such times as directed shall contain information as to the employment practice policies, program, and work force statistics of the Contractor, Subcontractor, vendor, Supplier, or lessee.

6. In the event of a Contractor's, Subcontractor's, vendor's, Supplier's, or lessee's non-compliance with the non-discrimination clause of this Contract or with any of such rules, regulations, or orders, this Contract may be canceled, terminated, or suspended in whole or in part, and the Contractor, Subcontractor, vendor, Supplier, or lessee may be declared ineligible for further City contracts in accordance with procedures provided in Executive Order No. 11246, and such other sanctions may be imposed and remedies invoked as provided in said Executive Order, or by rule, regulation, or order of the Secretary of Labor, or as may otherwise be provided by law.

7. The Contractor shall include the provisions of paragraphs 1 through 8 of this Equal Employment Opportunity Clause in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to Section 204 of Executive Order No. 11246 of September 24, 1965 so that such provisions will be binding upon each Subcontractor or vendor. The Contractor shall take such action with respect to any subcontractor or purchase order as the contracting agency may direct as a means of enforcing such provisions, including sanctions for noncompliance; provided, however, that in the event the Contractor becomes involved in, or is threatened with litigation with a Subcontractor or vendor as a result of such direction by the contracting agency, the Contractor may request the United States to enter into such litigation to protect the interests of the United States.

8. The Contractor shall file and shall cause each of his Subcontractors, if any, to file compliance reports with the City in the form and to the extent as may be prescribed by the Mayor's Office of Business Opportunity. Compliance reports filed at such times as directed shall contain information as to the practices, policies, programs, employment policies, and employment statistics of the Contractor and each Subcontractor.

NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION
TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY
(EXECUTIVE ORDER 11246)

1. The Offeror's or Bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth herein.

2. The goals and timetables for minority and female participation, expressed in percentage terms for the Contractor's aggregate work force in each trade on all construction work in the covered area, are as follows:

Timetable	Goals for Minority Participation for Each Trade	Goals for Female Participation for Each Trade
	26.2% - 27.3%	6.9%

These goals are applicable to all the Contractor's construction work (whether or not it is Federal or Federally-assisted) performed in the covered area.

The Contractor's compliance with the Executive Order and the regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals established for the geographical area where the Contract resulting from this solicitation is to be performed. The hours of minority and female employment and training must be substantially uniform throughout the length of the Contract, and in each trade, and the Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be a violation of the Contract, the Executive Order, and regulations in 41 CFR part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The Contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within 10 working days of award of any construction subcontract in excess of $10,000 at any tier for construction work under the Contract resulting from this solicitation. The notification shall list the name, address, and telephone number of the Subcontractor; employer identification number; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the Contract is to be performed.

4. As used in this Notice, and in the Contract resulting from this solicitation, the "covered area" is The Houston, Texas Standard Metropolitan Statistical Area.

STANDARD FEDERAL EQUAL EMPLOYMENT OPPORTUNITY
CONSTRUCTION CONTRACT SPECIFICATIONS
(EXECUTIVE ORDER 11246)

1. As used in these specifications:

   a. "Covered area" means the geographical area described in the solicitation from which this Contract resulted;

   b. "Director" means Director, Office of Federal Contract Compliance Programs, United States Department of Labor, or any person to whom the Director delegates authority;

   c. "Employer identification number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U. S. Treasury Department Form 941.

   d. "Minority" includes:

      (i) Black (all persons having origins in any of the Black African racial groups not of Hispanic origin);

      (ii) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American, or other Spanish culture or origin regardless of race);

      (iii) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and

      (iv) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).

2. Whenever the Contractor, or any Subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of $10,000 the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the solicitations from which this Contract resulted.

3. If the Contractor is participating (pursuant to 41 CFR 60-4.5) in a Hometown Plan approved by the U. S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the Plan area (including goals and timetables) shall be in accordance with that Plan for

those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each Contractor or Subcontractor participating in an approved Plan is individually required to comply with its obligations under the EEO clause, and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other Contractors or Subcontractors toward a goal in an approved Plan does not excuse any covered Contractor's or Subcontractor's failure to take good efforts to achieve the Plan goals and timetables.

4. The Contractor shall implement the specific affirmative action standards provided in Paragraphs 7a through p of these specifications. The goals set forth in the solicitation from which this Contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. The Contractor is expected to make substantially uniform progress toward its goals in each craft during the period specified.

5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement to refer either minorities or women, shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.

6. In order for the non-working training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U. S. Department of Labor.

7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:

   a. Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which Contractor's employees are assigned to work. The Contractor, where possible, shall assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.

b. Establish and maintain a current list of minority and female recruitment sources; provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.

c. Maintain a current file of the names, addresses, and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source, or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefor, along with whatever additional actions the Contractor may have taken.

d. Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.

e. Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under 7b above.

f. Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations by including it in any policy manual and collective bargaining agreement; by publicizing it in the company newspaper, annual report, etc.; by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.

g. Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination, or other employment decisions, including specific review of these items with on-site supervisory personnel such as superintendents, general foremen, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of

these meetings, persons attending, subject matter discussed, and disposition of the subject matter.

h. Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other contractors and subcontractors with whom the Contractor does or anticipates doing business.

i. Direct its recruitment efforts, both oral and written, to minority, female and community organizations, to schools with minority and female students, and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship or other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.

j. Encourage present minority and female employees to recruit other minority persons and women and, where reasonable, provide after school, summer, and vacation employment to minority and female youth both on the site and in other areas of a Contractor's work force.

k. Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.

l. Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities and encourage these employees to seek or to prepare, through appropriate training, etc., for such opportunities.

m. Ensure that seniority practices, job classifications, work assignments, and other personnel practices do not have a discriminatory effect by continually monitoring all personnel and employment-related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.

n. Ensure that all facilities and company activities are nonsegregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.

o. Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.

p. Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's EEO policies and affirmative action obligations.

8. Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7a through p). The efforts of a contractor association, joint contractor union, contractor-community, or other similar group of which the Contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under 7a through p of these Specifications provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female work force participation, makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.

9. A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specific minority group of women is under utilized).

10. The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.

11. The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.

12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspension, termination, and cancellation of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations, by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.

13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in Paragraph 7 of these specifications, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the

Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.B.

14. The Contractor shall designate a responsible official to monitor all employment-related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the Government, and to keep records. Records shall at least include for each employee the name, address, telephone number, construction trade, union affiliation, if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily-understandable and retrievable form; however to the degree that existing records satisfy this requirement, contractors shall not be required to maintain separate records.

15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

DESCRIPTION OF JOB CATEGORIES

Officials, Managers, and Administrators

Occupations requiring administrative personnel who set board policies, exercise overall responsibility for the execution of these policies, or provide specialized consultation on a regional, district, area basis, or direct individual departments or special phases of a firm's operations.

Includes: Officials, executives, middle management, plant managers, department managers, superintendents, salaried foremen who are members of management, purchasing agents, buyers, bureau chiefs, directors, deputy directors, wardens, examiners, sheriffs, police and fire chiefs, and kindred workers.

Professionals

Occupations which require specialized and theoretical knowledge which is usually acquired through college or experience of such kind and amount as to provide a comparable background.

Includes: Accountants, auditors, airplane pilots and navigators, architects, artists, chemists, designers, dieticians, editors, engineers, lawyers, librarians, mathematicians, natural scientists, registered professional nurses, personnel and labor relations workers, physical scientists, teachers, social workers, doctors, psychologists, economists, systems analysts, employment and vocational rehabilitation counselors, instructors, police and fire captains and lieutenants, and kindred workers.

Paraprofessionals

Occupations in which workers perform some of the duties of a professional or technician in a supportive role, which usually requires less formal training and/or experience normally required for professional or technical status. Such positions may fall within an identified pattern of a "New Careers" concept.

Includes: Library assistants, medical aides, child support workers, police auxiliary, welfare service aides, recreation assistants, homemakers aides, home health aides, and kindred workers.

Technicians

Occupations requiring a combination of basic scientific knowledge and manual skill which can be obtained through about two (2) years of post high school education, such as is offered in many technical institutes and junior colleges, or through equivalent on-the-job training.

Includes: Computer programmers and operators, draftsmen, engineering aides, junior engineers, mathematical aides, licensed practical or vocational nurses, photographers, radio operators, scientific assistants, surveyors, technical illustrators, technicians (medical, dental, electronics, physical sciences), police and fire sergeants, and kindred workers.

Protective Service Workers

Occupations in which workers are entrusted with public safety, security, and protection from destructive forces.

Includes: Police patrol officers, fire fighters, guards, deputy sheriffs, bailiffs, correctional officers, detectives, marshals, harbor patrol officers, and kindred workers.

Sales Workers

Occupations engaging wholly or primarily in direct selling.

Includes: Advertising agents and salespersons, insurance agents and brokers, real estate agents and brokers, stock and bond salespersons, demonstrators, salespersons and sales clerks, grocery clerks, cashiers, and kindred workers.

Office and Clerical

Occupations in which workers are responsible for internal and external communications, recording and retrieval of data and/or information and other paper work required in an office predominantly non-manual, though some manual work not directly involved with altering or transporting the products is included.

Includes: Bookkeepers, cashiers, collectors (bills and accounts), messengers and office helpers, office machine operators, shipping and receiving clerks, stenographers, typists and secretaries, telegraph and telephone operators, court transcribers, hearing reporters, statistical clerks, dispatchers, license distributors, payroll clerks, and kindred workers.

Skilled Craft Workers

Occupations in which workers perform jobs which require special manual skill through on-the-job training and experience, or through apprenticeship or other formal training programs. These workers exercise considerable independent judgment and usually receive an extensive period of training.

Includes: The building trades, hourly paid foremen and leadmen who are not members of management, mechanics and repairmen, skilled machining occupations, compositors and typesetters, electricians, engravers, job setters

(metal), motion picture projectionists, pattern and model makers, stationary engineers, tailors, heavy equipment operators, carpenters, and kindred workers.

Operatives (semi-skilled)

Workers who operate machine or processing equipment or perform other factory-type duties of intermediate skill level which can be mastered in a few weeks and require only limited training.

Includes: Apprentices (auto mechanics), plumbers, bricklayers, carpenters, electricians, mechanics, building trades, metal workers, machinists, printing trades, operatives, attendants (auto service and parking), blasters, chauffeurs, deliverymen, dressmakers and seamstresses (except factory), dryers, furnacemen, heaters (metal), laundry and dry cleaning operatives, milliners, miners, motormen, oilers, greasers, etc. (except auto), painters (except construction and maintenance), photographic process workers, stationary firemen, truck and tractor drivers, weavers (textile), welders and flame cutters, and kindred workers.

Laborers (unskilled)

Workers in manual occupations which generally require no special training. These workers perform elementary duties that may be learned in a few days and require the application of little or no independent judgment.

Includes: Garage workers, car washers and greasers, gardeners (except farm) and groundskeepers, longshoremen and stevedores, lumbermen, craftsmen, and wood choppers, laborers performing lifting, digging, mixing, loading, and pulling operations, and kindred workers.

Service/Maintenance Workers

Occupations in which workers perform duties which result in or contribute to the comfort, convenience, hygiene or safety for the general public or which contribute to the upkeep and care of buildings, facilities or grounds, or public property. Workers in this group may operate machinery.

Includes: Chauffeurs, laundry and dry cleaning operatives, truck drivers, trash collectors, custodial personnel, gardeners and groundskeepers, construction laborers, attendants (hospital and other institutions), professional and personal service, counter and fountain workers, elevator operators, firemen and fire protection, guards, watchmen and doorkeepers, stewards, porters, waiters, and kindred workers.

CERTIFICATION BY PROPOSED SUBCONTRACTOR REGARDING EQUAL EMPLOYMENT OPPORTUNITY

_____
Name of Prime Contractor

_____
Address

GENERAL

In accordance with Executive Order 11246 (30 F.R. 12319-25), the implementing rules and regulations thereof, and orders of the Secretary of Labor, a certification regarding Equal Opportunity is required of bidders or prospective contractors and their proposed subcontractors prior to the award of contracts or subcontracts.

SUBCONTRACTOR'S CERTIFICATION

Subcontractor's Name: _____

Address: _____

IRS Employer Identification Number: _____

Job Description : _____

1. Participation in a previous contract or subcontract.

   a. Subcontractor has participated in a previous contract or subcontract subject to the Equal Opportunity Clause. ____YES ____NO

   b. Compliance reports were required to be filed in connection with such contract or subcontract. ____YES ____NO

   c. Subcontractor has filed all compliance reports required by Executive Orders 10925, 11114, 11246, or by regulations of the Equal Employment Opportunity Commission issued pursuant to Title VII of the Civil Rights Act of 1964. ____YES ____NO

   d. If answer of Item c. is "No", please explain in detail on reverse side of this certification.

2. Dollar amount of proposed subcontract: $ _____

3. Anticipated performance period in days: _____

4. Expected total number of employees to perform the proposed subcontract: _____

5. Nonsegregated facilities.

a. Notice to prospective federally-assisted construction contractors
(1) A Certification of Nonsegregated Facilities, as required by the May 9, 1967, order (32 F.R. 7439, May 19, 1967) on Elimination of Segregated Facilities, by the Secretary of Labor, must be submitted to the Contractor prior to the award of a subcontract exceeding $10,000 which is not exempt from the provisions of the Equal Opportunity Clause.
(2) Contractors receiving subcontract awards exceeding $10,000 which are not exempt from the provisions of the Equal Opportunity Clause will be required to provide for the forwarding of this notice to prospective subcontractors for supplies and construction contracts where the subcontracts exceed $10,000 and are not exempt from the provisions of the Equal Opportunity clause.

b. Certification of non-segregated facilities

The federally-assisted construction contractor certified that he/she does not maintain or provide any segregated facilities at any of his/her establishments, and does not permit employees to perform their services at any location, under his/her control, where segregated facilities are maintained. The federally-assisted construction Contractor certifies further that he/she will not maintain or provide any segregated facilities at any of his/her establishments, and will not permit employees to perform their services at any location, under his/her control, where segregated facilities are maintained. The federally-assisted construction Contractor agrees that a breach of this certification is a violation of the Equal Opportunity Clause in this Contract. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants, and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive or are in fact segregated on the basis of race, creed, color, or national origin because of habit, local custom, or otherwise. The federally-assisted construction Contractor agrees that (except where he/she has obtained identical certifications from proposed Subcontractors for specific time periods) he/she will obtain identical certifications in duplicate from proposed Subcontractors prior to the award of subcontracts exceeding $10,000 which are not exempt from the provisions of the Equal Opportunity Clause, and that he/she will retain the duplicate of such certifications in his/her files. The Contractor will include the original in his/her Bid Package.

6. Race or ethnic group designation of bidder. Enter race or ethnic group in appropriate box:

☐ White ☐ Black ☐ Hispanic

☐ Pacific Islander, Asian ☐ American Indian, Aleut.

7. Gender

☐ Male ☐ Female

REMARKS:

Certification - The information above is true and complete to the best of my knowledge and belief.

_____
Company Officer (Please Type)

_____ _____
Signature Date

NOTE: The penalty for making false statements in offers is prescribed in 18 U.S.C. 1001.

Certification by Proposed Material Suppliers, Lessors, and Professional Service Providers Regarding Equal Employment Opportunity

Company Name: _____ $_____
(Supplier, Lessor, Professional Service Provider) (Amount of Contract)

Company Address: _____

Company Telephone Number: _____ Fax: _____

E-mail Address: _____

Web Page/URL Address: _____

Company Tax Identification Number: _____

Project No.: [*WBS/CIP/AIP/File No.*] _____

Project Name: [*Legal Project Name*] _____

In accordance with the City of Houston Ordinance 78-1538, Supplier/Lessor/Professional Service Provider represents to be an equal opportunity employer and agrees to abide by the terms of the Ordinance. This certification is required of all Suppliers/Lessors/Professional Service Providers (herein Supplier) with contracts in the amount of $10,000.00 or more.

[ ] Yes [ ] No Supplier agrees not to discriminate against any employee or applicant for employment because of race, religion, color, sex, national origin, or age.

[ ] Yes [ ] No Supplier agrees that all qualified applicants will receive consideration for employment without regard to race, religion, color, sex, national origin, or age.

[ ] Yes [ ] No Supplier will comply with all provisions of Executive Order No. 11246 and rules, regulations and applicable orders of the Department of Labor or other Federal Agency responsible for enforcement of applicable equal opportunity and affirmative action provisions and will likewise furnish all information and reports required by the Mayor or Contract Compliance Officers for the purpose of investigation to ascertain and effect compliance with the City of Houston's Office of Affirmative Action and Contract Compliance.

[ ] Yes [ ] No The Supplier shall file and cause their sub-tier contractors to file compliance reports with the City in the form and to the extent as may be prescribed by the Mayor or Contract Compliance Officers. Compliance reports filed at such times as directed shall contain information including, but not limited to, the practices, policies, programs, and employment policies.

I hereby certify that the above information is true and correct.

_____ _____
COMPANY OFFICER (Signature) DATE

_____
NAME AND TITLE (Print or type)

END OF DOCUMENT

Document 00808

REQUIREMENTS FOR THE CITY OF HOUSTON PROGRAM FOR MINORITY, WOMEN, AND SMALL BUSINESS ENTERPRISES AND PERSONS WITH DISABILITIES ENTERPRISES (PDBE)

CONSTRUCTION CONTRACTS

I. GENERAL

A. CITY AUTHORITIES

1. The "OBO Director" is the City of Houston's Office of Business Opportunity Director, or his or her designee.
   City of Houston
   611 Walker Street, 7th Floor
   Houston, Texas 77002

2. The "Contracting Department" for this Project is the City of Houston Department specified in Document 00520 – Agreement.

3. The "Project Manager" is for this Project specified in Document 00550 – Contract Approval Notification.

II. REOCCURRING REPORTS THAT MUST BE SUBMITTED DURING THE COURSE OF THE CONTRACT:

A. MWSBE MONTHLY REPORT PROCESS

The Contractor shall complete the MWSBE Monthly Utilization Report in the Contract Compliance and Monitoring System (available at https://houston.mwdbe.com/) .

B. The Contractor shall comply with further, applicable instructions regarding reporting and compliance as provided in Sections III.E and III.I below.

III. BUSINESS ENTERPRISE PROGRAM REQUIREMENTS:

A. PURPOSE

This Document facilitates implementation of City of Houston, Tex. Code of Ordinances Chapter 15, Article V, § 15-81 et seq., relating to MWSBE contract participation, and Code of Ordinances Chapter 15, Article VI, § 15-90 et seq., relating to PDBE contract participation (collectively, the "Business Enterprise Program or "MWSBE"). City of Houston, Tex. Ordinance 2013-0428, May 8, 2013.

B. POLICY

It is the policy of the City to encourage the full participation of Minority and Women-owned Business Enterprises, Small Business Enterprises, and Persons with Disabilities Business Enterprises in all phases of its procurement activities and to afford them a full and fair opportunity to compete for City contracts at all levels.

C. POLICY ELEMENTS

1. The Contractor agrees to ensure that MWSBE firms have a full and fair opportunity to participate in the performance of City contracts. In this regard the Contractor shall make all reasonable Good Faith Efforts to meet the Contract Goals for this Contract.

2. The Contractor and any Subcontractor shall not discriminate on the basis of race, color, religion, national origin, or sex in the performance of City contracts.

3. Contractor's performance in meeting the Participation Plan Percentage will be monitored during the construction phase of the Contract by the OBO Director and Contracting Department.

D. PERCENTAGE GOALS

The MWSBE goals and PDBE goals, if any, for the Work are specified in Document 00800 – Supplementary Conditions Goals.

E. CONTRACTOR RESPONSIBILITIES

1. Prior to Award:

The Bidder shall submit MWSBE documents in accordance with the requirements of Document 00410 – Bid Form Part A.

a. In accordance with the Code of Ordinances and the OBO Good Faith Efforts Policy (Attachment A), the Department shall approve an Apparent Low Bidder's MWSBE Participation Plan–Document 00470 (the "Bidder's Plan" or "Plan") within 3 business days of the Bid Opening only if the Department representative determines that Bidder's Plan meets the advertised Contract Goal and is administratively complete.

b. If the Department cannot approve the Bidder's Plan, it shall forward the Plan to the OBO Director, who shall review the Bidder's Plan, and if applicable, the Bidder's Document 00471 (Record of Good Faith Efforts) and Document 00472 (Pre-Award Deviation Request) and determine whether the Bidder has made Good Faith Efforts to meet the Contract Goals within 10 business days of the Bid Opening.

c. If the OBO Director determines that the Bidder has failed to provide a valid participation plan or make Good Faith Efforts or if the Bidder fails to provide documents and associated information required by this Document 00808 or reasonably requested in writing by the OBO Director, the OBO Director may declare the Bidder to be non-responsible.

d. If the OBO Director determines that the Bidder has made Good Faith Efforts, the Director may approve the Bidder's Contract Goal Deviation request. Thereafter, the Bidder/Contractor shall be bound by the Plan, as approved by the OBO Director.

e. The Contractor shall:

(1) ensure that all MWSBE firms listed in the Plan are certified by the Office of Business Opportunity prior to bid date. Qualified, non-certified firms may obtain priority consideration for certification if no more than two firms are certified with the same capability as the non-certified firm.

(2) execute written contracts with all certified Subcontractors and Suppliers. All such contracts must be executed and sent to the OBO Director and Contracting Department within 30 days after the date of the Notice to Proceed and must include provisions set forth in Articles 3 and 5 of Document 00700 - General Conditions.

(3) designate an MWSBE liaison officer who will administer the Contractor's MWSBE program and who shall document and maintain records of Good Faith Efforts to subcontract with MWSBE Subcontractors and Suppliers.

2. After Award:

a. The Contractor shall submit MWSBE Monthly Utilization Reports, requested in Article II above.

b. The Contractor shall complete and submit to the OBO Director a Post-Award Deviation Request–Document 00572 ("Post-Award Deviation Request") if the Contractor reasonably believes that it will not achieve the Business Enterprise Program Participation Plan Percentage documented in the Plan. The Contractors shall also submit to the OBO Director, with a Copy to the Contracting Department, a Record of Post-Award Good Faith Efforts (Document 00571) for each Certified Firm that the Contractor does not use in accordance with the Approved Plan before the Contractor uses another firm to perform the work.

c. The Contractor shall conform to the Plan unless the OBO Director grants a Post-Award Deviation Request. The OBO Director shall approve or reject a Deviation Request within 5 business days of receipt of the Deviation Request.

d. The OBO Director shall grant a Post-Award Deviation Request if

(1) for a reason beyond the Contractor's control, the Contractor is unable to use the certified MWSBE firm in the Plan to perform the specified work. In such cases, the Contractor shall use and document Good Faith Efforts to find a similarly qualified, certified MWSBE firm to perform such specified work; or

(2) the Contractor reasonably believes that, due to a change of scope, execution of the work in accordance with the directions from the Contracting Department is unlikely to meet the terms of the Plan. In such cases, the Contractor shall use and document Good Faith efforts to achieve a reasonable amount of MWSBE participation on the remaining work on the Contract.

(3) The OBO Director shall not unreasonably withhold approval of a Post-Award Deviation Request.

e. After the Date of Substantial Completion, the OBO Director shall evaluate the Contractor's Good Faith Efforts towards meeting the Plan, as it may amended.

f. If the Contractor fails to conform to the Plan and fails to submit a Post-Award Deviation Request or provide documents and associated information required by the Good Faith Efforts Policy or reasonably requested in writing by the OBO Director, the OBO Director may impose sanctions in accordance with Article VI of this Document 00808.

F. ELIGIBILITY OF MWSBE FIRMS FOR SUBCONTRACTING

1. To ensure that the City's Business Enterprise Program benefits only those firms that are owned and controlled by a minority person(s), a woman (women),a person(s) with a disability, or a small business enterprise, the Office of Business Opportunity will certify the eligibility of MWSBE and PDBE Contractors, Subcontractors, and Suppliers. Contact the Office of Business Opportunity Certification Section at 832-393-0600 for information regarding certification.

2. The Office of Business Opportunity maintains a Certified Minority, Women and Small Business Enterprises and Disabilities Business Enterprises Directory on the City's website. This Directory also lists federally-designated Disadvantaged Business Enterprises (DBEs).

NOTE: MWSBE firms, even if certified by another agency, may not qualify for Contract Goals unless certified by the Office of Business Opportunity prior to acceptance of the Participation Plan.

G. DETERMINATION OF MWSBE PARTICIPATION

MWSBE participation shall be counted toward meeting the Contract Goals in response to the following:

1. Once a firm is certified as a MWSBE firm, the total dollar value of the subcontract awarded to the MWSBE firm is counted toward the Contract Goals (See Sections III.G.4 and III.G.5 below). Safety and Participation goals do not count as a single goal concerning MWSBE/DBE requirements.

2. When the Contractor or Subcontractor is in a joint venture with one or more MWSBE firms, the OBO Director shall determine the percent of participation resulting from such joint venture to be counted toward the Contract Goals.

3. Contractor may count toward its Contract Goals only those MWSBE Subcontractors/ Suppliers performing a Commercially Usefully Function.
   a. **COMMERCIALLY USEFUL FUNCTION** means a discrete task or group of tasks, the responsibility for performance of which shall be discharged by the MWSBE firm by using its own forces or by actively supervising on-site the execution of the tasks by another entity for whose work the MWSBE firm is responsible. In determining whether a certified firm is performing a commercially useful function, factors including but not limited to the following shall be considered: (1) whether the firm has the skill and expertise to perform the work for which it is being utilized and possesses all necessary licenses; (2) whether the firm is in the business of performing, managing, or supervising the work for which it has been certified and is being utilized; and

(3) whether it is performing a real and actual service that is a distinct and verifiable element of the work called for in a contract. Without limiting the generality of the foregoing, a MWSBE will not be considered to be performing a commercially useful function, if it subcontracts to non-MWSBE firms or to other MWSBE firms, more than 50 percent of a contract being counted toward the applicable Contract Goals, unless such subcontracting in excess of 50 percent has been expressly approved by the OBO Director in a Goal or Plan Deviation Request (Document 00472 or Document 00572) (either pre-bid or post award).

b. The OBO Director shall approve a Plan Deviation Request if the Contractor demonstrates that the industry standard for the type of work involved is to subcontract over 50 percent of the work.

4. A MWSBE firm cannot subcontract more than 50 percent of the work for which it is responsible to perform unless the OBO Director grants a Deviation Approval.

5. The Contractor may count 100 percent of MWSBE Manufacturer Supplier's participation and 60 percent of MWSBE Non-Manufacturer Supplier's participation toward its Contract Goals. Such MWSBE Supplier contracts shall not exceed 50 percent of contract's goals.

6. The OBO Policy and Procedures Manual, as amended, shall apply to the Contract for other determinations regarding counting MWSBE participation not explicitly provided for in the Contract.

H. CONTRACTOR COMPLIANCE

To ensure compliance with MWSBE requirements, the OBO Director and Contracting Department will monitor Contractor's efforts regarding MWSBE Subcontractors/Suppliers during the performance of this Contract. This may be accomplished through the following: job site visits, reviewing of records and reports, and interviews of randomly selected personnel.

I. RECORDS AND REPORTS

1. In accordance with II.A of this Document, the Contractor shall submit an initial report outlining MWSBE participation, 40 days after the Notice to Proceed date, and on or before the 15th day of each month thereafter until all MWSBE subcontracting or material supply activity is completed. Each report shall cover the preceding month's activity. The Contractor shall use the MWSBE Contract Compliance and Monitoring System (B2G Now) to meet this requirement.

2. Contractor shall maintain the following records for review upon request by the OBO Director or Contracting Department:

   a. Copies of executed Subcontractor agreements and purchase orders;
   b. Documentation of payments and other transactions with MWSBE Subcontractors/ Suppliers;
   c. Appropriate explanations of any changes or replacements of MWSBE Subcontractors/Suppliers;

NOTE: All replacement MWSBE Subcontractors/Suppliers must be certified by the Office of Business Opportunity.

   d. Any other records required by the OBO Director or Contracting Department.

3. If a Participation Plan Percentage is not being met, the monthly report shall include a narrative description of the progress being made in MWSBE participation. If sufficient MWSBE Subcontractors or Suppliers to meet the Participation Plan Percentage are being utilized, they should be identified by name and the dollar amount paid to date for work performed or materials furnished by each MWSBE during the monthly period. Reports are required when no activity has occurred in a monthly period.

4. Contractor shall retain all such records for a period of four years following completion of the Work and shall be available at reasonable times and places for inspection by authorized representatives of the City including the City Controller.

IV. SANCTIONS:

A. SUSPENSION PERIOD AND WAIVER

Pursuant to Section 15-86 of the Code of Ordinances, the OBO Director is authorized to suspend for a period of up to, but not to exceed, five years, any Contractor who has failed to make Good Faith Efforts.

B. GUIDELINES FOR IMPOSITION OF SANCTIONS

1. General:

a. The OBO Director shall not impose any sanction except upon evidence of specific conduct on the part of a MWSBE or Contractor that is inconsistent with or in direct contravention of specific applicable requirements for Good Faith Efforts.

b. Imposition and enforcement of suspensions shall be consistent with applicable state law.

2. Severity of Sanctions:

a. In determining the length of any suspension, the OBO Director shall consider the following factors:

(1) Whether the failure to comply with applicable requirements involved intentional conduct or, alternatively, may be reasonably concluded to have resulted from a misunderstanding on the part of the Contractor or MWSBE of the duties imposed on them by Article V of Chapter 15 of the Code of Ordinances and these procedures;

(2) The number of specific incidences of failure by Contractor or MWSBE to comply;

(3) Whether the Contractor or MWSBE has been previously suspended;

(4) Whether the Contractor or MWSBE has failed or refused to provide the OBO Director with any information requested by the Director or required to be submitted to the Director pursuant to law or these procedures;

(5) Whether the Contractor or MWSBE has materially misrepresented any applicable facts in any filing or communication to the OBO Director; and

(6) Whether any subsequent restructuring of the subject business or other action has been undertaken to cure the deficiencies in meeting applicable requirements.

b. Suspensions may be for any length of time not to exceed five years. Suspensions in excess of one year shall be reserved for cases involving intentional or fraudulent misrepresentation or concealment of material facts, multiple acts in contravention of applicable requirements, cases where the Contractor or MWSBE has been previously suspended, or other similarly egregious conduct.

C. DELEGATION

A decision to implement a suspension may be taken after notice and an opportunity for a hearing by an impartial person(s) designated by the OBO Director as the hearing officer.

The hearing officer(s) shall not have participated in the actions or investigations giving rise to the suspension hearing.

D. NOTICE

1. Prior to imposing any suspension, the OBO Director shall deliver written notice to the Contractor or MWSBE setting forth the grounds for the proposed suspension and setting a date, time, and place to appear before the hearing officer(s) for a hearing on the matter.

2. Any notice required or permitted to be given hereunder to any Contractor or MWSBE may be given either by personal delivery or by certified United States mail, postage prepaid, return receipt requested, addressed to their most recent address as specified in the records of the Office of Business Opportunity or in the Contract if no address is on file with the Office of Business Opportunity.

E. HEARING PROCEDURES

Proceedings before a hearing officer shall be conducted informally and in accordance with the OBO Policy and Procedures Manual, as amended, provided that each party may be represented by counsel and may present evidence and cross-examine witnesses. The City shall have the burden to prove by a preponderance of evidence that the Contractor's or MWSBE firm's actions constitute misconduct or failure to make Good Faith Efforts. The decision shall be reduced to writing and notice provided to the Contractor or MWSBE.

F. APPEALS

Appeals authorized pursuant to Section 15-86(b) of the Code of Ordinances shall be conducted by the OBO Director. Pursuant to Section 15-86(b), The contractor may appeal the OBO Director's decision in accordance with Section 15-23 of the Code of Ordinances and OBO Policy and Procedures.

ATTACHMENT A

City of Houston
Office of Business Opportunity
Good Faith Efforts Policy

General Policy.

Good Faith Efforts are steps taken to achieve an Contract Goal or other requirements which, by their scope, intensity and usefulness demonstrates the bidder's responsiveness to fulfill the business opportunity objective prior to the award of a contract, as well as the contractor's responsibility to put forth measures to meet or exceed the Contract Goal throughout the duration of the contract.

Good Faith Efforts are required to be made and demonstrated by an apparent successful bidder on goal oriented contracts or proposer on a regulated contract prior to award of a contract. Good Faith Efforts are required on professional services and construction contracts and on procurement of goods and non-professional service contracts with goals. If a bidder, when submitting a participation plan at the time of bid or proposal submission, anticipates it cannot or will not meet the Contract Goal prior to the award, the bidder must demonstrate to Office of Business Opportunity ("OBO") it has made Good Faith Efforts to meet the Contract Goal, to be eligible for the contract award.

Good Faith Efforts shall be evaluated on a case-by-case basis in making a determination whether a bidder or contractor is in compliance with this policy. The efforts employed by a bidder or contractor should be those that one could reasonably expect a bidder or contractor to take if the bidder were actively and aggressively attempting to obtain MWSBE participation sufficient to meet the Contract Goal. Efforts taken that are mere formalities or other perfunctory acts shall not be considered Good Faith Efforts to meet Contract Goals.

The factors provided herein are representative of the types of actions OBO will consider in determining whether the bidder or contractor made Good Faith Efforts to obtain MWSBE participation to meet the Contract Goal. The factors prescribed below are not intended to be a mandatory checklist, nor is it intended to be exhaustive or exclusive. OBO may consider other factors or types of efforts that may be relevant in appropriate cases.

If a contractor fails to submit Good Faith Efforts documentation as provided in this Policy, it waives the right to appeal OBO decisions related to this Policy. OBO will review all the efforts made by the contractor, including the quality and quantity of those efforts.

Pre–Award.

A bidder must submit a participation plan (Document 00470) to OBO at the time the bidder submits the bid. If the participation by certified MWSBE subcontractors documented on the participation plan ("participation") is less than the Contract Goal, a bidder should submit a Record of Good Faith Efforts (Document 00471) with the bid. A bidder should also submit a request for a deviation (Document 00472) if the bidder, having used Good Faith Efforts, reasonably believes that it cannot meet the Contract Goal or a commercially useful deviation.

In making a determination that the bidder has made a good faith effort to meet the Contract Goals, OBO shall consider specific documentation concerning the steps taken to obtain MWSBE participation, with a consideration of, by way of illustration and not limitation, whether the bidder demonstrated a genuine effort to comply with the following factors:

1. Attended any pre-bid or pre-proposal meetings scheduled by the City Department;

2. Followed up with MWSBEs that attended the pre-bid or pre-proposal meetings to discuss subcontracting and supplier opportunities and contacted MWSBEs listed in the City's online directory;

3. Conducted outreach with minority and women focused organizations and associations far in advance of solicitation due date (no less than 10 business days);

4. Identified and designated portions of the work to be performed by MWSBEs to increase the likelihood of meeting the Contract Goals (including where appropriate breaking down the contract into reasonably sized subcontracts to ensure participation);

5. Advertised subcontracting opportunities in news media focused towards minority and women persons far in advance of solicitation due date;

6. Provided MWSBEs with a point of contact that was knowledgeable about the project and possessed decision-making authority to answer questions from interested MWSBEs;

7. Provided a reasonable number of MWSBEs certified with timely written notices via email, mail, and/or fax and/or with documented contact regarding the subcontracting/supplier opportunities. A "reasonable number of MWSBEs" shall be based on the number of MWSBEs available in the directory;

8. Solicited the MWSBEs within a reasonable amount of time (no less than seven business days) before bid submission, as well as followed up with the MWSBEs solicited to determine if they were interested in submitting a bid or proposal or participating on a team.

9. Provided interested MWSBEs certified to perform the solicited work with prompt access to the plans, specifications, scope of work and requirements of the contract;

10. Negotiated in good faith with interested MWSBEs, and not rejecting MWSBEs as unqualified without sound reasons based on a thorough investigation of their capabilities;

11. Entered into a formal contract, or signing enforceable letters of intent with MWSBEs;

12. Provided an explanation to any MWSBE whose bid or price quotation is rejected, unless another MWSBE is accepted for the same work, as follows:
    a. Where price competitiveness is not the reason for rejection, a written rejection notice including the reason for rejection will be sent to the rejected MWSBE firm;
    b. Where price competitiveness is the reason for rejection, a meeting must be held with the price-rejected MWSBE, if requested, to discuss the rejection;

13. Made efforts to assist interested MWSBEs in obtaining bonding, lines of credit, insurance required for the contract, and documenting MWSBE denied by bona fide surety agents;

14. Ensured that the conditions and requirements for subcontracts are commensurate with industry standards and would not cause an economic hardship on MWSBEs, such as unnecessary insurance or coupling bid bonds with retainage;

15. Incorporated efforts not attempted earlier or on previous bids that appear more likely to lead to attaining the Contract Goal. Past performance on similar contracts with similar scopes will also be taken in consideration when determining Good Faith Efforts. A bidder that continues to make same efforts without any significant change in the level of participation may not be making Good Faith Efforts.

Post–Award.

The contractor must sign the approved participation plan (Document 00470 or Document 00570) prior to starting work on the Project. A contractor should submit a request for deviation (Document 00572) from OBO if the contractor, having made Good Faith Efforts, reasonably believes that it will not achieve the Participation Plan Percentage documented in the approved participation plan. Unless OBO approves a deviation, a contractor must submit to OBO a Participation Summary (Document 00660) prior to City Council's consideration of any close-out, term extension, or change order. If participation is less than anticipated in the approved participation plan, the contractor must submit a Record of Good Faith Efforts (Document 00571) along with the Participation Summary. A contractor that fails to submit a deviation request and Good Faith Efforts documentation waives the right to appeal OBO decisions related to this Policy.

If the contractor is awarded the contract and fails to achieve the established Participation Plan Percentage, the contractor must demonstrate to OBO its efforts to meet the Participation Plan Percentage and failure to do so based on circumstances that the contractor could not reasonably control. In determining whether the contractor made Good Faith Efforts to ensure full participation and achievement of the Participation Plan Percentage, OBO shall consider the following factors:

1. Whether the contractor designated an MWSBE liaison officer to administer the Contractor's MWSBE programs and to be responsible for maintenance of records of Good Faith Efforts.

2. Whether the contractor furnished prompt MWSBE Utilization Reports in a timely and accurate manner through the online Contract Monitoring System or via hard copy.

3. Whether the contractor responded to efforts to resolve disputes with MWSBEs, and genuinely attempted to resolve these issues.

4. Whether the contractor disclosed payment discrepancies timely and within the monthly reporting period;

5. Whether the contractor complied with the participation plan, unless the contractor received a deviation from the OBO Director and whether upon approval, the contractor made Good Faith Efforts to replace a removed MWSBE with another certified firm;

6. Whether the contractor furnished prompt written responses to written inquiries from the Director or any employee of OBO regarding the MWSBE's performance or information germane to the MWSBE's certification;

7. Whether the contractor ensured that at all times during the performance of any contract or subcontract the MWSBE firm is engaging in a commercially useful function as that term is defined in Chapter 15 of the City of Houston Code of Ordinances;

8. Whether the contractor provided the OBO information, or other material, that was factually accurate and free of material misrepresentation; and

9. Whether the contractor furnished prompt responses to requests for information, books and records needed to verify compliance from the department administering the Contract, the City Attorney and the City Controller;

10. Whether the contractor attended all meetings and mediation hearings as requested by the Director or his/her designee; and

11. How the contractor may be affected by change orders, with consideration given to the size of the change orders.

Change Orders.

The requirement to make Good Faith Efforts to achieve the approved Participation Plan Percentage is applicable to change orders. Contractors should make Good Faith Efforts to ensure that the Participation Plan Percentage remains substantially the same after the issuance of change orders. If a contractor cannot maintain substantially the same level of participation provided in the latest approved Participation Plan (Document 00470 or Document 00570) due to a change order, the contractor shall submit to the OBO Director and Contracting Department a Document 00571 (Post-Award Record of Good Faith Efforts) and Document 00572 (Post-Award Plan Deviation Request) in a timely manner that does not cause disruption to the project. In addition to other relevant factors, in evaluating whether Good Faith Efforts were made by the contractor to meet the Participation Plan Percentage despite change orders, the OBO Director shall consider the contractor's efforts to timely and efficiently deliver the project.

END OF DOCUMENT

Document 00820

WAGE SCALE AND PAYROLL REQUIREMENTS FOR ENGINEERING CONSTRUCTION

Wage Scale Requirements

1.1 Contractor and its Subcontractors must pay the general prevailing wage rates for building construction for each craft or type of worker or mechanic employed in the execution of any building construction or repair under the Contract in accordance with Chapter 2258 of the Texas Government Code and City of Houston, Texas Ordinance Nos. 85-2070, 2000-1114, 2001-152, 2006-91 and 2006-168, and 2009- 247 all as amended from time to time. City Council has determined the prevailing wage rate in the locality in which the work is being performed, which is set forth in Exhibit "A".

1.2 This prevailing wage rate does not prohibit the payment of more than the rates stated.

1.3 In bidding, Contractor warrants and represents that it has carefully examined the classifications for each craft or type of worker needed to execute the Contract and determined that such classifications in Exhibit "A" include all necessary categories to perform the work under the Contract.

1.4 The wage scale for engineering construction is to be applied to all site work greater than five feet from an exterior wall of new building under construction or from an exterior wall of an existing building.

1.5 If Contractor believes that an additional classification for a particular craft or type of worker is necessary to perform work under the Contract, it must submit with its bid a request to the Contract Compliance Division of the Office Of Business Opportunity ("OBO") to use an additional labor classification not listed in Exhibit "A" and specify the proposed new classification. OBO shall determine whether a proposed classification is already covered in Exhibit "A", and, if it is, specify which classification is appropriate. OBO's decision is conclusive. If OBO decides that a new classification is necessary, it will determine the appropriate prevailing wage rate for any resurveyed, amended, new, or additional craft or type of worker not covered by Exhibit "A". Such determination must be decided in accordance with procedures established by OBO, and in compliance with Chapter 2258 of the Texas Government Code and City of Houston, Texas Ordinance Nos. 85-2070, 2000-1114, 2001-152, 2006-91, 2006-168 and 2009-247 subject to City Council approval.

1.6 Contractor must not use any labor classification not covered by Exhibit "A" until such classification is established and approved for use by OBO.

1.7 A Contractor or Subcontractor who violates Chapter 2258 of the Texas Government Code must pay to the City, $60 per each worker employed for each calendar day or part of the day that the worker is paid less than the wage rates set forth in Exhibit "A".

1.8 The City may withhold money required to be withheld under Chapter 2258 of the Texas Government Code from the final payment to Contractor or earlier payments if City Council makes a determination that there is good cause to believe that Contractor has not complied with these provisions and Chapter 2258 of the Government Code, in which case the City may withhold the money at any time subsequent to the finding by City Council.

1.9 Contractor and Subcontractors must keep records specifying:

(1) the name and classification of each worker employed under the Contract; and

(2) the actual per diem wages paid to each worker, and the applicable hourly rate.

The records must be open at all reasonable hours for inspection by the officers and agents of the City.

1.10 The hourly cost of salary for non-exempt workers for labor in excess of 40 hours per worker per week, shall be calculated at 1.5 times the worker's base pay, plus 1.0 times fringe benefits, for the applicable craft and level.

Certified Payroll Requirements

2.1 Employees are paid weekly and payrolls are submitted weekly using the City of Houston's electronic payroll submission module, unless the prime Contractor has been instructed to do otherwise by the Office of Business Opportunity. When no work is done after a Contractor has started work, the Contractor is required to submit a weekly compliance statement indicating no work was performed. The payrolls must reflect the exact work and classification of the workers, the exact amount that they were paid. Workers must be paid the contracted amount (prevailing wage rates). The Contractor will be penalized $60.00 a day for each employee who is underpaid per Texas Government Code §2258-023 for all contracts.

2.2 Payrolls must be submitted electronically & indicate whether the worker worked inside or outside the building area when both wage rates are applicable to the contract.

2.3 Payrolls must be submitted each week until all work by the contractor is complete and the electronic payroll submission is marked as final in the system.

2.4 Payrolls must cover a seven day period from the start of the work week and must be consecutive seven day periods until all work is complete.

2.5 Payrolls must have employees' names, addresses, last four digits of the social security numbers, and job classifications. The job classifications must be the same as the classifications on the prevailing wage rate schedule.

2.6 A payroll deduction authorization form must be submitted for each employee for any deductions other than Federal and FICA taxes.

2.7 Employees must be paid overtime (time and a half) for all hours worked over 40 hours a week on both federally and City-funded contracts.

2.8 The Contractor has the responsibility to comply with all Internal Revenue Service rules and regulations. Contractors who submit certified payrolls with **Owner Operators (truckers)** must submit a signed tax liability statement from Owner Operator acknowledging their responsibility for Federal Income Tax and FICA reporting obligations.

2.9 If the Contractor wants to use the apprentice wage rates for an employee, the apprenticeship certificates must be submitted to the Office of Business Opportunity in advance of the employee working on the project and appearing on the payroll. You must comply with the listed number of journeymen to apprentices as listed.

2.10 A poster of the Prevailing Wage Rate Schedule should be clearly displayed on each job site from the time the project starts until the work is completed, or in case of annual service agreements, in the Contractor's office.

2.11 The Contractor shall submit the "Certificate from Contractor Appointing Officer or Employee to Supervise Payment of Employees" (Exhibit "B") to the Monitoring Authority listed in Document 00495 prior to final execution of the contract.

2.12 During the course of the work, ALL Subcontractors shall submit the "Certificate from Subcontractor Appointing Officer or Employee to Supervise Payment of Employees" (Exhibit "C") to the Monitoring Authority listed in Document 00495.

2.13 Upon completion of the Project, as part of the contract-awarding department's total clearance process, the Office of Business Opportunity's Contract Compliance Section must review whether the Wage Rate and Payroll Requirements were met and report the results to the department.

REST OF PAGE INTENTIONALLY LEFT BLANK

EXHIBIT "A"

LABOR CLASSIFICATIONS AND PREVAILING WAGE RATES FOR
ENGINEERING CONSTRUCTION 2015

CLASSIFICATION	RATE	CLASSIFICATION	RATE
Asphalt Distributor Operator	$14.06	Milling Machine Operator - Fine Grade	$13.53
Asphalt Paving Machine Operator	$14.32	Mixer Operator	$10.33
Asphalt Raker	$12.36	Motor Grader Operator- Rough	$14.23
Asphalt. Shoveler	$11.68	Motor Grader Operator	$15.69
Broom or Sweeper Operator	$12.68	Oiler	$12.12
Bulldozer Operator	$11.81	Painter-Structures	$18.62
Carpenter- Rough	$12.49	Pavement Marking Machine Operator	$11.18
Concrete Finisher- Paving	$12.98	Pile Driverman	$14.95
Concrete Finisher- Structures	$12.98	Pipe Layer	$12.12
Concrete Paving Curbing Machine Operator	$11.71	Reinforcing Steel Setter - Paving	$15.15
Concrete Paving Finishing Machine Operator	$13.07	Reinforcing Steel Setter - Structure	$14.39
Concrete Paving Joint Sealer Operator	$11.00	Roller Operator, Pneumatic - Self-propelled	$11.57
Concrete Paving. Saw Operator	$13.99	Roller Operator, Steel Wheel, Flat Wheel/Tamping	$11.57
Concrete Paving Spreader Operator.	$10.44	Roller Operator, Steel Wheel, Plant Mix Pavement	$11.92
Concrete Rubber . . .	$9.00	Scraper Operator	$13.47
Crane Clamshell Backhoe Derrick, Dragline, Shovel Operator	$12.71	Servicer	$13.97
Crusher and Screening Plant Operator	$11.29	Sign Installer - PGM	$8.54
Electrician * 3 Journeyman 2 Apprentice Allowed	$27.11	Slip Form Machine Operator	$11.07
Flagger	$10.33	Spreader Box Operator	$13.58
Form Builder/Setter- Structures	$12.23	Structural Steel Worker	$14.39
Form Liner- Paving and Curb	$12.34	Tractor Operator - Crawler Type	$13.68
Form Setter- Paving and Curb	$12.34	Tractor Operator- Pneumatic	$10.07
Foundation Drill Operator - Crawler Mounted	$17.43	Transit Mixer Truck Driver	$11.00
Foundation Drill Operator - Truck Mounted	$15.89	Truck Driver, Lowboy-float	$16.03
Front Loader Operator	$13.17	Truck Driver, Single-Axle - Heavy	$11.46
Laborer Common	$11.02	Truck Driver, Single-Axle - Light	$11.48
Laborer- Utility	$11.73	Truck Driver, Tandem Axle Semi-Trailer	$12.27
Manhole Builder	$9.00	Work Zone Barricade Servicer	$11.67
Mechanic	$16.96	eceive rate prescribed for craft performing operation to which welding is incidental	
* Apprentices- must be in an approved USDOL Program and cannot exceed ratios			

Engineering Prevailing Wages Classification Definitions

Asphalt Distributor Operator
Drives distributor truck, sets spray bars and operates valves and levers to control distribution of bituminous material for highway surfacing. May oil, grease or otherwise service and make adjustments to equipment as needed. Performs other related duties.

Asphalt Paving Machine Operator
Operates paving machine that spreads and levels asphaltic concrete on highway subgrade. Controls movement of machine, raises and lowers screed, regulates width of screed. May, oil, grease, service and make adjustments to equipment as needed. Performs other related duties.

Asphalt Raker
Distributes asphaltic materials evenly over road surface by raking and brushing material to correct thickness; directs Laborers when to add or take away material to fill low spots or to reduce high spots. Performs other related duties.

Asphalt Shoveler
A general term used on construction work covering many unskilled classifications requiring work of a physical nature. A laborer works with all crews doing everything from pick and shovel work to cleaning up lumber with hammer, shoveling and placing concrete, uses air tools, cleans concrete joints and fills joints with sealing compound from bucket or with hose and nozzle from a central source, applies coating of oil to inside face of forms, may help set and strip forms, unloads and transports reinforcing steel, cures newly poured concrete, helps lower pipe into ditch for pipelayers, builds fences, works with dirt crew keeping construction layout stakes out of the way of dirt moving equipment.

Broom or Sweeper Operator
Operates a self-propelled machine to sweep and clean roadway surfaces. May oil grease, service and make adjustments to equipment as needed. Performs other related duties.

Bulldozer Operator
Operates a crawler tractor with a bulldozer mounted in front of chassis to level, distribute and push earth or other material. May operate a ripper attachment to break up rock or other hard material. May use a push block on front of tractor to push load scrapers. May oil, grease, or otherwise service and make minor repairs to equipment as needed. Performs other related duties.

Carpenter, Rough
Works from plans to build, assemble, fit together, align, plum, and set in place forms for molding concrete structures. Forms may be wood, steel, aluminum, fiberglass or any other type of material. Checks form while concrete is placed. May install miscellaneous materials integral to concrete structures. May set precast concrete elements. Prepares for slipforming traffic rail and median barrier. May install permanent metal deck forms. May work with power tools Performs other related duties.

Concrete Finisher, Paving
Finishes the exposed surfaces of fresh concrete paving, median barrier and every element of concrete structures to the final grade and contour structures to the final grade and contour with the use of straight edges and steel trowels. Operates bridge deck finishing machine. Finishes concrete curbs and gutters. Finishes exposed surface of concrete after forms have been removed by patching imperfections with fresh concrete, rubbing surface with abrasive stone, and directing others in removing excess or defective concrete with power tools. Performs other related duties.

Concrete Finisher, Structures
A worker semi-skilled in concrete finishing who assists Concrete finisher by performing specific or general duties of lesser skill and keeping Concrete Finisher supplied with materials, tools, and supplies; cleaning working area an equipment; and holding materials and tools. Performs other related duties.

Concrete Paving Curbing Machine Operator
Operates self - propelled machine(s) which may or may not travel on concrete paving forms, spreading and leveling fresh concrete to grade by use of augers and screeds. May oil, grease or otherwise service and make adjustments to equipment as necessary. Performs other related duties.

Concrete Paving Finishing Machine Operator
Operates self - propelled machine(s) which may or may not travel on concrete paving forms, spreading and leveling fresh

concrete to grade by use of augers and screeds. May oil, grease or otherwise service and make adjustments to equipment as necessary. Performs other related duties.

Concrete Paving Joint Sealer Operator
Cleans and seals joints requiring a hot or cold sealing compound in concrete paving, sidewalks, driveway and approach slabs. May oil, grease or make necessary repairs adjustments to equipment as needed. Performs other related duties.

Concrete Paving Saw Operator
Operates a water-cooled power saw with either or an abrasive blade to saw expansion and contraction joints in concrete paving. May also be used to saw asphaltic pavements. May oil grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Concrete Paving Spreader Operator
Operates self - propelled machine(s) which may or may not travel on concrete paving forms, spreading and leveling fresh concrete to grade by use of augers and screeds. May oil, grease or otherwise service and make adjustments to equipment as necessary. Performs other related duties.

Concrete Rubber
Finishes the exposed surface of concrete masonry after the forms have been removed by patching holes and broken corners with fresh concrete, rubbing surface with abrasive stone to remove rough spots, and removing high spots and defective concrete with hand chisel and hammer or pneumatic chisel and powered abrasive stone. Performs other related duties.

Crane, Clamshell, Backhoe, Derrick, Dragline, Shovel Operator
A worker who operates a lattice boom type crane can hoist and move materials, raise and lower heavy weights and perform other related operations. May be crawler type or rubber tired. May include placement of rock riprap, clamshell, dragline, pipe and pile driving operations. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Crusher and Screed Plant Operator
Operates a crusher or screening plant through which rock is run to break it into crushed stone for construction or to control flow of materials not needed. May include minor repairs and may service and make necessary adjustments to equipment as needed. Performs other related duties.

Electrician *3 Journeyman 2 Apprentice
Plans and directs the layout of metal electrical conduit, installs wiring systems, switch-panels, buss bars, works on overhead distribution systems and underground distribution systems. Performs other related duties.

Flagger
A worker who directs traffic in or around a construction site. May use signs or devices to direct traffic. May help assemble, position and clean devices or equipment used to direct traffic. Must be able to effectively communicate with the public. May require certain level of training by TXDOT specifications. Performs other related duties.

Form Builder/Setter, Structures
Fits together, aligns and sets to grade metal and wooden forms for placement of concrete. Forms may be wood, steel, aluminum, fiberglass or any other type of material. Checks forms while concrete is placed. May install miscellaneous materials integral to concrete structures. May set precast concrete elements. Prepares for slipforming traffic rail and median barrier. May install permanent metal deck forms. May work with power tools. Performs other related duties.

Form Liner, Paving & Curb
Fits together, panels align and sets to grade metal and wooden forms for placement of concrete. Works with survey crew to set stringline for panels or moles. Performs other related duties.

Form Setter, Paving & Curb
Fits together, align and set to grade metal and wooden forms for placement of concrete paving and curbs. Works with survey crew to set stringline for paving, curb and gutter curb. Performs other related duties.

Foundation Drill Operator, Crawler Mounted
Operates a hole-drilling machine that is crawler mounted. May include geotechnical operations such as soils nails, rock nails, tiebacks, anchors and jet grouting. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Foundation Drill Operator, Truck Mounted
Operates a hole drilling machine that is mounted on the rear of a rubber tired vehicle or truck. May include soils nails, rock nails, tiebacks, anchors and jet grouting. Drive truck from location to location or may have laborer who drives truck. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Front End Loader Operator
Operates a rubber tired, skid steer or crawler type tractor with an attached scoop type bucket on front end. Machine is used to load materials from stockpiles, excavation, charging batch plants, loading and unloading trucks. May be used with attachments in lieu of the bucket. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Laborer, Common
A general term used on construction work covering many unskilled classifications requiring work of a physical nature. A laborer works with all crews doing everything from pick and shovel work to cleaning up lumber with hammer, shoveling and placing concrete, uses air tools, cleans concrete joints and fills joints with sealing compound from bucket or with hose and nozzle from a central source, applies coating of oil to inside face of forms, may help set and strip forms, unloads and transports reinforcing steel, cures newly poured concrete, helps lower pipe into ditch for pipelayers, builds fences, works with dirt crew keeping construction layout stakes out of the way of dirt moving equipment.

Laborer, Utility
Performs a variety of manual duties, usually working in a utility capacity by working on multiple projects and tasks where demands require workmen with varied experience and ability to work without close direction. Unloads and transports reinforcing steel. May occasionally place and tie reinforcing steel. Directs common laborers in pouring concrete. Erects shoring and bracing. Assists in installation of pipe. Installs, operate and maintains dewatering systems. May assist equipment operators in positioning machines, verifying grades and signaling operators. Directs truck drivers and scraper operators to dumping positions to maintain grades as directed. Uses power tools and air tools. May work as lead man in a labor crew. His performance of a wide variety of construction jobs distinguishes him from a helper assigned to a specific craft. Installs and maintains erosion control. Is more or less a general utility construction worker. May be second step in learning a skill, and may later become a helper in a specific classification. Performs other related duties.

Manhole Builder
Constructs a means of permanent access to water and sewer lines for maintenance purposes. This work consists of laying brick or concrete slab at bottom of ditch up to an approximate grade line near the surface of the ground. Brick or block is normally laid to form a nearly circular manhole. Brick or block is laid in by eyesight and is normally to a plumb line. Chipped or culled brick can be used quite often is. No effort may be made to keep mortar off the face of the brick and joints are not pointed. May apply coating of concrete to interior and exterior surface. Performs other related duties.

Mechanic
Assembles, set up, adjusts and maintains and repairs all types of construction equipment and trucks. He may perform the duties of a welder in repair of equipment. Performs other related duties.

Milling Machine Operator, Fine Grade
Operates a power-driven milling machine that planes material of the to roadbed and discharges the material into a hauling unit or a windrow. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Mixer Operator
Performs a variety of manual duties, usually working in a utility capacity by working on multiple projects and tasks where demands require workmen with varied experience and ability to work without close direction. Unloads and transports reinforcing steel. May occasionally place and tie reinforcing steel. Directs common laborers in pouring concrete. Erects shoring and bracing. Assists in installation of pipe. Installs, operate and maintains dewatering systems. May assist equipment operators in positioning machines, verifying grades and signaling operators. Directs truck drivers and scraper operators to dumping positions to maintain grades as directed. Uses power tools and air tools. May work as lead man in a labor crew. His performance of a wide variety of construction jobs distinguishes him from a helper assigned to a specific craft. Installs and maintains erosion control. Is more or less a general utility construction worker. May be second step in learning a skill, and may later become a helper in a specific classification. Performs other related duties.

Motor Grader Operator, Rough
Operates a motor grader. Equipment is used to grade excavation and embankment and to lay asphalt, base and other materials. May blade haul roads and do other general motor grader work, but does not perform finish grade work to close

specification tolerances. This operator may be a learner in the first phase of learning the skills of motor grader work. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Motor Grader Operator
Operates a motor grader. Equipment is used to grade excavation and embankment and to lay asphalt, base and other materials. May blade haul roads and do other general motor grader work, but does not perform finish grade work to close specification tolerances. This operator may be a learner in the first phase of learning the skills of motor grader work. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Oiler
A learner or semi-skilled worker who under the direction of the watch engineer. May oil and grease or otherwise service all engines and necessary equipment as needed. He may clean and paint engine room as needed. Performs other related duties.

Painter, Structures
Paints and stains structural steel and concrete surfaces of bridges, retaining walls, or other structures. Directs cleaning and abrasive blasting of surfaces prior to painting or staining. Performs other related duties.

Pavement Marking Machine Operator
Operates machine used in laying paint stripes or markers on all types of paving. Loads machine with appropriate materials and may walk or ride on machine. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Piledriverman
Sets in place, aligns, plumbs directs driving of timber, concrete, steel, pipe and any other type of piling. Sets, drives and pulls steel, concrete and other types of sheet piling. Rigs pile and leads and bracing. Signals operator. Splices piles before and after driving. Directs pile cutoff. May direct jetting or drilling equipment in connection with installing piles to grade. Performs other related duties.

Pipelayer
Installs concrete, clay, steel, ductile iron, plastic, corrugated pipe and any other type of pipe for storm drainage, water lines, gas lines and sanitary sewer lines. Lays underground communication and electrical ducts. May install and set electrical ground boxes, hand holes, manholes, inlets and other structures. Caulks joints, makes threaded and flanged connections. Installs valves and other accessories. Performs other related duties.

Reinforcing Steel Setter, Paving
Works from plans to lay out and install reinforcing steel within forms or in mats of concrete paving. May direct unloading of material. Determines rigging required to complete work. Gives direction to reinforcing steel worker (helper) or common or utility laborers. May install miscellaneous materials integral to concrete structure or paving. May work with power tools. Performs other related duties.

Reinforcing Steel Setter, Structure
Works from plans to lay out and install reinforcing steel within forms or in mats of concrete paving. May direct unloading of material. Determines rigging required to complete work. Gives direction to reinforcing steel worker (helper) or common or utility laborers. May install miscellaneous materials integral to concrete structure or paving. May work with power tools. Performs other related duties.

Roller Operator, Pneumatic, Self-Propelled
Operates a self-propelled machine with either steel wheels pneumatic tires, which is used to compact and smooth all bituminous materials. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Roller Operator, Steel Wheel, Flat Wheel/Tamping
Operates a self-propelled machine with either steel wheels or pneumatic tires which is used to compact earth fills, subgrade, flexible base and all other types of materials except bituminous. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Roller Operator, Steel Wheel, Plant Mix Pavement
Operates a self-propelled machine with either steel wheels pneumatic tires, which is used to compact and smooth all bituminous materials. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Scraper Operator
Operates a self-contained wheeled tractor scraper both self loading or assisted by crawler tractors or other scrapers. Used to excavate and transport earth or other materials. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Servicer
Drives a truck, which carries various fuels, oils, greases and filters. Must have knowledge of and is responsible for the correct oiling and greasing and changing of filters on equipment according to the manufacturers' specifications. Uses compressed air grease guns, wrenches and other tools. May make adjustments to clutches, brakes and other mechanical items. Keeps record of service preventive maintenance records. May have laborer assisting him. May require CDL if driving truck on public highways. Performs other related duties.

Sign Installer (PGM)
Sets forms, reinforcing steel, anchor bolts and pours concrete for Sign foundations. Fabricates and erects pipe and angle Frameworks by bolting, welding or other means prior to installation of signs that are normally prefabricated. Works from plans in location and drilling holes for proper location and alignment of signs. May direct hoisting of signs into place. Fastens signs to framework by bolting and other means. Locates and sets lighting brackets. May perform other work associated with signing projects. Supervises sign erector helper. Performs other related duties.

Slip Form Machine Operator
Cleans and seals joints requiring a hot or cold sealing compound in concrete paving, sidewalks, driveway and approach slabs. May oil, grease or make necessary repairs adjustments to equipment as needed. Performs other related duties.

Spreader Box operator
Operates spreader box by adjusting hopper and strike off blade so that the gravel, stone or other material may be spread to a specific depth on road surface during seal coat and surface treatment operations. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Structural Steel Worker
Works from plans to lay out and install reinforcing steel within forms or in mats of concrete paving. May direct unloading of material. Determines rigging required to complete work. Gives direction to reinforcing steel worker (helper) or common or utility laborers. May install miscellaneous materials integral to concrete structure or paving. May work with power tools. Performs other related duties.

Tractor operator, Crawler Type
Operates a crawler tractor with a bulldozer mounted in front of chassis to level, distribute and push earth or other material. May operate a ripper attachment to break up rock or other hard material. May use a push block on front of tractor to push load scrapers. May oil, grease, or otherwise service and make minor repairs to equipment as needed. Performs other related duties.

Tractor Operator, Pneumatic
Operates a gasoline or diesel powered agricultural tractor that tows compaction rollers, plow, disc. water tanks, scrapers and other similar operations. May use other miscellaneous attachments. May oil, grease or otherwise service and make necessary adjustments to equipment as needed. Performs other related duties.

Traveling Mixer Operator
Drives a gasoline or diesel truck upon which is mounted a concrete mixer. Operates concrete mixer and dumps concrete on the grade, into forms or into concrete pumps or buckets. Cleans mixer drum. May require CDL license for on highway use. May service and make necessary adjustments for proper operation of equipment. Performs other related duties.

Truck driver, lowboy-Float
Drives a heavy-duty diesel powered truck to which is attached a trailer upon which heavy equipment is hauled. Driver is often required to operate heavy equipment to load or unload the lowboy. May require CDL license for on highway use. May service and make necessary adjustments for proper operation of equipment. Performs other related duties.

Truck driver, Single Axle, Heavy
Drive a light capacity truck for transporting loads of construction material. The truck is of single rear axle type, may have various kinds of beds attached, such as dump, flat bed, tank, etc. May require CDL license for driving on highway. May services and make necessary adjustments for proper operation equipment. Performs other related duties.

Truck driver, Single Axle-Light
Drive a light capacity truck for transporting loads of construction material. The truck is of single rear axle type, may have

various kinds of beds attached, such as dump, flat bed, tank, etc. May require CDL license for driving on highway. May services and make necessary adjustments for proper operation equipment. Performs other related duties.

Truck Driver, Tandem Axle, Semi-Trailer
Drives a diesel-powered tractor pulling a semi trailer hauling materials. Hauls dirt, rock, aggregates or other material. May require CDL license for driving on highway. May service and make necessary adjustments for proper operation of equipment. Performs other related duties.

Work Zone Barricade Servicer
Fabricates, erects and maintains temporary traffic control devices, including arrow boards, signs, barricades, channelizing devices, barrels and all message boards. May operates a truck during traffic control operations.

WELDERS - Receives rate for craft being performed to which welding is incidental.

EXHIBIT "B"

CERTIFICATE FROM CONTRACTOR APPOINTING OFFICER OR EMPLOYEE TO SUPERVISE PAYMENT OF EMPLOYEES

Project Name _____

_____

Project WBS#:_____Date_____

(I) (We) hereby certify that (I am) (we are) the **Prime Contractor** for _____

_____
(specify type of job)

in connection with construction of the above-mentioned Project, and that (I) (we) have appointed_____, whose signature appears below, to supervise the payment of (my) (our) employees beginning_____, 20___; that he/she is in a position to have full knowledge of the facts set forth in the payroll documents and in the statement of compliance required by the Copeland Act and the City of Houston, which he/she is to execute with (my) (our) full authority and approval until such time as (I) (we) submit to the City of Houston a new certificate appointing some other person for the purposes hereinabove stated.

_____ Phone:_____
(Identifying Signature of Appointee)

Attest: _____
(Name of Firm or Corporation)

By:_____ By:_____
(Signature) (Signature)

_____ _____
(Title) (Title)

NOTE: This certificate must be executed by an authorized officer of a corporation or by a member of a partnership, and shall be executed prior to and be submitted with the first payroll. Should the appointee be changed, a new certificate must accompany the first payroll for which the new appointee executes a statement of compliance required by the Copeland Act and the City of Houston.

EXHIBIT "C"

CERTIFICATE FROM SUBCONTRACTOR APPOINTING OFFICER OR EMPLOYEE TO SUPERVISE PAYMENT OF EMPLOYEES

Project Name _____

_____

Project WBS#:_____Date_____

(I) (We) hereby certify that (I am) (we are) the **Sub Contractor** for _____

_____
(specify type of job)

in connection with construction of the above-mentioned Project, and that (I) (we) have appointed_____, whose signature appears below, to supervise the payment of (my) (our) employees beginning_____, 20___; that he/she is in a position to have full knowledge of the facts set forth in the payroll documents and in the statement of compliance required by the Copeland Act and the City of Houston, which he/she is to execute with (my) (our) full authority and approval until such time as (I) (we) submit to the City of Houston a new certificate appointing some other person for the purposes hereinabove stated.

_____ Phone:_____
(Identifying Signature of Appointee)

Attest: _____
(Name of Firm or Corporation)

By:_____ By:_____
(Signature) (Signature)

_____ _____
(Title) (Title)

NOTE: This certificate must be executed by an authorized officer of a corporation or by a member of a partnership, and shall be executed prior to and be submitted with the first payroll. Should the appointee be changed, a new certificate must accompany the first payroll for which the new appointee executes a statement of compliance required by the Copeland Act and the City of Houston.

END OF DOCUMENT

Document 00830

TRENCH SAFETY GEOTECHNICAL INFORMATION

1.0 DOCUMENT INCLUDES

A. Trench Safety Geotechnical Information: Geotechnical information obtained for use in design of the trench safety system is included as an attachment to this document.

2.0 RELATED DOCUMENTS

A. Section 02260 - Trench Safety Systems.

END OF DOCUMENT

City of Houston
Pay or Play Program Requirements

I. Pay or Play Program Overview

A. Purpose

The Pay or Play Program was established with Ordinance 2007-534 on July 1, 2007 and is governed by Executive Order 1-7. The Pay or Play Program (POP Program) creates a more level playing field and enhances fairness in the bid process between competing contractors that choose to offer health benefits to their workforce and those who do not. The program also recognizes and accounts for the fact that there are cost associated with health care of the uninsured citizens of the Houston and Harris County area.

B. Program Elements

1. Covered contracts:

I.) Advertised after July 1, 2007 or which is executed on or after the effective date of this Executive Order.
II.) Contracts valued at or above $100,000.00 (contract) and $200,000.00 (sub-contract) including contingencies, amendments, supplemental terms and/or change orders.
III.) Professional Service, Construction, and Service type contracts.

2. Contracts not covered:

I.) Any contract in which the primary purpose is procurement of property, goods, supplies, and or equipment.
II.) An inter-governmental contract, inter-governmental agreement or purchasing cooperative.

3. Covered employees: This program applies to employees of a covered contractor or subcontractor, including contract labor, who are over age 18, work at least 30 hours per week and work any amount of time under a covered city contract or subcontract.

4. Pay or Play Option:

I.) "Pays" by contributing $1.00 per covered employee per regular hour for work performed under the contract with the City; or
II.) "Plays" by providing health benefits to covered employees. Health benefits must meet or exceed the following standards:

- The **employer will contribute no less than $150 per covered employee per month** toward the total premium cost.
- The **employee contribution, if any amount, will be no greater than 50% of the monthly premium cost and no more than $150 per month.**

Note: (1)A contractor is deemed to have complied with section 5.4 of E.O. 1-7 with respect to a covered employee who is not provided health benefits if the employee refuses the benefits and the employee's contribution to the premium is no more than $40 per month. (2) If applicable the contractor has the option to both Pay and Play.

5. **Exemptions/Waivers**: The City of Houston will award a contract to a contractor that neither Pays nor Plays only if the contractor has received an approved waiver (Form POP-4 requested by City departments only).

6. **Administration**: Contractor performance in meeting Pay or Play program requirements will be managed by the contracting department. The Office of Business Opportunity (OBO) has administrative oversight of the program, including audit responsibilities (department compliance). Questions about the program should be referred to the Department POP Liaison an updated contact list is available on http://www.houstontx.gov/obo/popforms.html or call Gracie Orr with the Office of Business Opportunity at 832-393-0633.

II. Documentation and Reporting Requirements

A. Document that must be signed and returned to administering department with the bid/proposal.

1.) City of Houston Pay or Play Program Acknowledgment Form (Form POP-1) acknowledges bidder/proposers' knowledge of the program and its requirements, and the intention to comply.

B. Documents that must be signed and returned to administering department within a period designated by the department's Contract Administrator, upon notification of low bidder or successful proposer status:

1.) Certification of Compliance with Pay or Play Program (Form POP-2)

Note - Contractors that opt to "play" must provide proof of coverage, including document from insurance provider, and names of covered employees.

2.) List of Subcontractors (Form POP-3)

Note- Review the affidavit statement at the bottom of this form for further important POP Compliance information.

C. Contractors reporting requirements:

1.) Contractors that opt to Pay
Provide monthly reports to administering department, detailing names of employees, hours worked, exemptions (if any) and amount owed. (Form POP-5)

2.) Contractors that opt to Play
Provide periodic reports to the contract administrator showing proof of coverage (insurance premium invoice or insurance card) reporting schedule will be determined by administering department based on length of contract. (Form POP-7)

3.) Employee Waiver Request
Contractor may request POP program waiver by submitting the request on POP-8 if the employee is less than 18 years old, employee has other health coverage such as through spouse or parents, or Medicare/Medicaid.

Note proof of coverage must be provided in the form of a copy of the employee's insurance card. (Remove social security numbers if applicable)

4.) Contractors shall submit an initial report with the second invoice to the department. Payments based on monthly reports are due to the contracting department with submission of the following month's invoice. Payments may be made out to the City of Houston preferably via cashier check or business check.

III. Compliance and Enforcement

The Office of Business Opportunity will audit program compliance. Contractors willfully violating or misrepresenting POP program compliance will be subject to corrective and/or punitive action, including but not limited to the assessment of fines and penalties and/or debarment. The Pay or Play Program Requirements Form and all other POP Forms are available for downloading from the City of Houston's Website at http://www.houstontx.gov/obo/popforms.html

Document 00910

ADDENDUM NO._____

Date of Addendum: _____
****Enter date by hand when signed for release****

PROJECT NAME: Lift Station Renewal/Replacement - Woodway #1 Lift Station Replacement

PROJECT NO: WBS No. R-000267-109B-4

BID DATE: April 2, 2015 (There is no change to the Bid Date.)

FROM: J. Timothy Lincoln, P.E., City Engineer
City of Houston, Department of Public Works and Engineering
611 Walker Street, Houston, Texas 77002
Houston, Texas 77002
Attn: *Akhter Hussain, P.E.*, Project Manager

TO: Prospective Bidders

This Addendum forms a part of the Bidding Documents and will be incorporated into the Contract documents, as applicable. Insofar as the original Project Manual and Drawings are inconsistent, this Addendum governs.

****

Use the following heading and select the appropriate wording for postponement of the Bid Date. Delete the statement beside Bid Date above which indicates that the Bid Date is unchanged. If change in Bid Date, issue as separate addendum. Delete this section entirely if there is no change in Bid Date.

****

CHANGE IN BID DATE

The Bid Date for this Project has been changed from _____ (Date) to _____ (Date).
[Time of day and place for submittal of bid remains the same]. [Time of submittal has been changed from _____ (Time) to _____ (Time). The place for submittal remains the same].

The bid date for this project has been indefinitely postponed.

****

Delete the following paragraph if the sole purpose of the Addendum is to postpone the Bid Date.
****

This Addendum uses the change page method: remove and replace or add pages, or Drawing sheets, as directed in the change instructions below. Change bars (|) are provided in the outside margins of pages from the Project Manual to indicate where changes have been made; no change bars are provided in added Sections. Reissued Drawing Sheets show the Addendum number below the title block and changes in the Drawing are noted by a revision mark and enclosed in a revision cloud.

****

Number each item of the Addendum beginning with 1 through the total number of change items in the Addendum. Sample entries are provided in brackets.
****

CHANGES TO PREVIOUS ADDENDA

****

Reference Addendum Number and item number to correct clarifications or make minor corrections of changes issued by previous Addenda.
****

ADDENDUM NO. _____

[1. Item 5. Change to read as follows:]

CHANGES TO PROJECT MANUAL

****

Follow this format to sequence changes to the Project Manual.
****

BIDDING REQUIREMENTS

****

Give the individual change instructions for each item of change by Document number and title. List changes in order of Document number.
****

[2. Document 00020 - Notice to Bidders. Replace page 00020-2.]

CONTRACT FORMS

[3. Document 00610 - Replace revised Performance Bond, page 00610-1.]

CONDITIONS OF THE CONTRACT

[4. Document 00800 - Supplementary Conditions. Replace page 00800-4 and add page 00800-5.]

SPECIFICATIONS

[5. Section 02050 - Demolition. Add section including pages 02050-1 through 02050-3.]

CHANGES TO DRAWINGS

[6. Delete Sheet S-9, Beam Schedule, and replace with Sheet S-9-A.]

CLARIFICATIONS

[7. Document 00210 - Supplementary Instructions to Bidders states that no substitutions will be considered during the bidding phase. Substitutions will be considered during the first 15 percent of the Contract Time or first 90 days of the Contract, whichever is less, as stated in Document 00700 - General Conditions.]

END OF ADDENDUM NO. _____

DATED: _____

Ravi Kaleyatodi, P.E.
Sr. Assistant Director
Department of Public Works and Engineering

RK:EN:IMR:AH:OKA:sdd

END OF DOCUMENT

Document 00911

NOTICE OF
ADDENDUM NO.

Date of Addendum: _____

PROJECT NAME: Lift Station Renewal/Replacement - Woodway #1 Lift Station Replacement

PROJECT NO: R-000267-109B-4

BID DATE: _____ (There is no change to the Bid Date.)

FROM: J. Timothy Lincoln, P.E., City Engineer
City of Houston
Department of Public Works and Engineering
611 Walker, 15th Floor
Houston, Texas 77002
Attn: Akhter Hussain, P.E., Project Manager

TO: Prospective Bidders

The referenced Addendum forms a part of the Bidding Documents and will be incorporated into the Contract documents, as applicable.

Written questions regarding this Addendum may be submitted to the Project Manager following the procedures specified in Document 00200 – Instructions to Bidders. Immediately notify the City Engineer through the named Project Manager upon finding discrepancies or omissions in the Bid Documents.

_____
Ravi Kaleyatodi, P.E.
Senior Assistant Director
Department of Public Works and Engineering

END OF DOCUMENT

Document 00931

REQUEST FOR INFORMATION

1. PROJECT No.: R-000267-109B-4
2. RFI No.: _____
3. PROJECT NAME: Lift Station Renewal/Replacement - Woodway #1 Lift Station Replacement
4. CONTRACTOR: [Contractor Name]
5. CONTRACT No.: _____
6. SPECIFICATION Nos.: _____
7. DRAWING Nos.: _____
8. RESPONSE CODE: [_] CRITICAL [_] ROUTINE 9.DATE RESPONSE REQUIRED: _____
10. INFORMATION REQUIRED:

11. _____ _____ _____
CONTRACTOR (Signature) TITLE DATE

12. RESPONSE:

13. _____ _____
PROJECT MANAGER (Signature) DATE

14. **If Contractor believes the response given in Item 12 requires an adjustment in Contract Price or Contract Time, Contractor shall submit a timely proposal so as not to delay Contractor's Work in accordance with General Conditions, Article 7 - Changes in the Work.**

END OF DOCUMENT

Section 01110

SUMMARY OF WORK

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Summary of the Work including broad scope of work by Contractor, work by the City, City furnished Products, Work sequence, Contractor use of Premises and special conditions for substantial completion and City occupancy.

B. **THIS PACKAGE OF PLANS AND SPECIFICATIONS WERE FORMERLY SUBMITTED AS A COMPREHENSIVE MULTI-LIFT STATION (5 FACILITIES) PACKAGE; THEREFORE, ANY REFERENCES AND/OR NOTATIONS RELATED TO BAYOU TIMBER (FN 010), BUCKINGHAM (FN 028), NORTH POST OAK LANE (FN 546) AND STABLEWOOD (FN 127) ARE NO LONGER APPLICABLE TO THIS CURRENT PROJECT.**

1.02 WORK COVERED BY CONTRACT DOCUMENTS

A. Work of the Contract is for the replacement of Woodway #1 Lift Station. The work includes but is not limited to the following bid items:

1. Bid Item No. 1 includes but is not limited to the following work: Mobilize sufficient workforce, equipment, and supervision to complete work for the construction of the Woodway #1 Lift Station Project. The project consists of replacing the Woodway #1 lift station with an upgraded wet well/valve vault system capable of handling existing flows and wastewater from the Bayou Timber, Buckingham, North Post Oak Lane and Stablewood Lift Stations. Associated construction includes the installation of a force-main bypass manhole, 3/4-inch water supply line from meter box to hose bibb; as well as a backflow preventer with lockable cover. Other upgrades include 24-inch RCP storm sewer, storm water inlets, concrete pavement including sidewalk and driveway; as well as, upgrades to fences, personnel and vehicular gates. Additionally, a new electrical control building will be installed as well as structural, mechanical and electrical systems for new lift station. The work also includes demolition of the existing lift station.

2. Bid Item No. 2 includes but is not limited to the following work: Furnish, install, maintain during construction, and remove after construction pumps with associating controls, power, and necessary temporary force main capable of pumping approximately 300 gallons per minute (GPM) at the Woodway lift station project as needed to construct the work for the duration of project from Contractor's notice to proceed to date of City acceptance of substantial completion. Contractor's Diversion/Bypass Pumping plan shall be approved by City of Houston Wastewater Operations prior to

commencing Diversion/By-pass Pumping. All applicable submittals shall be reviewed by the City of Houston Project Manager and Wastewater Operations prior to installation of Diversion Pumping System.

3. Bid Item No. 3 includes but is not limited to the following work: Furnish, install, and maintain all necessary diversion/by-pass pumping items including pumps with associating controls, power, and necessary temporary force main capable of pumping approximately 300 gallons per minute (GPM) from existing influent manhole servicing existing Woodway lift station to the proposed force-main bypass manhole (See Bid Item No. 11). The duration of long-term by-pass (if needed) will begin from the date of the City's acceptance of substantial completion for the lift station work and will continue until such date that City accepts the construction of the proposed 8" diameter sewer diversion to be constructed by others (Contractor for WBS. No. R-000267-109A-4). The Contractor's Long-Term Diversion/By-pass Pumping plan shall be approved by City of Houston Wastewater Operations prior to commencing the Long Term Diversion/By-passing Pumping. All applicable submittals shall be reviewed by the City of Houston Project Manager and Wastewater Operations prior to installation of Diversion Pumping System.

4. Bid Item No. 4 includes but is not limited to the following work: Provide traffic control and regulation for the Traffic Control Plan as shown, including but not limited to barricades, signage, and channeling devices for the duration of the project in compliance with COH specification 01555.

5. Bid Item No. 5 includes but is not limited to the following work: Provide flagmen and uniformed police officers for traffic control for the duration of the project in compliance with COH specifications 01555.

6. Bid Item No. 6 includes but is not limited to the following work: Furnish, install, maintain during construction, and remove after construction tree and plant protection per the Tree Protection Plan in accordance with COH specification 01562.

7. Bid Item No. 7 includes but is not limited to the following work: Furnish, install, maintain during construction and remove after construction, approximately 300 linear feet of inlet protection barrier per the Storm Water Pollution Prevention Plan in accordance with COH specification 01570.

8. Bid Item No. 8 includes but is not limited to the following work: Furnish, install, maintain during construction and remove after construction, approximately 750 linear feet of sandbag barrier per the Storm Water Pollution Prevention Plan in accordance with COH specification 01570.

9. Bid Item No. 9 includes but is not limited to the following work: Furnish, install, maintain during construction and remove after construction,

approximately 1,800 linear feet of filter fabric fence per the Storm Water Pollution Prevention Plan in accordance with COH specification 01570.

10. Bid Item No. 10 includes but is not limited to the following work: Furnish, install, maintain during construction and remove after construction, approximately 50 square yard of stabilized construction exit per the Storm Water Pollution Prevention Plan in accordance with COH specification 01575.

11. Bid Item No. 11 includes but is not limited to the following work: Furnish all materials, labor and equipment necessary to restore approximately 356 linear feet of the project alignment to its preconstruction condition including but not limited to asphalt and concrete pavement, pavement markings, traffic signage, sprinkler systems, fences, landscaping and sodding, and any other necessary items per COH specification 01740.

12. Bid Item No. 12 includes but is not limited to the following work: Furnish and install a 6-foot diameter precast concrete force main bypass manhole in accordance with COH specification 02082. This bid item includes but not limited to all items such as valves, fittings, hatches, coatings, connections associated with the installation of the 6-foot diameter precast concrete force main bypass manhole.

13. Bid Item No. 13 includes but is not limited to the following work: Furnish and install a 6-foot diameter corrosion resistant drop manhole, with force main connection in accordance with COH specification 02082 and plans. This bid item includes but not limited to all items such as valves, fittings, coatings, connections associated with the installation of the 6-foot diameter corrosion resistant precast concrete manhole and all connections.

14. Bid Item No. 14 includes but is not limited to the following work: Furnish all labor and equipment necessary to demolish the Woodway #1 Lift Station. Demolition includes the salvage of existing pumps, piping, valves, electrical and instrumentation devices and motors deemed salvable by the City of Houston. Contractor to coordinate with City of Houston Wastewater Operations to identify equipment and/or material to be salvaged and course of action of staging these items during demolition. Work also includes excavation/removal of all improvements, including structures, wet wells, valve vault, and pavement to a minimum of four feet below existing grade or to deeper depths as needed for completion of the work and hauling off and legal disposal of debris. Work includes removal of sludge from the wet well and boring the wet well structure and back filling in accordance to COH Specification 02220. Work also includes grout filling, plugging and abandon the existing force main from the lift station to the force main outfall. Remove portions of the existing 6" force main, 8" sanitary sewer, and 2" abandoned gas line as necessary to facilitate construction of new lift station items. Grading the existing site to drain is considered part of the demolition.

Removal of existing trees, shrubs and plants as called out in plans is also included within this bid item.

15. Bid Item No. 15 includes but is not limited to the following work: Remove and will legally disposing of approximately 1,500 SY of site pavement includes pavers, bricks, and/or concrete surfaces for all thickness encounter during course of work includes excavation and removal of all base and sub-base materials and/or underlying materials as needed to install the work include proposed new pavement and base materials. Cost to include saw cutting, removal, and legally disposing of existing concrete pavement and excavated materials. All work to be performed in accordance with COH specification 02221.

16. Bid Item No. 16 includes but is not limited to the following work: Trench Safety Systems for trench excavations for 30 linear feet associated with 8-inch clay pipe and 18-inch influent sewer stub out in accordance with COH specification 02260.

17. Bid Items No. 17, 18, and 19 includes but is not limited to the following work: Provide new ¾ inch diameter water supply line from existing water meter to back flow preventer and hose bibb locations. Includes furnish and install one ¾-inch freeze proof hose bib assembly, ¾-inch RPZ back flow preventer and assembly included protective lockable metal cage in accordance with COH specifications 02511, 02526.

18. Bid Item No. 20 includes but is not limited to the following work: Installation of approximately 18 linear feet of 8-inch clay vitrified drain line by open cut method from proposed electrical control building to wet well structure in accordance with COH specification 02531 and 02533.

19. Bid Item No. 21 includes but is not limited to the following work: Furnish and install approximately 20 linear feet of 18 inch diameter sanitary sewer (stub out from wet well structure) by and in accordance with COH specifications 02531, 02533, and 02534. 18-inch diameter sanitary sewer shall be capped at end (street side) for future service connection by others (Contractor WBS No. R-000267-109A-4).

20. Bid Item No. 22 includes but is not limited to the following work: Furnish and install approximately 276 linear feet of 12 inch diameter sanitary sewer force main by and in accordance with COH specification 02532.

21. Bid Item No. 23 includes but is not limited to the following work: Furnish and install approximately 356 linear feet of 24 inch diameter RCP storm sewer by in accordance with COH specification 02631 by open cut method includes all connections and collars.

22. Bid Item No. 24 includes but is not limited to the following work: Furnish and install four 36" x 36" Type A storm water inlets and connect to existing 24 inch diameter culvert in accordance with COH specification 02632.

23. Bid Item No. 25 includes but is not limited to the following work: Furnish and install approximately 212 tons of recycled crushed concrete base course 9 inches thick compacted and in-place, in accordance with COH specifications 02713.

24. Bid Item No. 26 includes but is not limited to the following work: Furnish and install approximately 663 square yards of 7 inch thick reinforced concrete pavement in accordance with COH specification 02751.

25. Bid Item No. 27 includes but is not limited to the following work: Furnish and install approximately 298 square feet of 7 inch thick reinforced concrete driveway in accordance with COH specification 02754.

26. Bid Item No. 28 includes but is not limited to the following work: Furnish and install approximately 75 square feet of 5 foot wide, 4 ½ inch thick concrete sidewalk in accordance with COH specification 02775.

27. Bid Item No. 29 includes but is not limited to the following work: Furnish and install approximately 155 linear feet 8 feet high vinyl fence and posts per plans and details shown and in accordance with COH specification 02830.

28. Bid Item No. 30 includes but is not limited to the following work: Furnish and install approximately 320 linear feet of 12 foot high hardwood fence and posts per the plans and details shown and in accordance with COH specification 02830.

29. Bid Item No. 31 includes but is not limited to the following work: Furnish and install one 4-foot wide, 8 foot high personnel gate per the plans and details and in accordance with COH specifications 02830.

30. Bid Item No. 32 includes but is not limited to the following work: Furnish and install one 20 foot wide double swing gate with steel padlock assembly per the plans and details and in accordance with COH specifications 02830.

31. Bid Item No. 33 includes but is not limited to the following work: Furnish and install approximately 200 square yards of sodding in accordance with COH specifications 02922.

32. Bid Item No. 34 includes but is not limited to the following work: Provide all materials, labor, equipment, and supervision necessary for the construction of the new control building including foundation slab, HVAC, roof drainage lines, electrical and instrumentation systems, controls, power distribution, lighting, telephone and data outlet and wiring, vented power panel

enclosure, control panel enclosure, grounding, cathodic protection, emergency power, instrumentation pressure gauges, programmable logic controller, panels, conduits, cables, poles, wiring, including quick-connect standby generator receptacle which meets current standards, codes and COH requirements and miscellaneous accessories incidental to completion of the work. For the operation of lift station in accordance with COH specification 03055 and 03310, and Division 16.

33. Bid Item No. 35 includes but is not limited to the following work: Provide all materials, labor, equipment, and supervision necessary for the construction of the proposed lift station structure including but not limited to wet well and valve vault structures per the plans. Work includes all but not limited to excavation, shoring, and back filling. Also included are the wet well hatches with safety grating, fiberglass grating, force main and drain line connections, wet well venting and miscellaneous accessories and appurtenances in accordance with COH specifications Division 3.

34. Bid Item No. 36 includes but is not limited to the following work: Provide all materials, labor, equipment, and supervision necessary for the installation of concrete corrosion protection system. This includes all of the following items but not limited to liner or spray-on system for all interior surfaces with wet well structure (except wet well floor), inclusive of all surface cleaning and preparation, installation and final application in accordance with COH specifications 09901,09904, and 09917.

35. Bid Item No. 37 includes but is not limited to the following work: Provide all materials, labor, equipment, and supervision necessary for the construction of New Lift Station Piping and Mechanical that includes installation of wet-well submersible pumps, cooling jackets, discharge piping, wet well piping brackets and supports, air release valves, isolation and check valves, and painting, force main and drain line connections, influent line connections, including miscellaneous accessories and appurtenances in accordance with COH specifications division 13 & 15.

1.03 CASH ALLOWANCES

A. Include the following specific Cash Allowances in Contract Price under provision of General Conditions Paragraph 3.11:

1. Building Permit Fee Allowance – This allowance to be used only for reimbursement of actual Building Permit fees.
2. Lane Closure Permit Fee Allowance – This allowance to be used only for reimbursement of actual Lane Closure Permit fees.
3. Street Cut Permit Fee Allowance – This allowance to be used only for reimbursement of actual Street Cut Permit fees.

4. Utility Reimbursement Fee Allowance – This allowance to be used for reimbursement of actual Utility Costs fees & costs associated with providing items necessary and required by local utility companies for completion of the work. This item also includes but is not limited to cost of meter upgrades and associated fees for installation.
5. Demolition Permit Fee Allowance – This allowance to be used only for reimbursement of actual Demolition Permit fees, includes fees by local, county and state agencies including COH Code Enforcement.
6. Flood Plain Permit Reimbursement Fee Allowance – This allowance to be used only for reimbursement of actual Flood Plain Permit fees.

1.04 ALTERNATE-Not Used

1.05 CITY-FURNISHED PRODUCTS

A. Items Furnished by the City for Installation and final connection by Contractor: **Water Meter.**

B. Contractor's Responsibilities:

1. Arrange and pay for Product delivery to the site.
2. Receive and unload Products at the site; jointly with the City, inspect for completeness or damage.
3. Handle, store, install, and finish Products.
4. Repair or replace damaged items.

1.06 WORK SEQUENCE

A. Construct the Work in Phases during the construction period, coordinate construction schedule and operations with the COH Project Manager:

1. Phase 1: Demolition existing lift station and install new lift station with all improvements, provide by-pass pumping as needed to complete work.

2. Phase 2: Provide long-term by-pass pumping as directed by COH Project Manager, until such time as Contractor for WBS No. R-000267-109A-4 has installed the necessary 8-inch sanitary sewer diversion to allow for sanitary wastewaters to flow by gravity into new lift station wet well structure.

B. Coordination of the Work: Refer to Section 01312 - Coordination and Meetings.

1. Contractor shall coordinate work with the "*Pine Hollow Home Owners Association*" as follows:

HOA Contact
Jack Lee, President
Oakmont Group, Inc.
109 North Post Oak Lane
Suite 525
Houston, Texas 77024
Office: 713-681-5566
Cell: 713-628-4640
Fax: 713-681-7774
jacklee@oakmontgrp.com

2. Contractor shall coordinate work with COH PM and applicable Contractor for:

"Water Line Replacement in Sherwood Forest Area" Project
WBS No. S-000035-0184-4.
Contact COH PM: Mumtaz Baig - PWE
Email: mumtaz.baig@houstontx.gov
Telephone (832) 395-2309.

3. Contractor shall coordinate work with COH PM and applicable Contractor for:

"*Lift Station Renewal/Replacement Project - Consolidation of North Post Oak Lane (FN 546), Stablewood (FN 127), and Buckingham (FN 028) Lift Stations*" Project
WBS No. R-000267-109A-4.
Contact COH PM: Akhter Hussian - PWE
Email: Akhter.Hussain@houstontx.gov
Telephone (832) 395-2294.

4. Contractor shall coordinate work with COH PM and applicable Contractor for:

"*Lift Station Renewal/Replacement Project - Consolidation of Bayou Timber Lift Station (FN 010)*" Project
WBS No. R-000267-109C-4.
Contact COH PM: Akhter Hussian - PWE
Email: Akhter.Hussain@houstontx.gov
Telephone (832) 395-2294.

5. Contractor to provide the following prior to startup of any diversion or by-pass pumping:

   a. Names & phone numbers of primary and secondary contacts of Contractor's representatives.

   b. Names & phone numbers of primary and secondary contacts of pump company representatives.

   c. Ability to connect to SCADA system at 4545 Groveway for monitoring bypass pumping.

   d. Use of existing power to energize any by pass pumping devices shall require prior written authorization from Owner.

   e. Review installation procedures under section 01506 and coordinate with work related to this section.

C. Coordination of Plug/Connection on 18" sanitary sewer between Manhole #66 and Woodway #1 Lift Station:

   1. Contractor responsible for this contract shall provide an 18" plug for the invert stub-out from the Lift Station wet well if Manhole #66 has not been installed by WBS No. R-000267-109A-4 contractor; if however manhole #66 is in service, contractor shall make the service connection to allow wet well to receive wastewater flow.

   2. Contractor responsible for WBS No. R-000267-109A-4 contract shall provide an 18" plug coming from Manhole #66 if the 18" influent to wet well (i.e. wet well stub out) has not yet been constructed. If however, the 18" influent to wet well is in-place, the contractor will be responsible for making the service connection to wastewater flow into the lift station wet well.

1.07 CONTRACTOR USE OF PREMISES

A. Comply with procedures for access to the site and Contractor's use of rights-of-way as specified in Section 01145 - Use of Premises.

B. Construction Operations: Limited to the City's rights-of-way, utility easements, and inside the wastewater treatment plant site.

C. Utility Outages and Shutdown: Provide notification to the City and private utility companies (when applicable) a minimum of 48 hours, excluding weekends and holidays, in advance of required utility shutdown. Coordinate all work with the City as required.

1.08 STREET CUT ORDINANCE

A. Excavations on or under pavement in the City's right-of-way must have a permit. Comply with City of Houston, Texas Ordinance No. 2000-1115, an ordinance amending Chapter 40 of the Code of Ordinances, Houston, Texas, relating to excavating in the Public right-of-way.

B. Comply with the latest edition of street cut "New Pavement Repair and Pavement Replacement details".

C. Quantities are included for street cut pavement and replacement in applicable Specification sections for Unit Price contracts.

D. Include Payment for street cut pavement repair and replacement in lump sum bid for Stipulated Price contracts.

1.09 WARRANTY

A. Comply with warranty requirements in accordance with Document 00700 - General Conditions.

1.10 ADDITIONAL CONDITIONS FOR SUBSTANTIAL COMPLETION

A. In addition to requirements outlined in document 00700-General Conditions, for contractor to be substantially complete with the Work and call for the inspection by the Project Manager to confirm, the following conditions must be met or completed:

1. Demonstrate the ability to receive and monitor video and Supervisory Control and Data Acquisition (SCADA) data from all remote sites.
2. All testing shall be completed and accepted by Project manager.
3. All SCADA and security equipment shall be installed, accepted by manufacturer's representative and approved for operation.
4. Draft O&M manuals shall be delivered to Project Manager.
5. Training shall be conducted, utilizing draft O&M manuals.
6. All Safety related work including pavement stripping, signing and signalization. 6. (b) all safety-related systems and equipment shall be installed, accepted by manufacturer's representative and approved for use.
7. All pay items complete report.
8. Complete removal of temporary diversion pumping systems as specified in Bid Item #2. .
9. Completed demolition at the existing lift station facility.
10. Abandonment and/or grout fill of noted force main, gravity sewer sections and wet well.
11. Completion of site restoration and pavement restoration.

12. Substantial completion shall be contingent on the successful completion of the seven-day operational test. Successful completion of the seven-day operational test is defined as normal operation of all lift station systems for seven consecutive days without shut downs, failures, system malfunctions or SCADA errors. The Contractor shall request, in writing, that the Project Manager notify the Wastewater Operations Branch (WOB) at least three weeks prior to the proposed start of the seven-day test to confirm that the facility to be tested and WOB is ready for the seven-day test. WOB will then authorize the Project Manager to run the seven-day and WOB will set the start date for this test.
13. Accepted Methods of sanitary sewer line testing passed.
14. Approval of warranty documents.

B. No additional conduction described in Paragraph 1.10 may be included in Contractor's punch list. Final acceptance shall require completion of all punch list items. This completion shall be approved by the Project Manager. Final acceptance shall require delivery, to Wastewater Operations Branch, the final O&M Manuals, spare parts, and completion of all operator and maintenance training. The Contractor is also required to deliver to Wastewater Operations, an active copy of the lift station PLC program for final acceptance. A .pdf version of the program is not acceptable.

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION - Not Used

END OF SECTION

Section 01145

USE OF PREMISES

1.01 SECTION INCLUDES

A. General use of the site including properties inside and outside of rights-of-way, work affecting road, ramps, streets and driveways and notification to adjacent occupants.

1.02 RIGHTS-OF-WAY

A. Confine access, and operations and storage areas to rights-of-way provided by the City as stipulated in Document 00700 - General Conditions; trespassing on abutting lands or other lands in the area is not allowed.

B. Make arrangements, at no cost to the City, for temporary use of private properties. Contractor and Surety shall indemnify and hold harmless the City against claims or demands arising from such use of properties outside of rights-of-way. Submit a copy of agreements between private property owners and Contractor prior to use of the area. Agreements between private property owners and Contractor shall be notarized or bear the signatures of two witnesses.

C. Obtain written permission from City of Houston Parks and Recreation Department for storage of materials on esplanades and other areas within rights-of-way under that department's jurisdiction. Submit copies of written permission prior to use of the area.

D. Restrict total length of distributed materials along the route of construction to 1,000 linear feet unless otherwise approved in writing by City Engineer.

1.03 PROPERTIES OUTSIDE OF RIGHTS-OF-WAY

A. Do not alter the condition of properties adjacent to and along rights-of-way.

B. Do not use ways, means, methods, techniques, sequences, or procedures that result in damage to properties or improvements.

C. Restore damaged properties outside of rights-of-ways at no cost to the city

1.04 USE OF SITE

A. Obtain approvals from governing authorities prior to impeding or closing public roads and streets. Do not close more than two consecutive intersections at one time.

B. Notify Project Manager and Public Works and Engineering Traffic Management Branch at least five working days prior to closing a street or street crossing. Obtain permits for street closures in advance.

C. Maintain 10-foot-wide minimum access lanes for emergency vehicles including access to fire hydrants.

D. Avoid obstructing drainage ditches or inlets. When obstruction is unavoidable due to requirements of the Work, provide grading and temporary drainage structures to maintain unimpeded flow.

E. Locate and protect private lawn sprinkler systems that may exist within the site. Repair or replace damaged systems to condition existing at start of the Work, or better. Test irrigation system prior to construction.

F. Conform to daily clean-up requirements of Article 3 of Document 00700 - General Conditions.

G. Beware of overhead power lines existing in area and in close proximity of the Project. When 10 feet of clearance between energized overhead power line and construction-related activity cannot be maintained, request Center Point Energy (CPE) de-energize or move conflicting overhead power line. Contact CPE representatives at (713) 207-2222. Schedule, coordinate and pay costs associated with de-energizing or moving conflicting overhead power lines. When there is no separate pay item for this effort, include these costs in various items of bid that make such work necessary.

1.05 NOTIFICATION TO ADJACENT OCCUPANTS

A. Notify individual occupants in areas to be effected by the Work of proposed construction and time schedule. Notify not less than 72 hours or more than two weeks prior to work performed within 200 feet of homes or businesses. Follow form and content of sample door hanger provided by Project Manager.

B. Include in notification nature of the Work, and names and telephone numbers of two company representatives for resident contact available on 24-hour call.

C. Submit proposed notification to Project Manager for approval. Consider ethnicity of the neighborhood where English is not the dominant language. Provide notice in an understandable language.

1.06 PUBLIC, TEMPORARY, AND CONSTRUCTION ROADS AND RAMPS

A. Construct and maintain temporary detours, ramps, and roads to provide for normal public traffic flow when it is necessary to close public roads or streets.

B. Provide mats or other means to prevent overloading or damage to existing roadways from tracked equipment, large tandem axle trucks or equipment that will damage the existing roadway surfaces.

C. Construct and maintain access roads and parking areas as specified in Section 01504 - Temporary Facilities and Controls.

1.07 EXCAVATION IN STREETS AND DRIVEWAYS

A. Avoid hindering or inconveniencing public travel on streets or intersecting alleys for more than two blocks at any one time, except by permission of City Engineer.

B. Obtain Traffic Management Branch and City Engineer's approval when nature of the Work requires closure of an entire street. Permits required for street closure are Contractor's responsibility. Avoid unnecessary inconvenience to abutting property owners.

C. Remove surplus materials and debris and open each block for public use, as work in that block is complete.

D. Acceptance of any portion of the Work will not be based on return of street to public use.

E. Avoid obstructing driveways or entrances to private property.

F. Provide temporary crossings or complete excavation and backfill in one continuous operation to minimize duration of obstruction when excavation is required across drives or entrances.

G. Provide barricades and signs in accordance with Section VI of the State of Texas Manual on Uniform Traffic Control Devices.

1.08 TRAFFIC CONTROL

A. Comply with traffic regulation as specified in Section 01555 - Traffic Control and Regulation.

1.09 SURFACE RESTORATION

A. Restore the site including landscaping to the condition existing before construction, or better.

B. Repair paved areas per the requirements of Section 02951 - Pavement Repair and restoration.

C. Repair damaged turf areas, level with bank run sand conforming to Section 02317 - Excavation and Backfill for Utilities, or topsoil conforming to Section 02911 - Topsoil, and re-sod in accordance with Section 02922 - Sodding. Water and level newly sodded areas with adjoining turf using appropriate steel wheel rollers for sodding. Do not use spot sodding or sprigging.

1.10 LIMITS OF CONSTRUCTION

A. Confine operations to lands within construction work limits shown on Drawings. Unless otherwise noted on Drawings adhere to the following:

1. Where utility alignment is within esplanade, and construction limits are shown on Drawings to extend to edge of esplanade, keep equipment, materials, stockpiles a minimum of five feet from back of curb.

2. Where construction limits shown on Drawings extend to property line, keep sidewalks free of equipment, materials, and stockpiles.

1.11 EQUIPMENT AND MATERIAL SALVAGE

A. Upon completion of the Work, carefully remove salvageable equipment and material. Deliver them to City of Houston as directed by Project Manager. Dispose of equipment offsite at no additional cost to the City when Project Manager deems equipment unfit for further use.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01255

CHANGE ORDER PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Procedures for processing Change Orders, including:

1. Assignment of a responsible individual for approval and communication of changes in the Work;

2. Documentation of change in Contract Price and Contract Time;

3. Change procedures, using proposals and Modifications;

4. Execution of Change Orders;

5. Correlation of Contractor submittals.

1.02 REFERENCES

A. Blue Book is defined as the Rental Rate Blue Book for Construction Equipment (a.k.a. Data Quest Blue Book).

B. Rental Rate is defined as the full-unadjusted base rental rate for the appropriate item of construction equipment.

1.03 RESPONSIBLE INDIVIDUAL

A. Provide a letter indicating the name and address of the individual authorized to execute Modifications, and who will be responsible for informing others in Contractor's employ and Subcontractors of changes to the Work. Provide this information at the pre-construction meeting.

1.04 DOCUMENTATION OF CHANGE IN CONTRACT PRICE AND CONTRACT TIME

A. Maintain detailed records of changes in the Work. Provide full information required for identification and evaluation of proposed changes, and substantiate costs of changes in the Work.

B. Document each proposal for change in Contract Price or Contract Time with sufficient data to allow evaluation of proposal.

C. Include the following minimum information on proposals:

1. Quantities of items in original Document 00410 – Bid Form with additions, reductions, deletions, and substitutions.

2. Quantities and cost of items in original Schedule of Values with additions, reductions, deletions and substitutions.

3. Provide Unit Prices for new items, with supporting information, for inclusion in Schedule of Unit Price Work.

4. Justification for changes in Contract Time.

5. Additional data upon request.

D. For changes in the Work performed on a time-and-material basis, provide the following additional information:

1. Quantities and description of Products.

2. Taxes, insurance and Bonds.

3. Overhead and profit as noted in Document 00700 - General Conditions.

4. Dates, times and by who work was performed.

5. Time records and certified copies of applicable payrolls.

6. Invoices and receipts for Products, rental equipment, and subcontracts, similarly documented.

E. For changes in the Work performed on a time-and-materials basis, rental equipment is paid as follows:

1. Actual invoice cost for duration of time required to complete extra work without markup for overhead and profit. When extra work comprises only a portion of a rental invoice where equipment would otherwise be on site, compute hourly equipment rate by dividing the actual monthly invoice by 176. One day equals eight hours and one week equals 40 hours.

2. Do not exceed estimated operating costs given in Blue Book for items of equipment. Overhead and profit will be allowed on the operating cost.

F. For changes in the Work performed on a time-and-materials basis using Contractor-owned equipment, use Blue Book rates as follows:

1. Contractor-owned equipment will be paid at the Blue Book Rental Rate for the duration of time required to complete extra work without markup for overhead and profit. Utilize lowest cost combination of hourly, daily, weekly or monthly rates. Use 150 percent of Rental Rate for double shifts, one extra shift per day, and 200 percent of Rental Rate for more than two shifts per day. Standby rates shall be 50 percent of the appropriate Rental Rate shown in Blue Book. No other rate adjustments apply.

2. Do not exceed estimated operating costs given in Blue Book. Overhead and profit will be allowed on operating costs. Operating costs will not be allowed for equipment on standby.

1.05 CHANGE PROCEDURES

A. Changes to Contract Price or Contract Time can only be made by issuance of Document 00941 - Change Order. Issuance of Document 00940 - Work Change Directive will be formalized into a Change Order. Changes will be in accordance with requirements of Document 00700 - General Conditions.

B. City Engineer will advise of Minor Changes in the Work as authorized by the Document 00700 - General Conditions by issuing Document 00942 – Minor Change.

C. Request clarification of Drawings, Specifications, Contract documents or other information by using Document 00931- Request for Information. Response by Project Manager to Requests for Information does not authorize Contractor to perform tasks outside scope of the Work. Changes must be authorized as described in this Section.

1.06 PROPOSALS AND CONTRACT MODIFICATIONS

A. Project Manager may issue Document 00932- Request for Proposal, which includes a detailed description of the proposed change with supplementary or revised Drawings and Specifications. Project Manager may also request a proposal in response to a Request for Information. Prepare and submit the proposal within seven days or as specified in request.

B. Submit requests for Contract changes to City Engineer describing proposed change and its full effect on the Work, with a statement describing reason for change and effect on Contract Price and Contract Time including full documentation.

C. Design Consultant may review Change Orders.

1.07 WORK CHANGE DIRECTIVE

A. City Engineer may issue a signed Work Change Directive instructing Contractor to proceed with a change in the Work. Work Change Directive will subsequently be incorporated into a Change Order.

B. Work Change Directives will describe changes in the Work and designate the method of determining change in Contract Price or Contract Time.

C. Proceed promptly to execute changes in the Work in accordance with the Work Change Directive.

1.08 STIPULATED PRICE CHANGE ORDER

A. A Stipulated Price Change Order will be based on an accepted proposal.

1.09 UNIT PRICE CHANGE ORDER

A. Where Unit Prices for affected items of the Work are included in Document 00410 – Bid Form, the Change Order will be based on Unit Prices, subject to Articles 7 and 9 of Document 00700 - General Conditions.

B. Where Unit Prices of the Work are not pre-determined in Document 00410-Bid Form, the Work Change Directive or accepted proposal will specify the Unit Prices to be used.

1.10 TIME-AND-MATERIAL CHANGE ORDER

A. Provide itemized account and supporting data after completion of change, within time limits indicated for claims in Document 00700 - General Conditions.

B. City Engineer will determine the change allowable in Contract Price and Contract Time as provided in Document 00700 - General Conditions.

C. Maintain detailed records for work done on time-and-material basis as specified in Paragraph 1.04 above.

D. Provide full information required for evaluation of changes and substantiate costs for changes in the Work.

1.11 EXECUTION OF CHANGE DOCUMENTATION

A. City Engineer will issue Change Orders, Work Change Directives, or Minor Change in the Work for signatures of Parties as described in Document 00700 - General Conditions.

1.12 CORRELATION OF CONTRACTOR SUBMITTALS

A. For Stipulated Price Contracts, promptly revise Schedule of Values and Application for Payment forms to record authorized Change Orders as separate line item.

B. For Unit Price Contracts, the next monthly estimate of the Work after acceptance of a Change Order will be revised to include new items not previously included with appropriate Unit Prices.

C. Promptly revise progress schedules to reflect change in Contract Time, and to adjust time for other items of work affected by the change, and resubmit for review.

D. Promptly enter changes to on-site and record copies of Drawings, Specifications or Contract documents as required in Section 01785 - Project Record Documents.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01270

MEASUREMENT AND PAYMENT

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Procedures for measurement and payment plus conditions for nonconformance assessment and nonpayment for rejected Products.

1.02 AUTHORITY

A. Measurement methods delineated in Specification sections are intended to complement criteria of this Section. In event of conflict, requirements of the Specification section shall govern.

B. Project Manager will take all measurements and compute quantities accordingly.

C. Assist by providing necessary equipment, workers, and survey personnel.

D. Measurement and Payment paragraphs are included only in those Specification sections of Division 01 where direct payment will be made. Include costs in the total bid price for those Specification sections in Division 01 that do not contain Measurement and Payment paragraphs,

1.03 UNIT QUANTITIES SPECIFIED

A. Quantity and measurement estimates stated in the Agreement are for contract purposes only. Quantities and measurements supplied or placed in the Work and verified by Project Manager will determine payment as stated in Article 9 of Document 00700 - General Conditions.

B. When actual work requires greater or lesser quantities than those quantities indicated in Document 00410 – Bid Form, provide required quantities at Unit Prices contracted, except as otherwise stated in Article 9 of Document 00700 - General Conditions.

1.04 MEASUREMENT OF QUANTITIES

A. Measurement by Weight: Reinforcing steel, rolled or formed steel or other metal shapes are measured by CRSI or AISC Manual of Steel Construction weights. Welded assemblies are measured by CRSI or AISC Manual of Steel Construction or scale weights.

B. Measurement by Volume:

1. Stockpiles: Measured by cubic dimension using mean length, width, and height or thickness.

2. Excavation and Embankment Materials: Measured by cubic dimension using average end area method.

C. Measurement by Area: Measured by square dimension using mean length and width or radius.

D. Linear Measurement: Measured by linear dimension, at item centerline or mean chord.

E. Stipulated Price Measurement: By unit designated in the Agreement.

F. Other: Items measured by weight, volume, area, or linear means or combination, as appropriate, as completed item or unit of the Work.

G. Measurement by Each: Measured by each instance or item provided.

H. Measurement by Lump Sum: Measure includes all associated work.

1.05 PAYMENT

A. Payment includes full compensation for all required supervision, labor, Products, tools, equipment, plant, transportation, services, and incidentals; and erection, application or Installation of an item of the Work; and Contractor's overhead and profit.

B. Total compensation for required Unit Price work shall be included in Unit Price bid in Document 00410 – Bid Form. Claims for payment as Unit Price work, but not specifically covered in the list of Unit Prices contained in Document 00410 – Bid Form, will not be accepted.

C. Interim payments for stored materials will be made only for materials to be incorporated under items covered in Unit Prices, unless disallowed in Document 00800 - Supplementary Conditions.

D. Progress payments will be based on Project Manager's observations and evaluations of quantities incorporated in the Work multiplied by Unit Price.

E. Final payment for work governed by Unit Prices will be made on the basis of actual measurements and quantities determined by Project Manager multiplied by the Unit Price for work which is incorporated in or made necessary by the Work.

1.06 NONCONFORMANCE ASSESSMENT

A. Remove and replace work, or portions of the Work, not conforming to the Contract documents.

B. When not practical to remove and replace work, City Engineer will direct one of the following remedies:

1. Nonconforming work will remain as is, but Unit Price will be adjusted lower at discretion of City Engineer.

2. Nonconforming work will be modified as authorized by City Engineer, and the Unit Price will be adjusted lower at the discretion of City Engineer, when modified work is deemed less suitable than specified.

C. Specification sections may modify the above remedies or may identify a specific formula or percentage price reduction.

D. Authority of City Engineer to assess nonconforming work and identify payment adjustment is final.

1.07 NONPAYMENT FOR REJECTED PRODUCTS

A. Payment will not be made for any of the following:

1. Products wasted or disposed of in an unacceptable manner.

2. Products determined as nonconforming before or after placement.

3. Products not completely unloaded from transporting vehicles.

4. Products placed beyond lines and levels of required work.

5. Products remaining on hand after completion of the Work, unless specified otherwise.

6. Loading, hauling, and disposing of rejected Products.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01292

SCHEDULE OF VALUES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Preparation and submittal of Schedule of Values for Stipulated Price Contracts or for Major Unit Price Work on Unit Price Contracts.

1.02 PREPARATION

A. For Stipulated Price Contracts, subdivide the Schedule of Values into logical portions of the Work, such as major work items or work in contiguous construction areas. Use Section 01325 - Construction Schedule as a guide to subdivision of work items. Directly correlate Items in the Schedule of Values with tasks in the Construction Schedule. Organize each portion using the Project Manual Table of Contents as an outline for listing value of the Work by Sections. A pro rata share of mobilization, Bonds, and insurance may be listed as separate items for each portion of the Work.

B. For Unit Price Contracts, items should include a proportional share of Contractor's overhead and profit so that total of all items will equal Contract Price.

C. For lump sum equipment items, where submittal of operation and maintenance data and testing are required, include separate items for equipment operation and maintenance data where:

1. submittal of maintenance data is valued at five percent of the lump sum amount for each equipment item and

2. submittal for testing and adjusting is valued at five percent of the lump sum amount for each equipment item.

Round off figures for each item listed to the nearest $100. Set the value of one item, when necessary, to make total of all values equal the Contract Price for Stipulated Price Contracts or the lump sum amount for Unit Price Work.

1.03 SUBMITTAL

A. Submit the Schedule of Values, in accordance with requirements of Section 01330 - Submittal Procedures, at least 10 days prior to processing of the first Certificate for Payment.

B Submit the Schedule of Values in an approved electronic spreadsheet file and an 81/2-inch by 11-inch print on white bond paper.

C. Revise Schedule of Values for items affected by Contract Modifications. After City Engineer has reviewed changes, resubmit at least 10 days prior to the next scheduled Certificate for Payment date.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01312

COORDINATION AND MEETINGS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. General coordination including pre-construction meeting, site mobilization conference, and progress meetings.

1.02 COORDINATION OF DOCUMENTS

A. Coordination is required throughout documents. Refer to Contract documents and coordinate as necessary.

1.03 CONTRACTOR COORDINATION

A. Coordinate scheduling, submittals, and work of various Specification sections to assure efficient and orderly sequence of Installation of interdependent construction elements.

B. Coordinate completion and clean up of the Work prior to the Date of Substantial Completion and for portions of the Work designated for City's partial occupancy.

C. Coordinate access to the site for correction of nonconforming work to minimize disruption of the City's activities where the City is in partial occupancy.

1.04 PRE-CONSTRUCTION MEETING

A. Project Manager will schedule pre-construction meeting.

B. Attendance Required: City representatives, Design Consultant, special consultants as required by Project Manager, Contractor, and major Subcontractors and Suppliers.

C. Agenda:

1. Distribution of Contract documents.

2. Designation of personnel representing the Parties and Design Consultant.

3. Review of insurance.

4. Discussion of formats for Schedule of Values and Construction Schedule.

5. Procedures and processing of Shop Drawings, substitutions, pay estimates or Applications for Payment, Requests for Information, Requests for Proposal, Modifications, and the Contract closeout, other submittals.

6. Scheduling of the Work and coordination with other contractors.

7. Review of Subcontractors and Suppliers.

8. Appropriate agenda items listed for the site mobilization conference, Paragraph 1.05.C, when pre-construction meeting and site mobilization conference are combined.

9. Procedures for testing.

10. Procedures for maintaining record documents.

1.05 SITE MOBILIZATION CONFERENCE

A. When required by Contract documents, Project Manager will schedule a conference at the Project site prior to Contractor mobilization.

B. Attendance Required: City representatives, Design Consultant, special consultants, Superintendent, and major Subcontractors.

C. Agenda:

1. Use of premises by the City and Contractor.

2. Safety and first aid procedures.

3. Construction controls provided by the City.

4. Temporary utilities.

5. Survey and layout.

6. Security and housekeeping procedures.

7. Field office requirements.

1.06 PROGRESS MEETINGS

A. Hold meetings at Project field office or other location designated by Project Manager. Hold meetings at monthly intervals, or more frequently when directed by Project Manager.

B. Attendance Required: Superintendent, major Subcontractors and Suppliers, City representatives, Design Consultant and its subconsultants as appropriate for agenda topics for each meeting.

C. Project Manager will make arrangements for meetings, and for recording minutes.

D. Project Manager will prepare the agenda and preside at meetings.

E. Provide required information and be prepared to discuss each agenda item.

F. Agenda:

1. Review minutes of previous meetings.
2. Review of construction schedule, pay estimates, cash flow curve, payroll and compliance submittals.
3. Field observations, problems, and necessary decisions.
4. Identification of problems that impede planned progress.
5. Review of submittal schedule and status of submittals.
6. Review of RFI and RFP status.
7. Modification status.
8. Review of off-site fabrication and delivery schedules.
9. Maintenance of Construction Schedule.
10. Corrective measures to regain Construction Schedule.
11. Planned progress during the succeeding work period.
12. Coordination of projected progress.
13. Maintenance of quality and work standards.

14. Effect of proposed Modifications on Construction Schedule and coordination.

15. Review Project Record Contract Drawings.

16. Other item relating to the Work.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01321

CONSTRUCTION PHOTOGRAPHS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Photographic requirements for construction photographs and submittals.

1.02 DEFINITIONS

A. Pre-construction Photographs: Photographs taken, in sufficient numbers and detail, prior to Date of Commencement of the Work, to show original construction site conditions.

B. Progress Photographs: Photographs, taken throughout the duration of construction at regular intervals and from fixed vantage points, pre-approved by the City, that document progress of the Work.

C. Finished Photographs: Photographs, taken by a professional photographer near Date of Substantial Completion and before City Council's acceptance of the Work, that are suitable for framing and for use in brochures or on the Internet

1.03 SUBMITTALS

A. Refer to Section 01330, Submittal Procedures, for submittal requirements.

B. Format and Media. Film or digital photography may be used. Submit color photographs, unless otherwise specified.

1. Prints. Submit each Progress or Pre-construction Photograph print in a three-hole plastic pocket or sleeve, bound in a three-ring notebook. Produce prints on photographic-quality paper approved by Project Manager. Minimum size for Pre-construction Photograph prints shall be 3-inches by 5-inches. Progress Photograph prints shall be 8-inches by 10-inches.

2. Film. Use 35mm or larger color film. Submit negatives used to make submitted photographs, in 3-hole 8-1/2 inch by 11-inch plastic sheets with sleeves for negatives.

3. Digital Photography. Use 2.1 megapixel density or greater for photographs. Scanned photographs must equal or exceed 400 dots

per inch when scanned from 8-inch by 10-inch prints. Submit digital photographic files on computer disks. Format disks for MS-DOS (Microsoft Disk Operating System) filing system and in JPEG (Joint Photographic Experts Group) format.

C. Submittal Quantities and Frequencies.

1. Pre-construction Photographs:
   a. For Stipulated Price Contracts, submit two sets of Pre-construction Photographs, if required, prior to first Application for Payment.
   b. For Unit Price Contracts, submit two sets of Pre-construction Photographs prior to start of construction operations.

2. Progress Photographs:
   a. For Stipulated Price Contracts, submit three sets of Progress Photographs with each Application for Payment at the times established for submittal of Applications for Payment. Monthly Applications for Payment shall be deemed incomplete if not accompanied by the required Progress Photographs. Contractor's failure or election to not submit a monthly Application for Payment shall not affect the requirement for monthly Progress Photographs.
   b. Progress Photographs are not required for Unit Price Contracts unless otherwise specified.

3. Finished Photographs: For Stipulated Price Contracts submit two sets of Finished Photographs, if required, after Date of Substantial Completion and prior to final payment. Each set shall contain one 11-inch by 14-inch matte finish color photographic print from each of the two vantage points pre-approved by the City. Vantage points for Finished Photographs will be approved separately from vantage points approved for Progress Photographs. Finished Photographs are not required for Unit Price Contracts unless otherwise specified.

D. Labeling. Place a label on the back of each photographic print, applied so as to not to show through on the front. Labels shall contain the following information:

1. Name of Project, address of Project and GFS Number.

2. Name and address of Contractor.

3. Date photograph was taken.

4. Location photo was taken from and short description of photo subject.

5. Name and address of professional photographer who took the photograph, if applicable.

E. Hand-deliver or transmit prints in standard photographic mailers marked "Photographs - Do Not Bend".

F. Photographic prints, negatives, photographic files and disks become the property of the City. Do not be publish photographs without written consent by the City.

1.04 QUALITY ASSURANCE

A. Contractor shall be responsible for the quality of and timely execution and submittal of photographs.

B. For Finished Photographs, Contractor shall use a professional photographer, with five years minimum professional experience in the Houston area. Contractor shall submit name, address and credentials of professional photographer for Project Manager's review and approval.

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION

3.01 PRE-CONSTRUCTION PHOTOGRAPHS

A. Prior to commencement of construction operations, photograph the site to include initial construction corridor, detour routes, and staging or storage areas.

1. For Stipulated Price Contracts, unless specified as a requirement in other Sections, these photographs are optional for Contractor, but are highly recommended for areas bounded by other property owners.

2. Pre-construction photographs are required for Unit Price Contracts. For line projects with scheduled construction segments, take Pre-construction Photographs prior to commencement of work on each segment.

B. Prepare Pre-construction Photographs as follows:

1. Show the following information on a non-reflective chalkboard placed within the picture frame:
   a. Job number.
   b. Project Number.
   c. Date and time photographs were taken (Automatic date/time in negative is acceptable).
   d. Baseline station, direction of view (i.e. N, S, NW, etc.) and house number or street address and street name.

2. Pre-construction Photographs shall indicate condition of the following:
   a. Esplanades and boulevards.
   b. Yards (near side and far side of street).
   c. House walks and sidewalks.
   d. Curbs.
   e. Areas between walks and curbs.
   f. Particular features (e.g. yard lights, shrubs, fences, trees).

3. Show date photographs were taken on negatives.

C. Show the location of vantage points and direction of shots on a key plan of the site.

3.02 PROGRESS PHOTOGRAPHS

A. Progress Photographs document monthly advancement of the Work. Select vantage points for each shot so as to best show status of construction and progress since last photograph submittal. Select camera stations that will require little or no movement or adjustment over the duration of construction.

B. Take monthly Progress Photographs at regular intervals to coincide with cutoff dates associated with each Application for Payment.

3.03 FINISHED PHOTOGRAPHS

A. Finished Photographs shall be "staged" and taken by a professional photographer to depict the most flattering images of a finished facility. Two vantage points, from which Finished Photographs will be taken, shall be agreed to in advance by the City. Photographer shall consider lighting, time of day, height of eye, landscaping and placement of vehicles, people and other props in each picture. Filters and post-photography processing may be utilized to achieve a finished product acceptable to the City.

3.04 LOCATION

A. Vantage points, times and conditions for camera stations and photography for Progress and Finished Photographs shall be mutually agreed upon by the City, Contractor and Photographer. Progress Photograph vantage points may be changed by mutual agreement as the Work progresses, at no additional cost to the City.

END OF SECTION

Section 01325

CONSTRUCTION SCHEDULE

PART 1 GENERAL

1.01 GENERAL

A. Provide Construction Schedules for the Work included in this Contract in accordance with requirements in this Section. Create Construction Schedule using Critical Path Method (CPM) computer software capable of mathematical analysis of Precedence Diagramming Method (PDM) plan. Provide printed activity listings and bar charts in formats described in this Section.

B. Combine activity listings and bar charts with narrative report to form Construction Schedule submittal for Project Manager.

1.02 SCHEDULING STAFF

A. Employ or retain services of individual experienced in CPM scheduling for duration of the Contract. Individual shall cooperate with Project Manager and update schedule monthly as required to indicate current status of the Work.

1.03 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. During preconstruction meeting, as described in Section 01312 - Coordination and Meetings, provide sample bar charts and activity listings produced from scheduling software proposed. Scheduling software is subject to review by Project Manager and must meet requirements provided in this Section. Project Manager will provide review of samples within seven days of submittal.

C. Within 21 days of receipt of approval of Contractor's format, or 30 days of Notice to Proceed, whichever is later, submit proposed Construction Schedule for review. Base Construction Schedule submittal on the following:

1. Level of detail and number of activities required in schedule are dependent on project type.
    a. For wastewater projects, categorize work type and area code in schedule.
        1) For wastewater rehabilitation projects, there are six work-type categories. An area code will be assigned for each

Meter Service Area or Basin. Include at least one activity for each unique combination of work type and area code. Normal schedules of wastewater rehabilitation projects contain between 35 and 100 activities, depending on number of basins and work types involved in each basin.

2) For wastewater relief projects (line work), area codes will be assigned geographically.

3) For wastewater plant or facility work, other criteria may apply to assignment of area codes, such as a combination of geographical and craft categories.

b. For projects with multiple types of tasks within scope, indicate types of work separately within schedule.

c. For projects with work at different physical locations or service areas, or different facilities within a site, indicate each location or facility separately within schedule. Show work on each floor of multi-story building as separate tasks.

d. For projects with multiple crafts or significant Subcontractor components, indicate elements separately within schedule. Unless permitted by Project Manager, tasks shall consist of work covered by only one division of Project Manual.

2. Unless permitted by Project Manager, each scheduled task shall be same as Schedule of Values line item, and vice versa.

3. For projects with Major Unit Price Work, indicate Shop Drawing submittal and review, purchase, delivery, and Installation dates on Project schedule. Include activities for testing, adjustment, and delivering O&M manuals.

4. No task except the acquisition of Major Unit Price Work shall represent more than one percent of Original Contract Price for facility projects and three percent of Original Contract Price for other projects. Duration of tasks may not exceed 40 calendar days.

5. For projects where operating facilities are involved, identify each period of work that will impact any process or operation in the schedule and that must be agreed to by Project Manager and facility operator prior to starting work in the area.

D. Construction Schedule submittals shall include:

1. printed bar charts that meet criteria outlined in this Section and are produced by Contractor's approved scheduling software;

2. activity listings that meet criteria outlined in this Section and are produced by Contractor's approved scheduling software; and

3. a predecessor/successor listing sorted by Activity ID that meets criteria outlined in this Section and is produced by Contractor's scheduling software.

4. A logic network diagram is required with the first Construction Schedule submittal for facilities projects.

5. Prepare and submit graphic or tabular display of estimated monthly billings (i.e. a cash flow curve for the Work) with the first schedule submittal. This information is not required in monthly updates, unless significant changes in work require re-submittal of schedule for review. Display shall allocate units indicated in bid schedule or Schedule of Values to Construction Schedule activities. Weighted allocations are acceptable, where appropriate. Dollar value associated with each allocated unit will be spread across the duration of that activity on a monthly basis. Total for each month and cumulative total will be indicated. These monthly forecasts are only for Project Manager's planning purposes. Monthly payments for actual work completed will be made in accordance with Document 00700 - General Conditions.

6. Narrative Report that provides the information outlined in this Section.

E. No payment will be made until Project Manager approves Construction Schedule and billing forecast.

F. If Contractor desires to make changes in its method of operating and scheduling, after Project Manager has reviewed original schedule, notify Project Manager in writing, stating reasons for changes. When Project Manager considers these changes to be significant, Contractor may be required to revise and resubmit for review all or affected portion of Contractor's Construction Schedule to show effect on the Work.

G. Upon written request from Project Manager, revise and submit for review all or any part of Construction Schedule submittal to reflect changed conditions in the Work or deviations made from original schedule.

H. Updated Construction Schedule with actual start and actual finish dates, percent complete, and remaining duration of each activity shall be submitted monthly. Data date used in updating monthly Construction Schedule shall be the same date as used in monthly Payment Application. Monthly update of Construction Schedule is required for monthly Payment Application to be processed for payment.

1.04 SCHEDULING COMPUTER SOFTWARE REQUIREMENTS

A. Contractor's scheduling software shall be capable of creating bar charts and activity listings, which can be sorted by various fields (i.e. Activity ID, Early Start, Total Float, Area Code, Specification Section number, and Subcontractor). Use software capable of producing logic network diagram.

B. Use scheduling software capable of producing activity listings and bar charts with the following information for each activity in the schedule:

1. Activity ID
2. Activity Description
3. Estimated (Original) Duration
4. Remaining Duration
5. Actual Duration
6. Early Start Date
7. Late Start Date
8. Early Finish Date
9. Late Finish Date
10. Free Float
11. Total Float
12. Activity Codes (such as Area Code, Work Type, Specification Section, Subcontractor)

C. Use scheduling software capable of printing calendars using mathematical analysis of schedule, indicating standard workdays of week and scheduled holidays.

D. Use scheduling software capable of printing activity listing that indicates predecessors and successors, lag factors and lag relationships used in creating logic of the schedule.

E. Use scheduling software to provide monthly time in Bar Chart format and scale with 12-month scale not to exceed one page width. Bar charts may be

printed or plotted on 8-1/2 by 11-inch, 8-1/2 by 14-inch or 11 by 17-inch sheet sizes. Over-size plots are not acceptable.

1.05 NARRATIVE SCHEDULE REPORT

A. Narrative schedule report shall list activities started this month, activities completed this month, activities continued this month, activities scheduled to start or complete next month, problems encountered this month, and actions taken to solve these problems.

B. Narrative schedule report shall describe changes made to Construction Schedule logic (i.e. changes in predecessors and lags), activities added to schedule, activities deleted from schedule, any other changes made to the schedule other than addition of actual start dates and actual finish dates and changes of data date and remaining durations for re-calculation of mathematical analysis.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01326

CONSTRUCTION SCHEDULE (BAR CHART)

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Provide an initial Construction Schedule as required by this section for the Work. Do not start construction until Project Manager reviews the schedule.

1.02 FORM AND CONTENT OF INITIAL CONSTRUCTION SCHEDULE

A. Bar Chart:

1. Show major construction activities such as pipe laying, by traffic control phases or other approved key areas; tunnel construction, pavement removal, pavement replacement, pressure testing, chlorination, clean up and punch list as separate activities on the schedule.

2. Show week duration for each activity.

3. Show separate activities for each Shop Drawing and Product Data submittal critical to timely completion. Show submittal dates and dates Project Manager needs to provide approved submittals.

4. Provide separate horizontal bar for each activity. List start and finish date for each activity at left side of diagram.

5. Horizontal Time Scale: Identify first work day of each week.

6. Scale and Spacing: Notes must be legible. Allow space for notations and future revisions.

7. Order of Listings: Order bar chart listings by phases or other approved groups of activities that are contiguous. List activities in chronological order within each phase or group.

B. Narrative Description:

1. Submit narrative descriptions of anticipated work sequences as indicated by the sequence of activities presented in the schedule.

2. Discuss any activity that affects the public (such as phases of traffic control), interaction with specific forces of the City (such as valve operation, chlorination and testing) or other associated contractors.

1.03 PROGRESS REVISIONS

A. Submit progress revisions or necessary information to complete and process Payment Applications. When required, re-submittals for rejected revisions must be submitted and reviewed prior to the following month's processing of a Payment Application. The following month's Payment Application will not be processed until the re-submittal is reviewed and required progress revisions are received.

B. Provide a narrative report to describe:

1. Major changes in scope.

2. Revised projections in progress, completion, or changes in activity duration.

3. Other identifiable changes.

4. Problem areas, anticipated delays, and the impact on schedule.

5. Corrective action recommended and its effect.

6. Effect of changes on schedules or other contractors.

7. Product delivery lead times.

C. Include additional data with Bar Chart described in Paragraph 1.03A of this Section:

1. Show original dates for each activity in the approved initial progress schedule by narrow bar next to a wider bar for the current schedule.

2. Show date each activity actually started or finished when an event has occurred. Clearly identify actual dates in two right-most columns in left portion of an 11 by 17-inch chart.

3. Indicate the percentage progress to the date of submittal for each activity.

1.04 SUBMITTALS

A. Submit the initial progress schedule within 15 days after award of contract. Project Manager will review the schedule and return a reviewed copy within 21 days after receipt.

B. Cut-off dates for progress revisions may be as early as the 20th of the month to avoid delaying processing of Payment Applications. Use the cut-off date for the first approved revision for further revisions.

C. When required, re-submit within seven days after return of review copy.

D. Include connecting lines between bars in the schedule to indicate the sequence that activities will be accomplished. Connecting lines when the activity's start or finish is modified will identify impact of preceding or succeeding activities. Submit a minimum of six copies of the bar chart on 11 by 17-inch opaque reproductions. Project Manager will retain five copies and return the remaining copy.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01330

SUBMITTAL PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Submittal procedures for:

1. Schedule of Values
2. Construction Schedules and Cash Flow Curve (billing forecast).
3. Shop Drawings, Product Data and Samples
4. Operations and Maintenance (O&M) Data
5. Manufacturer's Certificates
6. Construction Photographs
7. Project Record Documents and monthly certification.
8. Video Tapes
9. Design Mixes

1.02 SUBMITTAL PROCEDURES

A. Scheduling and Handling:

1. Submit Shop Drawings, data and Samples for related components as required by Specifications and Project Manager.
2. Schedule submittals well in advance of need for construction Products. Allow time for delivery of Products after submittal approval.
3. Develop submittal schedule that allows sufficient time for initial review, correction, resubmission and final review of all submittals. Allow a minimum of 30 days for initial review. Project Manager will review and return submittals to Contractor as expeditiously as possible but time required for review will vary depending on complexity and quantity of data submitted.

4. Project Manager's review of submittals covers only general conformity to Drawings, Specifications and dimensions that affect layout. Contractor is responsible for quantity determination. No quantities will be verified by Project Manager. Contractor is responsible for errors, omissions or deviations from Contract requirements; review of submittals does not relieve Contractor from the obligation to furnish required items in accordance with Drawings and Specifications.

5. Submit five copies of documents unless otherwise specified.

6. Revise and resubmit submittals as required. Identify all changes made since previous submittal.

7. Assume risk for fabricated Products delivered prior to approval. Do not incorporate Products into the Work, or include payment for Products in periodic progress payments, until approved by Project Manager.

B. Transmittal Form and Numbering:

1. Transmit each submittal to Project Manager with Transmittal letter which includes:
   a. Date and submittal number
   b. Project title and number
   c. Names of Contractor, Subcontractor, Supplier and manufacturer
   d. Identification of Product being supplied
   e. Location of where Product is to be Installed
   f. Applicable Specification section number

2. Identify deviations from Contract documents clouding submittal drawings. Itemize and detail on separate 8-1/2 by 11-inch sheets entitled "DEVIATIONS FOR _____." When no deviations exist, submit a sheet stating no deviations exist.

3. Have design deviations signed and sealed by an appropriate design professional, registered in the State of Texas.

4. Sequentially number transmittal letters beginning with number one. Use original number for resubmittals with an alphabetic suffix (i.e., 2A for the first resubmittal of submittal 2, or 15C for third resubmittal of submittal 15, etc.). Show only one type of work or Product on each submittal. Mixed submittals will not be accepted.

C. Contractor's Stamp:

1. Apply Contractor's Stamp certifying that the items have been reviewed in detail by Contractor and that they comply with Contract requirements, except as noted by requested variances.

2. As a minimum, Contractor's Stamp shall include:
   a. Contractor's name
   b. Job number
   c. Submittal number
   d. Certification statement Contractor has reviewed submittal and it is in compliance with the Contract
   e. Signature line for Contractor

D. Submittals will be returned with one of the following Responses:

1. "ACKNOWLEDGE RECEIPT" when no response and resubmittal is required.

2. "NO EXCEPTION" when sufficient information has supplied to determine that item described is accepted and that no resubmittal is required.

3. "EXCEPTIONS AS NOTED" when sufficient information has been supplied to determine that item will be acceptable subject to changes, or exceptions, which will be clearly stated. When exceptions require additional changes, the changes must be submitted for approval. Resubmittal is not required when exceptions require no further changes.

4. "REJECTED-RESUBMIT" when submittal does not contain sufficient information, or when information provided does not meet Contract requirements. Additional data or details requested by Project Manager must be submitted to obtain approval.

1.03 MANUFACTURER'S CERTIFICATES

A. When required by Specification sections, submit manufacturers' certificate of compliance for review by Project Manager.

B. Place Contractor's Stamp on front of certification.

C. Submit supporting reference data, affidavits, and certifications as appropriate.

D. Product certificates may be recent or from previous test results, but must be acceptable to Project Manager.

1.04 DESIGN MIXES

A. When required by Specification sections, submit design mixes for review.

B. Place Contractor's Stamp, as specified in this section, on the front of each design mix.

C. Mark each mix to identify proportions, gradations, and additives for each class and type of mix submitted. Include applicable test results from samples for each mix. Perform tests and certifications within 12 months of the date of the submittal.

D. Maintain copies of approved mixes at mixing plant.

1.05 CHANGES TO CONTRACT

A. Changes to Contract may be initiated by completing a Request for Information form. Project Manager will provide a response to Contractor by completing the form and returning it to Contractor.

1. If Contractor agrees that the response will result in no increase in cost or time, a Minor Change in the Work will be issued by City Engineer.

2. If Contractor and Project Manager agree that an increase in time or cost is warranted, Project Manager will forward the Request for Proposal for negotiation of a Change Order.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01340

SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Methods, schedules, and processes to be followed for Shop Drawings, Product Data and Sample submittals.

1.02 REQUIREMENT

A. Submit Shop Drawings, Product Data and Samples as required by Document 00700 - General Conditions and Specification sections, using procedures specified in Section 01330 - Submittal Procedures and the requirements of this Section.

B. Shop Drawings, Product Data and Samples are not considered Contract documents.

1.03 SHOP DRAWING/SUBMITTAL SCHEDULE

A. Submit a separate Shop Drawing submittal schedule at same time the Construction Schedule is submitted. List Products for which Shop Drawings and other submittals are required in the order that they appear in Specifications. Include Product Data and Sample submittals in the schedule. Payment Applications or Certificates for Payment will not be processed until Project Manager has approved the Shop Drawing submittal schedule.

1.04 SHOP DRAWINGS

A. Submit a minimum of seven sets of Shop Drawings and Product Data in a form and quality suitable for microfilming. Review and sign Shop Drawings indicating compliance with the Contract.

B. Place Contractor's Stamp on each drawing as described in Section 01330 - Submittal Procedures.

C. Show the following accurately and distinctly:

1. Field and erection dimensions;

2. Arrangement and section views;

3. Relation to adjacent materials or structure, including complete information for making connections between the Work and work under other contracts;

4. Types of Products and finishes;

5. Parts list and descriptions;

6. Assembly drawings of equipment components and accessories showing respective positions and relationships to the complete equipment package;

7. Identify details by referencing drawing sheet and detail numbers, schedule or room numbers as shown on the Contract drawings, where necessary for clarity.

D. Scale drawings to provide a true representation of the specific equipment or item Furnished.

E. Coordinate and submit components, necessary for Project Manager to adequately review submittal, as a complete package. Reproduction of the Drawings for use in Shop Drawings is not allowed.

F. For major changes to original documents, submit Computer-Aided Design (CAD) drawings on a media acceptable to Project Manager.

1.05 PRODUCT DATA

A. Submit Product Data for review as required in Specifications.

B. Place Contractor's stamp, on each data item submitted, as described in Section 01330 - Submittal Procedures.

C. Mark each copy to identify applicable Products, models, and options to be used in the Work. Where required by Specifications, supplement manufacturers' standard data to provide information unique to the Work.

D. Give manufacturers, trade name, model or catalog designation and applicable reference standard for Products specified only by reference standards.

E. Pre-approved and Pre-qualified Products.

1. For "pre-approved", "pre-qualified" and "approved" Products named in the City standard products list, provide an appropriate list designation,

as described in Section 01630 - Product Substitution Procedures, within 30 days after Notice to Proceed.

2. For Products proposed as alternates to "approved" products, provide information required to demonstrate that the proposed Products meet the level of quality and performance criteria of the "approved" product.

1.06 SAMPLES

A. Submit Samples for review as required by Specifications. Have Samples reviewed and signed by a Registered Professional.

B. Place Contractor's stamp on each Sample or firmly attach a sheet of paper with Contractor's stamp, as described in Section 01330 - Submittal Procedures.

C. Submit the number of Samples specified in Specifications; Project Manager will retain one.

D. Reviewed Samples that may be used in the Work are identified in Specifications.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

SECTION 01351

ENVIRONMENTAL SAFETY AND WORKER PROTECTION

PART 1 GENERAL

1.01 SECTION INCLUDES

Environmental Safety and Worker Protection including monitoring emissions and exposure to workers and providing an appropriate response. The role of the Certified Industrial Hygienist (CIH) is also defined.

1.02 MEASUREMENT AND PAYMENT

No separate measurement and payment for work performed under this Section. The Contractor shall include the cost for this work in the contract bid price for work of which this is a component part.

1.03 REFERENCES

The following is a list of applicable requirements to this project. It is not intended to be a complete listing of all laws and regulations to which the Contractor must comply.

A. Code of Federal Regulations

1. 29 CFR 1910, "Occupational Safety and Health Standards".

   a. 29 CFR 1910.146 "Permit-required confined spaces".

2. 29 CFR 1926, "Safety and Health Regulations for Construction" (Construction Industry Standards).

   a. 29 CFR 1926.33 "Access to Employee Exposure and Medical Records".

   b. 29 CFR 1926.51, "Sanitation Standard".

   c. 29 CFR 1926.59, "Hazard Communication".

   d. 29 CFR 1926.62, "Lead".

   e. 29 CFR 1926.103 "Respiratory Protection".

3. 40 CFR 50, "National Primary and Secondary Ambient Air Quality

Standards"

a. 40 CFR 50 Appendix B, "Reference Method for the Determination of Suspended Particulate Matter in the Atmosphere (High Volume Method)".

b. 40 CFR 50 Appendix G, "Reference Method for the Determination of Lead in Suspended Particulate Matter Collected from Ambient Air".

4. 40 CFR 58, "Ambient Air Quality Surveillance".

5. 40 CFR 60 Appendix A, "Visual Determination of Fugitive Emissions from Material Sources and Smoke Emissions from Fires".

6. 40 CFR 117, "Determination of Reportable Quantities for Hazardous Substances".

7. 40 CFR 122, "Administered Permit Program: The National Pollutant Discharge Elimination System".

B. National Institute for Occupational Health and Safety

NIOSH Method 7082, "Lead" (or equivalent).

C. American Society for Testing and Materials

ASTM D3335, "Test Method for Low Concentrations for Lead, Cadmium, and Cobalt in Paint by Atomic Absorption Spectroscopy."

D. EPA (Environmental Protection Agency) Publications

1. SW-846, "Test Methods for Evaluating Solid Waste - Physical/Chemical Methods".

2. EPA Method 3050, "Acid Digestion of Sediments, Sludges, and Soils".

E. SSPC Guide 6, "Guide for Containing Debris Generated During Paint Removal Operations".

F. SSPC Guide 7, "Guide for the Disposal of Lead Contaminated Surface Preparation Debris".

G. SSPC Publication 91-18, "Industrial Lead Paint Removal Handbook".

H. Texas Commission on Environmental Quality

1. Texas Administrative Code (TAC) 30, Chapter 101, "General Rules".

2. Texas Administrative Code (TAC) 30, Chapter 111, "Control of Air Pollution from Visible Emissions and Particulate Matter".

3. Texas Administrative Code (TAC) 30, Chapter 290, "Water Hygiene".

4. Texas Administrative Code (TAC) 30, Chapter 307, "Surface Water Quality Standards".

5. Texas Administrative Code (TAC) 30, Chapter 309, "Effluent Limitations".

6. Texas Administrative Code (TAC) 30, Chapter 335, "Industrial Solid Waste and Municipal Hazardous Waste".

1.04 SUBMITTALS

A. Submittals shall conform to requirements of Section 01330 – Submittal Procedures.

B. Submittals shall conform to appropriate codes for regulatory requirements.

1.05 DEFINITION

A. Acceptance Criteria: Minimum standards for the content of programs, plans, procedures, and designs required by this specification for the performance of this project. Acceptance criteria will be the basis for judging the responsiveness of Contractors' programs and will also be used as a basis for suspending work, if necessary.

B. Action Level: Employee exposure, without regard to the use of respirators, to an airborne concentration of lead of 30 micrograms per cubic meter of air (µg/m3) calculated as an eight hour time-weighted average (TWA).

C. CERCLA: Comprehensive Environmental Response, Compensation, and Liability Act; commonly called Superfund. Federal laws addressing the clean up of hazardous waste sites. Amended in 1986 by Superfund Amendments and Re-Authorization Act (SARA). EPA implementing regulations are contained in 40 CFR 300-373.

D. Competent Person: One who is capable of identifying existing and predictable lead hazards in the surroundings or working conditions and who has authorization to take prompt corrective measures to eliminate them.

E. Containment System: An enclosure built around lead paint removal areas designed to contain lead paint debris and prevent emissions to the environment.

F. Dust Collection: Mechanical ventilation system designed specifically for the containment, capture, and removal of airborne particulate from the containment. Dust collection systems shall include ductwork, plenums and/or hoppers, and dust collector(s) for the removal of leaded paint dust from the air stream prior to discharging to the atmosphere.

G. Emission: A release of material to the air, water, or ground.

H. Entry/Exit Airlock: An isolated enclosure located at the entrance of the containment in which the workers remove contaminated dust and debris from their work clothes.

I. EPA: The US. Environmental Protection Agency. Regulations are contained in Title 40 of the Code of Federal Regulations (40 CFR).

J. Hazardous Waste (lead paint debris): Waste that is classified as hazardous due to its concentrations of regulated hazardous substances. Paint debris is classified as hazardous waste if, after testing by the Toxicity Characteristic Leaching Procedure (TCLP), the leachate contains any of the 8 metals or other substances in concentrations at or above limits established in 40 CFR 261.

K. HEPA: A high efficiency particulate filter (HEPA) that is 99.97% efficient against particles of 0.3 microns in size or larger.

L. Lead Containing Dust and Debris: Dust and debris generated during the project which contains lead in any amount, including but not limited to pulverized paint, spent abrasive, filters (wet and dry), and containment materials upon which lead is still present.

M. NIOSH: National Institute of Occupational Safety and Health.

N. OSHA: Occupational Safety and Health Administration. Standards are contained in Title 29 of the Code of Federal Regulations, Parts 1910 and 1926 (29 CFR 1910 and 29 CFR 1926).

O. Owner: The City of Houston

P. PEL: Permissible Exposure Limit. An employee exposure, without regard to the use of respirators, to an airborne concentration of lead of 50 µg/m3 over an 8 hour TWA.

Q. POTW: Publicly Owned Treatment Works

R. RCRA: Resource Conservation and Recovery Act. Federal law pertaining to hazardous waste management. EPA implementing regulations are contained in 40 CFR 240-280.

S. Regulated Area: Area established by the Contractor to demarcate the zone(s) beyond which airborne concentrations of lead do not exceed the Action Level.

T. SSPC: Society for Protective Coatings. An independent, non-profit organization of engineers, technical specialists, and Contractors whose goal is research and development of new coatings and methods for removal, application, and disposal of existing coatings on industrial structures.

U. Tarpaulins: Flexible fabric, vinyl, plastic or canvas cover sheets, impenetrable to dust, wind, and water, used to enclose the cable and/or scaffold support system comprising the containment enclosure.

V. TCLP: Toxicity Characteristic Leaching Procedure. Laboratory tests conducted on wastes that determine the amount of hazardous materials that leach out into a test solution. The test is intended to simulate the properties of water as it leaches through a solid waste landfill. TCLP testing is defined in 40 CFR 261, Appendix II.

W. TSP: Total Suspended Particulate

PART 2 PRODUCTS

2.01 MATERIAL AND EQUIPMENT

A. The Contractor is to supply materials and equipment to insure the safety and protection of workers and the environment in accordance with these specifications.

PART 3 EXECUTION

3.01 ENVIRONMENTAL PROTECTION AND MONITORING

NOTE: Section 09971 "Painting and Protective Coatings", 2.04 "Containment System" specifically identifies containment system requirements.

A. Protection of Ambient Air: Visible emissions are to be controlled to meet, as a minimum, TAC 30 Chapter 111," Control of Air Pollution from Visible Emissions and Particulate Matter" requirements and SSPC-Guide 6I (CON), Level 1 Emissions. Air monitoring and analysis may be performed by the City during abrasive blast cleaning operations. Such monitoring will be in accordance with 40

CFR 50, Appendix B, "Reference Method for the Determination of Suspended Particulate Matter in the Atmosphere" and/or 40 CFR 50, Appendix G, "Reference Method for the Determination of Lead in Suspended Particulate Matter Collected from Ambient Air". The limits for down wind pollutant concentrations allowed during blasting operations are as follows:

PM-10: 450 micrograms/cubic meter/ 8 hr.. (40 CFR 50.6)

Lead (Pb): 13.5 micrograms/cubic meter/8 hr.. (40 CFR 50.12)

Visible emissions and/or monitored emissions for PM-10 and TSP lead in excess of the above levels shall be cause for shut down of the project until corrections to control/ containment system or paint removal/ surface preparation operations are made to comply with these requirements.

B. Protection of Surface and Storm Water: The Contractor shall take all necessary precautions to ensure lead contaminants do not enter surface waters or storm water drainage systems.

1. The Contractor shall protect the area around ditches and drainage inlets. Daily verification of proper protection to minimize the potential contaminants reaching the drainage system shall be performed.

2. The Contractor shall collect all potentially contaminated process waters for testing and, as appropriate, treatment. Process water from pressure washing, wet abrasive blast cleaning or hygiene facilities shall not be discharged to drainage systems or surface waters.

3. The Contractor may remove lead or other heavy metals from such waters through filtration, ion exchange or other approved means. Following treatment, water samples must be tested prior to disposal. Discharge to sanitary sewer lines requires authorization, in writing, from a POTW.

C. Protection of Soil and Grounds: The Contractor shall protect the soil around the structure to ensure that the soil does not become contaminated. Where lead is present in the coatings to be removed, as indicated in Section 02136 "Waste Material Handling and Disposal", the Contractor shall provide for the sampling and analysis of soil samples for total lead content.

1. Sampling and analysis shall be performed prior to commencement of paint removal operations to establish a background "base level". Soil samples shall be taken 3 feet from the base of the tank(s), at a distance of 6-10 feet beyond the proposed containment structure and at the property line.

2. Samples from each area shall be taken in a minimum of four directions, at

circular increments of 90^0, one of which shall include the direction of prevailing wind. Samples shall also be obtained, at the direction of the engineer, at the closest points of public access (i.e. housing, park, school).

3. The soil sampling procedure shall be as outlined in SSPC Guide 6 Section 5.5.5. Each sampling point shall be sufficiently identified on a site map to allow return to the exact location upon project completion.

4. Each sample shall be split in two portions, one for immediate analysis and the other sealed, preserved and furnished to the Engineer. The samples shall be analyzed in accordance with EPA Method 3050, "Acid Digestion of Sediments, Sludges and Soils", and shall be performed by a qualified laboratory approved by the Engineer.

5. Samples shall be obtained at the completion of work (post-construction samples) from all locations from which pre-construction samples were obtained. Samples shall be collected, handled and tested in the same manner as described above.

6. Upon completion of the work, soils found to be contaminated with lead in greater quantity than found in the background "base level", established at the start of the work, shall be removed by the Contractor to the depth necessary to achieve a lead content equivalent to, or below, the pre-construction back ground levels. Disposal shall be in accordance with applicable regulations.

7. The Contractor shall replace in-kind (i.e., topsoil, structural fill, etc.) with an equivalent amount of non-contaminated soil, compact in place and grade to pre-existing conditions. The Contractor shall also replace in-kind any surface improvements, such as grass, shrubs, etc. that were damaged or destroyed by the work. The soil removal, replacement and related work is to be performed by the Contractor at no additional cost to the Owner.

3.02 WORKER PROTECTION

A. The Contractor shall develop a written Compliance Program to establish and implement practices and procedures for assuring that no employee is exposed to lead at concentrations greater than 50 micrograms per cubic meter of air ($\mu g/m^3$), the OSHA permissible exposure limit (PEL). This program is in addition to other OSHA hazard communication and safety and health requirements of the project, and shall be revised and updated at least every six months.

1. The program shall establish methods for complying with this specification and the OSHA Construction Industry Lead Standard, 29 CFR 1926.62(e)(2)(ii). The Federal regulation is referred to as the "Lead

Standard" for the purpose of this specification.

2. The program shall apply to all Contractor employees associated with lead on the project, and to subcontractors working under the direct control of the Contractor who are associated with lead on the project.

3. The program shall assign the specific responsibility for implementation and enforcement of the program to the Contractors' company management. The Contractor's Competent Person(s) shall be identified, by name, and qualifications submitted. The Competent Person shall be on-site during any operations which involve the removal, handling or disturbing of lead containing materials.

4. The program shall contain a description of each activity in which lead is emitted (e.g. equipment used, material involved, controls in place, crew size, employee job responsibilities, operating procedures and maintenance practices).

5. The program shall contain a report of the technology considered in meeting the PEL and air monitoring data which documents the source of lead emissions.

6. The program shall contain a work practice program which includes items required in the lead standard such as protective clothing and equipment, housekeeping, and hygiene facilities and practices.

B. Exposure Monitoring: The Contractor shall be responsible for conducting and reporting worker exposure assessments in accordance with 29 CFR 1926.62.

1. Representative personal air samples shall be collected at the beginning of the lead removal work to determine employee lead exposures. Tasks involving potential lead exposure include, but are not limited to, paint removal operations, clean-up, and debris handling operations. Full shift (at least 7 hours) air samples shall be collected for each job classification in the exposure area. The range of exposures for lead removal and cleanup activities shall be determined.

2. During the initial monitoring, workers performing the following activities (or equivalent) shall be protected to the anticipated exposure levels which are dictated by the lead standard:

   a. 500 $\mu g/m^3$: Manual demolition of structures containing lead-containing coatings or paint (e.g., dry wall), manual scraping, manual sanding, heat gun applications, power tool cleaning with dust collection systems, and spray painting with lead paint.

b. 2,500 µg/m^3 : Using lead-containing mortar, lead burning, or conducting the following activities where lead-containing coatings or paint are present: rivet busting, power tool cleaning without dust collection systems, clean-up activities where dry expendable abrasives are used, and the movement and removal of abrasive blasting enclosures.

c. More than 2,500 µg/m^3: Activities involving lead containing coatings or paint on structures disturbed by abrasive blasting, welding, cutting, and torch burning.

3. Protection requires compliance with the necessary respiratory protection, personal protective clothing and equipment, change areas and washing facilities, blood lead and zinc protoporphyrin monitoring, and employee training. The protection measures shall be modified, as necessary, after the exposure results are received.

4. Where initial monitoring indicates that lead exposures are below the Action Level, and where work activities and conditions remain the same as at the time of initial sampling, additional monitoring need not be repeated for that work activity.

5. Where the initial monitoring of a given work activity indicates that lead exposures are at or above the Action Level, additional exposure monitoring shall be conducted monthly. The monthly monitoring is more frequent than frequencies established in the lead standard which are at least every 6 months if above the Action Level, but below the PEL, or every 3 months if above the PEL.

6. All air samples shall be collected and analyzed according to NIOSH Method 7082, or equivalent. All samples shall be analyzed by laboratories accredited by the American Industrial Hygiene Association for metals analysis.

7. All exposed employees shall be notified in writing of the monitoring results within five (5) days after receiving the results.

8. The Action Level for airborne lead exposure is 30 µg/m^3, as an 8-hour time weighted average (TWA) concentration, without regard to the use of respirators. Whenever workers' airborne lead exposures exceed the Action Level, the Contractor shall implement the following:

   a. Periodic Exposure Monitoring
   b. Employee Information and Training

c. Employee Medical Surveillance and Medical Removal Protection
d. Housekeeping
e. Record keeping
f. Signs and Regulated Areas

9. The Permissible Exposure Limit (PEL) for airborne lead exposure is 50 $\mu g/m^3$, as an 8-hour TWA concentration. When the work area contains airborne lead levels above the PEL the Contractor shall implement the following in addition to those items listed in 3.02.B.8 of this section:

a. Compliance Program
b. Respiratory Protection
c. Protective Clothing and Equipment
d. Hygiene Facilities and Practices

C. Respiratory Protection: After feasible engineering controls and work practices have been implemented, respiratory protection shall be used to maintain employees' lead exposures below the PEL.

1. Respirators shall be worn by all employees, other Contractors, inspectors, or observers who enter regulated areas.

2. The Contractor shall develop a written Respiratory Protection Program in compliance with 29 CFR 1910.134, paragraphs (b), (d), (e), and (f), and the lead standard. The program shall address the selection, use, maintenance, and inspection of respirators, and qualifications for respirator users.

D. Protective Clothing and Equipment: The Contractor shall provide protective clothing and equipment and ensure they are worn by all employees whose lead exposures exceed the PEL, or who enter regulated areas.

1. Protective clothing shall include washable and/or disposable full body coveralls, gloves, foot coverings, and hoods. Other protective equipment shall include face shields, hard hats, eye protection, and hearing protection as appropriate.

2. Disposable protective clothing shall be used for no more than one work day. Such clothing may have to be disposed of as hazardous waste.

3. Reusable protective equipment shall be cleaned or replaced weekly if exposure levels are less than 200 $\mu g/m^3$, or daily if the exposure levels are greater than or equal to 200 $\mu g/m^3$.

4. Clothing shall not be removed or "cleaned" by any means which could reintroduce the lead dust into the ambient air. This includes brushing,

shaking, and blowing. Vacuums equipped with HEPA filters shall be used for this purpose.

5. Reusable coveralls shall be collected at the end of each work day in closed containers. The containers shall be labeled in accordance with the requirements of 29 CFR 1926.62(g)(2)(vii). Contaminated clothing shall be cleaned in accordance with all applicable Federal, State, or local regulations pertaining to lead-contaminated laundry and water discharge. Laundries shall be informed that the clothing contains lead. If the clothing is washed on site, the discharge water shall be filtered, containerized, and arrangements made with the local POTW or other approved means of proper disposal.

6. Protective clothing and equipment shall be removed in the contaminated section of the change area and shall not be worn into any clean areas.

7. The Contractor shall provide the necessary clothing and equipment for use by the Owner and its designated representatives.

E. Housekeeping: Accumulations of lead-containing dust and debris generated by work activities shall be removed and cleaned daily.

1. All persons doing the cleanup shall be trained in performing lead activities, respirator qualified, and participate in the medical surveillance program. Respirators and protective clothing shall be worn by all persons doing the cleanup.

2. Compressed air may be used for housekeeping if used within containment and in conjunction with a ventilation system designed to capture the dust. Otherwise, HEPA-filtered vacuum cleaners shall be employed.

3. All lead-containing dust and debris shall be collected in sealed containers. The waste shall be tested to determine whether it will be disposed of as hazardous waste.

F. Personal Hygiene Facilities and Practices

1. Clean change areas shall be provided when employees' lead exposures exceed the PEL. The change areas shall be equipped with storage facilities for street clothing and a separate area for the removal and storage of lead-contaminated clothing and equipment. They shall be designed and used so that contamination of street clothing does not occur. Employees shall not leave the project site wearing any clothing worn while performing lead activities. Airborne lead exposures in the change area shall be maintained below the Action Level.

2. Shower facilities shall be provided whenever employees' lead exposures exceed the PEL. Shower facilities shall comply with OSHA Sanitation Standard, 29 CFR 1929.51. All employees whose lead exposures exceed the PEL shall shower at the end of each work shift or before leaving the project area. The shower facilities shall be made available for use by the Owner and its representatives, such as inspectors or observers.

3. Arrangements shall be made with the local POTW for the proper disposal of the shower and wash water after filtration (e.g., through a three stage 100, 50, and 5 micron filtering system), ion exchange, or other approved treatment technology.

4. Clean lunch areas shall be provided for all employees whose lead exposures exceed the PEL. Employees shall remove or clean (by vacuuming) their protective clothing and wash their hands and face before entering the lunch area. Lead exposures in the lunch area shall be maintained as free as practicable from lead contamination.

5. An adequate number of clean lavatory and hand washing facilities shall be provided. These shall comply with the OSHA Sanitation Standard, 29 CFR 1929.51.

6. Eating, drinking, smoking, chewing of food or tobacco products, or the application of cosmetics shall not be permitted in any areas where the lead exposures exceed the PEL. Thorough washing of hands and face is required prior to undertaking any of these activities.

G. Medical Surveillance and Medical Removal Protection

1. All employees who are exposed to lead above the Action Level in a single day during this project shall be provided with initial and periodic medical examinations and blood lead tests as required by the lead standard. A final blood lead test shall be provided for each worker upon completion of the project, or at any time a worker's employment at the project ceases.

2. When blood lead levels over 50 µg/dl are encountered, the Contractor shall provide for the temporary removal of employees from lead exposure above the Action Level. The required medical surveillance and periodic blood lead tests shall be provided in strict accordance with the lead standard throughout the removal.

3. Employees who will be required to wear a respirator or who request one shall be provided with a respirator and the necessary medical examinations to determine their ability to wear a respirator.

4. All examinations shall be provided by the Contractor and shall be performed by or under the direct supervision of a licensed physician.

H. Employee Information and Training

1. The Contractor shall provide lead training for all employees who are exposed to lead above the Action Level for this project.

2. The content of lead training shall include, as a minimum, those items listed in the lead standard.

3. Training shall also include hazard communication in accordance with 29 CFR 1926.59.

4. The Contractor shall notify other employers at the project site of the nature of the lead exposure work, the need to remain out of exposure areas, the warning sign and labeling system in effect, and the potential need for them to take measures to protect their employees.

I. Signs and Regulated Areas

1. The Contractor shall establish a regulated area surrounding activities where lead exposures exceed the Action Level. This includes locations where lead-containing debris is handled or transferred to storage containers.

2. The regulated area shall be demarcated by ropes, tape, walls, or containment's with caution signs posted at all accessible sides. Signs shall contain the legend:

WARNING
LEAD WORK AREA
POISON
NO SMOKING OR EATING

3. The Contractor shall control access of persons into regulated areas. Access shall be limited to individuals with proper training and personal protective equipment, and medical surveillance testing.

4. All persons entering regulated areas shall wear protective clothing and respirators.

5. Eating, drinking, smoking, and chewing of food or tobacco products shall be prohibited in regulated areas and in any area where lead exposures exceed the Action Level.

J. Record keeping: All records relating to training, medical examinations, blood lead monitoring, and exposure monitoring shall be maintained by the Contractor as required by the lead standard. All records shall be available for review by the Owner or its representative upon request.

3.03 CERTIFIED INDUSTRIAL HYGIENIST (CIH)

A. The Contractor shall provide for the services of a Certified Industrial Hygienist (CIH) who must be certified by the American Board of Industrial Hygiene in comprehensive practice.

B. Duties of the CIH shall be as follows:

1. Conduct and/or verify training for contractor employees in accordance with 29 CFR 1926.62 (l).

2. Review and approve Contractor's Written Compliance Plan for conformance to 29 CFR 1926.62(e)(2)(ii) and this Specification.

3. Monitor and evaluate work weekly to assure conformance with the approved plan and that hazardous exposure is adequately controlled in accordance with worker safety and health requirements of these specifications

4. Provide monthly reports of work compliance with control requirements in regards to working in a lead environment.

C. Activities of the CIH shall include:

1. Meet with City to discuss details of Contractor's Written Compliance Plan for lead paint removal.

2. Ensure worker and area air monitoring, testing and reporting are conducted by or under the direction of the CIH.

3. Furnish a detailed worker and area air monitoring schedule coordinated with Contractor's proposed production schedule.

4. Directing, monitoring and inspecting lead paint removal work to ensure that the requirements of the Contract have been satisfied during the entire lead paint removal operation.

5. Report results of air monitoring samples to the Engineer, signed by the CIH within 48 hours after the air samples are taken.

6. The CIH shall review sampling data, collected on a day when lead paint

removal operations occur, to determine if conditions require any change in work methods. Removal work shall not continue until approval is given by the CIH.

7. The CIH shall verify in writing and submit monitoring data to verify that:

   a. Air borne lead levels at and beyond the lead control (regulated) area were and remained less than 30 mg/m^3 of air

   b. Contractor conformance to 29 CFR 1926.62 and Item 3.02, above

   c. There were no visible accumulations of lead contaminated paint, dust or debris on the work site. Adjacent areas that may have become contaminated were properly cleaned and inspected.

   d. The CIH shall verify that the work area and contractor's equipment have been adequately cleaned of lead contamination prior to demobilization from the work site.

3.04 DEMOBILIZATION

The Contractor shall not remove the lead control area, boundaries, warning signs, etc. prior to proper removal of all hazardous wastes, debris and materials from the site and the City's receipt and acceptance of the CIH's verification.

END OF SECTION

Section 01410

TPDES REQUIREMENTS

1.01 SECTION INCLUDES

A. Documentation to be prepared and signed by Contractor/Operator before conducting construction operations, in accordance with the Texas Pollutant Discharge Elimination System (TPDES) Construction General Permit Number TXR 150000 issued February 15, 2008 (the Construction General Permit).

B. Implementation, maintenance inspection, and termination of storm water pollution prevention control measures including, but not limited to, erosion and sediment controls, storm water management plans, waste collection and disposal, off-site vehicle tracking, and other appropriate practices shown on the Drawings or specified elsewhere in the Contract.

C. Review of the Storm Water Pollution Prevention Plan (SWP3) implementation in a meeting with Project Manager prior to start of construction.

1.02 DEFINITIONS

A. Commencement of Construction Activities: The exposure of soil resulting from activities such as clearing, grading, and excavation activities, as well as other construction related activities (e.g., stock piling of fill material, demolition).

B. Large Construction Activity: Project that:o

1. disturbs five acres or more, or

2. disturbs less than five acres but is part of a larger common plan of development that will disturb five acres or more of land.

C. Small Construction Activity: Project that:

1. disturbs one or more acres but less than five acres, or

2. disturbs less than one acre but is part of a larger common plan of development that will ultimately disturb one or more acres but less than five acres.

D. TPDES Operator:

Operator - The person or persons associated with a large or small construction activity that is either a primary or secondary as defined below:

Primary Operator – the person or persons associated with a large or small construction activity that meets either of the following two criteria:

(a) the persons have operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; or

(b) the person or persons have day-to-day operational control of those activities at a construction site that are necessary to ensure compliance with a storm water pollution prevention plan (SWP3) for the site or other permit conditions (e.g., they are authorized to direct workers at a site to carry out activities required by the SWP3 or comply with other permit conditions).

Secondary Operator – The person whose operational control is limited to the employment of other operators or to the ability to approve or disapprove changes to plans and specifications. A secondary operator is also defined as a primary operators if there are no other operators if there are no other operators at the construction site.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N

3.01 SITE SPECIFIC STORM WATER POLLUTION PREVENTION PLAN (SWP3)

A. Prepare a SWP3 following Part III of the Construction General Permit and the Storm Water Management Handbook for Construction Activities issued under City Ordinance Section 47-695(b). If conflicts exist between the Construction General Permit and the handbook, the more stringent requirements will apply.

B. Update or revise the SWP3 as needed during the construction following Part III, Section E of the Construction General Permit.

C. Submit the SWP3 and any updates or revisions to Project Manager for review and address comments prior to commencing, or continuing, construction activities.

3.02 NOTICE OF INTENT For Large Construction Activity

A. Fill out, sign, and date TCEQ Form 20022 (03/05/2008) Notice of Intent (NOI) for Storm Water Discharges Associated with Construction Activity under the TPDES Construction General Permit (TXR 150000), **ATTACHMENT 1** of this Section 01410.

B. Transmit the signed Contractor's copy of TCEQ Form 20022 (03/05/2008), along with a $325.00 check, made out to Texas Commission on Environmental Quality, and the completed Payment Submittal Form to Project Manager.

C. Project Manager will complete a separate TCEQ Form 20022 (03/05/2008) for City's Notice of Intent, and will submit both Notices, along with checks for application fees, to the TCEQ.

D. Submission of the Notice of Intent form by both the City and Contractor to TCEQ if mailing is required a minimum of seven days before Commencement of Construction Activities.

3.03 CONSTRUCTION SITE NOTICE FOR SMALL CONSTRUCTION ACTIVITY

A. Fill out, sign, and date the Construction Site Notice, Attachment 2 to TPDES General Permit TXR 150000, "Construction Site Notice", **ATTACHMENT 2** of this Section 01410.

B. Transmit the signed Construction Site Notice to Project Manager at least seven days prior to Commencement of Construction Activity.

3.04 CERTIFICATION REQUIREMENTS

A. Fill out TPDES Operator's Information form, **ATTACHMENT 3** of this Section 01410, including Contractor's name, address, and telephone number, and the names of persons or firms responsible for maintenance and inspection of erosion and sediment control measures. Use multiple copies as required to document full information.

B. Contractor and Subcontractors shall sign and date the Contractor's / Subcontractor's Certification for TPDES Permitting, **ATTACHMENT 4** of this Section 01410. Include this certification with other Project certification forms.

C. Submit properly completed certification forms to Project Manager for review before beginning construction operations.

D. Conduct inspections in accordance with TCEQ requirements. Ensure persons or firms responsible for maintenance and inspection of erosion and sediment control measures read, fill out, sign, and date the Erosion Control Contractor's Certification for Inspection and Maintenance. Use the City of Houston Storm Water Pollution Prevention Plan, Construction Site Inspection Report, **ATTACHMENT 5** of this Section 01410 to record maintenance inspections and repairs.

3.05 RETENTION OF RECORDS

A. Keep a copy of this document and the SWP3 in a readily accessible location at the construction site from Commencement of Construction Activity until submission of the Notice of Termination (NOT) for Storm Water Discharges Associated with Construction Activity under TPDES Construction General Permit (TXR 150000). Contractors with day-to-day operational control over SWP3 implementation shall have a copy of the SWP3 available at a central location, on-site, for the use of all operators and those identified as having responsibilities under the SWP3. Upon submission of the NOT, submit all required forms and a copy of the SWP3 with all revisions to Project Manager.

3.06 REQUIRED NOTICES

A. Post the following notices from effective date of the SWP3 until date of final site stabilization as defined in the Construction General Permit:

1. Post the TPDES permit number for Large Construction Activity, with a signed TCEQ Construction Site Notice for large or Small Construction Activity. Signed copies of the City's and Contractor's NOI must also be posted.

2. Post notices near the main entrance of the construction site in a prominent place where it is safely and readily available for viewing by General Public, Local, State, and Federal Authorities. Post name and telephone number of Contractor's local contact person, brief project description and location of the SWP3.

   a. If posting near a main entrance is not feasible due to safety concerns, coordinate posting of notice with Project Manager to conform to requirements of the Construction General Permit.

   b. If Project is a linear construction project (e.g.: road, utilities, etc.), post notice in a publicly accessible location near active construction. Move notice as necessary.

3. Post a notice to equipment and vehicles operators, instructing them to stop, check, and clean tires of debris and mud before driving onto traffic lanes. Post at each stabilized construction access area.

4. Post a notice of waste disposal procedures in a readily visible location on site.

3.07 ON-SITE WASTE MATERIAL STORAGE

A. On-site waste material storage shall be self-contained and shall satisfy appropriate local, state, and federal rules and regulations.

B. Prepare list of waste material to be stored on-site. Update list as necessary to include up-to-date information. Keep a copy of updated list with the SWP3.

C. Prepare description of controls to reduce pollutants generated from on-site storage. Include storage practices necessary to minimize exposure of materials to storm water, and spill prevention and response measures consistent with best management practices. Keep a copy of the description with the SWP3.

3.08 NOTICE OF TERMINATION

A. Submit a NOT, **ATTACHMENT 7** of this Section 01410, to Project Manager within 30 days after:

1. Final stabilization has been achieved on all portions of the site that are the responsibility of the Contractor; or

2. Another operator has assumed control over all areas of the site that have not been stabilized; and

3. All silt fences and other temporary erosion controls have either been removed, scheduled to be removed as defined in the SWP3, or transferred to a new operator if the new operator has sought permit coverage.

B. Project Manager will complete City's NOT and submit Contractor and City's notices to the TCEQ and MS4 entities.

END OF SECTION

PAGE LEFT INTENTIONALLY BLANK

ATTACHMENT 1

Notice of Intent (NOI) for Storm Water Discharges Associated with Construction Activity under the TPDES Construction General Permit (TXR150000)

For help completing this application, read the TXR150000 NOI Instructions (TCEQ-20022-Instructions)

TCEQ Office Use Only
TPDES Permit Number: TXR15 __|__|__|__| - NO
GIN Number: |__|__|__|__|__|__|__|__|

A. Construction Site Operator ☐New ☐No Change Customer Reference Number: CN_____
Name:_____
Mailing Address:_____ City:_____ State:____ Zip Code:_____
Country Mailing Information (*if outside USA*) Territory:_____ Country Code:_____ Postal Code:_____
Phone Number:_____ Extension:_____ Fax Number:_____
E-mail Address:_____
Type of Operator: ☐ Individual ☐ Sole Proprietorship - D.B.A. ☐ Partnership ☐ Corporation ☐ Federal Government
☐ State Government ☐ County Government ☐ City Government ☐ Other:_____
Independent Operator? ☐ Yes ☐ No Number of Employees: ☐ 0-20 ☐ 21-100 ☐ 101-250 ☐ 251-500 ☐ 501 or higher
Federal Tax ID:_____ State Franchise Tax ID Number:_____ DUNS Number:_____

B. Billing Address
Name:_____
Mailing Address:_____ City:_____ State:____ Zip Code:_____
Country Mailing Information (*if outside USA*) Territory:_____ Country Code:_____ Postal Code:_____

C. Project / Site Information ☐New ☐No Change Regulated Entity Reference Number: RN_____
Name:_____
Mailing Address:_____ City:_____ State:____ Zip Code:_____
Physical Address:_____ City:_____ County:_____ Zip Code:_____
Location Access Description:_____
Latitude:___°___'___" N Longitude:___°___'___" W Degrees (°), Minutes ('), and Seconds (")
Latitude:_____ Longitude: -_____ Decimal Form
Standard Industrial Classification (SIC) code:_____ Also, describe the construction activity at this site (*do not repeat the SIC code*):
_____
Has a storm water pollution prevention plan been prepared as specified in the general permit (TXR150000)? ☐ Yes ☐ No
Estimated area of land disturbed (to the nearest acre):_____ Is the project / site located on Indian Country Lands? ☐ Yes ☐ No
Does this project / site discharge storm water into a municipal separate storm sewer system (MS4)? ☐ Yes ☐ No
If yes, provide the name of the MS4 operator:_____
Provide the name or segment number of the water body that receives storm water from this project / site:_____

D. Contact - If the TCEQ needs additional information regarding this application, who should be contacted?
Name:_____ Title:_____
Phone Number:_____ Extension:_____ Fax Number:_____
E-mail Address:_____

E. Payment Information - Check / Money Order Number:_____ Name on Check / Money Order:_____

F. Certification
I certify under penalty of law that this document was prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations

Construction Site Operator:
Prefix:_____ First:_____ Middle:_____
Last:_____ Suffix:_____ Title:_____
Signature:_____ Date:_____

If you have questions on how to fill out this form or about the storm water program, please contact us at (512) 239-4671.
Individuals are entitled to request and review their personal information that the agency gathers on its forms. They may also have any errors in their information corrected. To review such information, contact us at (512) 239-3282.

The completed NOI must be mailed to the following address. Use the attached document to submit the $100 application fee. Please note that the NOI and application fee are submitted separately to different addresses.

Texas Commission on Environmental Quality
Storm Water & General Permits Team; MC - 228
P.O. Box 13087
Austin, Texas 78711-3087

TCEQ-20022 (05/03) Page 1 of 2

ATTACHMENT 1

Texas Commission on Environmental Quality
Payment Submittal Form

The storm water application fee shall be sent under separate cover to the Texas Commission on Environmental Quality.

This form must be used to submit your Storm Water Application Fee. Please complete the following information, staple your check in the space provided at the bottom of this document, and mail it to:

BY REGULAR U.S. MAIL

Texas Commission on Environmental Quality
Financial Administration Division
Cashier's Office, MC-214
P.O. Box 13088
Austin, TX 78711-3088

BY OVERNIGHT/EXPRESS MAIL

Texas Commission on Environmental Quality
Financial Administration Division
Cashier's Office, MC-214
12100 Park 35 Circle
Austin, TX 78753

Fee Code: GPA

Storm Water General Permit: TXR150000

Check / Money Order No: _____ Amount of Check/Money Order: _____

Date of Check or Money Order: _____

Name on Check or Money Order: _____

Facility / Site Name: _____

Facility / Site Physical Address: _____

City: _____ Zip Code: _____

Staple Check In This Space

ATTACHMENT 1

Completing the Notice of Intent for Storm Water Discharges Associated with Construction Activity under the TPDES Construction General Permit (TXR150000)

A. Construction Site Operator Information

Check boxes and Customer Reference Number
These boxes designate the operator's status as a TCEQ "customer"—in other words, an individual or business that is involved in an activity that we regulate. We assign each customer a number that begins with "CN," followed by nine digits. ***This is not a permit number, registration number, or license number.*** In the remainder of this section, we will use "this customer" to mean the operator for Part A of the form.

- If this customer has not been assigned a Customer Reference Number or if this number is unknown, check "New" and leave the space for the Customer Reference Number blank.
- If this customer has already been assigned this number, enter the operator's Customer Reference Number and:
  - Check "No Change" if all the remaining customer information is the same as previously reported. However, you must still complete most blanks in this form for this notice of intent to be valid.
  - If this customer's information has changed since the last time it was reported to the TCEQ, check neither box and complete the remainder of this notice of intent.
- ***Do not enter a permit number, registration number, or license number in place of the Customer Reference Number.***

Name
Enter the legal name of this customer as authorized to do business in Texas. Include any abbreviations (LLC, Inc., etc.)

Mailing Address
Enter a central and general mailing address for this customer to receive mail from the TCEQ. For example, if this customer is a large company, this address might be the corporate or regional headquarters. On the other hand, for a smaller business, this address could be the same as the site address.

> ***If this is a street address, please follow US Postal Service standards.*** In brief, these standards require this information in this order.
> - the "house" number—for example, the 1401 in 1401 Main St
> - if there is a direction before the street name, the one- or two-letter abbreviation of that direction (N, S, E, W, NE, SE, SW, or NW)
> - the street name (if a numbered street, do not spell out the number—for example, 6th St, not Sixth St)
> - an appropriate abbreviation of the type of street—for example, St, Ave, Blvd, Fwy, Expy, Hwy, Cr, Ct, Ln
> - if there is a direction after the street name, the one- or two-letter abbreviation of that direction (N, S, E, W, NE, SE, SW, or NW)
> - if there is a room number, suite number, or company mail code

City, State, *and* ZIP Code
Enter the name of the city, the two-letter USPS abbreviation for the state (for example, TX), and the ZIP Code. (Enter the full ZIP+4 if you know it.)

Country Mailing Information
If this address is ***outside*** the United States, enter the territory name, country code, and any non-ZIP mailing codes or other non-U.S. Postal Service features here. If this address is ***inside*** the United States, leave these spaces blank.

Phone Number *and* Extension
This number should correspond to this customer's mailing address given earlier. Enter the area code and phone number here. Leave "Extension" blank if this customer's phone system lacks this feature.

Fax Number
This number should correspond to this customer's mailing address given earlier. Enter the area code and fax number here.

E-mail Address
As with the mailing address, this should be a general address that is appropriate for e-mail to this customer's central or regional headquarters, if applicable.

> ***If "No Change" was checked for this customer, you may skip the rest of the fields in this part of the form and continue to the next part of the NOI.***

Type of Operator
Check *only one* box.

Check ...	*if this customer ...*
Individual	is a person and has not established a business to do whatever causes them to be regulated by us.
Sole Proprietorship—D.B.A.	is a business that is owned by only one person and has not been incorporated. This business may: • be under the person's name • have its own name (doing business as " or d.b.a.) • have any number of employees
Partnership	is a business that is established as a partnership as defined by the Texas Secretary of State's Office
Corporation	meets all of these conditions: • is a legally incorporated entity under the laws of any state or country • is recognized as a corporation by the Texas Secretary of State • has proper operating authority to operate in Texas
Federal, state, county, or city government (as appropriate)	is either an agency of one of these levels of government or the governmental body itself (if a utility district, water district, tribal government, college district, council of governments, or river authority, check "Other" and write in the specific type of government.)
Other	fits none of the above descriptions. Enter a short description of the type of customer in the blank provided.

Independent Operator?
Check "No" if this customer is a subsidiary or part of a larger company. Otherwise, check "Yes."

Number of Employees
Check one box to show the number of employees for this customer's entire company at all locations. ***This is not necessarily the number of employees at the site named in this NOI.***

Federal Tax ID
All businesses except for some small sole proprietors, should have a federal taxpayer identification number (TIN). Enter this number here. Use no prefixes, dashes, or hyphens. Individuals and sole proprietors do not need to provide a federal tax ID.

State Franchise Tax ID
Corporations and limited liability companies that operate in Texas are issued a franchise tax identification number. If this customer is a corporation or limited liability company, enter this number here.

DUNS Number
Most businesses have a DUNS (Data Universal Numbering System) number issued by Dun and Bradstreet Corp. If this customer has one, enter it here.

B. Billing Address

We will mail the annual fee invoice for the site to the address entered in this section.

Name
Enter the legal name of the person or business to which we should mail this site's fee invoice each year.

Mailing Address
Enter the specific mailing address to which we should mail this site's fee invoice each year. If this is a street address, please follow the US Postal Service standards as described under "A. Construction Site Operator Information" on page 1 of these instructions.

City, State, *and* ZIP Code
Enter the name of the city, the two-letter USPS abbreviation for the state (for example, TX), and the ZIP Code. (Enter the full ZIP+4 if you know it.)

Country Mailing Information
If this address is ***outside*** the United States, enter the territory name, country code, and any non-ZIP mailing codes or other non-U.S. Postal

ATTACHMENT 1

Service features here. If this address is *inside* the United States, leave these spaces blank.

C. Project / Site Information

Check boxes *and* Regulated Entity Reference Number
These boxes designate this site's status as a TCEQ "regulated entity"—in other words, a location where an activity that we regulate occurs. We assign each regulated entity a number that begins with "RN," followed by nine digits. ***This is not a permit number, registration number, or license number.***

- If this site has not been assigned a Regulated Entity Reference Number or if this number is unknown, check "New" and leave the space for the Regulated Entity Reference Number blank.
- If this site has already been assigned this number, enter the Regulated Entity Reference Number and:
  - Check "No Change" if all the remaining information is the same as previously reported. However, even if there has been no change, you must complete this section at least through "E-mail Address" for this NOI to be valid.
  - If this site's information has changed since the last time it was reported to the TCEQ, check neither box and complete the remainder of this notice of intent.
- ***Do not enter a permit number, registration number, or license number in place of the Regulated Entity Reference Number.***

Name
Enter the name by which you want this site to be known to the TCEQ.

Mailing Address
Enter the specific mailing address for this site. If this is a street address, please follow the US Postal Service standards as described under "A. Construction Site Operator Information" on page 1 of these instructions. If the project / site's mailing address is the same as what is provided in Section A, you may enter "Same as Section A".

City, State, *and* ZIP Code
Enter the name of the city, the two-letter USPS abbreviation for the state (for example, TX), and the ZIP Code. (Enter the full ZIP+4 if you know it.)

Physical Address
Enter the physical address of the site itself. TCEQ staff should be able to use this address to find the site. Please follow the US Postal Service standards as described under "A. Construction Site Operator Information" on page 1 of these instructions. If the project / site does not have a physical address, enter "No Address".

City, County, *and* ZIP Code
Enter the name of the city, the county, and the ZIP Code. (Enter the full ZIP+4 if you know it.) This information must be provided even if you have entered "No Address" in the previous field.

Location Access Description
Enter a physical description of the location of the site based on highway intersections and/or permanent landmarks.

Latitude *and* Longitude
Enter the latitude and longitude of the site in ***either*** degrees, minutes, and seconds or decimal form.

For help obtaining the latitude and longitude, go to:
http://www.tnrcc.state.tx.us/gis/drgview.html

Standard Industrial Classification (SIC) Code and Activity Description

Provide the SIC code that best describes the construction activity being conducted at the site.

For help with SIC codes, go to:
http://www.osha.gov/oshstats/siceser.html

In addition to the SIC code, you must also provide a description of the construction activity being conducted at the site. This may include such descriptions as: "Apartment Building Construction" or "Shopping Center Construction."

Storm Water Pollution Prevention Plan
This plan identifies the areas and activities that could produce contaminated runoff at your site and then tells how you will ensure that this contamination is mitigated. For example, in describing your mitigation measures, your site's plan might identify the devices that collect and filter storm water, tell how those devices are to be maintained, and tell how frequently that maintenance is to be carried out. ***You must develop this plan before you complete this NOI.*** This plan must be available for a TCEQ investigator to review on request. Specific requirements for the development of the plan can be found in the *Texas Pollutant Discharge Elimination System Construction General Permit (TXR150000)*.

Estimated Area of Land Disturbed
Provide the approximate number of acres that the construction site will disturb. It is appropriate to enter a value less than 5, only if the project is part of a larger common plan that disturbs five or more acres. If the acreage is less than 1, enter 1. "Disturb" means any clearing, grading, excavating, or other similar activities.

Is the site located on Indian Country Lands?
Check "Yes" only if the site is on a reservation or other areas designated by the federal government as Indian Country Lands. If not, check "No."

Destination of Storm Water Discharge
The storm water from your site eventually reaches a receiving water body such as a local stream or lake, possibly via a drainage ditch. The discharge may initially be into a municipal separate storm sewer system (MS4). Check the appropriate boxes for whether storm water is discharged into an MS4. If you checked "Yes" to "An MS4?", then enter the name of the entity that operates the storm sewer—often a city, town, or utility district, but possibly another form of government.

You must also provide the name of the water body that receives the discharge from the construction site (a local stream or lake). Storm water may be discharged directly to a receiving stream or via a storm sewer system. If known, please include the segment number if the discharge is to a classified water body.

For a map that includes segment numbers, go to:
http://www.tnrcc.state.tx.us/water/quality/data/index.html

D. Contact

Give all the relevant information for the person whom TCEQ can contact if there are questions about any of the information on this form—perhaps the same person who completed the form.

E. Payment Information

Provide the number and account holder name from the check or money order used to pay the $100 application fee.

F. Certification

The operator must sign and date this statement to validate this NOI. Be sure to enter the full legal name of the person signing the form and the relevant title—for example, "Operator," "Vice-President," or "Partner." Use the "Prefix" blank for such titles as Dr., Mr., or Ms., as desired. Use the "Suffix" blank for such designations as Ph.D., Jr., Sr., III, or J.D., if applicable.

For a corporation, the application shall be signed by a responsible corporate officer. A responsible corporate officer means a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation; or the manager of one or more manufacturing, production, or operating facilities employing more than 250 persons or having gross annual sales or expenditures exceeding $25 million (in second-quarter 1980 dollars), if authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures. Corporate procedures governing authority to sign permit applications may provide for assignment or delegation to applicable corporate positions rather than to specific individuals.

For a partnership or sole proprietorship, the application shall be signed by a general partner or the proprietor, respectively.

For a municipality, state, federal, or other public agency, the application shall be signed by either a principal executive officer or a ranking elected official. For purposes of this application, a principal executive officer of a federal agency includes the chief executive officer of the agency, or a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g. regional administrator of the United States Environmental Protection Agency).

Questions?

If you have questions about any of the information on this form, contact our Storm Water Program at 512/239-4671 or look for "Storm Water" on our Web site.

www.tceq.state.tx.us

ATTACHMENT 2

CONSTRUCTION SITE NOTICE

FOR THE
Texas Commission on Environmental Quality (TCEQ)
Storm Water Program

TPDES GENERAL PERMIT TXR150000

The following information is posted in compliance with **Part II.D.2.** of the TCEQ General Permit Number TXR150000 for discharges of storm water runoff from construction sites. Additional information regarding the TCEQ storm water permit program may be found on the internet at:
www.tnrcc.state.tx.us/permitting/waterperm/wwperm/tpdestorm

Contact Name and Phone Number:	
Project Description: (Physical address or description of the site's location, estimated start date and projected end date, or date that disturbed soils will be stabilized)	
Location of Storm Water Pollution Prevention Plan :	

For Construction Sites Authorized Under Part II.D.2. (Obtaining Authorization to Discharge) the following certification must be completed:

I _____ (Typed or Printed Name Person Completing This Certification) certify under penalty of law that I have read and understand the eligibility requirements for claiming an authorization under Part II.D.2. of TPDES General Permit TXR150000 and agree to comply with the terms of this permit. A storm water pollution prevention plan has been developed and implemented according to permit requirements. A copy of this signed notice is supplied to the operator of the MS4 if discharges enter an MS4 system. I am aware there are significant penalties for providing false information or for conducting unauthorized discharges, including the possibility of fine and imprisonment for knowing violations.

_____ _____
Signature and Title Date

PAGE LEFT INTENTIONALLY BLANK

ATTACHMENT 3

TPDES OPERATOR'S INFORMATION

Owner's Name and Address: City of Houston

Mr. _____
(City Official)

_____
(Department)
P. O. Box 1562
Houston, Texas 77251-1562
(713) 247-1000

Contractors' Names and Addresses:

General Contractor: _____

Telephone: _____

Site Superintendent: _____

Telephone: _____

Erosion Control and
Maintenance Inspection: _____

Telephone: _____

Subcontractors' Names and Addresses:

_____ _____

Phone: _____ Phone: _____

Note: Insert name, address, and telephone number of person or firms

PAGE LEFT INTENTIONALLY BLANK

ATTACHMENT 4

CONTRACTOR'S / SUBCONTRACTOR'S

CERTIFICATION FOR TPDES PERMITTING

I certify under penalty of law that I understand the terms and conditions of TPDES General Permit No. TXR150000 and the Storm Water Pollution Prevention Plan for the construction site identified as part of this certification.

Signature: _____

Name: (printed or typed) _____

Title: _____

Company: _____

Address: _____

Date: _____

Signature: _____

Name: (printed or typed) _____

Title: _____

Company: _____

Address: _____

Date: _____

Signature: _____

Name: (printed or typed) _____

Title: _____

Company: _____

Address: _____

Date: _____

PAGE LEFT INTENTIONALLY BLANK

ATTACHMENT 5

EPA NPDES Construction Inspection Form

The following inspection is being performed in compliance with Part IV.D.4. of the NPDES Region 6 Storm Water Construction General Permit [63 Fed. Reg. 36502] and being retained in accordance with Part V of the Permit. Qualified personnel (provided by the permittee or cooperatively by multiple permittees) shall inspect disturbed areas of the construction site that have not been finally stabilized, areas used for storage of materials that are exposed to precipitation, placement and effectiveness of structural control measures, and locations where vehicles enter or exit the site. Inspections shall be performed at least once every 14 days and within 24 hours of the end of a storm event of 0.5 inches or greater. Where sites have been temporarily stabilized, runoff is unlikely due to winter conditions, or during seasonal arid periods in arid areas (0-10 inches of rainfall annually) and semi-arid areas (10-20 inches annually) such inspections shall be conducted at least once every month. This form is primarily intended for use with construction projects in Texas and New Mexico. Permittees on Indian Country lands in Oklahoma, Louisiana and Arkansas and some oil and gas facilities in Oklahoma may use this form if they are eligible for this permit. Other facilities need to check with their NPDES authority before using this form.

If you do not know your NPDES Permit Number, contact the NOI Processing Center at (301)495-4145. This form was prepared as an example and it is not a required form for use with the permit. Alternative forms may be used if they contain all of the required information as set forth in the permit. This form and additional information regarding the NPDES Region 6 storm water program may be found on the Internet at http://www.epa.gov/region6/6wq/. Any person with a complaint about the operation of this facility in regards to this permit should contact EPA Region 6 at (214)665-7112.

Permit Number(s) covered by this inspection (e.g. owners, developers, general contractor, builders)		
Signature and Certification in accordance with Part VI.G of the permit:	I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. Signature_____ Date_____	
Date of Inspection		
Inspector Name		
Is there a copy of the permit language with the SWPPP?	❒ YES	❒ NO
Is the inspector qualified and are the qualifications documented in the SWPPP?	❒ YES	❒ NO
Is an NPDES storm water construction sign posted at the entrance for all permittees?	❒ YES	❒ NO

You may want to use EPA Region 6 construction checklist to assure components of the SWPPP are complete. This form, the construction sign, and the checklist are available on the Region 6 NPDES Storm Water Forms and Documents web page which may be found on the internet at http://www.epa.gov/earth1r6/6en/w-formsw.htm. In addition to the checklist, you should provide a narrative (see next page) on the existing Best Management Practices and Structural Controls found during each inspection. Any problems identified in an inspection should be corrected within 7 days. The inspection should cover all components of the SWPPP and all potential pollutants. While eroded soil is the primary pollutant of concern, do not forget to inspect for other pollutant sources such as fuel tanks, paints, solvents, stabilization materials, concrete hardner, batch plants, and construction debris. The inspector will need to update the SWPPP to reflect findings of the inspection. The site map should be updated after an inspection to show controls that have been added or removed, to ensure the site map is kept current in accordance with Part IV.C. of the permit.

Revision 4, March 1, 2000

ATTACHMENT 5

Narrative Findings of the inspection:

Observations should include any findings of Best Management Practices or controls that are not in accordance with the SWPPP. If a control is not in place or failed, observe the reason why. A control removed temporarily for work is not necessarily a violation if properly recorded in the SWPPP. If it has been removed, record why it was removed and, if applicable, when it will be reinstalled. If the control has failed, observe the conditions so a conclusion may be made as to wether the control failed for improper maintenance or improper design. The qualified inspector will know when a failed control is inadequate and should be replaced by an improved control mechanism. Qualified inspectors are to have authority to make changes to the SWPPP to assure compliance. Controls that have not been installed should be given a reason why they are not installed and/or a scheduled date for installation if they are designed for a later phase of construction. After the inspection, the SWPPP and its site map should be updated to reflect current conditions of controls and Best Management Practices at the time of the inspection This includes removing uninstalled controls from the site map or otherwise denoting on the site map if they are no longer installed if the controls have been removed because they are no longer necessary (e.g. stabilization has been achieved in that area).

ATTACHMENT 6

City of Houston

Storm Water Pollution Prevention Plan
Construction Site Inspection Report

TPDES/EPA Permit Number _____

COH Storm Water Quality Permit Number _____

DATE _____

No exceptions noted.

The following must be corrected prior to continuing work:

Public Notice improperly posted

Initial Construction Site Inspection Report information requires updating

Copy of NOI not on site

Storm water pollution prevention plan not on site

Erosion and sediment controls improperly installed

Erosion and sediment control devices improperly maintained

Fueling or washout areas not properly protected

Portocan or other sanitary facilities not properly protected

Self-inspection and maintenance records incomplete

Sediment from site outside area of construction

Other (see description below)

_____

_____

Please contact the Storm Water Quality Engineer at
611 Walker, RA-257, Houston TX 77002
713-837-7383 fax 713-837-0570

Once the above items have been corrected, call to arrange for reinspection. No further inspections for any construction related activity shall be made until the above items have been corrected.

_____	_____
Inspector's Signature	Contractor's Signature
_____	_____
Inspector's Name	Contractor's Name

not present

Distribution Stormwater Quality Engineer, Code Enforcement, Inspector, Operator (Operator is Contractor)

Form _____ (10-01-01)

PAGE LEFT INTENTIONALLY BLANK

ATTACHMENT 7

Notice of Termination (NOT) for Storm Water Discharges Associated with Construction Activity under the TPDES Construction General Permit (TXR150000)

TCEQ Office Use Only
TPDES Permit Number: TXR15_____ - NO
GIN Number: _____

For help completing this application, read the TXR150000 NOI Instructions (TCEQ-20023-Instructions).

A. TPDES Permit Number: TXR15_____

B. Construction Site Operator Customer Reference Number: CN_____
Name:_____
Mailing Address:_____
City:_____ State:_____ Zip Code:_____
Country Mailing Information (*if outside USA*) Territory:_____ Country Code:_____ Postal Code:_____
Phone Number:_____ Extension:_____ Fax Number:_____
E-mail Address:_____

C. Project / Site Information Regulated Entity Reference Number: RN_____
Name:_____
Physical Address:_____
Location Access Description:_____
City:_____ County:_____ Zip Code:_____

D. Contact - If the TCEQ needs additional information regarding this termination, who should be contacted?
Name:_____ Title:_____
Phone Number:_____ Extension:_____ Fax Number:_____
E-mail Address:_____

E. Certification

I certify under penalty of law that authorization under the TPDES Construction General Permit (TXR150000) is no longer necessary based on the provisions of the general permit. I understand that by submitting this Notice of Termination, I am no longer authorized to discharge storm water associated with construction activity under the general permit TXR150000, and that discharging pollutants in storm water associated with construction activity to waters of the U.S. is unlawful under the Clean Water Act where the discharge is not authorized by a TPDES permit. I also understand that the submittal of this Notice of Termination does not release an operator from liability for any violations of this permit or the Clean Water Act.

Construction Site Operator Representative:

Prefix:_____ First:_____ Middle:_____
Last:_____ Suffix:_____
Title:_____

Signature:_____ Date:_____

If you have questions on how to fill out this form or about the storm water program, please contact us at (512) 239-4671. Individuals are entitled to request and review their personal information that the agency gathers on its forms. They may also have any errors in their information corrected. To review such information, contact us at (512) 239-3282.

The completed NOT must be mailed to the following address:

Texas Commission on Environmental Quality
Storm Water & General Permits Team; MC - 228
P.O. Box 13087
Austin, Texas 78711-3087

TCEQ - 20023 (02/03) Page 1 of 1

PAGE LEFT INTENTIONALLY BLANK

ATTACHMENT 7

Completing the Notice of Termination for Storm Water Discharges Associated with Construction Activity under the TPDES Construction General Permit (TXR150000)

Who May File a Notice of Termination (NOT) Form
Permittees disturbing 5 acres or more (or part of a larger common plan of development or sale disturbing 5 acres or more) who are presently covered under the Texas Pollutant Discharge Elimination System (TPDES) Construction General Permit must submit a Notice of Termination (NOT) when final stabilization has been achieved on all portions of the site that is the responsibility of the permittee; or another permitted operator has assumed control over all areas of the site that have not been finally stabilized and all silt fences and other temporary erosion controls have either been removed, scheduled for removal as defined in the SWP3, or transferred to a new operator if the new operator has sought permit coverage. Erosion controls that are designed to remain in place for an indefinite period, such as mulches and fiber mats, are not required to be removed or scheduled for removal.

Final Stabilization occurs when either of the following conditions are met:

(a) All soil disturbing activities at the site have been completed and a uniform (e.g. evenly distributed, without large bare areas) perennial vegetative cover with a density of 70% of the native background vegetative cover for the area has been established on all unpaved areas and areas not covered by permanent structures, or equivalent permanent stabilization measures (such as the use of riprap, gabions, or goetextiles) have been employed.

(b) For individual lots in a residential construction site by either:

(1) the homebuilder completing final stabilization as specified in condition (a) above; or

(2) the homebuilder establishing temporary stabilization for an individual lot prior to the time of transfer of the ownership of the home to the buyer and after informing the homeowner of the need for, and benefits of, final stabilization.

(c) For construction activities on land used for agricultural purposes (e.g. pipelines across crop or range land), final stabilization may be accomplished by returning the disturbed land to its preconstruction agricultural use. Areas disturbed that were not previously used for agricultural activities, such as buffer strips immediately adjacent to a surface water and areas which are not being returned to their preconstruction agricultural use must meet the final stabilization conditions of condition (a) above.

A. TPDES Permit Number
Provide the TPDES permit number assigned to the operator of the construction site.

B. Construction Site Operator Information
Customer Reference Number
This number designates the operator's status as a TCEQ "customer"—in other words, an individual or business that is involved in an activity that we regulate. We assign each customer a number that begins with "CN," followed by nine digits. ***This is not a permit number, registration number, or license number.*** In the remainder of this section, we will use "this customer" to mean the operator for Part B of the form.

- If this customer has not been assigned a Customer Reference Number, leave the space for the Customer Reference Number blank.
- If this customer has already been assigned this number, enter the operator's Customer Reference Number.
- ***Do not enter a permit number, registration number, or license number in place of the Customer Reference Number.***

Name
Enter the legal name of this customer as authorized to do business in Texas. Include any abbreviations (LLC, Inc., etc.).

Mailing Address
Enter a central and general mailing address for this customer to receive mail from the TCEQ. For example, if this customer is a large company, this address might be the corporate or regional headquarters. On the other hand, for a smaller business, this address could be the same as the site address.

If this is a street address, please follow US Postal Service standards. In brief, these standards require this information in this order:

- the "house" number—for example, the 1401 in 1401 Main St
- if there is a direction before the street name, the one- or two-letter abbreviation of that direction (N, S, E, W, NE, SE, SW, or NW)
- the street name (if a numbered street, do not spell out the number—for example, 6th St, not Sixth St)
- an appropriate abbreviation of the type of street—for example, St, Ave, Blvd, Fwy, Exwy, Hwy, Cr, Ct, Ln
- if there is a direction after the street name, the one- or two-letter abbreviation of that direction (N, S, E, W, NE, SE, SW, or NW)
- if there is a room number, suite number, or company mail code

City, State, *and* ZIP Code
Enter the name of the city, the two-letter USPS abbreviation for the state (for example, TX), and the ZIP Code. (Enter the full ZIP+4 if you know it.)

ATTACHMENT 7

Country Mailing Information
If this address is ***outside*** the United States, enter the territory name, country code, and any non-ZIP mailing codes or other non–U.S. Postal Service features here. If this address is ***inside*** the United States, leave these spaces blank.

Phone Number *and* Extension
This number should correspond to this customer's mailing address given earlier. Enter the area code and phone number here. Leave "Extension" blank if this customer's phone system lacks this feature.

Fax Number
This number should correspond to this customer's mailing address given earlier. Enter the area code and fax number here.

E-mail Address
As with the mailing address, this should be a general address that is appropriate for e-mail to this customer's central or regional headquarters, if applicable.

C. Project / Site Information

Regulated Entity Reference Number
This number designates this site's status as a TCEQ "regulated entity"—in other words, a location where an activity that we regulate occurs. We assign each regulated entity a number that begins with "RN," followed by nine digits. ***This is not a permit number, registration number, or license number.***

- If this site has not been assigned a Regulated Entity Reference Number, leave the space for the Regulated Entity Reference Number blank.
- If this site has already been assigned this number, enter the Regulated Entity Reference Number.
- ***Do not enter a permit number, registration number, or license number in place of the Regulated Entity Reference Number.***

Name
Enter the name by which you want this site to be known to the TCEQ.

Physical Address
Enter the physical address of the site itself. TCEQ staff should be able to use this address to find the site.

Location Description
Enter a physical description of the location of the site based on highway intersections and/or permanent landmarks.

City, County, *and* ZIP Code
Enter the name of the city, the county, and the ZIP Code. (Enter the full ZIP+4 if you know it.)

D. Contact

Give all the relevant information for the person whom TCEQ can contact if there are questions about any of the information on this form—perhaps the same person who completed the form.

E. Certification

The operator must sign and date this statement to validate this NOI. Be sure to enter the full legal name of the person signing the form and the relevant title—for example, "Operator," "Operator's attorney," or "Senior Site Manager." Use the "Prefix" blank for such titles as Dr., Mr., or Ms., as desired. Use the "Suffix" blank for such designations as Ph.D., Jr., Sr., III, or J.D., if applicable.

For a corporation, the application shall be signed by a responsible corporate officer. A responsible corporate officer means a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation; or the manager of one or more manufacturing, production, or operating facilities employing more than 250 persons or having gross annual sales or expenditures exceeding $25 million (in second-quarter 1980 dollars), if authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures. Corporate procedures governing authority to sign permit applications may provide for assignment or delegation to applicable corporate positions rather than to specific individuals.

For a partnership or sole proprietorship, the application shall be signed by a general partner or the proprietor, respectively.

For a municipality, state, federal, or other public agency, the application shall be signed by either a principal executive officer or a ranking elected official. For purposes of this application, a principal executive officer of a federal agency includes the chief executive officer of the agency, or a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g. regional administrator of the United States Environmental Protection Agency).

Questions?

If you have questions about any of the information on this form, contact our Storm Water Program at 512/239-4671 or look for "Storm Water" on our Web site:
www.tceq.state.tx.us

Section 01422

REFERENCE STANDARDS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Section includes general quality assurance as related to Reference Standards and a list of references.

1.02 QUALITY ASSURANCE

A. For Products or workmanship specified by association, trade, or Federal Standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.

B. Conform to reference standard by date of issue current on the date as stated in the General Conditions.

C. Request clarification from Project Manager before proceeding should specified reference standards conflict with Contract documents.

1.03 SCHEDULE OF REFERENCES

AASHTO	American Association of State Highway and Transportation Officials 444 North Capitol Street, N.W. Washington, DC 20001
ACI	American Concrete Institute P.O. Box 9094 Farmington Hills, MI 48333-9094
AGC	Associated General Contractors of America 333 John Carlyle Street Alexandria, VA 22314
AI	Asphalt Institute Research Park Drive P.O. Box 14052 Lexington, KY 40512

AITC	American Institute of Timber Construction 7012 S. Revere Parkway, Suite 140 Englewood, CO 80112
AISC	American Institute of Steel Construction One East Wacker Dr. Chicago, IL 60601
AISI	American Iron and Steel Institute 1101 17th Street NW, Suite 1300 Washington, DC 20036
ASME	American Society of Mechanical Engineers Three Park Avenue New York, NY 10016
ANSI	American National Standards Institute 1819 L Street NW Sixth Floor Washington, D.C. 20036
APA	American Plywood Association Box 11700 Tacoma, WA 98411
API	American Petroleum Institute 1220 L Street, N.W. Washington, DC 20005
AREA	American Railway Engineering and Maintenance-of-Way-Association 8201 Corporate Drive, Suite 1125 Landover, Maryland 20785
ASTM	American Society for Testing and Materials 100 Barr Harbor Drive West Conshohocken, PA 19428
AWPA	American Wood-Preservers' Association P.O. Box 5690 Granbury, TX 76049
AWS	American Welding Society 550 NW 42nd Avenue Miami, FL 33126

AWWA	American Water Works Association 6666 West Quincy Avenue Denver, CO 80235
COH	City of Houston P.O. Box 1562 Houston, TX 77251-1562
CLFMI	Chain Link Fence Manufacturers Institute 9891 Broken Land Parkway, Suite 300 Columbia, MD 21046
CRSI	Concrete Reinforcing Steel Institute 933 Plum Grove Road Schaumburg, IL 60173-4758
EJMA	Expansion Joint Manufacturers Association 25 North Broadway Tarrytown, NY 10591
FS	Federal Standardization Documents General Services Administration Specifications Unit (WFSIS) 7th and D Streets, S.W. Washington, DC 20406
ICEA	Insulated Cable Engineer Association P.O. Box 440 S. Yarmouth, MA 02664
IEEE	Institute of Electrical and Electronics Engineers 445 Hoes Lane P.O. Box 440 Piscataway, NJ 08855-459
ISA	International Society of Arboriculture P.O. Box 3129 Champaign, IL 61826-3129
MIL	Military Specifications General Services Administration Specifications Unit (WFSIS) 7th and D Streets, S.W. Washington, DC 20406

NACE	National Association of Corrosion Engineers 1440 South Creek Drive Houston, TX 77084-4906
NEMA	National Electrical Manufacturers' Association 1300 North 17th Street, Suite 1847 Rosslyn, VA 22209
NFPA	National Fire Protection Association 1 Batterymarch Park P.O. Box 9101 Quincy, MA 02269-9101
OSHA	Occupational Safety Health Administration U.S. Department of Labor Office of Public Affairs – Room N3647 Washington, DC 20210
PCA	Portland Cement Association 5420 Old Orchard Road Skokie, IL 60077-1083
PCI	Prestressed Concrete Institute 209 W. Jackson Blvd. Chicago, IL 60606
SDI	Steel Deck Institute P.O. Box 25 Fox River Grove, IL 60021
SSPC	Society for Protective Coatings (Steel Structures Painting Council) 40 24th Street, Sixth Floor Pittsburgh, PA 15222
TAC	Texas Administrative Code Texas Water Resources Conservation Commission P. O. Box 13087 Library MC-196 Austin, TX 78711-3087
TxDOT	Texas Department of Transportation 125 East 11th Street Austin, TX 78701-2483

UL	Underwriters' Laboratories, Inc. 333 Pfingston Road Northbrook, IL 60062
UNI-BELL	UNI-BELL Pipe Association 2655 Villa Creek Drive, Suite 155 Dallas, TX 75234

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION - Not Used

END OF SECTION

Section 01450

CONTRACTOR'S QUALITY CONTROL

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Quality assurance and control of Installation and manufacturers' field services and reports.

1.02 QUALITY ASSURANCE AND CONTROL OF INSTALLATION

A. Monitor quality control over Suppliers, manufacturers, Products, services, site conditions and workmanship, to produce work of specified quality at no additional cost to the City.

B. Comply fully with manufacturers' Installation instructions, including each step in sequence.

C. Request clarification from Project Manager before proceeding when manufacturers' instructions conflict with the Contract.

D. Comply with specified standards as minimum requirements for the Work except when more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.

E. Perform the Work by persons qualified to produce a specified level of workmanship.

1.03 REFERENCES

A. Obtain copies of standards and maintain at job site when required by individual Specification sections.

1.04 MANUFACTURERS' FIELD SERVICES AND REPORTS

A. When specified in individual Specification sections, or as required by Project Manager, provide Product suppliers' or manufacturers' technical representative to observe site conditions, conditions of surfaces and Installation, quality of workmanship, start-up of equipment, operator training, testing, adjusting and balancing of equipment as applicable and to initiate required operation. Conform to minimum time requirements for start-up operations and operator training when provided in Specification sections.

B. At Project Manager's request, submit qualifications of manufacturers' representative to Project Manager 15 days in advance of required representatives' services. Representative is subject to approval by Project Manager.

C. Manufacturer's representatives shall report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to a manufacturer's written instructions. Submit report within 14 days of observation to Project Manager for review.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01452

INSPECTION SERVICES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Inspection services and references

1.02 INSPECTION

A. City Engineer will appoint an Inspector to represent the City and perform inspections, tests, and other services specified in individual Specification sections.

B. City Engineer may also appoint, employ, and pay an independent firm to provide additional inspection or construction management services as indicated in Section 01454 - Testing Laboratory Services.

C. The independent firm will submit reports to Project Manager, indicating observations and results of tests and indicating compliance or noncompliance with Contract requirements.

D. Contractor shall assist and cooperate with the Inspector; furnish samples of materials, design mix, equipment, tools, and storage.

E. Contractor shall notify Project Manager 24 hours prior to expected time for operations requiring services.

F. Contractor shall sign and acknowledge reports for Inspector.

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION - Not Used

END OF SECTION

Section 01454

TESTING LABORATORY SERVICES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Testing laboratory services and Contractor responsibilities related to those services.

1.02 REFERENCES

A. ASTM C 1077 - Standard Practice for Laboratories Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Laboratory Evaluation.

B. ASTM D 3666 - Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Bituminous Paving Materials.

C. ASTM D 3740 - Standard Practice for Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction.

D. ASTM E 329 - Standard Specification for Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction.

E. ISO/TEC Guide 25 - General Requirements for the Competence of Calibration and Testing Laboratories.

1.03 SELECTION AND PAYMENT

A. The City will select, employ, and pay for services of an independent testing laboratory to perform inspection and testing identified in Part 3 of individual Specification sections.

B. Contractor shall employ and pay for services of an independent testing laboratory or laboratories to perform inspection and testing identified in Part 2 of individual Specification sections.

C. Employment of a testing laboratory by the City shall not relieve Contractor of its obligation to perform work in accordance with requirements of Contract documents.

D. The City will deduct a minimum two-hour charge for testing laboratory time from periodic progress payment when operations requiring testing or inspection are canceled without prior notification.

E. The City will deduct cost of retesting from periodic progress payment whenever failed work is removed, replaced and retested.

1.04 QUALIFICATION OF LABORATORY

A. Meet laboratory requirements of ASTM E 329 and applicable requirements of ASTM C 1077, ASTM D 3666, and ASTM D 3740.

B. Meet ISO/TEC Guide 17025 conditions for accreditation by the American Association for Laboratory Accreditation (A2LA) in specific fields of testing required in individual Specification sections.

C. If laboratory subcontracts are part of the testing services, such work will be placed with a laboratory complying with the requirements of this Section.

1.05 LABORATORY REPORTS

A. Testing laboratory shall provide and distribute copies of laboratory reports to the distribution list Project Manager provides at the pre-construction conference.

B. Keep one copy of each laboratory report distributed or faxed at the site field office for duration of the Work.

C. Laboratory will fax material supplier, Contractor and Project Manager reports that indicate failing test results by no later than close of business on the working day following test completion and review.

1.06 LIMITS ON TESTING LABORATORY AUTHORITY

A. Laboratory may not release, revoke, alter, or enlarge requirements of the Contract.

B. Laboratory may not approve or accept any portion of the Work.

C. Laboratory may not assume Contractor duties.

D. Laboratory has no authority to stop the Work.

1.07 CONTRACTOR RESPONSIBILITIES

A. Provide safe access to the Work and to manufacturer's facilities for Project Manager and for testing laboratory personnel.

B. Provide testing laboratory with a copy of the Construction Schedule and a copy of each update to Construction Schedule.

C. Notify Project Manager and testing laboratory during normal working hours of the day previous to expected time for operations requiring inspection and testing services. When Contractor fails to make timely prior notification, do not proceed with the operations requiring inspection and testing services.

D. Notify Design Consultant 24 hours in advance when Specification requires presence of Design Consultant for sampling or testing.

E. Request and monitor testing as required to provide timely results and to avoid delays to the Work. Provide samples to laboratory in sufficient time to allow required test to be performed in accordance with specified test methods before intended use of the Product.

F. Cooperate with laboratory personnel in collecting samples on site. Provide incidental labor and facilities for safe access to the Work to be tested, to obtain and handle samples at site or at source of Products to be tested, and to facilitate tests and inspections including storage and curing of test samples.

G. Make arrangements with laboratory through Project Manager. Payment for additional testing will be made in accordance with Document 00700 - General Conditions:

1. Re-testing required for failed tests.

2. Re-testing for nonconforming work.

3. Additional sampling and tests requested beyond specified requirements.

4. Insufficient notification of cancellation of tests for work scheduled but not performed.

PART 2 P R O D U C T S - Not Used

PART 3 EXECUTION

3.01 CONDUCTING TESTING

A Conform to laboratory sampling and testing methods specified in individual Specification sections to the latest issues of ASTM standards, TxDOT methods, or other recognized test standards as approved by Project Manager.

B Requirements of this Section shall also apply to those tests for approval of materials, for mix designs, and for quality control of materials as performed by employed testing laboratories.

END OF SECTION

Section 01502

MOBILIZATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Mobilization of construction equipment and facilities onto the site.

1.02 MEASUREMENT AND PAYMENT

A. Unit Price Contracts. If Contract is Unit Price Contract, measurement for mobilization is on a lump sum basis.

B. Stipulated Price (Lump Sum) Contract. If Contract is Stipulated Price Contract, payment for Work in this Section is included in total Stipulated Price.

C. Mobilization payments will be included in monthly payment estimates upon written application by Contractor subject to the following provisions:

1. Authorization for payment of 50 percent of that portion of Contract Price designated for mobilization will be made upon receipt and approval by Project Manager of the following items, as applicable:

a. Safety Program (Document 00700, Paragraph 10.1.1).

b. Site Utilization Plan (Section 01145).

c. Schedule of Values (Section 01292), if any.

d. Initial Construction Photographs (Section 01321), if needed.

e. Preliminary Construction Schedule and Billing Forecast (Section 01325).

f. Construction Schedule (Section 01325 or Section 01326, as applicable).

g. Submittal Schedule (Section 01330).

h. Site specific Storm Water Pollution Prevention Plan (SWPPP) and Notice of Intent (NOI) along with storm water application fee (Section 01410), if required.

i. Contractor's Quality Control Plan (Section 01450), if required.

j. Establishment of a Field Office for Project Manager meeting requirements of Section 01520 - Temporary Field Office.

k. Traffic Control Plan (Section 01555), if required.

l. Plan for Control of Ground and Surface Water (Section 01578), if required.

m. Project Signs Submittal (Section 01580).

n. Trench Safety Program (Section 02260), if required.

o. Dewatering plan, when required.

2. Authorization for payment of the balance of that portion of Contract Price designated for mobilization will be made upon completion of the Work amounting to five percent of Original Contract Price. The amount of Contract Price designated for mobilization may not be applied in computing whether or not five percent of the Original Contract Price has been obtained.

3. Mobilization payments will be subject to retainage amounts stipulated in Document 00700 – General Conditions.

PART 2 P R O D U C T S -Not Used

PART 3 E X E C U T I O N -Not Used

END OF SECTION

Section 01504

TEMPORARY FACILITIES AND CONTROLS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Temporary facilities and necessary controls for the Project, including utilities, telephone, sanitary facilities, storage sheds and building, safety requirements, first aid equipment, fire protection, security measures, protection of the Work and property, access roads and parking, environmental controls, pest and rodent control and disposal of trash, debris and excavated material.

B. Facilities and controls specified in this section are considered minimum for the Project. Provide additional facilities and controls for proper execution of the Work and to meet Contractor's responsibilities for protection of persons and property.

1.02 MEASUREMENT AND PAYMENT

A. UNIT PRICES

1. No separate payment will be made for any temporary facilities and controls required under this section. Include cost of such work in contract price listed for mobilization.

1.03 CONTRACTOR'S RESPONSIBILITY

A. Comply with applicable requirements specified in other sections of Specifications.

1. Maintain and operate temporary facilities and systems to assure continuous service.

2. Modify and extend systems as the Work progress requires.

3. Completely remove temporary materials and equipment when no longer required.

4. Restore existing facilities used for temporary services to specified or original condition.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 TEMPORARY UTILITIES

A. Obtaining Temporary Service:

1. Make arrangements with utility service companies for temporary services.

2. Abide by rules and regulations of the utility service companies or authorities having jurisdiction.

3. Be responsible for utility service costs until Date of Substantial Completion. Included are fuel, power, light, heat, and other utility services necessary for execution, completion, testing, and initial operation of work.

B. Water:

1. Provide water required for and in connection with work to be performed and for specified tests of piping, equipment, devices, or for other use as required for proper completion of the Work.

2. Water to be drawn from public fire hydrants. Obtain transit meter from City of Houston, Department of Public Works and Engineering, Taps and Meters Section. Pay required deposit based on rates established by latest ordinance.

3. Provide and maintain an adequate supply of potable water for domestic consumption by Contractor personnel, Project Manager and representatives of the City.

C. Electricity and lighting:

1. Provide electric power service required for the Work including required testing, lighting, operation of equipment, and other Contractor use.

2. Electric power service includes temporary power or generators required to maintain plant operations during scheduled shutdowns.

3. Minimum lighting level shall be 10 foot-candles for open areas; 20-foot-candles for stairs and shops. Provide a minimum of one 300-watt lamp for each 200 square feet of work area.

D. Temporary Heat and Ventilation:

1. Provide temporary heat necessary for protection or completion of the Work.

2. Provide temporary heat and ventilation to assure safe working conditions; maintain enclosed areas at a minimum of 50 degrees F.

E. Telephone:

1. Provide emergency telephone service at Project site for use by Contractor personnel and others performing work or furnishing services at the site.

2. Provide Houston-Metro lines, allowing unlimited calls, without charge in Greater Houston Metropolitan area with "call waiting" and "call forwarding" options. Provide one telephone answering machine with beeperless remote message retrieval capability.

F. Sanitary Facilities:

1. Provide and maintain sanitary facilities for persons on the site; comply with regulations of State and local departments of health.

2. Enforce use of sanitary facilities by construction personnel at site. Enclose sanitary facilities. Pit-type toilets are not permitted. No discharge will be allowed from these facilities. Collect and store sewage and waste so as not to cause nuisance or health problems. Haul sewage and waste off-site and properly dispose in accordance with applicable regulations.

3. Locate toilets near the Work site and secluded from view insofar as possible. Keep toilets clean and supplied throughout the course of the Work.

3.02 STORAGE SHEDS AND BUILDINGS

A. Provide adequately ventilated, watertight storage facilities with floor above ground level for Products susceptible to weather damage.

B. Storage of Products not susceptible to weather damage may be on blocks off the ground.

C. Store Products in a neat and orderly manner. Place Products to permit easy access for identification, inspection and inventory.

D. Fill and grade site for temporary structures to provide drainage away from temporary and existing buildings.

3.03 SAFETY REQUIREMENTS

A. Submit a safety program at the pre-construction meeting and follow the program in accordance with Document 00700 – General Conditions. Include documented response to trench safety requirements of Section 02260 - Trench Safety System.

B. Conduct operations in strict accordance with applicable Federal, State and local safety codes and statutes and with good construction practice. Establish and maintain procedures for safety of all work, personnel and equipment involved in the Work.

C. Observe and comply with Texas Occupational Safety Act (Art. 5182a, V.C.S.) and with all safety and health standards promulgated by Secretary of Labor under Section 107 of Contract Work Hours and Standards Act, published in 29 CFR Part 1926 and adopted by Secretary of Labor as occupational safety and health standards under Williams-Steiger Occupational Safety and Health Act of 1970, and to other legislation enacted for safety and health of Contractor employees. Safety and health standards apply to Subcontractors and Suppliers as well as to the Contractor.

D. Observance of and compliance with safety regulations is Contractor's responsibility without reliance or superintendence of or direction by Project Manager. Immediately advise Project Manager of investigation or inspection by Federal Safety and Health inspectors of Contractor's or Subcontractor's work or place of work on site under the Contract, and after investigation or inspection, advise Project Manager of results. Submit one copy of accident reports to Project Manager within 10 days of occurrence.

E. Protect areas occupied by workmen using the best available devices for detection of lethal and combustible gases. Test devices frequently to assure functional capability. Constantly observe infiltration of liquids into the Work area for visual or odor evidence of contamination, and immediately take appropriate steps to seal off entry of contaminated liquids to the Work area.

F. Implement safety measures, including but not limited to safety personnel, first-aid equipment, ventilating equipment and other safety equipment specified or detailed on Drawings.

G. Maintain required coordination with City Police and Fire Departments during entire period covered by the Contract.

H. Include Project safety analysis in safety plan. Itemize major tasks and potential safety hazards. Plan to eliminate hazards or protect workers and public from each hazard.

3.04 FIRST AID EQUIPMENT

A. Provide a first aid kit throughout the construction period. List telephone numbers for physicians, hospitals, and ambulance services in each first aid kit.

B. Have at least one person thoroughly trained in first aid and CPR procedures present on the site when work is in progress. Contractor to conform to protocols and requirements for training and protection against "blood borne pathogens".

3.05 FIRE PROTECTION

A. Conform to specified fire protection and prevention requirements established by Federal, State, or local governmental agencies and as provided in Safety Program.

3.06 SECURITY MEASURES

A. Protect the Work, materials, equipment, and property from loss, theft, damage, or vandalism. Protect City property used in performance of the Contract.

B. If existing fencing or barriers are breached or removed for purposes of construction, provide and maintain temporary security fencing equal to existing.

3.07 PROTECTION OF UTILITIES AND PIPELINES

A. Prevent damage to existing public utilities during construction. Approximate locations of known utilities are shown on Drawings, but all lines may not be shown. Excavate with caution and repair lines damaged by construction operations.

B. Use the Utility Coordinating Committee One Call System, telephone number, (713) 223-4567, which must be called 48 hours in advance. The toll free telephone number is 1-800-669-8344, Texas One Call System.

C. Before excavating, locate underground utilities by appropriate means including the use of metal detection equipment, and probes, or by excavation or surveys. Repair damage caused by investigative work and by failure to locate or to preserve underground utilities.

D. Give utility owners a minimum five days notice before commencing excavation to allow time to locate utilities and make adjustments or

relocations when they conflict with the Work. Include cost for temporary relocation of water, wastewater, and storm drainage lines, necessary to accommodate construction, in unit prices for utility construction unless otherwise noted. Bypassing of sanitary waste to storm drainage facilities is not allowed.

E. Prior to excavation near pipelines, request a representative of the pipeline company to meet with Contractor and Project Manager at the site to discuss procedures to be used. Request pipeline company's representative to locate the pipelines in at least three locations: at each side and at centerline of proposed excavation of proposed utility. Also request representative and Project Manager to be present to observe Contractor operations when excavation is conducted within 15 feet of pipeline.

F. Utility service lines are not shown on the construction document drawings. Contractor should anticipate that such service lines exit and should exercise extreme caution during construction. The utility service lines should be repaired and restored immediately as per the specification, if damaged due to any construction activities. No separate payment will be made for this repair and restoration work. Include payment in unit price for work in appropriate sections.

G. Prior to abandonment of utility, make appropriate arrangements with City and owner of utility to terminate service, remove meters, tranformers, and poles as may be required by site conditions.

3.08 PROTECTION OF THE WORK AND PROPERTY

A. Preventive Actions

1. Take necessary precautions and actions to prevent damage, injury, or loss to the Work or public and private property, including:

a. Storage of apparatus, supplies, and Products in an orderly, safe manner to limit interference with progress of the Work or work of other contractors, utility service companies, or the City's operations.

b. Suitable storage for Products subject to damage by exposure to weather, theft, breakage, etc.

c. Limitation of loading pressures imposed upon portions of the Work.

d. Frequent clean up of refuse, scrap materials, and debris from construction operations, necessary to maintain the site in a safe and orderly condition.

e. Provision of barricades and guard rails to protect pedestrian and traffic around openings, scaffolding, temporary stairs and ramps, excavations, elevated walkways, and other hazardous areas.

2. Protect public and private property adjacent to the site. Obtain written consent before entering or occupying privately-owned land except on easements provided for construction. Restore property damaged by construction operations to condition equal to or better than that existing before the damage.

B. Barricades and Warning Systems

1. Where work is performed on or adjacent to roadways, rights-of-ways, or public land, provide barricades, fences, lights, warning signs, danger signals, and other precautionary measures necessary for protection of persons or property and for protection of the Work.

a. Erect sufficient barricades to keep vehicles and pedestrians from entering the Work. Paint barricades to be visible at night. From sunset to sunrise, provide at least one light at each barricade.

b. Maintain barricades, signs, lights, and provide watchmen until Project Manager approves removal. Whenever work creates encroachment onto public roadways, station flagmen to manage traffic flow in accordance with approved traffic control plan.

c. Conform to requirements of section 01555 – Traffic Control and regulation.

C. PROTECTION OF EXISTING STRUCTURES

1. Underground Facilities

a. Known Underground Facilities are shown on the Drawings but all Facilities may not be shown. Explore sufficiently ahead of trenching and excavation work to locate Underground Facilities in order to prevent damage to them and to prevent interruption of utility services. Restore damage to Underground Facilities to original condition at no additional cost to the City.

b. If necessary to avoid unanticipated Underground Facilities, Project Manager may make changes in location of the Work.

c. If permanent relocation of an Underground Facility is required

and not provided for in the Contract documents, City Engineer will direct Contractor in writing to perform the Work under Modification provisions in Document 00700 - General Conditions.

2. Surface Structures include buildings, tanks, walls, bridges, roads, dams, channels, open drainage, piping, poles, wires, posts, signs, markers, curbs, walks, guard cables, fencing, and other facilities that are visible above the ground level.

3. Protection of Underground Facilities and Surface Structures:

   a. Support in place and protect Underground Facilities and Surface Structures located within or adjacent to the limits of the Work from damage. Install supports as required by the owner of the structure. Satisfy Project Manager that the owner of the facility or structure has approved methods and procedures before installing structure supports.

   b. Avoid moving or changing public utility or private corporation property without prior written consent of a responsible official of the facility or structure. Allow representatives of utilities to enter the construction site for maintenance and repair purposes or to make necessary changes.

   c. Notify utility and pipeline owners and operators of the nature of construction operations and dates when operations will be performed. When construction operations are required in immediate vicinity of existing structures, pipelines, or utilities, give a minimum of five working days advance notice. Probe and flag location of Underground Facilities prior to commencement of excavation. Keep flags in place until construction operations uncover the facility.

   d. Assume risk for damages and expenses to Underground Facilities and Surface Structures within or adjacent to the Work.

D. Employ a structural engineer to ensure protection measures are adequate for the safety and integrity of structures and facilities.

E. PROTECTION OF INSTALLED PRODUCTS:

1. Provide protection of Installed Products to prevent damage from subsequent operations. Remove protection facilities when no longer needed, prior to completion of the Work.

2. Control traffic to prevent damage to Products and surfaces.

3. Provide coverings to protect Products from damage. Cover projections, wall corners, jambs, sills, and exposed sides of openings in areas used for traffic and passage of materials in subsequent work.

3.09 ROADS AND PARKING

A. Prevent interference with traffic and operations of the City on existing roads.

B. Designate temporary parking areas to accommodate construction and City personnel. When site space is not adequate, provide additional off-site parking. Locate as approved by Project Manager.

C. Minimize use by construction traffic on existing streets and driveways.

D. Do not allow heavy vehicles or construction equipment in existing parking areas.

3.10 ENVIRONMENTAL CONTROLS

A. Use methods, equipment, and temporary construction necessary for control of environmental conditions at the site and adjacent areas.

B. Comply with statutes, regulations, and ordinances relating to prevention of environmental pollution and preservation of natural resources including National Environmental Policy Act of 1969, PL 91-190, Executive Order 11514.

C. Minimize impact to the surrounding environment. Do not use construction procedures that cause unnecessary excavation and filling of terrain, indiscriminate destruction of vegetation, air or stream pollution, or harassment or destruction of wildlife.

D. Limit disturbed areas to boundaries established by the Contract. Do not pollute on-site streams, sewers, wells, or other water sources.

E. Do not burn rubbish, debris or waste materials.

3.11 POLLUTION CONTROL

A. Provide methods, means, and facilities necessary to prevent contamination of soil, water or the atmosphere by discharge of Pollutants from construction operations.

B. Provide equipment and personnel to perform emergency measures to contain spillage, and to remove contaminated soils or liquids. Excavate and dispose of contaminated earth off-site in accordance with laws and regulations, and

replace with suitable compacted fill and topsoil.

C. Provide systems necessary for control of Pollutants.

1. Prevent toxic concentrations of chemicals.

2. Prevent harmful dispersal of Pollutants into the environment.

D. Use equipment that conforms to current Federal, State, and local laws and regulations.

3.12 PEST AND RODENT CONTROL

A. Provide rodent and pest control as necessary to prevent infestation of construction or storage areas.

B. Employ methods and use materials that will not adversely affect conditions at site or on adjoining properties.

3.13 NOISE CONTROL

A. Provide vehicles, equipment, and use construction activities that minimize noise to the greatest degree practicable. Conform to noise levels of Chapter 30 –Noise and Sound Level Regulation, City Code of Ordinances, and latest OSHA standards. Do not permit noise levels to interfere with the Work or create a nuisance to surrounding areas.

B. Conduct construction operations during daylight hours except as approved by Project Manager.

C. Select construction equipment that operates with minimum noise and vibration. When directed by Project Manager, correct objectionable noise or vibration produced by operation of equipment at no additional cost to the City. Sound Power Level (PWL) of equipment shall not exceed 85 dbA (re: 10^{-12} watts) measured five feet from the equipment, or at a lower level if prescribed by City Ordinances. Equipment noise requirements are contained in equipment specifications.

3.14 DUST CONTROL

A. Use water or other methods approved by Project Manager to control amount of dust generated by vehicle and equipment operations.

3.15 WATER RUNOFF AND EROSION CONTROL

A. Comply with requirements of section 01410 – TPDES Requirements.

B. Conduct fill, grading and ditching operations and provide adequate methods necessary to control surface water, runoff, subsurface water, and water from excavations and structures in order to prevent damage to the Work, the site, or adjoining properties.

1. Plan and execute construction and earthwork by methods that control surface drainage from cuts and fills, and from borrow and waste disposal areas.

2. Minimize area of bare soil exposed at one time.

3. Provide temporary control measures, such as berms, dikes, and drains.

4. Provide, operate, and maintain equipment and facilities of adequate size to control surface water.

5. Construct fill and waste areas by selective placement of materials to eliminate erosion of surface silts or clays that may erode.

6. Direct water away from excavations, pits, tunnels, and other construction areas to prevent erosion, sedimentation or damage.

7. Maintain existing drainage patterns adjacent to the site by constructing temporary earth berms, sedimentation basins, retaining areas, and temporary ground cover.

8. Dispose of drainage water in a manner to prevent flooding, erosion, or other damage to the site or adjoining areas, in conformance with environmental requirements.

9. Inspect earthwork periodically to detect any evidence of erosion. Take corrective measures as required to control erosion.

END OF SECTION

Section 01506S

DIVERSION PUMPING

The following supplements modify Section 01506 – Diversion Pumping Standard Specification. Where a portion of the Specification is modified or deleted by this Supplementary Specification, the unaltered portions of the Specification shall remain in effect.

1.02 SYSTEM DESCRIPTION: Insert the following paragraph:

C. Payment for by-pass pumping is on a lump sum basis for duration of project as needed to complete the work from contractor's notice to proceed to City of Houston approval of substantial completion of work.

D. Payment for long term by-pass pumping is on a per monthly basis for duration as directed by City of Houston Wastewater Operations and in coordination with City of Houston Construction Project Manager.

1.03 SUBMITTALS: Delete paragraph 1.03 B and replace with the following:

B. Submit a Diversion Pumping Plan prior to installation for all lift stations. Show location, number and size of pumps; show number, location, size and type of hoses or rigid piping, and location of downstream discharge; and special features where pipes or hoses cross roadways, temporary trenches, support bridges. Submit an emergency plan detailing procedures to be followed in the event any portion of the by-pass operation fails and causes either surcharging or overflow.

END OF SUPPLEMENT

Approved by:

Ebi Nassiri

Ebi Nassiri, P.E.
Assistant Director
Wastewater Engineering Section
Engineering and Construction Division

3/20/15
Date

Section 01506

DIVERSION PUMPING

PART 1 GENERAL

1.01 DEFINITIONS

A. Diversion-pumping: Installation and operation of bulkheads, plugs, hoses, piping, and pumps required to maintain sewer flow and prevent backups and overflows.

1.02 SYSTEM DESCRIPTION

A. Provides continuous sewer service to users of sewer systems while maintenance or construction operations are in progress, by diverting flow around construction locations. Maintain sewer flow to prevent backup or overflow onto streets, yards and unpaved areas or into buildings, adjacent ditches, storm sewers, and waterways. Do not divert sewage outside of sanitary sewer system.

B When pumps are operating, have an experienced operator on site to monitor operation, adjust pumps, make minor repairs to system, and report problems.

1.03 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittals Procedures.

B. For systems that bypass sanitary sewer line segments of 42-inch diameter or larger, submit a Diversion Pumping Plan prior to installation. Show location, number and size of pumps, number, location, size and type of hoses or rigid piping, and location of downstream discharge; and special features where pipes or hoses cross roadways, temporary trenches, support bridges.

1.04 SCHEDULING

A. When the City operates or maintains diversion pumping in construction areas, coordinate construction activities with Project Manager.

B. Cease operation of diversion pumping when approved by Project Manager.

PART 2 PRODUCTS

2.01 MATERIALS

A. Design piping, joints and accessories to withstand at least twice maximum system pressure or 50 psi, whichever is greater.

B. Use self-priming type or submersible electric pumps, with a working pressure gauge on the discharge. Pumps shall meet requirements of City of Houston Noise and Sound Level Regulations.

PART 3 EXECUTION

3.01 FIELD QUALITY CONTROL

A. During diversion pumping, do not allow sewage to leak, dump, or spill into or onto areas outside of existing sanitary sewer systems.

B. In the event of an accidental spill or overflow, immediately stop discharge and take action to clean up and disinfect spill. Promptly notify Project Manager so required reporting can be made to the Texas Commission on Environmental Quality (TCEQ) and the Environmental Protection Agency (EPA).

3.02 CLEANING

A. When diversion-pumping operations are complete, drain sewage within piping into sanitary sewers prior to disassembly.

END OF SECTION

Section 01520

TEMPORARY FIELD OFFICE

PART 1 GENERAL

1.01 SECTION INCLUDES

A Temporary field office building and associated parking area.

1.02 FACILITY DESCRIPTION

A Temporary field office to be utilized by authorized representatives of the City to coordinate and monitor daily construction activities performed by Contractor.

B. Field office shall be a non-smoking facility.

PART 2 PRODUCTS

2.01 FIELD OFFICE

A General:

1. Locate office in vicinity of the Work at a location approved by Project Manager or where indicated on Drawings.

2. Furnish, Install and maintain field office for exclusive use of authorized representatives of the City. Provide sufficient room for Project meetings and Inspector's office.

3. Provide office within 10 days of Date of Commencement of the Work.

4. Construct two all-weather, hard surfaced parking spaces for exclusive use of authorized representatives of the City. Provide all-weather surfaced walk between parking spaces and field office.

B. Minimum Construction:

1 Structurally sound foundation and superstructure.

Weather tight with insulated roof, walls and 7-foot ceiling (minimum).

3. Stairs or walkway with handrail and covered entrance platform (minimum 4 feet by 4 feet) with mud scraper at door.

4. Resilient floor covering.

5. Screened windows with area equal to approximately 10 percent of floor area sufficient for light, view of the site, and ventilation. Provide each window with operable sash and burglar bars.

6. Secure exterior doors with dead-bolt cylinder locks and burglar bars.

C. Minimum Services:

1. Exterior entrance light.

2. Interior lighting of 75 foot-candles minimum at desktop height

3. Automatic heating to maintain 65 degrees F in winter.

4. Automatic cooling to maintain 75 degrees F in summer.

5. Electric power service.

6. Three telephone service lines one for voice, one for data, and one for fax, for exclusive use of authorized representatives of the City.

7. Sanitary facilities in field office with one water closet, one lavatory, and one medicine cabinet for exclusive use of authorized representatives of the City.

D. Minimum Furnishings:

1. One 5-drawer desk

2. Two swivel desk chairs with casters.

3. One plan table.

4. One drawing plan rack.

5. One 4-drawer legal file cabinet complete with fifty legal-size hanging folders and two full-sized carriers.

6. One marker board with cleaner and markers.

7. Two waste baskets.

8. One 30-inch by 36-inch tack board.

9. One all-purpose fire extinguisher.

10. Six protective helmets (hard hats) with ratchet adjustment for exclusive use of authorized representatives of the City.

11. Conference table and chairs to accommodate 10 persons.

12. All in one printer, copier, plain paper fax machine.

13. Telephone instrument separate from fax machine.

E. Provide adequate space for one set of Contract documents for ready reference.

PART 3 EXECUTION

3.01 MAINTENANCE

A Maintain all-weather surface driveway and parking areas, buildings, walkways, stairs and required furnishings and equipment for duration of the Contract.

B. Provide janitorial services for duration of the Contract consisting of twice weekly sweeping and mopping floors, trash removal, weekly restroom cleaning, and weekly dusting of furniture and equipment.

C. Provide soap, paper towels, toilet paper, cleansers and other necessary consumables.

D. Immediately repair damage, leaks or defective service.

3.02 PROJECT CLOSEOUT

A Remove temporary field office and signs and restore site as specified in Section 01770 - Closeout Procedures.

END OF SECTION

SECTION 01554

TRAFFIC CONTROL AND STREET SIGNS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Materials, hardware and installation of Traffic Signs.

1.02 SUBMITTALS

A. Contractor shall submit a list of intended suppliers and products to be used for all signs, posts, and associated hardware. City reserves the right to request actual product samples prior to approval.

1.03 MEASUREMENT AND PAYMENT

A. Signs installed or replaced will be measured by the each sign. Signs refurbished will be measured by each sign.

B. Payment for installation of traffic signs will be on the basis of each sign installed.

C. The price is full compensation for furnishing and installing new signs and hardware. Cost of associated posts, footings, and miscellaneous mounting hardware will not be paid for directly but is to be included in the unit price bid for installation of each traffic sign.

D. Non-standard signs installed or replaced will be measured by the square foot of the sign face. Non-standard signs shall not be installed without prior approval from the City.

PART 2 PRODUCTS

2.01 MATERIALS

A. The following ASTM Standards and documents, of the issue in effect on the date of Invitation for Bid, form a part of this specification to the extent herein.

1. ASTM B 209 Specification for Aluminum and Aluminum Alloy Sheet and Plate

2. ASTM D 523 Standard Method for Test for Specular Gloss

3. ASTM D 4956 Standard Specification for Retroreflective Sheeting for Traffic Control

4. ASTM E 284 Standard Definition of Terms Relating to Appearance of Materials

5. ASTM E 308 Computing the Colors of Objects by Using the CIE System

6. ASTM E 810 Standard Test Method for Coefficient of Retroreflection of Retroreflective Sheeting

7. ASTM E 1164 Standard Practice for Obtaining Spectrophotometric Data for Object-Color Evaluation

B. Substrate (Sign Blanks). This shall be aluminum alloy 5052-H38 and otherwise in conformance with ASTM B-209 and have gold chromate finish. The size, shape and thickness of the sign blanks are as indicated on the standard detail sheet in the plans or as specified by the Engineer.

1. Metal working. The aluminum shall be free of burrs and pits on both sides, including
edges and holes, and shall be made ready for applications of the sheeting.

2. Surface Preparation. The aluminum shall be thoroughly cleaned and degreased with solvent and alkaline emulsions cleaner by immersion, spray, or vapor degreasing and dried prior to application of the gold chromate sheeting coat. The aluminum shall be new and corrosion-free with holes drilled or punched, corners rounded to the radii shown in the standard detail sheet, and all edges smoothed prior to application of sheeting. The heavy or medium chromate coating shall conform in color and corrosion resistance to that imparted by the Alodine 1200F treatment.

3. Size. The dimensions of substrate applications for regulatory, warning, and guide signs shall be as specified by the Engineer and as shown on the plans.

C. Sign Face (Background, Legends, Symbols, and Colors). These shall be in accordance with the Standard Highway Sign Designs (SHSD) for Texas and with the Texas Manual of Uniform Traffic Control Devices (TMUTCD).

1. The sign face, made of electronic film and retro-reflective sheeting shall comply with the appearance, specification, and good workmanship designated by the using agency for sign faces constructed of screen processed retro-reflective sheeting of the same type.

2. All sign blanks shall be covered with appropriate retro-reflective sheeting.

   a. All ground mounted stop signs, warning signs, and other regulatory signs, shall use at a minimum High Intensity Prismatic Reflective Sheeting.

   b. All overhead signs shall use Diamond Grade Reflective Sheeting.

   c. All other signs shall use Super Engineer Grade Sheeting

3. Application Methods. The method of application of sheeting, letters, numbers, and symbols shall be precisely as prescribed in writing by the manufacturer.

   a. Legend Spacing and Layout. Spacing and layout for all traffic control signs shall conform to the SHSD.

   b. Tolerance for Horizontal Alignment. Letters, numerals, and symbols shall be horizontally aligned to a tolerance of 1/16 inch.

   c. Tolerance for Vertical Alignment. Letters, numerals, and symbols shall be vertically aligned to a tolerance of 1/16 on each letter in each line.

D. Sign Posts. Steel post shall conform to the standard specification for hot rolled carbon sheet steel, structural quality, ASTM designation A570, Grade 50. Average minimum yield strength after cold forming is 60,000 psi. The cross section of the post shall be square tube formed steel, carefully rolled to size and shall be welded directly in the corner by high frequency resistance welding or equivalent process and externally scarified to agree with corner radii. Sign posts shall be hot dipped galvanized conforming to ASTM A653, G90.

1. Installation. The square end of the post shall not be modified or pointed.

   a. Flange. When sign post installation is required over building basements, bridges and cavities, a galvanized cast iron pipe flange shall be used. The base shall be 8 inches in diameter with six 5/16 inch holes drilled equidistant around the circumference, ⅝ inch from the outer edge. The neck of the flange shall be 3inches in diameter, drilled and threaded to receive a 2 inch diameter galvanized post.

   b. Hardware. All ground mounted signs shall be attached to posts using 5/16" nut and bolt assembly, the bolt being 2 ½" in length. Stainless steel banding material, brackets and clips will be used for signs installed on light standards or mast arms.

c. Construction. Anchors shall be anchored in a minimum of one cubic foot of class "C" concrete, 28 inches deep, with a 6 inch long, ⅜ inch diameter pin inserted through the pre-drilled hole 3 inches from the bottom of the pole. Where the pole installation requires surface mounting, an 8 inch flange with a 2 inch threaded collar shall be used. The pole shall be galvanized, two inches in diameter and threaded to fit the flange. Sign placement and orientation shall be as specified in the construction plans.

E. Each finished sign shall have the following sticker affixed to the back in a location where it will be visible when the sign is installed:

The sticker shall be Zebra Technologies Z-Ultimate 3000 White or approved equal. Finished product shall be weather and fade resistant for the expected life of the sign.

F. Warranty. The Contractor shall warrant the materials and workmanship of each sign in accordance with the maximum limits of material warranties extended by manufacturers of raw materials, subject to the conditions they specify. The retro-reflective sheeting will be considered unsatisfactory if it has deteriorated due to natural causes to the extent that: (1) the sign is ineffective for its intended purpose when viewed from a moving vehicle under normal day and night driving conditions; or (2) the coefficient of retro-reflection is less than the minimum specified for that sheeting. When sign failure occurs prior to the minimum years indicated and an inspection demonstrates that the failure is caused by materials warranted to contractor to endure at least that long, the sign will be replaced or repaired free of materials charges. When failure occurs and inspection demonstrates that such failure is due to poor workmanship, the sign will be replaced or repaired at Contractor's expense, including shipping charges.

PART 3 EXECUTION

3.01.1 EQUIPMENT

A. The contractor shall provide machinery, tools, and equipment necessary for proper execution of the work.

3.01.2 CONSTRUCTION

A. Construction shall be high quality with no visible defects in the finished product. Fabrication shall be in accordance with these specifications. Street name signs shall always be supplied and installed at each project intersection whether signs previously existed at the location or not.

B. The removal of existing signs shall be coordinated with the Traffic Operations Section of the Public Works Department (713-803-3054) and arrangements made for a convenient time to deliver City signs and poles. All salvaged traffic signs shall be delivered to the Traffic Operations Center located at 2200 Patterson Street. All deliveries to the Traffic Operations Center requires a minimum notice of two (2) working days prior to returning or delivering any sign and/or sign related material.

3.03 RESPONSIBILITIES

A. The contractor is responsible for providing and supplying aluminum traffic signs covered with retro-reflective sheeting, applying standard legends (or special legends if shown in the plans) to the covered sign blanks, galvanized steel sign poles, pole anchors, all hardware for installing the signs and poles, and for installing traffic signs, poles and anchors as shown in the plans or call for in the contract documents, complete and ready for field installations.

END OF SECTION

Section 01555-S

TRAFFIC CONTROL AND REGULATION

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices: *Delete subparagraph 2 and 2b replace with the following.*

2. Payment for traffic control for wastewater or water line projects will be authorized by Project Manager in three (3) parts. Partial payment will be made according to following schedule:

   b. A payment of 50 percent of traffic control amount will be authorized when pavement replacement commences. This limiting percentage will be prorated based upon linear footage, as measured along centerline axis of wastewater or water line, of pavement replaced.

END OF SUPPLEMENT

Approved by:

J. Timothy Lincoln, P.E.
Office of the City Engineer
Planning and Development Service Division

10/4/13
Date

Section 01555

TRAFFIC CONTROL AND REGULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Requirements for signs, signals, control devices, traffic barriers, flares, lights and traffic signals; construction parking control, designated haul routes, and bridging of trenches and excavations.

B. Qualifications and requirements for use of flagmen.

1.02 MEASUREMENT AND PAYMENT

A. Unit Price Contracts.

1. Traffic control and regulation. Payment for traffic control and regulation is on a lump sum basis. Include preparation and submittal of traffic control plan if different than shown on Drawings, and provision of traffic control devices, equipment, and personnel necessary to protect the Work and public. Payment will be based on Contractor's Schedule of Values for traffic control and regulation.

2. Payment for traffic control will be authorized by Project Manager in three (3) parts. Partial payment will be made according to following schedule:

   a. Payment of 25 percent of traffic control amount will be authorized when permanent control devices and necessary temporary markings, sufficiently deployed along job site as required to maintain progress of work, are installed at job site and approved. This limiting percentage will be prorated based upon extent of Contractor's setup.

   b. A payment of 50 percent of traffic control amount will be authorized when pavement replacement commences. This limiting percentage will be prorated based upon linear footage, as measured along centerline axis of water main, of pavement replaced.

   c. A payment of 25 percent of traffic control amount will be authorized when permanent pavement markings are restored and all unnecessary permanent and temporary control devices removed. This limiting percentage will be prorated based upon the extent of restoration.

3. Flagmen: Measurement is on a lump sum basis for flagmen as required for the project. The amount invoiced shall be determined based on the schedule of value submitted for flagmen.

4. New Portable Concrete Low Profile Traffic Barrier Provided. Payment is on a unit price basis for each linear foot of low profile traffic barrier provided, installed with hardware assemblies and connected together in accordance with the approved traffic control plan.

5. Portable Concrete Low Profile Traffic Barrier picked up from City of Houston Stockpile. Payment is on a unit price basis for each linear foot of low profile traffic barrier picked up from designated stockpile, moved onto the project, set at location and connected together.

6. Portable Concrete Low Profile Traffic Barrier Installed. Payment is on a unit price basis for each linear foot of low profile traffic barrier delivered to the project location, installed with hardware assemblies and connected together in accordance with the approved traffic control plan.

7. Portable Concrete Low Profile Traffic Barrier Moved and Reset. Payment is on a unit price basis for each linear foot of low profile traffic barrier disassembled, moved on the project, reset at the new locations and connected together. Include cost to repair roadway in the unit price.

8. Portable Concrete Low Profile Traffic Barrier Removed. Payment is on a unit price basis for each linear foot of low profile traffic barrier removed from the project, including hardware assemblies, and stockpiling at location listed in Section 01110 – Summary of Work. Include cost to repair roadway in the unit price.

9. Refer to Section 01270 - Measurement and Payment for unit price procedures.

B. Stipulated Price Contracts. Include payment for work under this section in the total Stipulated Price.

1.03 REFERENCES

A. Texas Manual on Uniform Traffic Control Devices (TMUTCD)

B. Article 4413 (29bb), commonly referred to as Private Investigators and Private Security Agencies Act, and Article 2.12, Texas Code of Criminal Procedure.

C. Code of Ordinances, City of Houston, Texas.

1. Chapter 10 Buildings And Neighborhood Protection, Article X Cleanup After Demolition Or Removal Of Structures

2. Chapter 40 Streets and Sidewalks, Article XVII Pedestrian Way Impairments

1.04 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. Traffic control plan:

1. If using traffic control plan contained in the Contract without modification, submit a letter confirming use of the plan.

2. If using a different traffic control plan, submit the plan for approval. The plan must conform to TMUTCD requirements and be sealed by a Registered Texas Professional Engineer.

C. Submit copies of approved lane closure permits issued by City Traffic Engineering Branch.

D. Submit Schedules of Values for traffic control plan and flagmen within 30 days following Notice to Proceed.

E. Submit records verifying qualifications of Uniformed Peace Officers and Certified Flagmen proposed for use on the Work.

F. When working in the central business district, submit copies of approved Pedestrian Way permits issued by the City's Traffic Engineering Branch.

1.05 FLAGMEN

A. Use Uniformed Peace Officers and Certified Flagmen to control movement of vehicular and pedestrian traffic when construction operations encroach on public traffic lanes. Unless otherwise approved by Project Manager, use Uniformed Peace Officer for work along major thoroughfares, schools, churches, hospitals and Work at signalized intersections.

B. Uniformed Peace Officer: Individual employed full-time as a peace officer who receives separate compensation as a privately employed flagman. Private employment may be an employee-employer relationship or on an individual basis. Flagman may not be in the employ of another peace officer nor be a reserve peace officer.

1. Uniformed Peace Officers may be:

   a. sheriffs and their deputies;

   b. constables and deputy constables;

   c. marshals or police officers of an incorporated city, town or village; or

   d. as otherwise provided by Article 2.12, Code of Criminal Procedure.

2. The Uniformed Peace Officer must be a full-time peace officer, must work a minimum average of 32 paid hours per week, and must be paid a rate not less than the prevailing minimum hourly wage rate set by the federal Wage and Hour Act. The individual must be entitled to vacation, holidays, and insurance and retirement benefits.

C. Certified Flagman: Individual who receives compensation as a flagman and meets the following qualifications:

1. Formally trained and certified in traffic control procedures by the City s E. B. Cape Center.

2. Speaks English. Ability to speak Spanish is desirable but not required.

3. Paid for flagman duty at an hourly rate not less than the wage rate set for Rough Carpenter under the City's Wage Scale for Engineering Construction.

D. Certified Flagmen must wear a distinctive uniform, bright-colored vest, and be equipped with appropriate flagging and communication devices while at the Work site. They must also have in their possession while on duty, a proof of training identification card issued by the appropriate training institute.

PART 2 P R O D U C T S

2.01 SIGNS, SIGNALS, AND DEVICES

A. Comply with TMUTCD requirements.

B. Traffic cones and drums, flares and lights: Conform to local jurisdictions' requirements.

C. When working in the Central business district, provide pedestrian pathway

signage approved by the City's Traffic Engineering Branch.

2.02 PORTABLE LOW PROFILE CONCRETE BARRIERS

A. The low profile concrete barrier is a patented design. Information concerning this barrier may be obtained from Texas Transportation Institute, Texas A&M University System, College Station, Texas 77843-3135, (409) 845-1712.

PART 3 EXECUTION

3.01 PUBLIC ROADS

A. Submit requests forms for lane closure and sidewalk closure to the City's Traffic Engineering Branch at least three working days prior to need for blocking vehicular lanes or sidewalks. Do not block lanes or sidewalks without approved permits. Obtain application from the City's Traffic Engineering Branch at 611 Walker, 5th floor or at the following internet address: http://www.ci.houston.tx.us/pwe/mrow/laneclosure.htm.

B. Follow laws and regulations of governing jurisdictions when using public roads. Pay for and obtain permits from jurisdiction before impeding traffic or closing lanes. Coordinate activities with Project Manager.

C. Give Project Manager one-week notice before implementing approved traffic control phases. Inform local businesses of impending traffic control activities.

D. Notified police department, fire department, METRO, and local schools, churches, and businesses in writing a minimum of five business days prior to beginning work.

E. Maintain 10-foot wide all-weather lanes adjacent to the Work for emergency vehicle use. Keep all-weather lanes free of construction equipment and debris.

F. Do not to obstruct normal flow of traffic from 7:00 a.m. to 9:00 a.m. and 4:00 p.m. to 6:00 p.m. on designated major arterials or as directed by Project Manager.

G. Maintain local driveway access to residential and commercial properties adjacent to work areas at all times. Use all-weather materials approved by Project Manager to maintain temporary driveway access to commercial and residential driveways.

H. Keep streets entering and leaving job site free of excavated material, debris, and foreign material resulting from construction operations in compliance with

applicable ordinances.

I. Remove existing signage and striping that conflict with construction activities or that may cause driver confusion.

J. Provide safe access for pedestrians along major cross streets.

K. Alternate closures of cross streets so that two adjacent cross streets are not closed simultaneously.

L. Do not close more than two consecutive esplanade openings at a time without prior approval from Project Manager.

3.02 CONSTRUCTION PARKING CONTROL

A. Control vehicular parking to prevent interference with public traffic and parking, access by emergency vehicles, and the City's operations.

B. Monitor parking of construction personnel's vehicles in existing facilities. Maintain vehicular access to and through parking areas.

C. Prevent parking on or adjacent to access roads or in non-designated areas.

3.03 FLARES AND LIGHTS

A. Provide flares and lights during hours of low visibility to delineate traffic lanes and to guide traffic.

3.04 HAUL ROUTS

A. Utilize haul routes designated by authorities or shown on drawings for construction traffic.

B. Confine construction traffic to designated haul routes.

C. Provide traffic control at critical areas of haul routes to regulate traffic and minimize interference with public traffic.

3.05 TRAFFIC SIGNS AND SIGNALS

A. Construct necessary traffic control devices for temporary signals required to complete the Work including loop detectors, traffic signal conduits, traffic signal wiring and crosswalk signals. Notify the City's Traffic Engineering Branch a minimum of 60 days in advance of need for control boxes and switchgear. The City will perform necessary service, programming or adjustments, to signal boxes and switchgear if required during construction.

B. Install and operate traffic control signals to direct and maintain orderly traffic flow in areas under Contractor's control affected by Contractor's operations. Post notices, signs and traffic controls before moving into next phase of traffic control.

C. Relocate traffic signs and signals as the Work progresses to maintain effective traffic control.

D. Unless otherwise approved by Project Manager, provide driveway signs with name of business that can be accessed from each crossover. Use two signs for each crossover.

E. Replace existing traffic control devices in Project area.

F. Project Manager may direct Contractor to make minor adjustments to traffic control signage to eliminate driver confusion and maintain orderly traffic flow during construction at no additional cost to the City.

3.06 BRIDGING TRENCHES AND EXCAVATIONS

A. When necessary, construct bridges over trenches and excavation to permit an unobstructed flow of traffic across construction areas and major drives. Use steel plates of sufficient thickness to support H-20 loading and install to operate with minimum noise.

B. Shore trench or excavation to support bridge and traffic.

C. Secure bridging against displacement with adjustable cleats, angles, bolts or other devices when:

1. bridging is placed over existing bus routes,

2. more than five percent of daily traffic is comprised of commercial or truck traffic,

3. more than two separate plates are used for bridging, and

4. when bridge is to be used for more than five consecutive days.

D. Extend steel plates used for bridging a minimum of 1 foot beyond edges of trench or excavation. Use temporary paving materials such as premix to feather edges of plates to minimize wheel impact on secured bridging.

3.07 REMOVAL

A. Remove equipment and devices when no longer required.

B. Repair damage caused by installation.

C. Remove post settings to a depth of 2 feet.

3.08 TRAFFIC CONTROL, REGULATION AND DIRECTION

A. Use Flagmen to control, regulate and direct an even flow and movement of vehicular and pedestrian traffic, for periods of time as may be required to provide for public safety and convenience, where:

1. multi-lane vehicular traffic must be diverted into single lane vehicular traffic,

2. vehicular traffic must change lanes abruptly,

3. construction equipment must enter or cross vehicular traffic lanes and walks,

4. construction equipment may intermittently encroach on vehicular traffic lanes and unprotected walks and crosswalk,

5. traffic regulation is needed due to rerouting of vehicular traffic around the Work site, and

6. where construction activities might affect public safety and convenience.

B. Use of Flagmen to assist in the regulation of traffic flow and movement does not relieve Contractor of responsibility to take other means necessary to protect the Work and public.

3.09 INSTALLATION STANDARDS

A. Place temporary pavement for single lane closures, in accordance with TMUTCD.

B. Reinstall temporary and permanent pavement markings as approved by Project Manager. When weather conditions do not allow application according to manufacturer's requirements, alternate markings may be considered. Submit proposed alternate to Project Manager for approval prior to installation. No additional payment will be made for use of alternate markings.

3.10 MAINTENANCE OF EQUIPMENT AND MATERIAL

A. Submit name, address and telephone number of individual designated to be

responsible for maintenance of traffic handling at construction site to Project Manager. Individual must be accessible at all times to immediately correct deficiencies in equipment and materials used to handle traffic including missing, damaged, or obscured signs, drums, barricades, or pavement markings.

B. Inspect signs, barricades, drums, lamps and temporary pavement markings daily to verify that they are visible, in good working order, and conform with traffic handling plans as approved by Project Manager. Immediately repair, clean, relocate, realign, or replace equipment or materials that are not in compliance.

C. Keep equipment and materials, signs and pavement markings, clean and free of dust, dirt, grime, oil, mud, or debris.

D. Obtain approval of Project Manager to reuse damaged or vandalized signs, drums, and barricades.

END OF SECTION

Section 01562

TREE AND PLANT PROTECTION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Tree and plant protection.

B. Minimum qualifications of Arborist and Urban Forester.

1.02 MEASUREMENT AND PAYMENT

A. Payment for Tree Protection, including tree pruning or tree removal, shall be paid as a Lump Sum basis that shall include all items specified in this section unless payment is specified otherwise in this section

B Payment for Zero Curb Cutback will be on a per linear foot basis.

C. Payment for Checker Plate will be on a square foot basis.

D. Refer to Section 01270-Measurement and Payment for unit price procedures.

1.03 SUBMITTALS

A. Conform to requirements of Section 01330 – Submittal Procedures.

B. Submit name and experience of qualified Arborist, proposed for use on the Work, to Project Manager.

1.04 PROJECT CONDITIONS

A. Preserve and protect existing trees and plants to remain from foliage, branch, trunk, or root damage that could result from construction operations.

B. Prevent following types of damage:

1. Compaction of root zone by foot or vehicular traffic, or material storage.

2. Trunk damage from equipment operations, material storage, or from nailing or bolting.

3. Trunk and branch damage caused by ropes or guy wires.

4. Root or soil contamination from spilled solvents, gasoline, paint, lime slurry, and other noxious materials.

5. Branch damage due to improper pruning or trimming.

6. Damage from lack of water due to:

   a. Cutting or altering natural water migration patterns near root zones.

   b. Failure to provide adequate watering

7. Damage from alteration of soil pH factor caused by depositing lime, concrete, plaster, or other base materials near roots zones.

8. Cutting of roots larger than one inch in diameter.

1.05 DAMAGE ASSESSMENT

A. When trees other than those designated for removal are destroyed or damaged as result of construction operations, remove and replace with same size, species, and variety up to and including 8 inches in trunk diameter. Trees larger than 8 inches in diameter shall be replaced with an 8 inch diameter tree of the same species and variety and total contract amount will be reduced by an amount determined from the following formula and paid to Tree Fund 0.7854 x D2 x $13.25 where D is diameter in inches of tree or shrub trunk measured 12 inches above grade for that portion of the tree which is greater than 8 inches in diameter. A permit must be applied for and approved by the City of Houston, Urban Forestry Division prior to removal of any tree not scheduled for removal in the tree treatment schedule. Contractor shall contact City of Houston, Urban Forestry, at 832-395-8459 to apply for tree removal permit when needed.

PART 2 PRODUCTS

2.01 MATERIALS

A. Pruning Paint: Black latex, water based paint, free of all petroleum products.

B. Fertilizer: Fertilizer shall be a root stimulant that contains at a minimum the following ingredients: Ectomycorrhizal Fungi, VA Mycorrhizal (VAM) Fungi, Rhizosphere Bacillus spp., Kelp Meal Humic Acid, and Soluble Yucca.

C. Tree Protection Fencing: Orange, plastic mesh fenching, 4 feet in height with 6 feet high "t" bar posts installed 10 feet on centers as per drawings.

D. Plastic Root/Soil Protection: Clear polyethylene sheeting, minimum 6 mil, thickness.

PART 3 EXECUTION

3.01 PROTECTION OF EXISTING TREES AND SHRUBS

A. Site preparation work and/or construction work shall not begin in any area where tree preservation measures have not been completed and approved.

B. Protect exposed roots and root zone areas from contamination from stabilization materials and concrete using polyethylene.

C. Cover exposed roots within 4 hours to reduce damage caused by desiccation. Roots may be covered with soil, mulch, polyethylene, or wet burlap to help protect them from drying.

D. Designate limited areas as concrete washout areas. Locate concrete washout areas away from root zones.

E. Install root pruning trenching where designated in tree treatment schedule and shown on the tree protection drawings. Trees scheduled for root pruning are called out specifically in the treatment schedule. Trench shall be located 2 ft. from the edge of proposed waterline or sanitary sewer for trees called out for root pruning for water or fittings, or sanitary sewer in the treatment schedule, 2 ft. from edge of proposed storm sewer pipe for trees called out for root pruning for storm in the treatment schedule, 30" back of proposed curb for trees called out for root pruning for street, and at edge of sidewalk for trees called out for root pruning for sidewalk. Root pruning shall not be performed where there is not adequate space to be located sufficiently away from tree to prevent damage. All pruning must be evaluated by Contractor's Certified Arborist and reviewed and approved by City Forester before being performed. Trench locations shown on tree preservation plan are drawn to scale and should be located in field as drawn on plan. Exact locations shall be approved in the field by engineer and/or project urban forester prior to installation. Trenching depth shall be a minimum of 2 ft. deep and a maximum of 6 inches wide for water, fittings, sanitary sewer, storm, and street. Trenching depth shall be to the anticipated bottom of sidewalk and base material for sidewalk root pruning, roots lower than sidewalk shall not be pruned. All roots shall be cut by trencher, chainsaw, or handsaw to the specified depth. Roots shall be cut cleanly, and or not ripped, torn, or chopped. Trench shall be backfilled and compacted immediately after trenching. Trench shall be installed prior to any clearing and grubbing, excavation for underground, or any other site work.

F. Install tree protection fencing around each tree to be preserved as indicated in the tree treatment schedule and on the tree protection plan.

1. Each tree to be preserved shall be protected with a tree protection fence. The fencing shall be continuous between posts, shall be pulled taut prior to securing to posts, and shall be firmly attached to the posts with a minimum of 4 wire ties.

2. All tree protection fencing shall be installed prior to site work or construction activity. The fence shall be placed in a continuous alignment as shown on the tree protection plan. Fences shown on tree protection plan are drawn to scale and shall be installed as drawn, in the field. In general fences shall be placed 30" back of existing curb or edge of pavement where root pruning or zero curb cutback is not specified, and 6" back of root pruning trench where root pruning is specified and immediately back of curb where zero curb cutback is specified. Exact locations shall be approved by the project urban forester and/or engineer in the field. The Fences shall be placed to protect roots, trunks, and foliage. The contractor shall not remove or relocate tree protection fencing and shall not operate within the limits shown without direct approval of the project urban forester. In areas where the proposed waterline is located in the existing road side ditch and where tree protection fencing can not be installed across the ditch, the fencing shall be installed at the top of outside ditch bank and no bore pits, peep holes, service taps, or any excavation should occur in the area immediately in front of the tree protection fencing for trees called out with "bore" in the Tree Treatment Schedule. The "bore" limits shall be the same as the limits of the tree protection fencing.

3. Storage of equipment or materials will not be allowed inside a fence. Entryways and access into a protected area shall not be provided unless approved by the project urban forester.

4. Damage to tree fences occurring during the progress of the work shall be repaired immediately at no additional cost to owner. Workmen shall be clearly instructed to exercise caution in performance of work near trees being preserved.

5. Tree protection fencing shall be removed by contractor, at no additional costs, upon completion of all construction activity in each work zone area. Tree protection fencing materials used in the first two work zone areas shall be removed and utilized in subsequent work zone areas. Materials and labor shall be paid for each linear foot of fencing installed in first two work areas. All fencing installed in subsequent work zone areas shall be paid for labor only.

G. Boring/Auguring of water lines or sanitary sewer lines

1. Water line or sanitary sewer line shall be bored/augured/ horizontally drilled under

critical root zones areas of trees designated with auger or bore in the tree treatment schedule. The entire area protected with tree protection fencing shall be bored. No bore pits, come through holes, peep holes, push pits, or long or short side service taps shall be allowed in the areas protected by tree protection fencing. The tree protection plan takes into consideration the limits of augering equipment, there should be room for adequately spaced bore pits, peep holes, come through holes, and push pits. Any changes to the location of the tree protection fencing shall be authorized by the project Urban Forester and City Engineer.

H. Hand digging of Service taps and leads

1. Trees called out for Hand dig short side service tap are located in very close proximity to existing short side water meters. Excavating the service tap with machinery would significantly impact the tree and be in violation of the City of Houston's Street Tree Ordinance. These short side service taps shall be excavated with manual labor to expose any roots 1" in diameter and larger. The first 24" of excavation shall be completed manually to expose the roots. Any root 1" in diameter and larger shall remain undamaged, the roots shall not be cut , nor shall the bark and cambium layer be scraped or damaged. Once the roots are exposed, if there is adequate room to utilize a mini-excavator without damaging the roots, the mini-excavator can be utilized to complete the excavation down to the water line. 1" plywood shall be placed on grade to provide root protection in the area of access of the mini-excavator. If roots 1" diameter or larger are cut or damaged, responsible party will be subject to a citation under the Street Tree Ordinance, and may also be required to incur the cost of tree removal and replacement of damaged tree on an inch for inch basis, if required by City of Houston Urban Forestry Division.

2. Trees called out for Hand dig short side or long side service lead are located in very close proximity to existing water meters. Excavating the service lead with machinery would significantly impact the tree and be in violation of the City of Houston's Street Tree Ordinance. Short side leads shall be excavated with manual labor to expose any roots 1" in diameter and larger from the service tap of the meter. Come out hole and excavation required for long service leads shall be excavated with manual labor to expose roots 1" in diameter and larger, from the come out hole to the meter. In each case, all roots 1" in diameter and larger shall remain undamaged, the roots shall not be cut, nor shall the bark and cambium layer be scraped or damaged. If roots 1" diameter or larger are cut or damaged, responsible party will be subject to a citation under the cost of tree removal and replacement of damaged tree on an inch by inch basis, if required by City of Houston Urban Forestry Division.

3. Trees called out for Hand dig sanitary stub up are located in very close proximity to proposed service lead. Excavating the service lead with machinery would significantly impact the tree and be in violation of the City of Houston's Street Tree

Ordinance. Excavation for sanitary stub up shall be completed with manual labor to expose any roots 1" in diameter and larger. The lead shall be bored from face of curb to stub up hole when called out in the tree treatment schedule. Come out and stub up holes shall be excavated with manual labor to expose roots 1" in diameter and larger. In case, all roots 1" in diameter and larger shall remain undamaged, the roots shall not be cut, nor shall the bark and cambium layer be scraped or damaged. If roots 1" diameter or larger are cut or damaged, responsible party will be subject to a citation under the Street Tree Ordinance, and may be required to incur the cost of tree removal and replacement of damaged tree on an inch by inch basis, if required by City of Houston Urban Forestry Division.

4. Long side service taps shall not be located in an area specified to be bored in the tree treatment schedule. Should it be absolutely necessary to locate a long side service tap in an area specified to be bored, the excavation shall be completed as specified in paragraph 1 of this section-Hand digging short side service taps.
5. All water meters and sanitary service leads called out on P&P drawings and visible in the field have been addressed in the Tree Protection Plan. Should any additional meters or lead be found during construction, or in any new meters or leads installed beneath the canopy of any tree, fenced for tree protection, the excavation shall be completed as specified in paragraph 1 and/or 2 of this section and paid for at the unit cost for each included in contract.

I. Pruning of Trees

1. Trees shall be pruned in accordance with the American National Standard for tree pruning, ANSI A300 (Part 1) – 2001 Pruning Revision of ANSI A300-1995 Tree, Shrub and Other Woody Plant Maintenance – Standard Practices. Pruning shall be completed by professional arborists who has received training in proper pruning techniques.

2. Clearance prune designated trees for public streets, sidewalks, and construction areas. Provide minimum 14 feet and maximum of 18 feet of vertical clearance over proposed water trunk lines. Provide minimum of 14 feet and maximum of 16 feet of vertical clearance over proposed street construction, from 24" back of curb on one side to 24" back of curb on the other side. Provide 20' of vertical clearance over proposed storm sewer up to 38" in size, and 30' of vertical clearance for storm sewer larger than 38" in size. Pruning to be installed prior to any construction activity. Contractor shall notify property owner prior to trimming or pruning any trees with trunks located on private property. Exceptions will be made for trees determined to be arboriculturally significant by City of Houston Urban Forestry. Pruning of trees identified will be completed with approval and supervision of City of Houston Urban Forestry.

3. All cuts should be made sufficiently close to the parent limb or trunk without cutting into the branch collar or leaving a protruding stub, so that closure can readily start under normal conditions. All lateral cuts shall be made to a lateral that is least 1/3 the diameter of the parent limb. Clean cuts shall be made at all times.

4. Trees shall be pruned in a manner that will not destroy or alter the natural shape and character of the tree. Apply black latex paint to all fresh wounds on Oak (Quercus) species immediately after each cut is made.

5. Crown cleaning prune designated trees shall include selective removal of dead, diseased, and/or broken limbs.

J. Tree Removal

1. Trees scheduled for removal shall be sawed down and debris hauled from the site the same day. The stump shall be ground to 6" below grade and excess grindings shall be hauled from the site the same day, so that a pile of grindings is not left where the stump was ground. Enough grindings should be left so that an open hole does not remain.

2. Only those trees called out for removal in the Tree Treatment Schedule shall be removed, or otherwise damaged. Should it be determined that any additional trees must be removed, a permit must be applied for and approved from the City of Houston Urban Forestry Division prior to removal. Contractor shall contact Urban Forestry at 832-395-8459.

K. Root Stimulation

1. Deep root stimulate designated trees. Mix fertilizer with wetting agent per label instructions.

2. Stimulate entire root zone area within the dripline of the tree and continue 10 feet beyond the dripline, leaving out areas of anticipated root loss (construction areas).

3. Mixture shall be injected into the top 10 inches of soil under pressure of 150 to 200 psi as soil conditions warrant.

4. Mix in a tank with agitation capability per label instructions. Inject the mixture on a 2.5 ft. square grid at 4 lbs, actual nitrogen per 1,000 sq. ft.

L. Regularly water trees which have received root damage, to eliminate additional stress caused by lack of moisture. Water during periods without adequate rainfall. For example, should 1.0" of rain not be received within a week period, the trees should be thoroughly watered.

March through September, water once every two weeks. October through February, water every three weeks. Water thoroughly to saturate the entire root zone area.

M. Chemically treat tree trunks with evidence of borer activity with the appropriate approved insecticide mixed and applied per the manufacturer's product application recommendations. Trees shall be sprayed within 24 hours after observance of borer activity.

N. Grading and filling around trees.

1. Maintain existing grade within the dripline of trees, unless otherwise indicated.

2. Where existing grade around trees is above new finish grade, under supervision of project urban forester, carefully hand excavate within the dripline to make transition to new finish grade.

3. Where existing grade is below new finish grade, place clean bank sand in a single layer to make the transition to new grade. Do not compact; hand grade to required elevation. Specifically to areas where proposed curb is higher than existing and backfill will be required.

O. Demolition, Forming and Pouring Sidewalks (Sidewalk on Grade)

1. Demolition of existing sidewalks, located in or adjacent to the limits of tree protection fencing, shall be completed without disturbing, cutting, or otherwise damaging tree roots and soil located beneath them.

2. The new sidewalk shall be formed at or above the elevation of the existing sidewalk, without disturbing, cutting or otherwise damaging tree roots. Every effort has been made to address tree root and sidewalk elevation issues with information available in the field and on plan and profile sheets. The elevation of every tree root was not available, if tree roots are found to be in conflict with proposed sidewalk, project engineer and urban forester shall be consulted as to how to install sidewalks with minimal impacts to adjacent trees.

3. Checkerplate shall be installed in areas called out only if tree root elevations prohibit construction of ADA compliant sloped concrete sidewalks. Checkerplate shall be installed per detail.

P. Zero curb cutback

1. Disturbance of tree roots or soil behind the existing and/or proposed curb within root zones of trees designated for zero curb cutback shall be prohibited. If the curb can not be removed without disturbing soil or damaging roots back of curb when using

equipment for demolition, the curb shall be broken using a hand held jackhammer and removed by hand.

2. The exposed roots and soil shall be covered immediately after demolition with 6 mil polyethylene in order to avoid desiccation, and contamination by the lime used for road bed stabilization. The polyethylene shall be placed so that it covers the vertical face of soil back of curb and laid back onto the grade 12 inches back of curb. The polyethylene should remain in place, across the entire area specified for zero curb cutback, from the time the existing curb is demolished until the time when the new curb is formed and backfilled. The polyethylene can be pulled up from the vertical face while the road bed is being graded or mixed, to avoid catching the plastic with machinery, but shall be replaced immediately after equipment has completed. The vertical face shall not be exposed for more than 8 hours in any 24 hour period.

3. There shall be no stabilization back of curb in the zero curb cutback areas, or forming with steel forms. The existing grade and roots back of existing curb shall not be disturbed. This may require forming of the new street with wooden forms with stakes inside forms, which may require leaving the forms in place after the street is poured. Should wooden forms be utilized, the wood shall be at minimum a 2x6. The new curb may require hand finishing, as a slip curb machine may not have adequate clearance without disturbing the roots that are to be protected with the zero curb cutback.

4. Roots extending into the street, or on top of the existing curb, in areas to paved shall be cut and removed by hand prior to disturbance or removal with equipment. Roots shall be pruned flush with the proposed back of curb. Roots one inch in diameter and larger shall be cut in a manner to provide a smooth, clean cut surface. Cuts shall be made with the appropriate pruning shears or pruning saws. Roots shall not be chopped or broken.

5. In areas where proposed curb will be may be lower than existing top of curb and tree roots 2" diameter or larger are present, the soil and roots shall not be graded or laid back. The existing elevation shall be maintained and the curb formed to meet elevation or a short elevation difference roots and top of curb maintained.

Q. Demolition, Forming and Pouring of Drive Way Approaches

1. Demolition of existing driveway approaches located beneath the dripline of any tree shall be completed without disturbing, cutting, or otherwise damaging tree roots and soil located beneath them.

2. The new approach shall be formed at or above the elevation of the existing approach where tree roots 2" diameter or larger are present, without disturbing, cutting or

otherwise damaging tree roots. Maximum drive slopes may be needed at bottom of apron to allow forming of drive over tree roots at top of drive. As with sidewalks, the elevation of every tree roots was not available in design. If tree roots are found to be in conflict with proposed approach, project engineer and urban forester shall be consulted as to how to install drive way with minimal impacts to adjacent trees.

R. Replacement Trees for Tree Removals under Ordinance

1. Location, species, and size of replacement trees are indicated on the drawings. Contractor shall layout individual trees at locations shown on drawings. Contractor shall layout individual trees at locations shown on drawings and be responsible for utility locate requirements. In case of conflicts, notify City Engineer and City Urban Forestry before proceeding with work. Trees shall be laid out and locations approved by City Engineer prior to planting.

2. Trees shall meet and be planted according to City of Houston Standard Specification 02915.

S. Arborist and Urban Forester Qualifications

1. Arborist – Employ qualified arborist acceptable to City's Parks and Recreation Department to complete all tree treatments. Arborist shall be normally engaged in the field and have a minimum of 5 years experience. Qualifications of the selected arborist shall be submitted for review and approval by the project engineer and City of Houston.

2. Urban Forester – An Urban forester shall be hired to monitor and assist with field layout (exact locations of fencing, root pruning, and zero curb cutback) of the tree preservation program during demolition and construction to ensure tree protection procedures and techniques are practiced as specified to address concerns and conditions which occur in the field. At a minimum, the individual responsible for monitoring and field layout of the tree protection shall have a minimum of 5 years of experience as a consultant, and shall not be affiliated with a tree care contractor in the Houston area. Qualifications of the selected urban forester shall be submitted for review and approval by the project engineer and City of Houston Urban Forestry Department.

END OF SECTION

Section 01570

STORM WATER POLLUTION PREVENTION CONTROL

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Implementation of Storm Water Pollution Prevention Plans (SWP3) described in Section 01410 – TPDES Requirement.

B. Installation, maintenance and removal, of storm water pollution prevention structures: diversion dikes, interceptor dikes, diversion swales, interceptor swales, down spout extenders, pipe slope drains, paved flumes and level spreaders. Structures are used during construction and prior to final development of the site.

C. Filter Fabric Barriers:

1. Type 1: Temporary filter fabric barrier for erosion and sediment control in non-channelized flow areas.

2. Type 2: Temporary reinforced filter fabric barrier for erosion and sediment control in channelized flow areas.

D. Hay Bale Fence.

E. Drop Inlet Basket

F. Inlet Sediment Traps

G. Brush Berm

H. Sand Bag Barrier

I. Bagged Gravel Barrier

J. Sediment Basin

K. Inlet Protection Barrier

1.02 MEASUREMENT AND PAYMENT

A. UNIT PRICES

1. Payment for filter fabric barrier is on a linear foot basis measured between limits of beginning and ending of stakes.

2. Payment for reinforced filter fabric barrier is on a linear foot basis measured between limits of beginning and ending of stakes.

3. Payment for drop inlet baskets is on a unit price basis for each drop inlet basket.

4. Payment for storm inlet sediment traps is on a unit price basis for each storm inlet sediment trap.

5. Payment for storm water pollution prevention structures is on a lump sum basis for the project. Earthen structures with outlet and piping include diversion dikes, interceptor dikes, diversion swales, interceptor swales, and excavated earth-outlet sediment trap, embankment earth-outlet sediment trap, down spout extenders, pipe slope drains, paved flumes, stone outlet sediment trap, and level spreaders.

6. Payment for hay bale barrier, if included in Document 00410 - Bid Form, is on a linear foot of accepted bale barriers, if not include in cost of storm water pollution prevention structures.

7. Payment for brush berm, if included in Document 00410 - Bid Form, is on a linear foot of accepted brush berm, if not include in cost of storm water pollution prevention structures.

8. Payment for sandbag barrier, if included in Document 00410 - Bid Form, is on a linear foot basis measured between limits of beginning and ending of sandbags, if not include in cost of storm water pollution prevention structures.

9. Payment for bagged gravel barrier, if included in Document 00410 - Bid Form, is on a linear foot basis measured between limits of beginning and ending of bagged gravel barrier, if not include in cost of storm water pollution prevention controls.

10. Payment for inlet protection barriers, if included in Document 00410 - Bid Form, is on a linear foot basis measured along outside face of inlet protection barrier, if not include in cost of storm water pollution prevention structures.

11. Refer to Section 01270 - Measurement and Payment for unit price procedures.

B. Stipulated Price (Lump Sum) Contract. If Contract is Stipulated Price Contract, payment for Work in this Section is included in total Stipulated

1.03 REFERENCE STANDARDS

A. ASTM

1. A 36 – Standard Specification for Carbon Structural Steel.

2. D698 – Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft3 (600kN-m/m3)).

3. D3786 – Standard Test Method for Hydraulic Bursting Strength for knitted Goods and Nonwoven Fabrics.

4. D 4355 - Standard Test Method for Deterioration of Geotextiles from Exposure to Ultraviolet Light and Water (Xenon-Arc Type Apparatus).

5. D 4491 - Standard Test Methods for Water Permeability of Geotextiles by Permittivity.

6. D 4632 - Standard Test Method for Grab Breaking Load and Elongation of Geotextiles.

7. D 4833 - Standard Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products.

8. D 6382 - Standard Practice for Dynamic Mechanical Analysis and Thermogravimetry of Roofing and Waterproofing Membrane Material.

B. Storm Water Management Handbook for Construction Activities prepared by City of Houston, Harris County and Harris County Flood Control District.

1.04 SYSTEM DESCRIPTIONS

A. Filter Fabric Barrier Type 1 and Type 2: Install to allow surface or channel runoff percolation through fabric in sheet-flow manner and to retain and accumulate sediment. Maintain Filter Fabric Barriers to remain in proper position and configuration at all times.

B. Hay Bale Fence: Install to allow surface runoff percolation through hay in sheet-flow manner and to retain and accumulate sediment. Maintain Hay Bale Fence to remain in proper position and configuration at all times.

C. Interceptor Dikes and Swales: Construct to direct surface or channel runoff around the project area or runoff from project area into sediment traps.

D. Drop Inlet Baskets: Install to allow runoff percolation through the basket and to retain and accumulate sediment. Clean accumulation of sediment to prevent clogging and backups.

E. Sediment Traps: Construct to pool surface runoff from construction area to allow sediment to settle onto the bottom of trap.

F. Sand Bags: Are used during construction activities in unstabilized minor swales, ditches, or streambeds when the contributing drainage area is no greater than 2 acres. It is also sediment barrier for stage one Inlet.

G. Bagged Gravel Barrier: Are used during construction activities in unstabilized minor swales, ditches, or streambeds when the contributing drainage area is no greater than 2 acres. It is also sediment barrier for stage two Inlet.

H. Drop Inlet Insert Basket: Is a temporary barrier placed within a storm drain inlet (Lower Portion of Stage I and Upper Portion of Stage II Inlets) consisting of a filter fabric supported by a metal frame work to prevent sediment and other pollutants from entering convey system.

I. Brush Berm: Brush Berm is constructed at the perimeter of a distribute site within the developing area.

1.05 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. Submit manufacturer's literature for product specifications and installation instructions.

C. Submit manufacturer-s catalog sheets and other product data on geotextile or filter fabrics, outlet pipe, perforated riser and connectors.

D. Submit proposed methods, equipment, materials, and sequence of operations for storm-water pollution prevention structures.

E. Submit shop drawings for Drop Inlet Baskets.

PART 2 P R O D U C T S

2.01 CONCRETE

A. Concrete: Class B in accordance with Section 03315 – Concrete for Utility Construction or as shown on the Drawings.

2.02 AGREGATE MATERIALS

A. Use poorly graded cobbles with diameter greater than 3 inches and less than 5 inches.

B. Provide gravel lining in accordance with Section 2320 – Utility Backfill Materials or as shown on the drawings.

C. Provide clean cobbles and gravel consisting of crushed concrete or stone. Use clean, hard crushed concrete or stone free from adherent coatings, salt, alkali, dirt, clay, loam, shale, soft or flaky materials, or organic matter.

D. Sediment Pump Pit Aggregate: Use nominal 2-inch diameter river gravel.

2.03 PIPE

A. Polyethylene culvert pipe or PVC sewer pipe in accordance with Section 02505- High Density Polyethylene (HDPE) Solid and Profile Wall Pipe and Section 02506 Polyvinyl Chloride Pipe or as shown on the Drawings.

B. Inlet Pipes: Galvanized steel pipe in accordance with Section 02642 Corrugated Metal Pipe or as shown on the Drawings.

C. Standpipe for Sediment Pump Pits: Galvanized round culvert pipe or round PVC pipe, minimum of 12-inch and a maximum of 24-inch diameter, perforate at 6 to 12 inch centers around circumference.

2.04 GEOTEXTILE FILTER FABRIC

A. Woven or nonwoven geotextile filter fabric made of either polypropylene, polyethylene, ethylene, or polyamide material, in continuous rolls of longest practical length.

B. Grab Strength: 100 psi in any principal direction (ASTM D-4632), Mullen burst strength >200 psi (ASTM D-3786), and equivalent opening size between 50 and 140.

C. Furnish ultraviolet inhibitors and stabilizers for minimum 6 months of expected usable construction life at temperature range of 0 degrees F to 120 degrees F.

D. Mirafi, Inc., Synthetic Industries, or equivalent

2.05 BARRIER

A. Wire Barrier: Woven galvanized steel wire, 14 gauge by 6-inch square mesh spacing, minimum 24 inch roll or sheet width of longest practical length.

B. Barrier Stakes: Nominal 2 by 2 inch moisture-resistant treated wood or steel posts (min. of 1.25 lbs. per linear foot and Brinell Hardness greater than 140) with safety caps on top; length as required for minimum 8 inch bury and full

height of filter fabric.

2.06 SANDBAGS

A. Provide woven material made of polypropylene, polyethylene, or polyamide material.

1. Minimum unit weight of four ounces per square yard.

2. Minimum grab strength of 100 lbs in any principal direction (ASTM D4632)

3. Mullen burst strength exceeding 300 lbs (ASTM D4833).

4. Ultraviolet stability exceeding 70 percent. After 500 hours of exposure (ASTM 4355).

5. Size: Length:18 to 24 inches. Width: 12 to 18 inches. Thickness: 6 to 8 inches. Weight: Approximately 40 to 50 pounds not to exceed 75 pounds.

2.07 Bagged gravel Barrier

1. Minimum unit weight of four ounces per square yard.

2. Minimum grab strength of 100 lbs in any principal direction (ASTM D4632)

3. Mullen burst strength exceeding 300 lbs (ASTM D4833).

4. Ultraviolet stability exceeding 70 percent. After 500 hours of exposure (ASTM 4355).

5. Size: Length:18 to 24 inches. Width: 12 to 18 inches. Thickness: 6 to 8 inches. Weight: Approximately 40 to 50 pounds not to exceed 75 pounds.

2.08 DROP INLET BASKET

A. Provide steel frame members in accordance with ASTM A36.

B. Construct top frame of basket with two short sides of 2 inch by 2 inch and single long side of 1 inch by 1 inch, 1/8 inch angle iron. Construct basket hangers of 2 inch by 1/4 inch iron bars. Construct bottom frame of 1 inch by 1/4 inch iron bar or 1/4 inch plate with center 3 inches removed. Use minimum 1/4 inch diameter iron rods or equivalent for sides of inlet basket.

Weld minimum of 14 rods in place between top frame/basket hanger and bottom frame. Exact dimensions for top frame and insert basket will be determined based on dimensions of type of inlet being protected.

2.09 HAY BALE

A. Hay: Standard-baled agricultural hay bound by wire, nylon, or polypropylene rope. Do not use jute or cotton binding.

B. Hay Bale Stakes (applicable where bales are on soil): No. 3 (3/8 diameter) reinforcing bars, deformed or smooth at Contractor's option, length as required for minimum 18 inch bury and full height bales.

PART 3 EXECUTION

3.01 PREPARATION, INSTALLATION AND MAINTEINANCE

A. Provide erosion and sediment control structures at locations shown on the Drawings.

B. Do not clear, grub or rough cut until erosion and sediment control systems are in place unless approved by Project Manger to allow installation of erosion and sediment control systems, soil testing and surveying.

C. Maintain existing erosion and sediment control systems located within project site until acceptance of Project or until directed by Project Manger to remove and discard existing system.

D. Regularly inspect and repair or replace damaged components of erosion and sediment control structures. Unless otherwise directed, maintain erosion and sediment control structure until project area stabilization is accepted. . Redress and replace granular fill at outlets as needed to replenish depleted granular fill. Remove erosion and sediment control structures promptly when directed by Project Manger. Dispose of materials in accordance with Section 01576 - Waste Material Disposal.

E. Remove and dispose sediment deposits at the designated spoil site for the Project. If a project spoil site is not designated on Drawings, dispose of sediment off site at approved location in accordance with Section 01576 - Waste Material Disposal.

F. Unless otherwise shown on the Drawings, compact embankments, excavations, and trenches in accordance with Section 02315 Roadway

Excavation or Section 2317 Excavation and Backfill for Utilities.

G. Prohibit equipment and vehicles from maneuvering on areas outside of dedicated right of way and easements for construction. Immediately repair damage caused by construction traffic to erosion and sediment control structures.

H. Protect existing trees and plants in accordance with Section 1562 – Tree and Plant Protection.

3.02 SEDIMENT TRAPS

A. Install sediment traps so that surface runoff shall percolate through system in sheet flow fashion and allow retention and accumulation of sediment.

B. Inspect sediment traps after each rainfall, daily during periods of prolonged rainfall, and at a minimum once each week. Repair or replace damaged sections immediately.

C. Use fill material for embankment in accordance with Section 02320 – Utility Backfill Materials.

D. Excavation length and height shall be as specified on Drawings. Use side slopes of 2:1 or flatter.

E. Stone outlet sediment traps:

1. Maintain minimum of 6 inches between top of core material and top of stone outlet, minimum of 4 inches between bottom of core material and existing ground and minimum of 1 foot between top of stone outlet and top of embankment.

2. Embed cobbles minimum of 4 inches into existing ground for stone outlet. Core shall be minimum of 1 foot in height and in width and wrapped in triple layer of geotextile filter fabric.

F. Sediment Basin with Pipe Outlet Construction Methods: Install outlet pipe and riser as shown on the Drawings.

G. Remove sediment deposits when design basin volume is reduced by one-third or sediment level is one foot below principal spillway crest, whichever is less.

3.03 FILTER FABRIC BARRIER CONSTRUCTION METHODS

A. Fence Type 1: Filter Fabric: Barrier

1. Install stakes 3 feet on center maximum and firmly embed minimum 8 inches in soil. If filter fabric is factory preassembled with support netting, then maximum support spacing is 8 feet. Install wood stakes at a slight angle toward the source of anticipated runoff.

2. Trench in the toe of the fence lines so the downward face of the trenches is flat and perpendicular to direction of flow. V-trench configuration as shown on Drawings may also be used.

3. Lay fabric along edges of trenches in longest practical continuous runs to minimize joints. Make joints only at a support post. Splice with minimum 6-inch overlap and seal securely.

4. Staple filter fabric to stakes at maximum 3 inches on center. Extend fabric minimum 18 inches and maximum 36 inches above natural ground.

5. Backfill and compact trench.

B. Barrier Type 2: Reinforced Filter Fabric Barrier

1. Layout barrier same as for Type 1.

2. Install stakes at 6 feet on center maximum and at each joint in wire fence, firmly embedded 1-foot minimum, and inclined it as for Type 1.

3. Tie wire fence to stakes with wire at 6 inches on center maximum. Overlap joints minimum one bay of mesh.

4. Install trench same as for Type 1.

5. Fasten filter fabric wire fence with tie wires at 3 inches on center maximum.

6. Layout fabric same as for Type 1. Fasten to wire fence with wire ties at 3 inches on center maximum and, if applicable, to stakes above top of wire fence it as for Type 1.

7. Backfill and compact trench.

8. Attach filter fabric to wooden fence stakes spaced a maximum of 6 feet apart or steel fence stakes spaced a maximum of 8 feet apart and embedded a minimum of 12 inches. Install stakes at a slight angle toward source of anticipated runoff.

9. Trench in toe of filter fabric barrier with spade or mechanical trencher so that downward face of trench is flat and perpendicular to direction of flow. A V-trench configuration may also be used. Lay filter fabric along edges of trench. Backfill and compact trench upon completion of Construction.

10. Filter fabric fence shall have a minimum height of 18 inches and a maximum height of 36 inches above natural ground.

11. Cut length of fence to minimize use of joints. When joints are necessary, splice fabric together only at support post with minimum 6 inch overlap and seal securely.

12. When used in swales, ditches or diversions, elevation of barrier at top of filter fabric at flow line location in channel shall be lower than bottom elevation of filter fabric at ends of barrier or top of bank, whichever is less, in order to keep storm water discharge in channel from overtopping bank.

C. Triangular Filter Fabric Barrier Construction Methods

1. Attach filter fabric to wire fencing, 18 inches on each side. Provide a fabric cover and skirt with continuous wrapping of fabric. Skirt should form continuous extension of fabric on upstream side of fence.

2. Secure triangular fabric filter barrier in place using one of the following methods:
   a. Toe-in skirt 6 inches with mechanically compacted material;
   b. Weight down skirt with continuous layer of 3-inch to 5-inch graded rock; or
   c. Trench-in entire structure 4 inches.

3. Anchor triangular fabric filter barrier structure and skirt securely in place using 6-inch wire staples on 2-foot centers on both edges and on skirt, or staked using 18-inch by 3/8-inch diameter re-bar with tee ends.

4. Lap fabric filter material by 6 inches to cover segment joints. Fasten joints with galvanized shoat rings.

3.04 DIKE AND SWALE

A. Unless otherwise indicated, maintain minimum dike height of 18 inches, measured from cleared ground at up slope toe to top of dike. Maintain side slopes of 2:1 or flatter.

B. Dike and Swale Stabilization: When shown on the Drawings, place gravel lining 3 inches thick and compacted into the soil or 6 inches thick if truck crossing is expected. Extend gravel lining across bottom and up both sides of swale minimum height of 8 inches vertically, above bottom. Gravel lining on dike side shall extend up the up slope side of dike a minimum height of 8 inches, measured vertically from interface of existing or graded ground and up slope toe of dike, as shown on Drawings.

C. Divert flow from dikes and swales to sediment basins, stabilized outlets, or sediment trapping devices of types and at locations shown on Drawings. Grade dikes and swales as shown on Drawings, or, if not specified, provide positive drainage with maximum grade of 1 percent to outlet or basin.

D. Clear in accordance with Section 2233 – Clearing and Grubbing Compact embankments in accordance with Section 2315 – Roadway Excavation.

E. Carry out excavation for swale construction so that erosion and water pollution is minimal. Minimum depth shall be 1 foot and bottom width shall be 4 feet, with level swale bottom. Excavation slopes shall be 2:1 or flatter. Clear, grub and strip excavation area of vegetation and root material.

3.05 DOWN SPOUT EXTENDER

A. Down spout extender shall have slope of approximately 1 percent. Use pipe diameter of 4 inches or as shown on the Drawings. Place pipe in accordance with Section 2317 - Bedding and Backfill for Utilities.

3.06 PIPE SLOPE DRAIN

A. Compact soil around and under drain entrance section to top of embankment in lifts appropriately sized for method of compaction utilized.

B. Inlet pipe shall have slope of 1 percent or greater. Use pipe diameter as shown on the Drawings.

C. Top of embankment over inlet pipe and embankments directing water to pipe shall be at least 1 foot higher at all points than top of inlet pipe.

D. Pipe shall be secured with hold-down grommets spaced 10 feet on centers.

E. Place riprap apron with a depth equal to pipe diameter with 2:1 side slopes.

3.07 PAVED FLUME

A. Compact soil around and under the entrance section to top of the embankment in lifts appropriately sized for method of compaction utilized.

B. Construct subgrade to required elevations. Remove and replace soft sections and unsuitable material. Compact subgrade thoroughly and shape to a smooth, uniform surface.

C. Construct permanent paved flumes in accordance with Drawings.

D. Remove sediment from riprap apron when sediment has accumulated to depth of one foot.

3.08 LEVEL SPREADER

A. Construct level spreader on undisturbed soil and not on fill. Ensure that spreader lip is level for uniform spreading of storm runoff.

B. Maintain at required depth, grade, and cross section as specified on Drawings. Remove sediment deposits as well as projections or other irregularities which will impede normal flow.

3.09 INLET PROTECTION BARRIER

A. Place sandbags for Stage I, Bagged gravel for Stage II and filter fabric barriers at locations shown on the SWP3. Maintain to allow minimal inlet in flow restrictions / blockage during storm event.

3.10 DROP INLET BASKET CONSTRUCTION METHODS

A. Fit inlet insert basket into inlet without gaps around insert at locations shown on the SWP3.

B. Support for inlet insert basket shall consist of fabricated metal as shown on Drawings.

C. Push down and form filter fabric to shape of basket. Use sheet of fabric large enough to be supported by basket frame when holding sediment and extend at least 6 inches past frame. Place inlet grates over basket/frame to serve as fabric anchor.

D. Remove sediment deposit after each storm event and whenever accumulation exceeds 1-inch depth during weekly inspections.

3.11 HAY BALE FENCE CONSTRUCTION METHODS

A. Place bales in row with ends tightly abutting adjacent bales. Place bales with bindings parallel to ground surface.

B. Embed bale in soil a minimum of 4 inches.

C. Securely anchor bales in place with Hay Bale Stakes driven through bales a minimum of 18-inches into ground. Angle first stake in each bale toward previously laid bale to force bales together.

D. Fill gaps between bales with straw to prevent water from channeling between bales. Wedge carefully in order not to separate bales.

E. Replace with new hay bale fence every two months or as required by Project Manager.

3.12 BRUSH BERM CONSTRUCTION METHODS

A. Construct brush berm along contour lines by hand placing method. Do not use machine placement of brush berm.

B. Use woody brush and branches having diameter less than 2-inches with 6-inches overlap. Avoid incorporation of annual weeds and soil into brush berm.

C. Use minimum height of 18-inches measured from top of existing ground at upslope toe to top of berm. Top width shall be 24 inches minimum and side slopes shall be 2:1 or flatter.

D. Embed brush berm into soil a minimum of 4-inches and anchor using wire, nylon or polypropylene rope across berm with a minimum tension of 50 pounds. Tie rope securely to 18-inch x 3/8-inch diameter rebar stakes driven into ground on 4-foot centers on both sides of berm.

3.13 STREET AND SIDEWALK CLEANING

A. Keep areas clean of construction debris and mud carried by construction vehicles and equipment. If necessary, install stabilized construction exits at construction, staging, storage, and disposal areas, following Section 01575-Stabilized Construction Exit.

B. In lieu of or in addition to stabilized construction exits, shovel or sweep pavements as required to keep areas clean. Do not waterhose or sweep debris and mud off street into adjacent areas, except, hose sidewalks during off-peak hours, after sweeping.

3.14 WASTE COLLECTION AREAS

A. Prevent water runoff from passing through waste collection areas, and prevent water runoff from waste collection areas migrating outside collection areas.

3.15 EQUIPMENT MAINTENANCE AND REPAIR

A. Confine maintenance and repair of construction machinery and equipment to areas specifically designated for that purpose, so fuels, lubricants, solvents, and other potential pollutants are not washed directly into receiving streams or storm water conveyance systems. Provide these areas with adequate waste disposal receptacles for liquid and solid waste. Clean and inspect maintenance areas daily.

B. Where designated equipment maintenance areas are not feasible, take precautions during each individual repair or maintenance operation to prevent potential pollutants from washing into streams or conveyance systems. Provide temporary waste disposal receptacles.

3.16 VEHICLE/ EQUIPMENT WASHING AREAS

A. Install wash area (stabilized with coarse aggregate) adjacent to stabilized construction access, as required to prevent mud and dirt run-off. Release wash water into drainage swales or inlets protected by erosion and sediment controls. Build wash areas following Section 01575- Stabilized Construction access. Install gravel or rock base beneath wash areas.

B. Wash vehicles only at designated wash areas. Do not wash vehicles such as concrete delivery trucks or dump trucks and other construction equipment at locations where runoff flows directly into waterways or storm water conveyance systems.

C. Locate wash areas to spread out and evaporate or infiltrate wash water directly into ground, or collect runoff in temporary holding or seepage basins.

3.17 WATER RUNOFF AND EROSION CONTROL

A. Control surface water, runoff, subsurface water, and water from excavations and structures to prevent damage to the Work, the site, or adjoining properties. Follow environment requirements.

B. Control fill, grading and ditching to direct water away from excavations, pits, tunnels, and other construction areas, and to direct drainage to proper runoff courses to prevent erosion, sedimentation or damage.

C. Provide, operate, and maintain equipment and facilities of adequate size to control surface water.

D. Retain existing drainage patterns external to the site by constructing temporary earth berms, sedimentation basins, retaining areas, and temporary ground cover as required to control conditions.

E. Plan and execute construction and earth work to control surface drainage from cuts and fills, and from borrow and waste disposal areas, to prevent erosion and sedimentation.

1. Hold area of bare soil exposed at one time to a minimum.

2. Provide temporary controls such as berms, dikes, and drains.

F. Construct fill and waste areas by selective placement to eliminate surface silts or clays which will erode.

G. Inspect earthwork periodically to detect start of erosion. Immediately apply corrective measures as required to control erosion.

H. Dispose of sediments offsite, not in or adjacent to waterways or floodplains, nor allow sediments to flush into streams or drainage ways. Assume responsibility for offsite disposal location.

I. Unless otherwise indicated, compact embankments, excavations, and trenches by mechanically blading, tamping, and rolling soil in maximum of 8-inch layers. Provide compaction density at minimum 90 percent Standard Proctor ASTM D-698-78 density. Make at least one test per 500 cubic yards of embankment.

J. Prohibit equipment and vehicles from maneuver on areas outside of dedicated rights-of-way and easements for construction. Immediately repair damage to erosion and sedimentation control systems caused by construction traffic.

K. Do not damage existing trees intended to remain.

3.18 REMOVAL OF CONTROLS

A. Remove erosion and sediment controls when the site is finally stabilized or as directed by Project Manager.

B. Dispose of sediments and waste products following Section 01505-Temporary Facilities.

END OF SECTION

Section 01575

STABILIZED CONSTRUCTION ACCESS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Installation and removal of erosion and sediment control for stabilized construction access used during construction and prior to final development of site, as shown in City of Houston Standard Construction details, DWG No. 01571-01.

1.02 MEASUREMENT AND PAYMENT

A. Unit Price Contracts. If Contract is Unit Price Contract, payment for work in this Section will be based on the following:

1. Stabilized construction roads, parking areas, access and wash areas: per square yard of aggregate/recycled concrete without reinforcing placed in 8-inch layers. No separate payment will be made for street cleaning necessary to meet TPDES requirements. Include cost of work for street cleaning under related Specification section.

B. Stipulated Price (Lump Sum) Contracts. If the Contract is a Stipulated Price Contract, include payment for work under this Section in the total Stipulated Price.

1.03 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. Submit manufacturers catalog sheets and other Product Data on geotextile fabric.

C. Submit sieve analysis of aggregates conforming to requirements of this Specification.

1.04 REFERENCES

A. ASTM D 4632 - Standard Test Method for Grab Breaking Load and Elongation of Geotextiles.

B. Storm Water Quality Management Handbook For Construction Activities prepared by the City of Houston, Harris County and Harris County Flood Control District.

PART 2 PRODUCTS

2.01 GEOTEXTILE FABRIC

A. Provide woven or non-woven geotextile fabric made of polypropylene, polyethylene, ethylene, or polyamide material.

B. Geotextile fabric: Minimum grab strength of 200 lbs in any principal direction (ASTM D-4632) and equivalent opening size between 50 and 140.

C. Geotextile and threads: Resistant to chemical attack, mildew, and rot and contain ultraviolet ray inhibitors and stabilizers to provide minimum of six months of expected usable life at temperature range of 0 to 120 degrees F.

D. Representative Manufacturers: Mirafi, Inc. or equal.

2.02 COARSE AGGREGATES

A. Coarse aggregate: Crushed stone, gravel, crushed blast furnace slag, or combination of these materials. Aggregate shall be composed of clean, hard, durable materials free from adherent coatings of, salt, alkali, dirt, clay, loam, shale, soft or flaky materials, or organic and injurious matter.

B. Coarse aggregates to consist of open graded rock 2" to 8" in size.

PART 3 EXECUTION

3.01 PREPARATION AND INSTALLATION

A. Provide stabilized construction roads and access at construction, staging, parking, storage,
and disposal areas to keep street clean of mud carried by construction vehicles and equipment. Construct erosion and sediment controls in accordance with Drawings and Specification requirements.

B. Do not clear grub or rough cut until erosion and sediment control systems are in place, unless approved by Project Manager to allow soil testing and surveying.

C. Maintain existing construction site erosion and sediment control systems until acceptance of the Work or until removal of existing systems is approved by Project Manager.

D. Regularly inspect, repair or replace components of stabilized construction access. Unless otherwise directed, maintain stabilized construction roads and

access until the City accepts the Work. Remove stabilized construction roads and access promptly when directed by Project Manager. Discard removed materials off-site.

E. Remove and dispose of sediment deposits at designated spoil site for Project. If a spoil site is not designated on Drawings, dispose of sediment off-site at a location not in or adjacent to stream or flood plain. Assume responsibility for off-site disposal.

F. Spread compacted and stabilized sediment evenly throughout site. Do not allow sediment to flush into streams or drainage ways. Dispose of contaminated sediment in accordance with existing federal, state, and local rules and regulations.

G. Prohibit equipment and vehicles from maneuvering on areas outside of dedicated rights-of-way and easements for construction. Immediately repair damage to erosion and sediment control systems caused by construction traffic.

H. Conduct construction operations in conformance with erosion control requirements of Specification 01570 – Storm Water Pollution Control.

3.02 CONSTRUCTION MAINTENANCE

A. Provide stabilized access roads, subdivision roads, parking areas, and other on-site vehicle transportation routes where shown on Drawings.

B. Provide stabilized construction access and vehicle washing areas, when approved by Project Manager, of sizes and at locations shown on Drawings or as specified in this Section.

C. Clean tires to remove sediment on vehicles leaving construction areas prior to entering public right-of-ways. Construct wash areas needed to remove sediment. Release wash water into drainage swales or inlets protected by erosion and sediment control measures.

D. Details for stabilized construction access are shown on Drawings. Construct other stabilized areas to same requirements. Maintain minimum roadway widths of 14 feet for one-way traffic and 20 feet for two-way traffic and of sufficient width to allow ingress and egress. Place geotextile fabric as a permeable separator to prevent mixing of coarse aggregate with underlaying soil. Limit exposure of geotextile fabric to elements between laydown and cover to a maximum 14 days to minimize potential damage.

E. Grade roads and parking areas to provide sufficient drainage away from stabilized areas. Use sandbags, gravel, boards, or similar materials to prevent sediment from entering public right-of-ways, waterways or

storm water conveyance systems.

F. Inspect and maintain stabilized areas daily. Provide periodic top dressing with additional coarse aggregates to maintain required depth. Repair and clean out damaged control systems used to trap sediment. Immediately remove spilled, dropped, washed, or tracked sediment from public right-of-ways.

G. Maintain lengths of stabilized areas as shown on Drawings or a minimum of 50 feet. Maintain a minimum thickness of 8 inches. Maintain minimum widths at all points of ingress or egress.

H. Stabilize other areas with the same thickness, and width of coarse aggregate required for stabilized construction access, except where shown otherwise on Drawings.

I. Stabilized areas may be widened or lengthened to accommodate truck washing areas when authorized by Project Manager.

J. Clean street daily before end of workday. When excess sediments have tracked onto streets, Project Manager may direct Contractor to clean street as often as necessary. Remove and legally dispose of sediments.

K. Use other erosion and sediment control measures to prevent sediment runoff during rain periods and non-working hours and when storm discharges are expected.

END OF SECTION

Section 01576

WASTE MATERIAL DISPOSAL

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Disposal of waste material and salvageable material.

1.02 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. Submit copy of approved "Development Permit", as defined in Chapter 19 of Flood Plain Ordinance (City Ordinance Number 81-914 and Number 85-1705), prior to disposal of excess material in areas designated as being in "100-year Flood Hazard Area" within the City. Contact the City of Houston Flood Plain Manager, 3300 Main Street, at (713) 525-7605 for flood plain information.

C. Obtain and submit disposal permits for proposed disposal sites, if required by local ordinances.

D. Submit copy of written permission from property owner, with description of property, prior to disposal of excess material adjacent to Project. Submit written and signed release from property owner upon completion of disposal work.

E. Describe waste materials expected to be stored on-site and a description of controls to reduce Pollutants from these materials, including storage practices to minimize exposure of materials to storm water; and spill prevention and response measures in the Project's Storm Water Pollution Prevention Plan (SWPPP). Refer to Section 01410 – TPDES Requirements.

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION

3.01 SALVAGEABLE MATERIAL

A. Excavated Material: When indicated on Drawings, load, haul, and deposit excavated material at location or locations shown on Drawings outside limits of Project.

B. Base, Surface, and Bedding Material: Load shell, gravel, bituminous, or other base and surfacing material designated for salvage into City trucks.

C. Pipe Culvert: Load culverts designated for salvage into City trucks.

D. Other Salvageable Materials: Conform to requirements of individual Specification Sections.

E. Coordinate loading of salvageable material on City trucks with Project Manager.

3.02 EXCESS MATERIAL

A. Remove and legally dispose of vegetation, rubble, broken concrete, debris, asphaltic concrete pavement, excess soil, and other materials not designated for salvage from job site.

B. Excess soil may be deposited on private property adjacent to Project when written permission is obtained from property owner. See Paragraph 1.02 D above.

C. Verify flood plain status of any proposed disposal site. Do not dispose of excavated materials in area designated as within 100-year Flood Hazard Area unless "Development Permit" has been obtained. Remove excess material placed in "100-year Flood Hazard Area" within the City, without "Development Permit", at no additional cost to the City.

D. Remove waste materials from site daily, in order to maintain site in neat and orderly condition.

END OF SECTION

Section 01578

CONTROL OF GROUND AND SURFACE WATER

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Dewatering, depressurizing, draining, and maintaining trenches, shaft excavations, structural excavations and foundation beds in stable condition, and controlling ground water conditions for tunnel excavations.

B. Protecting work against surface runoff and rising floodwaters.

C. Trapping suspended sediment in the discharge form the surface and ground water control systems.

1.02 MEASUREMENT AND PAYMENT

A. UNIT PRICES

1. When noted, dewatering of trench or excavation during course of project shall be measured per linear foot and paid for at contract unit prices for dewatering, when directed to perform such work by Project Manager. Dewatering must be fully detailed in submittal and submittal must be approved prior to performing dewatering work before payment will be made for dewatering. No payment will be made for work unless directed to perform work by Project Manager.

2. Presence of a pump on project does not constitute dewatering for payment under bid item "Ground Water Control for Open Cut Construction."

3. Dewatering required during course of project to lower water table for other utility installation less than 24 inches in diameter, construction of structures, removal of standing water, surface drainage seepage, or to protect against rising waters or floods shall be considered incidental to Work unless otherwise noted.

4. No separate payment will be made for groundwater control associated with augering, tunnels or casing. Include cost in unit price for augering.

5. Refer to Section 01270 - Measurement and Payment for unit price procedures.

B. Stipulated Price (Lump Sum) Contract. If the Contract is a Stipulated Price Contract, include payment for work under this section in the total Stipulated

Price.

1.03 REFERENCES

A. ASTM D 698 - Standard Test Methods for Laboratory Compaction of Soils Using Standard Effort (12,400 ft-lbf/ft3 (600kN-m/m3)

B. Federal Regulations, 29 CFR Part 1926, Standards-Excavation, Occupational Safety and Health Administration (OSHA)

C. Storm Water Management Handbook for Construction Activities prepared by City of Houston, Harris County and Harris County Flood Control District.

1.04 DEFINITIONS

A. Ground water control system: system used to dewater and depressurize water-bearing soil layers.

1. Dewatering: lowering the water table and intercepting seepage that would otherwise emerge from slopes or bottoms of excavations, or into tunnels and shafts; and disposing of removed water. Intent of dewatering is to increase stability of tunnel excavations and excavated slopes, prevent dislocation of material from slopes or bottoms of excavations, reduce lateral loads on sheeting and bracing, improve excavating and hauling characteristics of excavated material, prevent failure or heaving of bottom of excavations, and to provide suitable conditions for placement of backfill materials and construction of structures and other installations.

2. Depressurization: includes reduction in piezometric pressure within strata not controlled by dewatering alone, necessary to prevent failure or heaving of excavation bottom or instability of tunnel excavations.

B. Excavation drainage: includes keeping excavations free of surface and seepage water.

C. Surface drainage: includes use of temporary drainage ditches and dikes and installation of temporary culverts and sump pumps with discharge lines necessary to protect Work from any source of surface water.

D. Monitoring facilities for ground water control system: includes piezometers, monitoring wells and flow meters for observing and recording flow rates.

1.05 PERFORMANCE REQUIREMENTS

A. Conduct subsurface investigations to identify groundwater conditions and to

provide parameters for design, installation, and operation of groundwater control systems. Submit proposed method and spacing of readings for review prior to obtaining water level readings.

B. Design ground water control system, compatible with requirements of Federal Regulations 29 CFR Part 1926 and Section 02260 - Trench Safety Systems, to produce following results:

1. Effectively reduce hydrostatic pressure affecting:

   a. Excavations

   b. Tunnel excavation, face stability or seepage into tunnels

2. Develop substantially dry and stable subgrade for subsequent construction operations

3. Preclude damage to adjacent properties, buildings, structures, utilities, installed facilities and other work

4. Prevent loss of fines, seepage, boils, quick condition, or softening of foundation strata

5. Maintain stability of sides and bottom of excavations

C. Provide ground water control systems that include single-stage or multiple-stage well point systems, eductor and ejector-type systems, deep wells, or combinations of these equipment types.

D. Provide drainage of seepage water and surface water, as well as water from other sources entering excavation. Excavation drainage may include placement of drainage materials, crushed stone and filter fabric, together with sump pumping.

E. Provide ditches, berms, pumps and other methods necessary to divert and drain surface water from excavation and other work areas.

F. Locate ground water control and drainage systems so as not to interfere with utilities, construction operations, adjacent properties, or adjacent water wells.

G. Assume sole responsibility for ground water control systems and for any loss or damage resulting from partial or complete failure of protective measures and settlement or resultant damage caused by ground water control operations. Modify ground water control systems or operations if they cause or threaten to cause damage to new construction, existing site improvements, adjacent property, adjacent water wells, or potentially contaminated areas. Repair damage caused by ground water control systems or resulting from

failure of system to protect property as required.

H. Install an adequate number of piezometers installed at proper locations and depths, necessary to provide meaningful observations of conditions affecting excavation, adjacent structures and water wells.

I. Install environmental monitoring wells at proper locations and depths necessary to provide adequate observations of hydrostatic conditions and possible contaminant transport from contamination sources into work area or ground water control system.

1.06 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittals Procedures.

B. Submit Ground Water and Surface Water Control Plan for review by Project Manager prior to start of excavation work. Include the following:

1. Results of subsurface investigations and description of extent and characteristics of water bearing layers subject to ground water control

2. Names of equipment Suppliers and installation Subcontractors

3. Description of proposed ground water control systems indicating arrangement, location, depth and capacities of system components, installation details and criteria and operation and maintenance procedures

4. Description of proposed monitoring facilities indicating depths and locations of piezometers and monitoring wells, monitoring installation details and criteria, type of equipment and instrumentation with pertinent data and characteristics

5. Description of proposed filters including types, sizes, capacities and manufacturer's application recommendations

6. Design calculations demonstrating adequacy of proposed systems for intended applications. Define potential area of influence of ground water control operation near contaminated areas.

7. Operating requirements, including piezometric control elevations for dewatering and depressurization

8. Excavation drainage methods including typical drainage layers, sump pump application and other means

9. Surface water control and drainage installations

10. Proposed methods and locations for disposing of removed water

C. Submit following records upon completion of initial installation:

1. Installation and development reports for well points, eductors, and deep wells

2. Installation reports and baseline readings for piezometers and monitoring wells

3. Baseline analytical test data of water from monitoring wells

4. Initial flow rates

D. Submit the following records weekly during control of ground and surface water operations:

1. Records of flow rates and piezometric elevations obtained during monitoring of dewatering and depressurization. Refer to Paragraph 3.02, Requirements for Eductor, Well Points, or Deep Wells.

2. Maintenance records for ground water control installations, piezometers and monitoring wells

1.07 ENVIRONMENTAL REQUIREMENTS

A. Comply with requirements of agencies having jurisdiction.

B. Comply with Texas Commission on Environmental Quality regulations and Texas Water Well Drillers Association for development, drilling, and abandonment of wells used in dewatering system.

C. Obtain necessary permits from agencies with jurisdiction over use of groundwater and matters affecting well installation, water discharge, and use of existing storm drains and natural water sources. Since review and permitting process may be lengthy, take early action to obtain required approvals.

D. Monitor ground water discharge for contamination while performing pumping in vicinity of potentially contaminated sites.

PART 2 PRODUCTS

2.01 EQUIPMENT AND MATERIALS

A. Select equipment and materials necessary to achieve desired results for dewatering. Selected equipment and materials are subject to review by Project Manager through submittals required in Paragraph 1.06, Submittals.

B. Use experienced contractors, regularly engaged in ground water control system design, installation, and operation, to furnish and install and operate educators, well points, or deep wells, when needed

C. Maintain equipment in good repair and operating condition.

D. Keep sufficient standby equipment and materials available to ensure continuous operation, where required.

E. Portable Sediment Tank System: Standard 55-gallon steel or plastic drums, free of hazardous material contamination.

1. Shop or field fabricate tanks in series with main inlet pipe, inter-tank pipes and discharge pipes, using quantities sufficient to collect sediments from discharge water.

PART 3 EXECUTION

3.01 GROUND WATER CONTROL

A. Perform necessary subsurface investigation to identify water bearing layers, piezometric pressures and soil parameters for design and installation of ground water control systems. Perform pump tests, if necessary to determine draw down characteristics. Present results in the Ground Water and Surface Water Control Plan. submittal

B. Provide labor, material, equipment, techniques and methods to lower, control and handle ground water in manner compatible with construction methods and site conditions. Monitor effectiveness of installed system and its effect on adjacent property.

C. Install, operate, and maintain ground water control systems in accordance with the Ground Water and Surface Water Control Plan. Notify Project Manager in writing of changes made to accommodate field conditions and changes to Work. Provide revised drawings and calculations with notification.

D. Provide continuous system operation, including nights, weekends, and holidays. Arrange appropriate backup if electrical power is primary energy source for dewatering system.

E. Monitor operations to verify systems lower ground water piezometric levels at rate required to maintain dry excavation resulting in stable subgrade for

subsequent construction operations.

F. Depressurize zones where hydrostatic pressures in confined water bearing layers exist below excavations to eliminate risk of uplift or other instability of excavation or installed works. Define allowable piezometric elevations in the Ground Water and Surface Water Control Plan.

G. Removal of ground water control installations.

1. Remove pumping system components and piping when ground water control is no longer required.

2. Remove piezometers, including piezometers installed during design phase investigations and left for Contractor's use, upon completion of testing, as required in accordance with Part 3 of applicable specification.

3. Remove monitoring wells when directed by Project Manager.

4. Grout abandoned well and piezometer holes. Fill piping that is not removed with cement-bentonite grout or cement-sand grout.

H. During backfilling, maintain water level a minimum of 5 feet below prevailing level of backfill. Do not allow the water level to cause uplift pressures in excess of 80 percent of downward pressure produced by weight of structure or backfill in place. Do not allow water levels to rise into cement-stabilized sand until at least 48 hour after placement.

I. Provide uniform pipe diameter for each pipe drain run constructed for dewatering. Remove pipe drains when no longer required. If pipe removal is impractical, grout connections at 50-foot intervals and fill pipe with cement-bentonite grout or cement-sand grout after removal from service.

J. The extent of ground water control for structures with permanent perforated underground drainage systems may be reduced, for units designed to withstand hydrostatic uplift pressure. Provide a means to drain affected portions of underground systems, including standby equipment. Maintain drainage systems during construction operations.

K. Remove systems upon completion of construction or when dewatering and control of surface or ground water is no longer required.

L. Compact backfill to not less than 95 percent of maximum dry density in accordance with ASTM D 698.

M. Foundation Slab: Maintain saturation line at least 3 feet below lowest elevations where concrete is to be placed. Drain foundations in areas where

concrete is to be placed before placing reinforcing steel. Keep free from water for 3 days after concrete is placed.

3.02 REQUIREMENTS FOR EDUCTOR, WELL POINTS, OR DEEP WELLS

A. For aboveground piping in ground water control system, include a 12-inch minimum length of clear, transparent piping between each eductor well or well point and discharge header to allow visual monitoring of discharge from each installation.

B. Install sufficient piezometers or monitoring wells to show that trench or shaft excavations in water bearing materials are pre-drained prior to excavation. Provide separate piezometers for monitoring of dewatering and for monitoring of depressurization. Install piezometers and monitoring wells for tunneling as appropriate for selected method of work.

C. Install piezometers or monitoring wells at least one week in advance of the start of associated excavation.

D. Dewatering may be omitted for portions of under drains or other excavations, where auger borings and piezometers or monitoring wells show that soil is pre-drained by existing systems and that ground water control plan criteria are satisfied.

E. Replace installations that produce noticeable amounts of sediments after development.

F. Provide additional ground water control installations, or change method of control if, ground water control plan does not provide satisfactory results based on performance criteria defined by plan and by specifications. Submit revised plan according to Paragraph 1.06B.

3.03 SEDIMENT TRAPS

A. Install sediment tank as shown on approved plan.

B. Inspect daily and clean out tank when one-third of sediment tank is filled with sediment.

3.04 SEDIMENT SUMP PIT

A. Install sediment sump pits as shown on approved plan.

B. Construct standpipe by perforating 12 inch to 24-inch diameter corrugated metal or PVC pipe.

C. Extend standpipe 12 inches to 18 inches above lip of pit.

D. Convey discharge of water pumped from standpipe to sediment trapping device.

E. Fill sites of sump pits, compact to density of surrounding soil and stabilize surface when construction is complete.

3.05 EXCAVATION DRAINAGE

A. Use excavation drainage methods if well-drained conditions can be achieved. Excavation drainage may consist of layers of crushed stone and filter fabric, and sump pumping, in combination with sufficient ground water control wells to maintain stable excavation and backfill conditions.

3.06 MAINTENANCE AND OBSERVATION

A. Conduct daily maintenance and observation of piezometers or monitoring wells while ground water control installations or excavation drainage is operating at the site, or water is seeping into tunnels, and maintain systems in good operating condition.

B. Replace damaged and destroyed piezometers or monitoring wells with new piezometers or wells as necessary to meet observation schedules.

C. Cut off piezometers or monitoring wells in excavation areas where piping is exposed, only as necessary to perform observation as excavation proceeds. Continue to maintain and make specified observations

D. Remove and grout piezometers inside or outside of excavation area when ground water control operations are complete. Remove and grout monitoring wells when directed by Project Manager.

3.07 MONITORING AND RECORDING

A. Monitor and record average flow rate of operation for each deep well, or for each wellpoint or eductor header used in dewatering system. Also, monitor and record water level and ground water recovery. Record observations daily until steady conditions are achieved and twice weekly thereafter.

B. Observe and record elevation of water level daily as long as ground water control system is in operation, and weekly thereafter until Work is completed or piezometers or wells are removed, except when Project Manager determines more frequent monitoring and recording are required. Comply with Project Manager's direction for increased monitoring and recording and

take measures necessary to ensure effective dewatering for intended purpose.

3.08 SURFACE WATER CONTROL

A. Intercept surface water and divert it away from excavations through use of dikes, ditches, curb walls, pipes, sumps or other approved means. Requirement includes temporary works required to protect adjoining properties from surface drainage caused by construction operations.

B. Divert surface water and seepage water into sumps and pump it into drainage channels or storm drains, when approved by agencies having jurisdiction. Provide settling basins when required by agencies.

END OF SECTION

Section 01580

PROJECT IDENTIFICATION SIGNS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Project identification sign description.

B. Project sign installation.

C. Maintenance and removal of Project sign.

1.02 SYSTEM DESCRIPTION

A. Sign Construction: Construct signs of new materials in accordance with Standard Detail provided at the Pre-construction Conference.

B. Appearance: Maintain signs to present a clean and neat look throughout Contract duration.

C. Sign Manufacturer: Experienced professional sign company.

D. Sign Placement: At locations shown in Drawings unless otherwise specified by Project Manager at pre-construction meeting.

1. Provide one sign at each end of a linear Project involving paving, overlay, sewer line, storm drainage, or water main construction located in rights-of-ways.

2. Provide one sign for site or building construction Contracts

3. Provide one sign at each site for Contracts with multiple sites.

4. Sign Relocation: As work progresses, relocate signs if directed by Project Manager in writing. Include cost for one relocation of post-mounted signs in Contract Price. Subsequent relocations, if directed by Project Manager in writing, will be subject to Change Order.

E. Skid-mounted signs: Use for projects with noncontiguous locations where work progresses from one location to another. Design skid structure to withstand a 60 mile-per-hour wind load to the face or back of sign using stakes, straps, or ballast. Contractor shall be responsible for security of signs at each site.

1.03 SUBMITTALS

A. Submit Shop Drawings under provisions of Section 01330 - Submittal Procedures.

B. Show content, layout, lettering style, lettering size, and colors. Make sign and lettering to scale, clearly indicating condensed lettering, if used.

PART 2 P R O D U C T S

2.01 SIGN MATERIALS

A. Structure and Framing: Use new sign materials.

1. Sign Posts: 4-inch by 4-inch pressure treated wood posts, 9 feet long for skid mounting and 12 feet long minimum for in-ground mounting.

2. Skid Bracing: 2-inch by 4-inch wood framing material.

3. Skid Members: 2-inch by 6-inch wood framing material.

4. Fasteners:
   a. Galvanized steel.
   b. Attach sign to posts with 1/2-inch by 5-1/2 inch button head carriage bolts and secure with nuts and flat head washers.
   c. Cover button heads with white reflective film or paint to match sign background.
   d. Use metal brackets and braces and 3/4-inch wood screws to attach sign header.

B. Sign and Sign Header: 3/4-inch thick marine plywood. Use 4-foot by 8 -foot sheet for the sign and a single piece for the header to minimize joints. Do not piece wood sheets to fabricate sign face.

C. Paint and Primers: White industrial grade, fast-drying, oil-based paint with gloss finish for structural and framing members, sign, and sign header material surfaces. Paint all sign surfaces prior to adding adhesive applications.

D. Colors:

1. Sign Background: Reflective white 3M Scotchlite Engineer Grade, Pressure Sensitive Sheeting (White), or approved equal.

2. Border: For red border around area, which designates project name and project amount, use reflective red 3M Scotchlite Engineer Grade, Pressure Sensitive Sheeting (Red), or approved equal.

3. Sign Film: 3M Scotchcal Pressure Sensitive Films, or approved equal for legends, symbols, lettering, and artwork. Match colors to 3M Scotchcal Pressure Sensitive Films.

a.	Lettering Below Seal:	Black
b.	Lettering Above Project Name:	Vivid Blue
c.	Lettering on Blue Background:	White
d.	Background Behind Project Name:	Vivid Blue

E. City Seal: Project Manager will provide City seals to Contractor, as needed.

2.02 SIGN LAYOUT

A. Lettering:

1. Style, Size, and Spacing: Helvetica Regular lettering.

2. Condensed Style: Text may be condensed if needed to maintain sign composition.

B. Composition:

1. Lines with Standard Text
   a. Top line shall read "BUILDING TOGETHER FOR THE FUTURE".
   b. Use lower left below City Seal to list names and titles for Mayor, Controller and Council Members. Place as shown on Drawings with indicated size and spacing.
   c. Center telephone number of the Customer Response Center, "311", near the bottom of the area with the blue background.

2. Lines with Variable Text. Use blue background space for Project name and dollar amount.
   a. Project Manager will provide Project name and dollar amount of Project for preparation of sign. Center name on one or two lines, and dollar amount immediately below Project name, in area with blue background. Use condensed lettering if necessary.

2.03 LAYOUT AND COMPOSITION FOR HEADER

A. City of Houston Seal:
   1. A space of approximately 24 inches in diameter is provided for the City seal, the top 6 inches of which extends above the sign on the sign header.

   2. Construct sign header of same material as sign face. Cut material to match curve of the City seal.

   3. Project Manager will provide the seal to be affixed to the sign by sign maker.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install Project identification signs within seven days after Date of Commencement of the Work.

B. Erect signs at locations shown in Drawings unless otherwise designated by Project Manager at pre-construction meeting. Position sign so it is fully visible and readable to general public.

C. Erect sign level and plumb.

D. If mounted on posts, sink posts 3 to 4 feet below grade and stabilize posts to minimize lateral motion. Leave a minimum of 8 feet of post above existing grade for mounting of sign.

E. Erect sign so that top edge of sign is at a nominal 8 feet above existing grade.

3.02 MAINTENANCE AND REMOVAL

A. Keep signs and supports clean. Repair deterioration and damage.

B. Remove signs, framing, supports, and foundations to a depth of at least 2 feet upon completion of Project. Restore area to a condition equal to or better than before construction.

END OF SECTION

PROJECT No.: (FILE NO:)	**CONTRACT No.:**	**REVIEWED BY:**

***INSTRUCTIONS TO SIGN MAKER** (LIST COMPANY NAME):		
QTY.	**ACTION ITEMS:**	
	Make new sign(s)	
	Follow City standards attached	
	Provide submittal (drawing) to the City for project sign showing content, layout, lettering style, lettering size, and colors	
VARIABLE TEXT		
Line 1	Project Name:	
Line 2	Project Amount (rounded to nearest $1000):	
ATTACHMENTS INCLUDED		
QTY.	**SEALS / LOGOS**	
	City of Houston - 24" diameter	
	STANDARDS	
	Standard Specification Section 01580 - Project Identification Signs	
	Standard Detail 01580-02 Construction Sign	

(Instructions on reverse.)

INSTRUCTIONS

Contractor produces this form. Contractor shall insert the information and provide the form to the sign maker with Contractor's purchase order.

List PROJECT No., (FILE No.), CONTRACT No., and name of City's Project Manager REVIEWED BY.

INSTRUCTIONS TO SIGN MAKER:

- Give COMPANY NAME of sign maker.
- Indicate QUANTITY of new signs to be made.
- Direction for sign maker to follow City Standards in making signs.
- Require submittals from sign maker, who provides Shop Drawing of Project sign showing content, layout, lettering style, lettering size, and colors.

VARIABLE TEXT:

- Give PROJECT NAME. Write it out in all caps and suggest line break. Lines are required.
- Give Project amount to be listed on sign. Round off to nearest $1000.

ATTACHMENTS INCLUDED:

- **Seals**

  City provides the quantity of City seals required, one for each Project sign.

- **Standards**

  Contractor provides set of Standards to sign maker, including (Specification Section 01580 - Project Identification Signs, and Standard Detail No. 01580-02 - Construction Sign.

Section 01581

EXCAVATION IN PUBLIC WAY PERMIT SIGNS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Project sign installation.

B. Maintenance and removal of Project sign.

1.02 SYSTEM DESCRIPTION

A. Sign Construction: Construct signs of new materials.

B. Appearance: Maintain signs to present a clean and neat look throughout the Contract duration.

C. Sign Placement: Place signs at each street entrance to street cut excavation.

1.03 SUBMITTALS

A. Submit Shop Drawings under provisions of Section 01330 - Submittal Procedures.

B. Show content, layout, lettering style, lettering size and colors. Make sign and lettering to scale, clearly indicating condensed lettering, if used.

PART 2 PRODUCTS

2.01 SIGN LAYOUT

A. Conform to Texas Manual on Uniform Traffic Control Devices. Minimum size: 36 inches by 36 inches.

B. Lettering: Uppercase Helvetica Regular lettering.

C. Composition: Include on sign copy of street cut permit, title "City of Houston", contracting department's name, address, and emergency telephone number and Contractor's name. Project Manager will provide department name, address, and emergency telephone number for preparation of sign.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install Project signs before commencement of pavement excavation in Public Way.

B. Position sign so it is fully visible and readable to general public.

C. Erect sign level and plumb.

D. Erect sign so that top edge of sign is at a nominal 8 feet above existing grade.

3.02 MAINTENANCE AND REMOVAL

A. Keep signs and supports clean. Repair deterioration and damage.

B. Remove signs, framing, supports and foundations to depth of at least 2 feet upon completion of the Work. Restore area to condition equal to or better than before construction.

END OF SECTION

Section 01610

BASIC PRODUCT REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Requirements for transportation, delivery, handling, and storage of Products.

1.02 PRODUCTS

A. Products: Defined in Document 00700 – General Conditions. Does not include machinery and equipment used for preparation, fabrication, conveying and erection of the Work. Products may also include existing materials or components designated for reuse.

B. For material and equipment specifically indicated or specified to be reused in the work:

1. Use special care in removal, handling, storage and reinstallation, to assure proper function in completed work.

2. Arrange for transportation, storage and handling of products which require off-site storage, restoration or renovation. Include cost in unit price for related items.

C. When contract documents require that installation of work comply with manufacturer's printed Instructions, obtain and distribute copies of such instructions to parties involved in installation, including two copies to Project Manager. Maintain one set of complete instructions at job site during installation until completion.

D. Provide Products from the fewest number of manufacturers as practical, in order to simplify spare parts inventory and to allow for maximum interchangeability of components. For multiple components of the same size, type or application, use the same make and model of component throughout the Work.

1.03 TRANSPORTATION

A. Make arrangements for transportation, delivery, and handling of Products required for timely completion of the Work.

B. Transport and handle Products in accordance with manufacturer's instructions.

C. Consign and address shipping documents to proper party giving name of the Project and its complete street address. Shipments shall be delivered to

Contractor.

1.04 DELIVERY

A. Arrange deliveries of Products to accommodate short-term site completion schedules and in ample time to facilitate inspection prior to Installation. Avoid deliveries that cause lengthy storage or overburden of limit storage space.

B. Coordinate deliveries to avoid conflict with the Work and conditions at the site and to accommodate the following:

1. Work of other contractors or the City.

2. Limitations of storage space.

3. Availability of equipment and personnel for handling Products.

4. The City's use of premises.

C. Have Products delivered to the site in manufacturer's original, unopened, labeled containers.

D. Immediately upon delivery, inspect shipment to assure:

1. Product complies with requirements of the Contract.

2. Quantities are correct.

3. Containers and packages are intact; labels are legible.

4. Products are properly protected and undamaged.

1.05 PRODUCT HANDLING

A. Coordinate off-loading of Products delivered to the site. If necessary during construction, move and relocate stored Products at no additional cost to the City.

B. Provide equipment and personnel necessary to handle Products, including those provided by the City, by methods to prevent damage to Products or packaging.

C. Provide additional protection during handling as necessary to prevent breaking, scraping, marring, or otherwise damaging Products or surrounding areas.

D. Handle Products by methods to prevent over-bending or overstressing.

E. Lift heavy components only at designated lifting points.

F. Handle Products in accordance with manufacturer's recommendations.

G. Do not drop, roll, or skid Products off delivery vehicles. Hand-carry or use Suitable materials handling equipment.

1.06 STORAGAE OF PRODUCTS

A. Store and protect Products in accordance with manufacturer's recommendations and requirements of these Specifications.

B. Make necessary provisions for safe storage of Products. Place Products so as to prevent damage to any part of the Work or existing facilities and to maintain free access at all times to all parts of the Work and to utility service company installations in the vicinity of the Work. Keep Products neatly and compactly stored in locations that will cause minimum inconvenience to other contractors, public travel, adjoining owners, tenants, and occupants. Arrange storage in a manner so as to provide easy access for inspection.

C. Restrict storage to areas available on the site for storage of Products as shown on Drawings or approved by Project Manager.

D. Provide off-site storage and protection when on-site storage is not adequate. Provide addresses of, and access to, off-site storage locations for inspection by Project Manager.

E. Do not use lawns, grass plots, or other private property for storage purposes without written permission of owner or other person in possession or control of premises.

F. Protect stored Products against loss or damage.

G. Store in manufacturers' unopened containers.

H. Neatly, safely, and compactly stack Products delivered and stored along the line of the Work to avoid inconvenience and damage to property owners and general public, and maintain at least 3 feet clearance around fire hydrants. Keep public, private driveways and street crossings open.

I. Repair or replace damaged lawns, sidewalks, streets or other improvements to satisfaction of Project Manager. Total length that Products may be distributed along route of construction at one time is 1000 linear feet, unless otherwise approved in writing by Project Manager.

PART 2 P R O D U C T S - Not Used

PART 3 EXECUTION - Not Used

END OF SECTION

Section 01630

PRODUCT SUBSTITUTION PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Options for making Product or process selections.

B. Procedures for proposing equivalent Products or processes, including pre-approved, pre-qualified, and approved Products or processes.

1.02 DEFINITIONS

A. Product: As defined in Document 00700 – General Conditions. Product does not include machinery and equipment used for production, fabrication, conveying, and erection of the Work. Products may also include existing materials or components designated for reuse.

B. Process: Any proprietary system or method for installing system components resulting in an integral, functioning part of the Work. For this Section, the word Products includes Processes.

1.03 SELECTION OPTIONS

A. Pre-approved Products: Construction products of certain manufacturers or Suppliers designated in Specifications as "pre-approved." The City maintains a list of pre-approved products. Pre-approved Products for this Project are designated as pre-approved in Specifications. Products of other manufacturers or suppliers are not acceptable for this Project and will not be considered under the submittal process for approving alternate products.

B. Pre-qualified Products: Construction products of certain manufacturers or Suppliers designated in Specifications as "pre-qualified." Pre-qualified Products for this Project are designated as pre-qualified in Specifications. Products of other manufacturers or suppliers are not acceptable for this Project and will not be considered under the submittal process for approving alternate products.

C. Approved Products: Construction products of certain manufacturers or Suppliers designated in Specifications followed by words "or approved equal." Approval of alternate products not listed in Specifications may be obtained through provisions for product options and substitutions in Document 00700 - General Conditions, and by following submittal procedures specified in

Section 01330- Submittal Procedures. The procedure for approval of alternate products is not applicable to pre-approved or pre-qualified products.

D. Product Compatibility: To the maximum extent possible, provide Products that are of the same type or function from a single manufacturer, make, or source. Where more than one choice is available, select Product that is compatible with other Products already selected, specified, or in use by the City.

1.04 CONTRACTOR'S RESPONSIBILITY

A. Responsibility related to Product options and substitutions is defined in Document 00700 - General Conditions.

B. Furnish information Project Manager deems necessary to judge equivalency of alternate Product.

C. Pay for laboratory testing, as well as any other review or examination costs, needed to establish equivalency between products in order to obtain information upon which Project Manager can base a decision.

D. If Project Manager determines alternate product is not equal to that named in Specifications, Furnish one of the specified Products.

1.05 CITY REVIEW

A. Use alternate Products only when approved in writing by Project Manager. Project Manager's determination regarding acceptance of proposed alternate Product is final.

B. Alternate Products shall be accepted if Products are judged by Project Manager to be equivalent to specified Product or to offer substantial benefit to the City.

C. The City retains the right to accept any Product deemed advantageous to the City, and similarly, to reject any product deemed not beneficial to City.

1.06 SUBSTITUTION PROCEDURE

A. Collect and assemble technical information applicable to the proposed Product to aid in determining equivalency as related to the approved Product specified.

B. Submit a written request for a construction Product to be considered as an alternate Product.

C. Submit Product information after the effective date of the Contract and within the time period allowed for substitution submittals given in Document 00700 - General Conditions. After the submittal period has expired, requests for alternate Products shall be considered only when specified Product becomes unavailable because of conditions beyond Contractor's control.

D. Submit five copies of each request for alternate Product approval. Include the following information:

1. Complete data substantiating compliance of proposed substitution with the Contract.

2. For Products:
   a. Product identification, including manufacturer's name and address.
   b. Manufacturer's literature with Product description, performance and test data, and reference standards.
   c. Samples, as applicable.
   d. Name and address of similar projects on which Product was used and date of installation. Include names of Owner, design consultant, and installing contractor.

3. For construction methods:
   a. Detailed description of proposed method.
   b. Drawings illustrating methods.

4. Itemized comparison of proposed substitution with Product or method specified.

5. Data relating to changes in Construction Schedule.

6. Relation to separate contracts, if any.

7. Accurate cost data on proposed substitution in comparison with Product or method specified.

8. Other information requested by Project Manager.

E. Approved alternate Products will be subject to the same review process as the specified Product would have been for Shop Drawings, Product Data, and Samples.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01725

FIELD SURVEYING

PART 1 GENERAL

1.01 QUALITY CONTROL

A. Conform to State of Texas laws for surveys requiring licensed surveyors. Employ a surveyor acceptable to Project Manager if required by the Contract.

1.02 MEASUREMENT AND PAYMENT

A. UNIT PRICES

1. No separate payment will be made for field surveying. Include cost in unit price for related items.

1.03 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. Submit name, address, and telephone number of Surveyor to Project Manager before starting survey work.

C. Submit documentation verifying accuracy of survey work on request.

D. Submit certificate signed by Surveyor, that elevations and locations of the Work are in conformance with the Contract.

1.04 PROJECT RECORD DOCUMENTS

A. Maintain a complete and accurate log of control and survey work as it progresses.

B. Prepare a certified survey setting forth dimensions, locations, angles, and elevations of construction and site work upon completion of foundation walls and major site improvements.

C. Submit record documents under provisions of Section 01785 - Project Record Documents.

1.05 EXAMINATION

A. Verify locations of survey control points prior to starting the Work.

B. Notify Project Manager immediately if any discrepancies are discovered.

1.06 SURVEY REFERENCE POINTS

A. The City will establish survey control datum as provided in Document 00700 - General Conditions and as indicated on Drawings. Inform Project Manager in Advance of time horizontal and vertical control points will be established so

verification deemed necessary by Project Manager may be done with minimum inconvenience to the City or Contractor.

B. Locate and protect survey control points prior to starting site work; preserve permanent reference points during construction.

C. Notify Project Manager a minimum of 48 hours before relocation of reference points is needed due to changes in grades or other reasons.

D. Promptly report loss or destruction of reference points to Project Manager.

E. Reimburse the City for cost of reestablishment of permanent reference points disturbed by construction operations.

1.07 SURVEY REQUIREMENTS

A. Utilize recognized engineering survey practices.

B. Establish a minimum of two permanent benchmarks on site, referenced to established control points. Record horizontal and vertical location data on Project record documents.

C. Establish elevations, lines and levels to provide quantities required for measurement and payment and for appropriate controls for the Work. Locate and lay out the following with appropriate instruments:

1. Site improvements including grading, fill and topsoil placement, utilities, and footings and slabs

2. Grid or axis for structures

3. Building foundation, column locations, and ground floor elevations

D. Periodically verify layouts.

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION - Not Used

END OF SECTION

Section 01731

CUTTING AND PATCHING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Cutting, patching and fitting of the Work or work under construction. Coordinating Installation or connection of the Work to existing facilities, or uncovering work for access, inspection or testing and related submittals.

1.02 MEASUREMENT AND PAYMENT

A. UNIT PRICES

1. No separate payment will be made for cutting and patching. Include cost in unit price for related items.

1.03 CUTTING AND PATCHING

A. Perform activities to avoid interference with facility operations and work of others in accordance with Document 00700 - General Conditions of Contract.

B. Execute cutting and patching, including excavation, backfill and fitting to:

1. Remove and replace defective work or work not conforming to Drawings and Specifications;

2. Take samples of installed work as required for testing;

3. Remove construction required to provide for specified alterations or additions to existing work;

4. Uncover work to allow inspection or reinspection by Project Manager or regulatory agencies having jurisdiction;

5. Connect uninstalled work to completed work in proper sequence;

6. Remove or relocate existing utilities and pipes that obstruct work;

7. Make connections or alterations to existing or new facilities;

8. Provide openings, channels, chases and flues and cut, patch, and finish; if required; or

9. Provide protection for other portions of the Work.

C. Restore existing work to a condition equal to or better than that which existed Prior to cutting and patching, and to standards required by Specifications.

D. Support, anchor, attach, match, trim and seal materials to work of others. Unless otherwise specified, Furnish and Install sleeves, inserts, and hangers required for execution of the Work.

E. Provide shoring, bracing and support necessary to maintain structural integrity and to protect adjacent work from damage during cutting and patching. Request written approval from Project Manager, before cutting structural members such as beams, anchors, lintels, or other supports. Follow approved submittals, as applicable.

F. Match new materials to existing materials by bonding, lapping, mechanically tying, anchoring or other effective means in order to prevent cracks and to minimize evidence of patching. Conceal effects of demolition and patching by blending new construction to existing surfaces. Avoid obvious breaks, joints or changes of surface appearance unless shown on Drawings or authorized by Project Manager.

1.04 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. Submit a written request to Project Manager for consent to proceed, before conducting cutting operations that might affect structural integrity, design function, City operations, or work of another contractor.

C. Include the following in submittal:

1. Identification of Project

2. Description of affected work

3. Necessity for cutting

4. Effect on other work and on structural integrity

5. Describe the proposed work including:
   a. Scope of cutting and patching
   b. Contractor, Subcontractor or Supplier who will execute the work
   c. Proposed Products
   d. Extent of refinishing
   e. Schedule of operations

6. Alternatives to cutting and patching

D. When work conditions or schedules dictate the need for change of materials or methods, submit a written recommendation to Project Manager that includes:

1. conditions necessitating the change;

2. recommendations for alternative materials or methods; and

3. submittals required for proposed substitutions

E. Notify Project Manager in writing when work will be uncovered for observation. Do not begin cutting or patching operations until authorized by Project Manager.

1.05 CONNECTIONS TO EXISTING FACILITIES

A. Perform construction operations necessary to complete connections and tie-ins to existing facilities. Keep existing facilities in continuous operation unless otherwise permitted in the Specifications or approved in writing by Project Manager.

B. Coordinate interruption of service requiring connection to existing facilities with Project Manager. Do not bypass wastewater or sludge to waterways. Provide temporary pumping facilities to handle wastewater if necessary. Use temporary bulkheads to minimize disruption. Provide temporary power and piping to facilitate construction where necessary.

C. Submit a detailed schedule of proposed connections, including shut-downs and tie-ins. Include proposed time and date as well as anticipated duration of work. Coordinate the connection schedule with the construction schedule.

1. Submit specific times and dates to Project Manager at least 48 hours in advance of proposed work.

D. Procedures and Operations:

1. Operate existing pumps, valves and gates in required sequence under supervision of Project Manager. Do not operate valves, gates or other items of equipment without Project Manager's knowledge.

2. If possible, test equipment under operating conditions before making final tie-ins to connect equipment to existing facility.

3. Coordinate work and schedules. Notify Project Manger at least 48 Hours before shutdowns or bypasses are required.

PART 2 P R O D U C T S Not Used

PART 3 E X E C U T I O N Not Used

END OF SECTION

Section 01732

PROCEDURE FOR WATER VALVE ASSISTANCE

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Operation of valves. City of Houston employees will operate existing valves. Contractor's employees may operate new valves included in the Project prior to acceptance by the City.

1.02 PROCEDURE

A. Perform activities listed in Exhibit A attached to this Section.

1.03 SUBMITTALS

A. Submit request for work order planning meetings in accordance with Exhibit A. Include information listed in Step 1 of Exhibit A, attached to this Section.

1.04 CANCELLATION

A. Contractor, Project Manager, or Public Utilities Division may cancel a scheduled valve assistance appointment at no extra cost or payment to Contractor. Contractor shall notify City's appointed Project Inspector ("Inspector") 24 hours in advance of cancellation. Inspector shall notify Central Operation Service (COS) immediately upon receipt of cancellation notice. Cancellation may be caused by bad weather, preparation work taking longer than anticipated, or unforeseen delays by one or more of the three parties.

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION - Not Used

END OF SECTION

PAGE LEFT INTENTIONALLY BLANK

EXHIBIT A

PROCEDURE FOR VALVE ASSISTANCE

The following procedure will be used by Utility Maintenance Branch personnel when completing a service request from individual Contractors, through Inspector, for operation of existing water valves.

ROUTINE VALVE ASSISTANCE REQUEST (NON-EMERGENCY JOBS):

Step 1. a. When notified by Contractor, Inspector will schedule a work order planning meeting by calling Central Operation Service (COS) at **(713) 295-5521** and providing information shown below. The work order planning meeting shall be conducted a minimum of three days after the request; excluding weekends, holidays, inclement weather days, and the day of the call.

Location of Work (Street Intersection)	Project #
Project Description	Contractor (Company Name)
Job Superintendent's Name	Superintendent's Office #/Mobile #/Pager #
Contractor's Emergency Information	Name and Phone #/Mobile #/Pager #
Inspector/Senior Inspector	Name, Phone #/Mobile #/Pager #
Date & Time assistance is requested	

b. COS will create a work order for each wet connection, cut and plug, etc. that will be designated as a "Code 40" (Private Contractor).

c. COS will give Inspector the work order number. This work order number must be used as a reference in all communications regarding this request for Valve Assistance.

d. Valve personnel must have the work order number on their route sheet. When valve personnel arrive at the job site for the Work Order Planning Meeting between Inspector, Contractor, and Utility Maintenance valve personnel, they will verify the street intersection and work order number with the Inspector before beginning Work Order Planning Meeting.

e. During Work Order Planning Meeting, the work to be performed will be outlined and the actual date work will be performed will be mutually determined by Inspector, Contractor and City's Utility Maintenance Division valve personnel, based upon relevant factors such as preparatory work needed, customer requirements, etc.

f. Valve personnel will perform work specifically outlined in the work order requested. Also, Utility Maintenance Branch valve personnel will only operate existing water valves. Inspector must contact COS and request a new work order for additional work.

g. Valve personnel will contact the dispatcher and advise when the job is complete. Valve personnel will list all appropriate information on the Crew Activity Report.

Step 2. Should valve personnel not be able to keep an appointment to provide valve assistance, Utility Maintenance Branch will provide notification to appropriate Inspector by phone at least 24 hours prior, with that fact and rescheduling information, if available.

Step 3. Inspector will notify COS if valve personnel have not arrived at the site within 30 minutes of scheduled appointment. If Contractor is not ready when valve operator arrives to provide valve assistance, the City shall charge Contractor $50.00 per hour, starting 15 minutes after the scheduled appointment time, minimum one hour charge.

Step 4. Contractor will not be due delay claims or downtime if Utility Maintenance Branch has notified Inspector that they will not be able to provide valve assistance as scheduled.

Step 5. Test installed new valves in the presence of Inspector before substantial completion inspection is scheduled. Place new valves in open position on or before the Date of Substantial Completion.

Step 6. Project Manager will notify, in writing, Utility Maintenance Branch two months before the warranty expires to report any problems they have with new water lines. Project Manager will notify Contractor about these problems.

EMERGENCY REQUEST FOR VALVE ASSISTANCE PROCEDURE:

Step 1. When notified by Contractor, Inspector will request emergency Valve Assistance due to a broken line/service, etc. by calling COS at **(713) 295-5521** and providing the following information:

Location of Work (Street Intersection)	Project #
Project Description	Superintendent's Office #/Mobile #/Pager #
Contractor (Company Name)	Name and Phone #/Mobile #/Pager #
Job Superintendent's Name	Name, Phone #/Mobile #/Pager #
Contractor's Emergency Information	
Inspector/Senior Inspector	
Date & Time assistance is requested	

Step 2. COS will create an emergency work order number and describe the work to be performed.

Step 3. COS will give Inspector the emergency work order number. Reference work order number in all communications regarding request for Valve Assistance.

Step 4. COS will contact designated valve personnel and assign emergency work order. Dispatcher will follow standard COS procedures if this situation occurs after normal working hours.

Step 5. Valve personnel must have the emergency work order number on the route sheet. When valve personnel arrive at the job site for emergency work, they will verify the street intersection and emergency work order number with Inspector prior to beginning work requested for operating existing water valves. Valve personnel will coordinate verification of street intersection and work order number with Inspector prior to performing work.

Section 01740

SITE RESTORATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Restoration of site affected by the Work in public or private property, including pavement, esplanades, sidewalks, driveways, fences, lawns and landscaping.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices.

1. Payment for restoration of Project site disturbed by utility construction operations is on a linear foot basis. Measurement will be as provided for corresponding utility in each Specification section. No separate payment made for branch pipe, valves and, other associated work for utilities. Measurement for restoration with multiple utilities within the same right-of-way will be on a linear foot basis for only one utility.

2. No separate payment made for facility or roadway projects. Include cost in the surface improvements associated with the facility or roadway construction.

3. Payment includes required site restoration within the right-of-way or easement regardless of size or type of pipe, method of construction, paved or unpaved areas or thickness and width of pavement.

4. No separate payment made for site restoration for service connections under this Section. Include cost in appropriate utility section.

5. Refer to Section 01270 – Measurement and Payment for Unit Price procedures.

B. Stipulated Price (Lump Sum) Contracts. If Contract is Stipulated Price Contract, include payment for work under this section in total Stipulated Price.

1.03 DEFINITIONS

A. Phase: Locations identified on the plans and listed in Section 1110 – Summary of Work under Work Sequence.

B. Site Restoration: Replacement or reconstruction of Site Improvements located in rights-of-way, easements, public property, and private property affected or altered by the Work.

C. Site Improvement: Includes pavement, curbs and gutters, esplanades, sidewalks, driveways, fences, lawns, irrigation systems, landscaping, and other improvements in existence at the Project site before commencement of construction operations.

1.04 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. Schedule of testing, service connections, abandonment, backfill, and site restoration.

C. Sample of notices to residents outlining their responsibility for maintenance of site improvements adjacent to the Project that are not disturbed by construction operations

1.05 SCHEDULING

A. Schedule testing, service connections, abandonment, backfill and site restoration immediately following completion of pipe laying work or paving within each block or line segment.

B. Phased Construction:

1. Commencement of subsequent Phase will follow scheduling of site restoration of prior Phase. Limit work to a maximum of two Phases of the project.

C. Construction of Projects with no Phases listed in Section 01110- Summary of Work:

1. Complete site restoration prior to disturbing over 50% of total project linear feet or 2,000 linear feet, whichever is greater, of right-of-way or easement.

2. Limit work to a maximum of 50% of total project linear feet or 2,000 linear feet, whichever is greater, of right-of-way and easement. Commence work in additional right-of-way or easement after completion of site restoration.

PART 2 PRODUCTS

2.01 MATERIALS

A. Pavement, Sidewalks and Driveways: Materials specified in Section 02951 - Pavement Repair and Resurfacing.

B. Seeding and Sodding: Sod specified in Section 02922 - Sodding and Seed specified in Section 02921 - Hydromulch Seeding.

C. Trees, Shrubs and Plantings: Conform to requirements of Section 01562 – Tree and Plant Protection.

PART 3 EXECUTION

3.01 Preparatory Work

A. Provide cleanup and restoration crews to work closely behind pipe laying and roadway construction crews, and where necessary, during testing, service restoration, abandonment, backfill and surface restoration.

B. Water Lines: Unless otherwise approved by Project Manager, comply with the following:

1. Once Project Manager approves work within a Phase, immediately begin preparatory work for disinfection effort.

2. No later than three days after completing disinfection preparatory work, submit to City appropriate request for disinfection.

3. If City fails to perform initial disinfection of lines in accordance with Section 2514 - Disinfection of Water Lines, within seven days from submission of appropriate request, and if approved by Project Manager, pipe laying operations may continue beyond approved limits until the City responds.

4. Immediately after transfer of services, begin abandonment of old water lines and site restoration.

C. Wastewater Lines:

1. Once Project Manager approves work within a Line Segment, immediately begin preparatory work for testing effort.

2. No later than three days after completing preparatory work for testing, initiate testing work.

3. Immediately after transfer of service connections, begin abandonment of old wastewater lines, and site restoration.

D. Street Construction and Paving Projects

1. Once Project Manager approves work within a Line Segment or block, immediately begin preparatory work for testing effort.

2. No later than three days after completing preparatory work for testing, initiate testing work.

3. Immediately after testing begin site restoration.

E. Street Construction and Paving Projects

1. Once Project Manager approves work within a block, immediately begin preparatory work for sidewalk construction, sodding and hydromulching and tree planting.

2. No later than seven days after completing preparatory work, initiate construction.

3.02 CLEANING

A. Remove debris and trash to maintain a clean and orderly site in accordance with requirements of General Conditions and Section 01576 - Waste Material Disposal.

3.03 LANDSCAPING AND FENCES

A. Seeding and Sodding.

1. Remove construction debris and level area with bank sand so that new grass surface matches level of existing grass and maintains pre-construction drainage patterns. Level and fill minor ruts or depressions caused by construction operations with bank sand, where grass is still viable.

2. Restore previously existing turfed areas with sod and fertilize in accordance with Section 02922 - Sodding. Sod to match existing turf.

3. Restore unpaved areas not requiring sodding with hydromulch seeding conforming to Section 02921 - Hydromulch Seeding.

B. Trees, Shrubbery and Plants.

1. Remove and replant trees, shrubs, and plants in accordance with requirements of Section 01562 – Tree and Plant Protection.

C. Fence Replacement.

1. Replace removed or damaged fencing to equal or better condition than existed prior to construction, including concrete footings and mow strips. Provide new wood posts, top and bottom railing and panels. Metal fencing material, not damaged by the Work, may be reused.

2. Remove and dispose of damaged or substandard material.

3.04 MAINTENANCE

A. Maintain shrubs, plantings, sodded areas and seeded areas.

B. Replace shrubs, plantings and seeded or sodded areas that fail to become established.

C. Refer to Section 01562 - Tree and Plant Protection, Section 02921 - Hydromulch Seeding and Section 02922 - Sodding for maintenance requirements.

END OF SECTION

Section 01755

STARTING SYSTEMS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Starting systems.

B. Demonstration and instructions.

C. Testing, adjusting and balancing.

PART 2 PRODUCTS - Not Used

PART 3 EXECUTION

3.01 PREPARATION

A. Coordinate schedule for start-up of various equipment and systems.

B. Notify Project Manager seven days prior to startup of each item.

C. Verify each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, control sequence, or other damage-causing conditions.

D. Verify tests, meter readings, and specified electrical characteristics agree with those required by equipment or system manufacturer.

E. Verify wiring and support components for equipment are complete and tested.

F. Execute start-up under supervision in accordance with manufacturer's instructions.

G. When specified in individual Specification sections, require manufacturer to provide an authorized representative to be present at the site to inspect, check and approve equipment or system installation prior to start-up, and to supervise placing equipment or system in operation.

H. Submit written report indicating that equipment or system has been properly installed and is functioning correctly.

3.02 DEMONSTRATION AND INSTRUCTIONS

A. Demonstrate operation and maintenance of Products to Project Manager two weeks prior to Date of Substantial Completion.

B. Utilize O&M Manuals as the basis for instruction. Review contents of manual with Project Manager in detail to explain aspects of operation and maintenance.

C. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of each item of equipment at agreed-upon times, at the equipment location.

D. Prepare and insert additional data in O&M Manuals when the need for additional data becomes apparent during instruction.

E. At a minimum, Contractor will demonstrate the following:

1. Products and procedures to be used in maintaining various surfaces, e.g., counter tops, toilet partitions, tile floors and carpeting;

2. procedures to set and maintain landscape irrigation system;

3. procedures to set and maintain security and fire alarm systems; and

4. procedures to set and maintain HVAC systems.

3.03 TESTING, ADJUSTING AND BALANCING

A. Contractor shall appoint, employ and pay for the services of an independent firm to perform testing, adjusting and balancing.

B. Submit reports by the independent firm to Project Manager describing observations and results of tests and signifying compliance or non-compliance with specified requirements and requirements of the Contract.

END OF SECTION

Section 01770

CLOSEOUT PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Procedures to establish Date of Substantial Completion.

B. Closeout procedures for final submittals, O&M data, warranties, spare parts and maintenance materials.

C. Texas Department of Licensing and Regulation (TDLR) inspection for Texas Accessibility Standards (TAS) compliance.

1.02 SUBSTANTIAL COMPLETION

A. Comply with Document 00700 - General Conditions regarding Date of Substantial Completion when Contractor considers the Work, or portion thereof designated by Project Manager, to be substantially complete.

B. Insure the following items have been completed when included in the Work, prior to presenting a list of items to be inspected by Project Manager for issuance of a Certificate of Substantial Completion:

1. cutting, plugging, and abandoning of water, wastewater, and storm sewer lines, as required by Contract documents for each item;

2. construction of, and repairs to, pavement, driveways, sidewalks, and curbs and gutters;

3. sodding and hydromulch seeding, unless waived by Project Manager in writing;

4. general clean up including pavement markings, transfer of services, successful testing and landscape;

5. additional requirements contained in Section 01110 - Summary of Work.

C. Assist Project Manager with inspection of Contractor's list of items and complete or correct the items, including items added by Project Manager, within specified time period.

D. Should Project Manager's inspection show failure of Contractor to comply with requirements to obtain Date of Substantial Completion, including those items in Paragraph 1.02 B. of this section, Contractor shall complete or correct the items, before requesting another inspection by Project Manager.

1.03 CLOSEOUT PROCEDURES

A. Comply with Document 00700 - General Conditions regarding final completion and final payment when the Work is complete and ready for Project Manager's final inspection.

B. Provide Project Record Documents in accordance with Section 01785 - Project Record Documents.

C. Complete or correct items on punch list, with no new items added. Address new items during warranty period.

D. The City will occupy portions of the Work as specified in other sections.

1.04 FINAL CLEANING

A. Execute final cleaning prior to final inspection.

B. For facilities, clean interior and exterior glass and surfaces exposed to view; remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, vacuum carpeted and soft surfaces.

C. Clean equipment and fixtures to sanitary condition.

D. Clean or replace filters of operating equipment.

E. Clean debris from roofs, gutters, down spouts, and drainage systems.

F. Clean site; sweep paved areas, and rake clean landscaped surfaces.

G. Remove waste and surplus materials, rubbish, and temporary construction facilities from site following final test of utilities and completion of the Work.

1.05 ADJUSTING

A. Adjust operating equipment to ensure smooth and unhindered operation. Value of this testing and adjusting is five percent of Lump Sum Price in the Schedule of Values for item being tested.

1.06 OPERATION AND MAINTENANCE DATA

A. Submit O&M data as noted in Section 01330 - Submittal Procedures.

B. Five percent of lump sum amount of each piece of equipment as indicated in Schedule of Unit Price Work or Schedule of Values will be paid after the required O&M data submittals are received and approved by Project Manager.

1.07 WARRANTIES

A. Provide one original of each warranty from Subcontractors, Suppliers, and manufacturers.

B. Provide Table of Contents and assemble warranties in a 3-ring/D binder with durable plastic cover.

C. Submit warranties prior to final progress payment.

D. Warranties shall commence in accordance with the requirements in Document 00700 - General Conditions.

1.08 SPARE PARTS AND MAINTENANCE MATERIALS

A. Provide Products, spare parts, maintenance and extra materials in quantities specified in individual Specification sections.

B. Deliver to a location within the City limits as directed by Project Manager. Applicable items must be delivered prior to issuance of a final Certificate for Payment.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01782

OPERATIONS AND MAINTENANCE DATA

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Submittal requirements for equipment and facility Operations and Maintenance (O&M) Manuals

1.02 MEASUREMENT AND PAYMENT

A. Measurement for equipment O&M Manuals is on a lump sum basis equal to five percent of the individual equipment value contained in Schedule of Unit Prices or Schedule of Values. The lump sum amount may be included in the first Progress Payment following approval of the O&M Manuals by Project Manager.

1.03 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures. Submit a list of O&M Manuals and parts manuals for equipment to be incorporated into the Work.

B. Submit documents with 8-1/2 x 11-inch text pages, bound in 3-ring/D binders with durable plastic covers.

C. Print "OPERATION AND MAINTENANCE INSTRUCTIONS", Project name, and subject matter of binder on covers when multiple binders are required.

D. Subdivide contents with permanent page dividers, logically organized according to the Table of Contents, with tab titling clearly printed under reinforced laminated plastic tabs.

E. O&M Manual contents: Prepare a Table of Contents for each volume, with each Product or system description identified.

1. Part 1 - Directory: Listing of names, addresses, and telephone numbers of Design Consultant, Contractor, Subcontractors, and major equipment Suppliers.

2. Part 2 - O&M instructions arranged by system. For each category, identify names, addresses, and telephone numbers of Subcontractors and Suppliers and include the following:
   a. Significant design criteria.
   b. List of equipment.
   c. Parts list for each component.
   d. Operating instructions.
   e. Maintenance instructions for equipment and systems.
   f. Maintenance instructions for special finishes, including recommended cleaning methods and materials and special precautions identifying detrimental agents.

3. Part 3 - Project documents and certificates including:
   a. Shop Drawings and relevant data.
   b. Air and water balance reports.
   c. Certificates.
   d. Photocopies of warranties.

F. Submit two copies of O&M Manuals and parts manuals, for review, within one month prior to placing the equipment or facility in service.

G. Submit one copy of completed volumes in final form 10 days prior to final inspection. One copy with Project Manager comments will be returned after final inspection. Revise content of documents based on Project Manager's comments prior to final submittal.

H. Revise and resubmit three final volumes within 10 days after final inspection.

1.04 EQUIPMENT O&M DATA

A. Furnish O&M Manuals, prepared by manufacturers for all equipment. Manuals must contain, as a minimum, the following:

1. Equipment functions, normal operating characteristics, and limiting conditions.

2. Assembly, Installation, alignment, adjustment, and checking instructions.

3. Operating instructions for start-up, normal operation, regulation and control, normal shutdown, and emergency shutdown.

4. Detailed drawings showing the location of each maintainable part and lubrication point with detailed instructions on disassembly and reassembly of the equipment.

5. Troubleshooting guide.

6. Spare parts list, predicted life of parts subject to wear, lists of spare parts recommended to be on hand for both initial start-up and for normal operating inventory, and local or nearest source of spare parts availability.

7. Outline, cross-section, and assembly drawings with engineering data and wiring diagrams.

8. Test data and performance curves.

B. Furnish parts manuals for all equipment, prepared by the equipment manufacturer, which contain, as a minimum, the following:

1. Detailed drawings giving the location of each maintainable part.

2. Spare parts list with predicted life of parts subject to wear, lists of spare parts recommended on hand for both initial start-up and for normal operating inventory, and local or nearest source of spare parts availability.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 01785

PROJECT RECORD DOCUMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Maintenance and submittal of record documents and Samples.

1.02 MAINTENANCE OF DOCUMENTS AND SAMPLES

A. Maintain one record copy of documents at the site in accordance with Document 00700 - General Conditions.

B. Store record documents and Samples in field office, if a field office is required by the Contract, or in a secure location. Provide files, racks, and secure storage for record documents and Samples.

C. Label each document "PROJECT RECORD" in neat, large, printed letters.

D. Maintain record documents in a clean, dry, and legible condition. Do not use record documents for construction purposes. Do not use permit drawings to record Modifications to the Work.

E. Keep record documents and Samples available for inspection by Project Manager.

F. Bring record documents to progress review meetings for viewing by Project Manager and, if applicable, Design Consultant.

1.03 RECORDING

A. Record information legibly with red ink pen on a set of blueline opaque drawings, concurrently with construction progress. Maintain an instrument on site at all times for measuring elevations accurately. Do not conceal work until required information is recorded

B. Contract Drawings and Shop Drawings: Mark each item to record completed Modifications, or when minor deviations exist, the actual construction including:

1. Measured depths of elements of foundation in relation to finish first floor datum.
2. Measured horizontal locations and elevations of Underground Facilities and appurtenances, referenced to permanent surface improvements.

3. Elevations of Underground Facilities referenced to City of Houston benchmark utilized for the Work.

4. Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.

5. Dimensions and details of field changes

6. Changes made by Modifications.

7. Details not on original Drawings.

8. References to related Shop Drawings and Modifications.

C. Survey all joints of water mains at the time of construction. Record on Drawings, water main invert elevation, elevation top of manway, and centerline horizontal location relative to baseline.

D. For large diameter water mains, mark specifications and addenda to record:

1. Manufacturer, trade name, catalog number and Supplier of each Product actually Installed.

2. Changes made by Modification or field order.

3. Other matters not originally specified.

E. Annotate Shop Drawings to record changes made after review.

1.04 SUBMITTALS

A. At closeout of the Contract, deliver Project record documents to Project Manager.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 02105

CHEMICAL SAMPLING AND ANALYSIS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Preparatory work related to site remediation and excavation in a Potentially Petroleum Contaminated Area (PPCA).

B. Sampling and analysis of site material.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. Preparatory work is paid on a lump sum basis. Item includes hiring environmental consultants, preparing Environmental Health and Safety Plan, preparing Environmental Work Plan, training personnel, and obtaining permits and additional insurance.

2. Underground Utility Construction in PPCA.

a. Underground utility construction and appurtenances in areas identified within PPCA limits is on a linear foot basis, each basis, or lump sum basis, as shown in Document 00405 - Schedule of Unit Price Work.

b. Payment includes compensation for labor, equipment, and supervision for mobilization, environmental monitoring and field screening, handling, sampling, and testing of contaminated soil and ground water. Contaminated soil may be Category I or II. Contaminated groundwater will be that encountered during excavation for underground utilities and flowing at a rate not greater than 20 gallons per minute. Included in this pay item is incremental cost for upgraded piping, gaskets, and appurtenant materials.

c. Limits of measurement under this section are noted on Drawings as ABegin PPCA Excavation≅ and AEnd PPCA Excavation,≅ and other areas determined by Project Manager during the course of the work.

d. Payment will be made upon receipt of field test reports from approved analytical laboratory.

3. A force account for Extra Work for PPCA Handling will be used to compensate for time and materials required for additional work associated with PPCA when directed by Project Manager to perform such work and for which there is no bid item. Authorization and compensation for this work will be in accordance with Document 00700 - General Conditions.

4. Refer to Section 01270 - Measurement and Payment for unit price procedures.

B. Stipulated Price (Lump Sum). If the Contract is a Stipulated Price Contract, payment for work in this Section is included in the total Stipulated Price.

1.03 REFERENCE STANDARDS

A. ASTM D 5092 - Practice for Design and Installation of Groundwater Monitoring Wells in Aquifers.

B. Code of Federal Regulation (CFR), Title 40, Section 261.24. - Protection of the Environment.

C. CFR, Title 29, Section 1910.120. - Occupational Safety and Health Administration, Department of Labor.

D. CFR, Title 29, Section 1926. - Occupational Safety and Health Administration, Department of Labor.

E. CFR, Title 40, Section 261, Appendix II. - Protection of the Environment.

F. Texas Administrative Code (TAC), Title 30, Chapter 335. - Industrial Solid Waste & Municipal Hazardous Waste.

G. TAC, Title 30, Chapter 334. - Underground and Aboveground Storage Tanks.

H. TAC, Title 30, Chapter 106.533. - Exemptions from Permitting, Subchapter X. Waste Processes and Remediation.

I. U.S. Environmental Protection Agency (EPA), (SW-846) Test Methods for Evaluating Solid Waste, Office of Solid Waste and Emergency Response, Washington, D.C. (P1388-239223, November 1986).

J. Texas Commission on Environmental Quality (TCEQ) Interoffice Memo, dated 4/12/94, by Chris Chandler, RPR Section, PST Division, regarding

ARevised Procedures for Classifying and Assigning Waste Codes for Underground and Aboveground Petroleum Storage Tank Wastes (text attached following this section).

1.04 DEFINITIONS

A. Petroleum: Crude oil, natural gas, natural gas liquids, liquefied natural gas, and synthetic gas usable for fuel, as well as distillates of crude oil including gasoline, kerosene, diesel oil, motor oil, waste oil, jet fuels, and fuel oil.

B. Potentially Petroleum Contaminated Area (PPCA): An area within station-to-station locations identified on Drawings where petroleum contamination has been detected in the soil or groundwater. PPCA also includes areas where contamination is suspected or encountered during utility installation outside areas identified on Drawings, and such contamination has been verified by Project Manager.

C. Category I Soil: Soil containing visual or physical evidence of contamination, as described in paragraph 3.01, and that is not Category II Soil.

D. Category II Soil: Soil that contains petroleum contamination in excess of levels identified in paragraph 3.04, and is consistent with a classification as Special Waste-PST as defined by TCEQ in their interoffice memo dated 4/12/94, or soil that contains visible free product or is impacted with non-petroleum compounds detected above Risk Reduction Standard Number 2 levels as defined in Texas Administrative Code, Title 30, Chapter 335.

E. Potentially Contaminated Groundwater: Water recovered in a groundwater control system located in PPCA or groundwater that contains visual or physical evidence of contamination, as described in paragraph 3.01, and such contamination has been verified by Project Manager.

1.05 SUBMITTALS

A. Conform to requirements of Section 01330 - Submittal Procedures.

B. Submit an Environmental Work Plan within 30 days after issuance of Notice to Proceed.

1. The Environmental Work Plan shall be prepared by a Corrective Action Project Manager licensed in Texas, who has completed 40-hours of Health and Safety Training and the required annual refresher training, and in the employment of a registered Corrective Action Specialist firm.

2. The Environmental Work Plan shall include the following items. Compile and arrange in a format that can be reviewed by TCEQ.

a. Proposed sequence of construction through PPCA;

b. Procedures for screening soil in PPCA, identifying Category I or II Soil;

c. Procedures for handling material from PPCA;

d. Proposed location of stockpile areas;

e. Proposed reuse of Category I Soil as trench backfill below depths of 30 inches;

f. Proposed methods for disposal or recycling of Category I or II Soil;

g. Proposed carriers of Category I or II Soil or potentially contaminated groundwater with verification each is properly licensed;

h. Proposed recycle/disposal sites for Category I or II Soil or potentially contaminated groundwater with verification that each is properly licensed;

i. Copy of permit required for discharge of potentially contaminated groundwater in sanitary sewer system, if to be disposed in sanitary sewer;

j. Name and qualifications of Corrective Action Project Manager and professional environmental consultants for health, environmental, and safety issues regarding operations within PPCA; and,

k. Proposed analytical laboratory with verification it is accredited by A2LA or other recognized association, or it is a participant in the EPAs Performance Evaluation Program.

3. Do not commence work in PPCA until Environmental Work Plan has been reviewed and accepted by Project Manager.

C. Submit Environmental Health and Safety Plan within 30 days after issuance of Notice to Proceed.

1. The Health and Safety Plan shall be prepared by a Corrective Action Project Manager licensed in Texas, who has completed 40 hours of

health and safety training, and required annual refresher training, or a Certified Industrial Hygienist.

2. Include methods and procedures for assuring work, which will be conducted under conditions expected in the field, is safe.

D. As work proceeds, submit field screening, monitoring and analytical laboratory test results on a weekly basis for soil and on a daily basis for groundwater. Summarize test results in tables together with applicable regulatory criteria.

E. Submit copies of correspondence, reports, permits and other documents provided to, or received from, regulatory agencies.

1.06 PERSONNEL REQUIREMENTS

A. Provide trained personnel who have completed minimum health and safety programs specified by the Occupational Safety and Health Administration in 29 CFR 1910.120. Before beginning work at the site, each employee that will work in PPCA is required to have completed 40 hours health and safety training and the required annual refresher training.

PART 2 PRODUCTS

2.01 MATERIALS

A. Do not use polyvinyl chloride or other plastic material, unless approved by Project Manager.

B. Water Line Pipe Material.

1. Furnish ductile-iron pipe or steel pipe material within station-to-station locations identified as PPCA on Drawings.

2. Provide restrained joints for ductile-iron pipe or welded joints for steel pipe.

3. Provide pipe material conforming to Section 02501 - Ductile-Iron Pipe and Fittings or Section 02502 - Steel Pipe and Fittings.

C. Sanitary Sewer Pipe Material.

1. Furnish ductile-iron pipe, centrifugally cast fiberglass pipe, or equivalent protective materials approved by Project Manager.

2. Provide restrained joints.

3. Provide pipe material conforming to Section 02501 - Ductile-Iron Pipe and Fittings or Section 02504 - Centrifugally Cast Fiberglass Pipe. Use pipe with a minimum pressure rating of 150 psi.

D. Use Viton (FKM) type gaskets, or other material as recommended by the pipe manufacturer, for water lines, sanitary and storm sewer pipe, and appurtenances requiring gaskets.

PART 3 EXECUTION

3.01 POTENTIALLY PETROLEUM CONTAMINATED AREAS

A. Conduct operations in PPCA in accordance with the accepted Environmental Work Plan and the Environmental Health and Safety Plan and to minimize the spread of contamination. In other areas which are either detected or suspected to be potentially petroleum contaminated areas, immediately notify Project Manager and proceed with work in accordance with this Section, unless otherwise directed by Project Manager.

B. Immediately notify Project Manager and TCEQ=s Region 12 Field Office whenever Category I or II Soil or potentially contaminated groundwater are encountered.

1. Provide location, depth, type (soil or groundwater), source (if known), and evidence of suspected contamination.

2. Determine if Category I Soil or potentially contaminated groundwater is present by visual or physical evidence of contamination. Visual or physical evidence includes:

   a. Petroleum or chemical odor.

   b. Indication of levels of contamination by air monitoring devices employed as part of the Environmental Health and Safety Plan.

   c. Soil or groundwater discoloration.

   d. Material oozing/dripping into excavation.

   e. Liquid or oily sheen floating on groundwater.

   f. Buried containers or refuse.

g. Field screening Ahead-space≅ results in excess of a 25 ppm reading on a photoionization detector (PID) or flame ionization detector (FID).

C. Install piping and gasket materials and appurtenances in conformance with appropriate section, except as modified in this Section.

D. Construct trench dams within a utility trench at each boundary of PPCA and laterals to minimize potential for contaminant transport within pipe bedding material. A trench dam shall consist of at least 24 inches of cement stabilized sand with 10 percent bentonite clay added, extending from 6 inches below bottom of trench to within 12 inches of limits of topsoil or pavement.

3.02 ENVIRONMENTAL MONITORING

A. An environmental consultant shall monitor conditions in PPCA, as specified in the Environmental Health and Safety Plan. Maintain safe working conditions in accordance with OSHA requirements (29 CFR 1926).

3.03 SCREENING PPCA SOILS

A. An environmental consultant shall perform field screening of soil removed from excavation or tunneling in PPCA.

B. Screening Procedures.

1. Place samples in a sealed plastic bag and place in a warm location for 15 minutes prior to screening.

2. Properly calibrate the PID/FID using a calibration gas. For PID use 100 ppm isobutylene and for FID use 100 ppm methane.

3. Open bag just enough to insert instrument probe and take maximum headspace reading.

4. Screen at least twice per hour while removing soils in open cut areas or shafts.

5. During tunneling, screen once for each pipe length in pipe jacked tunnels or each advance of tunnel shield in primary-lined tunnels. Screen at least once per shift when excavating.

3.04 SAMPLING AND TESTING

A. Frequency.

1. Sample soil in PPCA at a rate of not less than one composite sample for every 20 cubic yards of excavation or volume corresponding to every 50 linear feet of installed underground utility, whichever is more frequent.

2. Sample water from PPCA to be discharged to a sanitary sewer one week prior to initiation of discharge, and at a rate of one grab sample once per day during discharge to sanitary sewer.

B. Analyze soil samples for parameters listed in Table 01160-1, Soil Criteria - Petroleum Only, and in accordance with SW-846. Handle as a Category II Soil if analytical results indicate any one, or more, parameters exceed allowable Maximum Concentration listed in Table 01160-1. If benzene concentration from composite sample is greater than 5 milligrams per kilogram (mg/kg) or lead concentration is greater than 30 mg/kg, perform Toxicity Characteristic Leaching Procedure (TCLP) analysis of appropriate compound for that sample to determine if a more stringent disposal classification is warranted. If contaminants other than petroleum are suspected, immediately notify Project Manager who will determine the list of parameters to be analyzed. If such are encountered, compensation will be made under the Allowance for PPCA Handling. Use a 4-part representative composite sample for analysis of parameters, except when inconsistent with SW-846.

C. Analyze groundwater samples for discharge to sanitary sewers. Analyze samples for BTEX by EPA Method 602, 8020, or 8021; TPH by EPA Method 418.1 or Method TX 1005; and LEL in accordance with EPA Method 1010.

D. Conduct analyses by proposed analytical testing laboratory listed in Environmental Work Plan.

3.05 AIR MONITORING REQUIREMENTS

A. Ensure health and safety of workers at the construction site. Maintain air quality within the construction zone to conform to exposure limits specified in Code of Federal Regulations (CFR) Title 29, Section 1910.120 enforceable by OSHA.

B. Provide adequate shoring and sufficient escape ladders in accordance with applicable trench safety regulatory requirements.

C. In the trench, continuously operate a combustible gas indicator (CGI) with LEL/O_2 meter to monitor vapor and oxygen levels. Properly calibrate CGI and provide an alarm that sounds if greater than or equal to 20 percent Lower Explosive Limit (LEL), less than or equal to 19.5 percent oxygen, or greater

than or equal to 25 percent oxygen is reached. Record monitoring data from CGI every 15 minutes to ensure safe work conditions.

D. Take appropriate measures during construction to keep LEL levels below 20 percent in the trench. If vapor concentrations exceed 20 percent of LEL stop construction work, turn off equipment, and have workers immediately vacate the PPCA in an upwind direction.

E. Take readings with PID/FID 50 feet downwind of area during excavation or work in contaminated excavation areas and until one hour after cessation of such work. Take readings within breathing zone at approximately 4 feet above ground level. Record readings, date, time, initials of person taking reading, PID/FID serial number and last calibration date of PID/FID in bound field book.

END OF SECTION

Attachment to Section 02105

PETROLEUM CONTAMINATION

Following, for informational purposes only, is the text of the 4/12/94 Interoffice Memo from Chris Chandler of the Texas Commission on Environmental Quality (TCEQ), RPR Section, PST Division, regarding Revised Procedures for Classifying and Assigning Waste Codes for Underground and Aboveground Petroleum Storage Tank Wastes:

This document is a revision of the waste classification memo dated July 18, 1991 which revised the original March 11, 1991 document. The main difference between the first two documents was the elimination of the distinction between industrial and nonindustrial petroleum substance wastes. This latest version has been revised to reflect changes in the rules and in the agency itself. Significant changes are denoted by underlines. Please discard the previous document.

An appropriate response to any leaking petroleum storage tank incident must always include the proper handling and disposal of all generated wastes. In the majority of cases these wastes include contaminated soils and/or wastewater. Before a disposal destination can be determined for a particular waste, the waste must be classified based on the concentrations of contaminants. The procedures for classification of petroleum contaminated wastes are detailed in the attached Guidance Document for the proper Management of Wastes Associated With Underground and Aboveground Petroleum Storage Tanks. The waste first must be analyzed by a laboratory and then, based upon the results of the analysis, a classification can be assigned to the waste with its corresponding waste code number. The waste code is a predesignated number based upon both the waste=s classification and the type of contaminants.

Many disposal facilities are now requiring the generator of any petroleum substance waste to obtain a waste classification from TCEQ that assigns a waste code number to that particular waste before the facility will accept it (even though this is not a regulatory requirement for nonhazardous PST wastes). In order to receive this waste code, the generator first must submit laboratory reports and other information providing the results of analysis for the waste. This information should be attached to a completed copy of TCEQ Form No. 0197. Only after receipt of this documentation should the waste code assignment be made. Waste code numbers should never be issued based upon analytical results unsupported by laboratory documentation.

Laboratory reports should include a description of the analytical procedures utilized, the condition in which the sample was received, and the signature of the laboratory personnel. Also, reports must be accompanied by a description of the sample collection and handling procedures. If the procedures described are not in accordance with EPA-approved and/or TCEQ-accepted procedures, the results should be rejected as invalid.

Soil samples should be collected at the rate of one sample for every fifty cubic yards of material, and each sample should be a composite which is representative of the fifty

cubic yard unit. Water samples from inside storage vessels should be collected from the top of the water column in order to identify the highest contaminant level. Water should be sampled at the rate of one sample per 3000 gallons of water, or a minimum of one sample per container if there is more than one container.

When a waste is categorized as Class II PST or Special Waste-PST, the generator must document the volume, means of transportation, and ultimate destination for the waste. Once all of the proper information has been received by the PST of FO Division in writing, the waste classification and code number can be verbally issued to the generator. The number should be written on the submitted Form No. 0197 in the space marked TCEQ Use Only, and a copy of the form mailed or faxed to the Responsible Party (not the contractor or consultant). Also include the date, the person issuing the code number and the Regional Office number on the form. A copy of the completed form and all submitted information should be sent to the Central Office (or regional office as appropriate).

Regional Field Inspectors as well as PST Division Coordinators should issue waste classifications and code numbers for only Class II PST and Special Wastes-PST on cases they are responsible for coordinating.

Additionally, for all waste classification requests which are not associated with LPST sites (such as for disposal of water used to clean tanks or for disposal of soil/backfill material not associated with a confirmed release), the I&HW Division or the appropriate Regional Office should oversee the waste classification. All hazardous and industrial Class I waste must be manifested in accordance with the Industrial Solid Waste Rules, Chapter 335, Texas Administrative Code. Generators of any hazardous wastes or industrial Class I waste should be referred to the Waste Evaluation Section of the TCEQ Industrial and Hazardous Waste Division at (512) 239-6832.

Following are the waste classification and code numbers for typical nonhazardous wastes generated at leaking underground and aboveground petroleum storage tank sites involving the release of petroleum substances only (i.e., gasoline, diesel, kerosene, jet fuel, etc.).

CONTAMINATED SOILS

Contaminant Level	**Classification**	**Waste Code Number**
If greater than 150 ppm BTEX **OR** 600 ppm TPH	Special Waste PST	PSTW4891
If less than 150 ppm BTEX **AND** 600 ppm TPH	Class II PST Waste	PSTW4892

Note Soils saturated (Adrippy≅) with gasoline are likely to be ignitable. Contaminated soils analyzed as ignitable are classified as hazardous waste and therefore can only be transported by a registered hazardous waste hauler and only disposed of at a permitted facility authorized to receive hazardous wastes.

CONTAMINATED WATER

Contaminant Level	**Classification**	**Waste Code Number**
Any concentration of dissolved contamination with no phase-separated product	Class II PST Waste	PSTW1021

As routinely requested in TCEQ=s letters, documentation of the handling and disposition of all wastes generated in a LPST response action must be provided to TCEQ. It is essential that we track PST wastes through signed receipts and, when required, manifests to prevent their illegal dumping.

Should you have any questions or comments, please contact me at 512/239-2245 or the Waste Evaluation Section at 512/239-6832.

(Signed) Chris Chandler

END OF ATTACHMENT

Section 02120

OFF-SITE TRANSPORTATION AND DISPOSAL

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Off-site disposal of non-hazardous and hazardous solid, liquid and resinous waste.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. Payment for transportation and disposal of Class II Soil at approved facility is on a cubic yard basis.

2. Payment for transportation and disposal of Class I Soil at approved facility is on a cubic yard basis.

3. No separate payment will be made for soil reused as backfill material.

4. Payment for transportation and disposal of contaminated groundwater at approved facility is on a per gallon basis.

5. No separate payment for ground water discharged into a sanitary sewer.

6. Refer to Section 01270 - Measurement and Payment for unit price procedures.

B. Stipulated Price (Lump Sum). If the Contract is a Stipulated Price Contract, payment for work in this Section is included in the total Stipulated Price.

1.03 REFERENCES

A. CFR, Title 29, Section 1910.120.- Occupational Safety and Health Administration, Department of Labor.

B. Texas Administrative Code (TAC), Title 30, Chapter 335.- Industrial Solid Waste & Municipal Hazardous Waste.

C. TAC, Title 30, Chapter 334.- Underground and Aboveground Storage Tanks.

D. TAC, Title 30, Chapter 106.533.- Exemptions from Permitting, Subchapter X, Waste Processes and Remediation.

E. U.S. Environmental Protection Agency (EPA), (SW-846) Test Methods for Evaluating Solid Waste, Office of Solid Waste and Emergency Response, Washington, D.C. (P1388-239223, November 1986).

PART 2 P R O D U C T S (Not Used)

PART 3 E X E C U T I O N

3.01 HANDLING CATEGORY I AND II SOILS

A. Do not place Category II Soil back into excavation. Properly dispose of Category II Soil at the facility listed in Environmental Work Plan. Category I Soil consistent with classification as Class II PST Waste as defined by Texas Commission on Environmental Quality (TCEQ) in their interoffice memo dated 4/12/94, and not Category II Soil (as demonstrated through laboratory testing) can be reused as backfill material, provided;

1. Soil is reused in the same area from which it originated at depths greater than 30 inches below top of pavement, finished grade or ditch flowline, whichever is lower.

2. Soil has suitable engineering properties for backfill material as specified in Section 02320 - Utility Backfill Material.

3. Does not have indications of impact by contaminants other than petroleum.

B. Do not spread Category I or II Soil on ground surface.

C. Place Category I or II Soil in covered roll-off box with a minimum 20-mil plastic liner or in a stockpile at temporary storage area, pending receipt of analytical results and receipt of authorization from TCEQ and the disposal site for final disposal; or, in trucks for transport directly to the disposal facility.

1. Do not commingle Category I or II Soil from different locations or with different sources.

2. Temporary storage area to meet following criteria:

a. Within 2 miles of project site, to allow access by City personnel, unless otherwise approved by Project Manager.

b. Outside the 100-year floodplain.

c. Outside of, and not adjacent to, an area known or suspected to be a wetland.

d. Acceptable to Project Manager.

3. Secure using temporary fencing or other means of controlling access.

4. Place stockpiled soils on an impervious membrane. Surround with a berm to prevent migration of soils or moisture either into or out of the stockpile, other than evaporation.

5. Protect and cover the stockpile with minimum 20-mil plastic or other approved waterproof membrane covering. Replace damaged covers.

6. Do not place soil over monitoring wells or piezometers, utility line manholes, or any other potential route for water to migrate to subsurface.

7. Handle runoff from the temporary storage area in accordance with paragraph 3.06, Handling Water.

8. Do not stockpile soil for greater than 30 days.

9. Remove remaining material, including excavated soil from construction site, from temporary storage area prior to completion of Work.

D. Remove, handle, transport, stockpile, and dispose of Category II Soil under direction of Corrective Action Project Manager. Dispose waste classified (i.e., meets characteristics or other definitions of) a hazardous waste consistent with Resource Conservation and Recovery Act (RCRA) and 30 TAC Chapter 335.

E. Transport Category I or II Soil in accordance with Department of Transportation (DOT) and TCEQ rules and regulations.

F. Dispose Category I Soil, not reused as backfill, under direction of Corrective Action Project Manager, at a properly licensed facility with prior approval of Project Manager.

G. Obtain signed manifests from the receiving facility and provide originals to Project Manager.

H. Decontaminate large equipment to prevent cross-contamination with clean material. Steam clean or pressure wash dump trucks, bulldozers, backhoes, and other large equipment prior to use in uncontaminated areas after being used in PPCA.

3.02 HANDLING WATER

A. Prior to discharging petroleum contaminated groundwater, obtain an Industrial Wastewater Discharge Permit (no cost) from the City for disposal directly to a sanitary sewer which discharges to a City-owned wastewater treatment plant.

B. Procedures.

1. Provide equipment sized to handle flows anticipated by dewatering operations.

2. Include commercially available oil/water separator unit as part of the treatment system for dewatering operation discharging to sanitary sewer.

3. Do not exceed limits listed in Table 01160-2, Potentially Contaminated Groundwater Discharge Limits for groundwater discharged to the sanitary sewer. Provide additional treatment systems as needed prior to discharge to sanitary sewers where groundwater contamination levels exceed those noted in Table 01160-2. Approval by Project Manager shall be obtained for proposed treatment system prior to initiation of treatment and discharge.

4. Comply with all applicable requirements of 30 TAC, Chapter 106.533, including submitting a PI-7 form to the TCEQ for a standard exemption of oil/water separator unit, and any additional treatment systems. Submit copy of PI-7 form to Project Manager.

5. Do not discharge treated water into sanitary sewer if water level is within one foot of the top of sanitary sewer manhole or would cause an overflow situation.

6. Recover free product collected in treatment equipment. Recycle for beneficial reuse or dispose of recovered contaminants in a manner acceptable to Project Manager and TCEQ.

7. Transport potentially contaminated groundwater and free product in accordance with DOT and TCEQ rules and regulations for flammable products. Use DOT-licensed carrier for transport.

8. Obtain signed manifests for potentially contaminated groundwater and free product from the receiving facility and provide originals to Project Manager.

9. Furnish laboratory reports to Project Manager within one week of sample date.

C. Install and operate groundwater control systems, as described in Section 01578 - Control of Groundwater and Surface Water. Design and operate groundwater control systems so water from PPCA is handled in a system separated and isolated from groundwater control systems outside PPCA.

D. Handle, test, treat, and discharge potentially contaminated groundwater to the sanitary sewer in accordance with City of Houston, Industrial Wastewater Discharge Permit requirements, or have water evacuated and hauled for off-site treatment and disposal at a TCEQ-permitted facility. Perform discharge under direction of Corrective Action Project Manager.

3.03 AIR MONITORING REQUIREMENTS

A. Ensure health and safety of workers at the construction site. Maintain air quality within the construction zone to conform to exposure limits specified in Code of Federal Regulations (CFR) Title 29, Section 1910.120 enforceable by OSHA.

B. Provide adequate shoring and sufficient escape ladders in accordance with applicable trench safety regulatory requirements.

C. In the trench, continuously operate a combustible gas indicator (CGI) with LEL/O_2 meter to monitor vapor and oxygen levels. Properly calibrate CGI and provide an alarm that sounds if greater than or equal to 20 percent Lower Explosive Limit (LEL), less than or equal to 19.5 percent oxygen, or greater than or equal to 25 percent oxygen is reached. Record monitoring data from CGI every 15 minutes to ensure safe work conditions.

D. Take appropriate measures during construction to keep LEL levels below 20 percent in the trench. If vapor concentrations exceed 20 percent of LEL stop construction work, turn off equipment, and have workers immediately vacate the PPCA in an upwind direction.

E. Take readings with PID/FID 50 feet downwind of area during excavation or work in contaminated excavation areas and until one hour after cessation of such work. Take readings within breathing zone at approximately 4 feet above ground level. Record readings, date, time, initials of person taking

reading, PID/FID serial number and last calibration date of PID/FID in bound field book.

3.04 DISPOSAL OF MATERIAL

A. Non-categorized Material. Dispose of excess or unsuitable excavated materials, not Category I or II Soil, off-site in accordance with Section 01576 - Waste Material Disposal.

B. Category I or II Soil. Dispose of excess or unsuitable excavated materials off-site at a state registered Treatment, Storage, or Disposal (TSD) facility. Obtain signed manifests from the receiving facility and provide originals to Project Manager.

TABLE 01160-1
SOIL CRITERIA - PETROLEUM ONLY

Contaminant	Maximum[a] Concentration (mg/kg)	Method
TPH	1500	EPA 418.1/TX 1005
Total BTEX[b]	150	EPA 8020/8021
Total Lead[c]	250	EPA 6000/6010/7000

Notes: [a] If any parameters exceed the maximum concentrations, then the soil shall be considered Category II Soil and a Special Waste-PST as defined by the TCEQ in their interoffice memo dated 4/12/94.
[b] If benzene is greater than 5.0 mg/kg then analyze TCLP benzene which should be <0.3 mg/l.
[c] If total lead is greater than 30 mg/kg then analyze TCLP lead which should be <1.5 mg/l.

Definitions: TCLP - toxicity characteristic leachate procedure (40 CFR 261, Appendix II)
BTEX - benzene, toluene, ethyl benzene, and total xylenes
TPH - total petroleum hydrocarbons
mg/kg - milligrams per kilogram
mg/l - milligrams per liter

TABLE 01160-2
POTENTIALLY CONTAMINATED GROUNDWATER DISCHARGE LIMITS

Parameter	Discharge to Sanitary Sewer	
	Limit	Method
TPH (mg/l)	30.0	EPA 418.1/TX 1005
Total BTEX (mg/l)	1.0	EPA 602/8020/8021
Lower Explosive Limit (%)	10	EPA 1010

Notes: See definitions above.

END OF SECTION

Section 02220

DEMOLITION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Demolishing and removing existing structures, equipment and materials.

B. Disposing of demolished materials and equipment.

C. Delivery of salvaged equipment.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. Measurement for demolition is on a lump sum basis for each contiguous area, including submittal of proposed demolition and removal schedule.

2. For removal of pavement, refer to Section 02221 - Removing Existing Pavements and Structures. For abandoned sewers, refer to Section 02222 - Abandonment of Sanitary Sewers.

3. Refer to Section 01270 - Measurement and Payment for unit price procedures.

B. Stipulated Price (Lump Sum). If the Contract is a Stipulated Price Contract, payment for work in this Section is included in the total Stipulated Price.

1.03 SUBMITTALS

A. Submittals shall conform to requirements of Section 01330 - Submittals.

B. Submit proposed methods, equipment, materials and sequence of operations for demolition of structures. Describe coordination for shutting off, capping, and removing temporary utilities. Plan operations to minimize temporary disruption of utilities to existing facilities or adjacent property.

C. Submit proposed demolition and removal schedule for approval. Notify Project Manager in writing at least 48 hours before starting demolition.

D. Submit an approved copy of demolition schedule to Fire Department prior to commencement of demolition operations.

E. Obtain a permit for building demolition, as required.

1.04 OWNERSHIP OF MATERIAL AND EQUIPMENT

A. Materials and equipment designated for reuse or salvage are listed below:

- Plug valves
- Check valves
- Electric Motors
- Lift Pumps
- Sump Pump

Protect items designated for reuse or salvage from damage during demolition, handling and storage. Restore damaged items to satisfactory condition.

B. Materials and equipment not designated for reuse or salvage become the property of the Contractor.

1.05 STORAGE AND HANDLING

A. Store and protect materials and equipment designated for reuse until time of installation.

B. Deliver items to be salvaged to City facility area at 7440 Cullen, Houston, Texas, 77051). Items will be unloaded by the Contractor.

C. Remove equipment and materials not designated for reuse or salvage and all waste and debris resulting from demolition from site. Remove material as work progresses to avoid clutter.

1.06 ENVIRONMENTAL CONTROLS

A. Minimize spread of dust and flying particles. If required by governing regulations, use temporary enclosures and other suitable methods to prevent the spread of dust, dirt and debris.

B. Use appropriate controls to limit noise from demolition to levels designated in City ordinances.

C. Do not use water where it can create dangerous or objectionable conditions, such as localized flooding, erosion, or sedimentation of nearby ditches or streams.

D. Stop demolition and notify Project Manager if underground fuel storage tanks, asbestos, PCB's, contaminated soils, or other hazardous materials are encountered.

E. Dispose of removed equipment, materials, waste and debris in a manner conforming to applicable laws and regulations.

PART 2 PRODUCTS

2.01 EQUIPMENT AND MATERIALS FOR DEMOLITION

A. Use equipment and materials approved under Paragraph 1.03, Submittals.

B. Fires are not permitted.

C. Do not use a "drop hammer" where the potential exists for damage to underground utilities, structures, or adjacent improvements.

PART 3 EXECUTION

3.01 EXAMINATION

A. Prior to demolition, make an inspection with Project Manager to determine the condition of existing structures and features adjacent to items designated for demolition.

B. Project Manager will mark or list existing equipment to remain the property of the City.

C. Do not proceed with demolition or removal operations until after the joint inspection and subsequent authorization by Project Manager.

3.02 PROTECTION OF PERSONS AND PROPERTY

A. Provide safe working conditions for employees throughout demolition and removal operations. Observe safety requirements for work below grade.

B. Maintain safe access to adjacent property and buildings. Do not obstruct roadways, sidewalks or passageways adjacent to the work.

C. Perform demolition in a manner to prevent damage to adjacent property. Repair damage to City property or adjacent property and facilities.

D. The Contractor shall be responsible for safety and integrity of adjacent structures and shall be liable for any damage due to movement or settlement. Provide proper framing and shoring necessary for support. Cease operations if an adjacent structure appears to be endangered. Resume demolition only after proper protective measures have been taken.

E. Erect and maintain enclosures, barriers, warning lights, and other required protective devices.

3.03 UTILITY SERVICES

A. Follow rules and regulations of authorities or companies having jurisdiction over communications, pipelines, and electrical distribution services.

B. Notify and coordinate with utility company and adjacent building occupants when temporary interruption of utility service is necessary.

3.04 BUILDING DEMOLITION

A. Demolish structure to the lines and grades shown on Drawings. Where no limits are shown, the limits shall be 4 inches outside new items to be installed. Removals beyond these limits shall be at the Contractor's expense; satisfactorily reconstruct excess removals.

B. Proceed with demolition from the top of the structure to the ground. Complete demolition work above each floor or tier before disturbing supporting members of lower levels.

C. Demolish concrete and masonry in small sections.

D. Carefully remove structural framing members and lower them to the ground by means of hoists, derricks or other suitable devices.

E. Do not overload existing roof or structures.

F. Provide temporary coverings for openings through walls and roof to prevent water damage to buildings and structures which are to remain.

G. Where existing concrete must be removed, but will be replaced subsequently:

1. Make initial cut with a concrete saw; do not cut reinforcement.

2. After removing concrete, cut cross bars at center of breakout and protect for subsequent concrete work.

H. Demolish structures to a minimum of 4 feet below finished grade, unless otherwise indicated on Drawings.

3.05 DISPOSAL

A. Remove from the site all items contained in or upon the structure not

designated for reuse or salvage. Conform to requirements of Section 01504 - Temporary Facilities and Controls or Section 01576 - Waste Material Disposal.

B. Follow method of disposal as required by regulatory agencies.

3.06 BACKFILL

A. Backfill holes in accordance with specification sections governing materials indicated on Drawings. Where no material is indicated, backfill with approved borrow and compact to a density of 90 percent standard Proctor.

B. Do not backfill with material from demolition unless approved by Project Manager.

3.07 MECHANICAL WORK ITEMS

A. Mechanical removals consist of dismantling and removing existing piping, pumps, motors, water tanks, equipment and other appurtenances. It includes cutting, capping, and plugging required to restore use of existing utilities.

B. Remove existing process, water, chemical, gas, fuel oil and other piping indicated to be removed on Drawings. Take out piping to the limits shown. Piping not indicated on Drawings shall be removed to the nearest solid support, capped, and the remainder left in place even though it does not interfere with new work. Purge chemical and fuel lines and tanks. Verify that such lines are safe prior to removal or capping.

C. Where piping that is to be removed passes through existing walls, cut and cap piping on each side of the wall. Use cap appropriate for pipe material to be capped. Provide fire-rated sealant for walls classified as fire-rated.

D. When underground piping is to be altered or removed, cap the remaining piping. Abandoned underground piping may be left in place unless it interferes with new work or is shown or specified to be removed. Piping less than 15 inches in diameter may be plugged and abandoned in place. For piping 15 inches in diameter and greater to be abandoned, fill with sand, pressure grout or other approved method and plug with concrete or brick masonry bulkhead.

E. Remove waste and vent piping to points shown. Plug pipe and cleanouts and plugs. Where vent stacks pass through an existing roof that is to remain, remove the stack and patch the hole in the roof, making it watertight. Comply with requirements of existing roof installer so as to maintain roof warranty.

F. Conform to applicable codes when making any changes to plumbing and

heating systems.

G. For demolition of water line, refer to Section 02516 - Cut, Plug, and Abandonment of Mains.

3.08 ELECTRICAL WORK ITEMS

A. Electrical removals consist of disconnecting and removing existing switchgear, distribution switchboards, control panels, bus duct, conduits and wires, panelboards, lighting fixtures, and miscellaneous electrical equipment.

B. Remove existing electrical equipment and fixtures to prevent damage to allow continued operation of existing systems and to maintain the integrity of the grounding systems.

C. Remove poles and metering equipment, if designated for removal on the Drawings. Coordinate electrical removals with the power company, as necessary. Verify that power is properly de-energized and disconnected.

D. Where shown or otherwise required, remove wiring in underground duct systems. Verify function of wiring before disconnecting and removing. Plug ducts which are not to be reused at entry to buildings.

E. Changes to electrical systems shall conform to applicable codes.

END OF SECTION

Section 02221S

REMOVING EXISTING PAVEMENTS, STRUCTURES, WOOD, AND DEMOLITION DEBRIS

The following supplements modify Specification Section 02221 – Removing Existing Pavements, Structures, Wood, and Demolition Debris. Where a portion of the Specification or Detail is modified or deleted by this Supplementary Specification, the unaltered portions of the Specification shall remain in effect.

1.03 REGULATORY REQUIREMENTS: Add the following Paragraph C:

C. For removal of asbestos containing materials, or material that could potentially contain asbestos, comply with applicable provisions of OSHA 29 CFR 1926.1101 – Asbestos, OSHA 29 CFR 1926.32 – General Safety and Health Provisions, and EPA 40 CFR 61 Subpart M – National Emission Standard for Asbestos.

3.01 PREPARATION: Add the following Paragraph C:

C. For removal of asbestos containing materials, or materials that could potentially contain asbestos, comply with the following:

1. Crew members must be trained in accordance with OSHA 29 CFR 1926.1101 – Asbestos.
2. Conduct negative exposure assessment to demonstrate asbestos exposure below permissible exposure limit (PEL) in accordance with OSHA 29 CFR 1926.1101 – Asbestos and EPA 40 CFR 763 – Asbestos.
3. If negative exposure assessment not conducted, or if results are above PEL, provide respiratory protection in accordance with Paragraph 3.02 of this Section.

3.02 PROTECTION: Add the following Paragraph B:

B. When required, provide respiratory protection in accordance with OSHA 29 CFR 1910.134 – Respiratory Protection, and National Institute of Occupational Safety and Health (NIOSH).

3.03 REMOVALS: Add the following Paragraph G:

G. Labeling of Asbestos Cement (AC) Pipe:

1. Label leak-tight container with warning statement of hazardous asbestos content in accordance with OSHA 29 CFR 1926.1101 and as noted below.
2. Label waste material with following warning:

DANGER
CONTAINS ASBESTOS FIBERS
MAY CAUSE CANCER
CAUSES DAMAGE TO LUNGS
DO NOT BREATHE DUST
AVOID CREATING DUST

3. Neatly print labels in letters of sufficient size and contrast so label is easily visible and legible.

3.05 DISPOSAL: Add the following Paragraph C:

C. For asbestos-containing materials:

1. Comply with 40 CFR Part 61 and 30 TAC Sections 330.137(b) for Industrial Class 1 waste.
2. Inspect load to ensure correct packaging and labeling.
3. Line vehicles with two layers of 6-mil polyethylene sheeting.
4. Remove asbestos-containing waste from site daily.

END OF SUPPLEMENT

Approved by:

Mark L. Loethen, P.E., CFM, PTOE
City Engineer
Department of Public Works & Engineering

11/17/2012
Date

Section 02511S

WATER LINES

The following supplements modify Section 02511 - Water Lines Standard Specification. Where a portion of the Specification is modified or deleted by this Supplementary Specification, the unaltered portions of the Specification shall remain in effect.

1.02 MEASUREMENT AND PAYMENT: replace Paragraph 1.02 A. 1 with the following:

1. Payment for water lines installed by open- cut or trenchless construction or aerial crossing, with or without restrained joints, with or without casing, within limits of pipe offset section or within limits of Potentially Petroleum Contaminated Area (PPCA) or within limits of Fault Hazard Zone (FHZ) is on a linear foot basis for each size of pipe installed. Payment will include welded and restrained joints, for large diameter water lines. Separate pay items are used for each type of installation:

    a. Mains: Mains Measure along axis of pipe and include fittings and valves.

    b. Branch Pipe: Measure from axis of water line to end of branch.

Insert the following paragraph:

2.05 FLEXIBLE EXPANSION JOINTS:

A. Install Flexible Expansion Joints at locations indicated on drawings, within limits of Fault Hazard Zone, in accordance with the manufacturer's recommendations.

3.01 PREPARATION: Delete Paragraph I and replace with the following:

I. If asbestos-cement (A.C.) pipe is encountered, follow safety practices outlined in OSHA 29 CFR 1926.1101 – Asbestos. Refer to Section 02221 – Removing Existing Pavements, Structures, Wood, and Demolition Debris for removing and disposing of A.C. pipe.

END OF SUPPLEMENT

Approved by:

James T. Lincoln, P.E.
City Engineer
Department of Public Works & Engineering

Date 10/21/13

Section 02524S

AIR RELEASE AND VACUUM RELIEF VALVES

The following supplements modify Section 02524 – Air Release and Vacuum Relief Valves. Where a portion of the Specification is modified or deleted by this Supplementary Specification, the unaltered portions of the Specification shall remain in effect.

Delete Paragraph 1.05A from the Specification.

1.05 QUALITY CONTROL:

A Provide manufacturer's affidavit that air release and vacuum relief valves purchased for work, were manufactured and tested in United States and conform to requirements of this Section.

END OF SUPPLEMENT

Approved by:

Ebi Nassiri, P.E.
Assistant Director,
Wastewater Engineering Section,
Engineering and Construction Division

01/16/14
Date

Section 2752S

The following supplement modifies Section 02752 Standard Specification. Where a portion of the Specification is modified or deleted by this Supplementary Specification, the unaltered portions of the Specification shall remain in effect.

1.01 SECTION INCLUDES.

Add Part C as follows.
C. Full depth saw cutting of concrete pavement as required by other agency.

1.02 MEASUREMENT AND PAYMENT

Add item 6.
6. Full depth Saw cutting for concrete pavement will be paid on linear foot base, if required by other agency for joining with existing roadway.

Renumber item 6 as 7

END OF SUPPLEMENT

Approved:

John H. Kuo, P.E.
Assistant Director
Engineering and Construction Division

12/29/09
Date

Section 02830

FENCES AND GATES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Fence framework, fabric, and accessories.

B. Excavation for post bases, concrete foundation for posts and center drop for gates.

1. Manual gates and related hardware.

1.02 MEASUREMENT AND PAYMENT

A. Payment for fencing shall be on a linear foot basis for height noted.

B. Payment for gates shall be per unit.

C. Refer to Section 01270 - Measurement and Payment for Unit Price Procedures.

1.03 REFERENCES

A. ANSI/ASTM A 123 - Zinc (Hot Dip Galvanized) Coatings on Iron and Steel Products.

B. ANSI/ASTM F 567 - Installation of Chain-Link Fence.

C. ASTM A 116 - Zinc-Coated (Galvanized) Steel Woven Wire Fence Fabric.

D. ASTM A 120 - Pipe, Steel, Black and Hot-Dipped Zinc Coated (Galvanized) Welded and Seamless, for Ordinary Uses.

E. ASTM A 153 - Zinc Coating (Hot-Dip) on Iron and Steel Hardware.

F. ASTM A 392 - Zinc-Coated Steel Chain-Link Fence Fabric.

G. ASTM A 428 - Weight of Coating on Aluminum-Coated Iron or Steel Articles.

H. ASTM C 94 - Ready-mixed Concrete.

I. ASTM D 412 – Test Methods for Rubber Properties in Tension

J. ASTM D 1499 – Recommended Practice for Operating Light- and Water-

Exposure Apparatus (Carbon-Arc Type) for Exposure of Plastics.

K. ASTM D 2240 Test Method for Rubber Property – Durometer Hardness

L. ASTM F 573 - Residential Zinc-Coated Steel Chain Link Fence Fabric.

M. ASTM F 668 - Poly (Vinyl Chloride) (PVC) Coated Steel Chain Link Fence Fabric.

N. Chain Link Fence Manufacturers Institute (CLFMI) - Product Manual.

O. FS RR-F-191 - Fencing, Wire and Post Metal (and Gates, Chain Link Fence Fabric, and Accessories).

1.04 SYSTEM DESCRIPTION

A. Fence height shall match height of existing.

B. Extension arms for barbed wire shall match existing.

C. Line post spacing shall not exceed 10 feet, or as shown on Drawings.

D. Fence material shall match existing.

E. All material shall be of the same color vinyl coating. Painted finishes are not acceptable.

F. Proposed gates shall match existing fence material and fence height.

G. Padlocks: One for each gate with 3 keys each. Padlocks keyed for the City of Houston Standard Key.

1.05 SUBMITTALS

A. Submit under provisions of Specification Section 01330 - Submittal Procedures.

B. Shop Drawings: Indicate plan layout, spacing of components, post foundation dimensions, hardware anchorage, and schedule of components.

C. Product Data: Provide data on fabric, posts, accessories, fittings, and hardware that indicates that items match or exceed the quality of existing items.

1.06 QUALIFICATIONS

A. Manufacturer: Company specializing in manufacturing the products specified in this Section with minimum three years experience.

1.07 FIELD MEASUREMENTS

A. Verify that field measurements are as indicated on shop drawings.

PART 2 PRODUCTS

2.01 GALVANIZED FENCING

A. Fence fabric shall be No. 9 steel wire, hot galvanized after weaving, to match or exceed existing fence fabric.

B. The vinyl coating shall conform to FS RR-F-191/1C. Colors shall be stabilized, and shall have a light fastness to withstand a minimum Weather-O-Meter exposure of at least 1500 hours without any deterioration when tested in accordance with ASTM D 1499. Specific gravity shall be between 1.26 and 1.30 in accordance with ASTM D792. Hardness shall be A90 +/- 5 in accordance with ASTM D 2240. Tensile strength shall be between 2600 to 3000 psi in accordance with ASTM D412. Vinyl coating shall be exposure-resistant to dilute solutions of most common mineral acids, sea-water, salts, and alkali. Vinyl coating shall be continuously bonded to the wire under 5000 psi pressure before the wire is woven into fabric. The fabric shall contain 90% privacy slats as required.

C. Framework shall be hot-dipped galvanized with a minimum coating of 2 ounces/sf, or one ounce/sf plus 30 micrograms/square-inch chromate conversion coating.

D. Line posts shall conform to ASTM A 570 Grade 45 steel or ASTM A 569, cold rolled steel.

E. End corner, angle, and pull posts shall conform to ASTM A 570 Grade 45 steel or ASTM A 569 for steel pipe.

F. Top rails shall be 1.65 x 1.25-inch formed C-section; or 1.6-inch round ASTM A 569, 1.35 lbs/ft; or 1-5/8-inch outside diameter steel pipe, 2.27 lbs/ft. Top rails shall pass through openings provided for that purpose in post tops.

G. Fabric ties shall be hog rings, galvanized steel wire not less than 9-ga with a zinc coating of not less than 1.2 ounces/sf.

H. Bolts and nuts shall be in conformance with ASTM A 307 and shall be galvanized in accordance with AASHTO M 232.

I. Install horizontal braces fabricated of 1-5/8-inch, 2.27-lb copper bearing steel pipe at all corner, gate, and end posts.

J. Bottom tension wire shall not less than 9-gauge galvanized same as ties.

K. Gates shall be either swing or slide as shown on the plans. Swing gates shall be hinged to swing 90 degrees from closed to open or hinged to swing 180 degrees from close to open. Slide gates shall be roller type with no vertical obstructions. All gate leaves shall have intermediate members and diagonal stress rods as required for rigid construction and shall be free from sag or twist. All gates shall be filted with vertical extension arms or shall have frame end number extended to carry barbed wire. Gate posts for gates shall be 4-inch, 9.1 lb pipe. Gate frames shall be made of 2-inch outside diameter, castings. Fabric shall be the same as for the fence. Gates shall have malleable iron ball and socket hinges, catches, stops and padlocks with 3 keys each. Posts for single gates shall be the same as end posts.

2.02 WOOD POSTS AND PICKETS

A. All wood posts and pickets shall be southern yellow pine pressure treated with creosote according to the American Wood Preservers Association specifications with a minimum absorption of 8 pcf.

B. 2-inch by 4-inch braces shall be southern yellow pine pressure treated same as posts.

C. Wood post domes to be dome or cut on 45-degree angle downwards toward the site.

PART 3 EXECUTION

3.01 INSTALLATION

A. Install fence in accordance with the directions of the manufacturer, these Specifications and ASTM Practice 567. PVC Coated Material shall be handled with care. If PVC coating is damaged during installation, contractor must replace or repair the material at own expense.

B. Install fence posts at not more than 10-foot centers and at least 36 inches into the ground in a Class B concrete base. Allow concrete to cure for at least 7 days before erecting remainder of fence. Fasten fabric to line posts with wire ties spaced about 14 inches apart and to top rail spaced about 24 inches apart.

C. For chain link fence, use standard chain link fence stretching equipment to stretch the fabric before tying it to the rails and posts. Repeat the stretching and tying operations about every 100 feet.

D. Stretches of fence more than 250 feet in length shall have one intermediate pull post with braces in two directions for every 250 feet.

E. Erect gates so they swing or slide in the appropriate direction. Provide gate stops as required. Secure hardware, adjust, and leave in perfect working order. Adjust hinges and diagonal bracing so that gates will hang level. Adjust rollers and guides of sliding gates so that gates are level.

F. At small natural or drainage ditches where it is not practical for the fence to conform to the contour of the ground, span the opening below the fence with wire fastened to stakes of required length. The finished fence shall be plumb, taut, true to line and ground contour. When directed, stake down the fence at several points between posts.

G. Where new fence joins an existing fence, set a corner post and brace post at the junction and brace as directed. If the connection is made at other than the corner of the new fence
the last span of the old fence shall contain a brace.

H. Tack weld all bolted connections.

END OF SECTION

THE FOLLOWING ITEMS SHOULD BE CHECKED FOR COORDINATION DURING DESIGN:

****

A. Coordinate this specification with other related specifications including the following related Sections.

RELATED SECTIONS - For use by Specifier. Do not include list in Project Specifications.
Section 03401 - Cast-in-place Concrete.

****

END OF NOTES

Section 03055

CONCRETE STRUCTURES

PART 1 GENERAL

1.01 SCOPE

A. Extent of Work: This Section governs for construction of all types of structures involving structural concrete.

B. Related Work (if utilized in this project)

1. Excavation: Per Section 02316 – Excavation and Backfill for Structures

2. Concrete: Per Section 03310 – Structural Concrete

3. Reinforcing Steel: Per Section 03211 – Reinforcing Steel

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Refer to Section 01270 – Measurement and Payment for Unit Price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

1.03 QUALITY ASSURANCE

A. Submittals: For samples, mix designs, tests and reports per Section 03310 – Structural Concrete.

B. Prior to start of work submit following information when requested:

1. Methods of construction.

2. Plans for forms and falsework.

3. Amount and type of equipment.

4. Concrete placing schedule with facilities for handling concrete shrinkage.

5. Tabulation of concrete surfaces indicating types of finish on each surface.

PART 2 PRODUCTS

2.01 MATERIALS

A. Concrete: Per Section 03310 – Structural Concrete, class as shown on Plans.

B. Expansion Joint Material: As per ASTM D1752. Furnish test results as to compliance with ASTM D545 if requested.

C. Waterstop: Manufactured from virgin polyvinyl chloride plastic compound conforming to U.S. Corps of Engineers Specification No. CRD-C572-65 and containing no scrap or reclaimed material. Unless otherwise specified or shown, water stops to conform to size and shape of Servicisized/Durajoint as manufactured by W. R. Grace & Company, Cambridge Mass. or equivalent of the type indicated as follows:

1. Expansion Joint: Type 3

2. Construction Joint: Type C2

D. Curing Materials: Unless otherwise designated on Plans, use either of the following:

1. Water Curing: Water to meet requirements for concrete mixing water, and which will not stain or leave unsightly residue.

2. Membrane Curing Compound: Per ASTM C309.

3. Cotton Mats for Curing: A filling material cotton "bat" or "bats" (min. 12 oz. per sq. yd.), covered with unsized cloth (min. 6 oz. per sq. yd.), tufted or stitched to maintain stability, free from tears, and in good general condition.

E. Forms and Falsework

1. Timber

a) Seasoned timber of good quality, free from loose or unsound knots, knot holes, twists, shakes, decay and other imperfections which would affect its strength or impair finished surface of concrete.

b) Wedges, when required, to be hardwood.

2. Metal

a) See Paragraph 3.02.D

b) Aluminum not permitted.

F. Nonshrinking Grout: Premixed grout which is nonmetallic, noncorrosive, and nonstaining; containing specially selected silica sands, cement, shrinkage compensating agents, plasticizing and water reducing agents.

1. Conform to requirements of Corps of Engineers CRD-C588. Test Method CRD-C589.

2. Yield: 0.9 cubic foot to 1.0 cubic foot per 100 pounds.

3. Mixing water per 100 pounds:

a) Stiff: 2 gallons.

b) Plastic: 2¼ gallons.

c) Flowable: 2½ gallons.

4. Minimum 28-day compressive strength of 3,000 psi.

5. Maintain grout temperature during placement between 50 degrees F and 90 degrees F.

G. Polyethelene Film for Permanent Moisture Barrier: Minimum thickness of .006-inch (six mils) and high impact strength rating.

H. Concrete Bonding Agent: Any of the following:

1. "Daraweld-C" as manufactured by W. R. Grace and Company.

2. "Bond Crete-S" as manufactured by Burke Concrete Accessories, Inc.

3. Or equivalent.

I. Paint Type Coating: Synthetic elastomer-polyester base coating containing fiberglass, mica, perlite and may be either of the following:

1. "Tex-Cote" concrete gray fine textured "Bridge Coat" (Textured Coating of America, Inc.).

2. "Scotch Shield" coatings (Preston Company).

3. Or equivalent.

PART 3 EXECUTION

3.01 GENERAL REQUIREMENTS

A. Time Sequence of Construction Operations

1. Do not place superstructure members, forms, falsework or erection equipment on substructure before concrete has cured for four days.

2. Erect forms on footings supported by piling or drilled shafts after concrete has cured for 4 days. Such work may begin on spread footings after concrete has aged at least 2 curing days.

3. Support of tie beam and/or cap forms by falsework placed on previously placed tie beams is permissible, provided curing requirements are completed and tie beams are properly supported to eliminate stresses not provided for in design.

4. For bridges and direct traffic culverts, construction traffic and traveling public permitted in accordance with the following:

a) Authorization for light construction traffic not to exceed a three-quarter ton truck may be given after last slab concrete has been in place at least 14 days.

b) Authorization for normal construction traffic and, when necessary, to traveling public may be given after last slab concrete has been in place 30 days.

5. Forms, or screed supports for bridges may be attached to I-beams or girders by welding per American Welding Society (AWS) requirements.

3.02 CONSTRUCTION

A. Forming

1. General Requirements: Design and construct to carry maximum anticipated loads and provide rigidity to prevent settlement or deformation.

2. Design Loads: Use 150 pounds per cubic foot for concrete and live load of 50 pounds per square foot of horizontal surface of form work with 125 percent of allowable stresses used for design of structures.

3. Falsework

a) Make timber sills and grillages large enough to support superimposed load without settlement.

b) Place falsework which cannot be founded on a satisfactory spread footing, on piling or drilled shafts.

c) Cap each falsework bent transversely by a member of proper size, and fasten caps securely to each pile or column in bent and set at proper elevation allowing for a construction camber.

d) Use wedges, if required, in pairs and arrange so as to ensure uniform bearing.

e) Use of wedges to compensate for incorrectly cut bearing surfaces not permitted.

B. Forms

1. General

a) Provide mortar-tight forms sufficient in strength to prevent bulging or sagging.

b) If bulging or sagging occurs remove concrete causing such condition and reset forms.

c) Remove metal alignment appliances from forms to a depth of at least ½-inch from concrete surface without undue chipping or spalling, leaving a smooth opening in the concrete surface.

i) Turning off of rods, bolts or ties not permitted.

ii) Cut wire ties back at least ½-inch from face of concrete.

iii) Prior to erection treat facing of forms with oil or other bond-breaking coating which will not discolor or otherwise injuriously affect concrete surface.

iv) Wet surface of forms to be in contact with concrete immediately before placing concrete.

C. Timber

1. Timber for facing or sheathing surfaced on at least one side and two edges.

2. Use nominal 2-inch lumber minimum thickness for forms for bottoms of beams.

3. Use lumber or nominal 1-inch minimum thickness elsewhere, generally, and back by sufficient number of studs and wales.

4. Plywood form lining made with waterproof adhesive to be ¼-inch minimum thickness, oiled at mill, and reoiled or lacquered on job before using.

5. Use tempered Masonite Concrete Form Board, 3/16-inch minimum thickness, as alternate form lining.

   a) Keep moist at least 12 hours before applying to sheathing by moistening screen side of board and stacking boards screen side to screen side.

   b) Use smooth, hard face as concrete contact surface of form.

6. Plywood forms to be minimum ¾-inch thickness made with waterproof adhesive backed by adequate studs and wales, with form lining not required.

7. Molding for chamfer strips or other uses.

   a) Redwood, cypress, or pine.

   b) Use quality which will not split when nailed and will hold true lines.

   c) Mill cut, dressed on all faces.

d) Fillet sharp corners and edges with triangular chamfer strips, ¾-inch on sides.

D. Metal

1. Lining not required.

2. Thickness of metal forms as required to maintain true shape without warping or bulging.

3. Countersink bolt and rivet heads on facing sides of metal forms.

4. Straight metal panel forms may be used for all structures with straight walls, and for those structures with curved walls only below ground level.

5. Curved metal panels may be used for all structures with curved walls.

E. Joints

1. Expansion Joints

a) Remove form from formed joints as soon as possible to permit free expansion of concrete.

b) Anchor expansion joint fillers to concrete on side of joint by means of copper wire not lighter than No. 12 B&S gage or copper nails of approved size.

c) Ensure complete separation of concrete sections by joint material.

2. Construction Joints

a) Other than those indicated, joints not permitted without written authorization.

b) Roughen previously placed concrete surface so as to expose aggregate particles.

c) Remove loose materials, and wash and scrub surface clean with stiff brooms.

d) Keep concrete surface moist for 12 hours prior to placing

adjacent concrete.

e) For horizontal joints in walls, slosh surface of concrete with coating of mortar approximately ¼-inch thick immediately prior to placing concrete thereon.

f) Use regular concrete mix, less coarse aggregate, for mortar.

g) Apply mortar on previously placed vertical surfaces by brushing, where possible, and work mortar into irregularities of surface.

F. Placing Reinforcement: Per Section 03211 – Reinforcing Steel

G. Placing Concrete

1. Seal Slabs

a) Use in all excavations for structures requiring reinforcing steel in base slab, except for retaining wall footings and bridge footings, unless shown in Plans.

b) Excavate 2-inches minimum below bottom of structural slab and pour seal slab concrete to structural slab bottom elevation.

c) Provide rough float finish.

4) No direct payment made for seal slab concrete.

2. General Requirements

a) Give advance notice before placing concrete.

b) Place concrete only after forms and reinforcing placement have been checked.

c) Discontinue pile driving and other causes of vibration until concrete has attained an age of at least 18 hours.

d) Mix, place, and finish concrete in daylight hours. If necessary to continue after daylight hours, light entire working area.

e) Do not place concrete when impending weather conditions, such as rain, sleet, or snow, threaten to impair quality of finished work.

f) If rainfall occurs during concrete placement, provide covering to protect work.

3. Handling and Transportation

a) Use method and equipment to maintain rate of placement as required to prevent cold joints.

b) Place concrete by buckets, chutes, buggies, pipes, or troughs, which prevent separation of concrete ingredients.

c) With prior written approval, use belt conveyers or pumps, and test samples at discharge end.

d) Protect concrete transported by conveyers from sun and wind, to prevent loss of slump and workability.

e) Pipes used to pump concrete to be shaded and/or wrapped with wet burlap to prevent loss of slump and workability.

f) Do not transport concrete through aluminum pipes, tubes, or other aluminum equipment.

g) Use of chutes in excess of 35-feet total length prohibited.

4. Depositing: Contractor to provide thermometer to measure temperature of concrete.

a) Equip chutes with baffles for depositing concrete on steep slopes, or make chutes in short lengths that reverse lateral direction of movement.

b) Provide downpipe at end of chute.

c) Use no slope steeper than one vertical to two horizontal.

d) Discharge concrete from chutes and troughs either vertically down inside of forms or into pockets outside of forms from which it may flow through holes left in forms.

e) Keep chutes, troughs, and pipes clean and free from coatings of hardened concrete.

f) Deposit concrete in continuous horizontal layers maximum 12-inches thick.

g) Depositing large quantities at one point and running or working it along forms not permitted.

h) Limit free fall of concrete to 4-feet, except in walls 10-inches or less in thickness, if segregation can be prevented.

i) Use tremies for placing concrete in walls over 10-inches thick.

j) Remove hardened concrete spatter ahead of plastic concrete.

k) Do not jar forms after concrete has taken initial set, or place any strain on projecting reinforcement.

l) Make tremies in sections, or provide in several lengths, so outlet may be adjusted to proper heights during placing operations.

m) Place each layer while preceding layer is still plastic, but do not allow more than one hour to elapse between placement of successive layers.

n) Apply vibrators to concrete immediately after depositing, and move throughout mass, through layer of concrete just placed and several inches into plastic layer below.

o) Consolidate concrete and flush mortar to form surfaces by continuous working with immersion-type vibrators.

p) Do not attach vibrators to forms or reinforcement.

q) Provide one standby vibrator for emergency use.

r) If excessive bleeding causes water to form on surface of concrete in tall forms, use stiffer mix.

s) In walls and deep beams, place concrete to a point approximately 1-foot below finished elevation of bottom of slab or beam to be poured monolithically with wall, and allow to settle; but to avoid a cold joint, resume placement of concrete before initial set occurs.

t) Overfill forms and screed off excess concrete after partial stiffening.

u) Placing Concrete in Cold Weather: Minimum temperature of all concrete at time of placement to be not less than 50° F.

1) Maintain slab temperatures at 50° F or above for period of 72 hours from time of placement and above 40° F for additional 72 hours.

2) Maintain temperature of all other structural elements at 40° F or above for period of 72 hours from time of placement.

3) Maintain temperature of concrete placed on or in the ground above 40° for a period of 72 hours from time of placement.

4) Protect concrete against freezing during curing period in accordance with Portland Cement Association "Design and Control of Concrete Mixtures".

5) Protect concrete from temperatures below 40° F until it has cured for a minimum of three days at 70° F or five days at 50° F. Remove and replace, at Contractor's expense, all concrete deemed unsatisfactory by Engineer.

6) Protection may consist of additional covering, insulated forms, artificial heatings, or other means approved by Engineer.

v) Placing Concrete in Hot Weather: When air temperature is above 90° F, use approved retarding agent in all exposed concrete, and in all cased drilled shafts regardless of temperature.

1) Reinforcing steel, steel beam flanges, and other surfaces in contact with concrete, to be cooled to below 90° F by means of water spray or other approved methods.

2) Concrete temperature prior to placement not to exceed 85° F, plus a maximum tolerance of 5° F. Concrete above this maximum will be rejected.

3) Reduce concrete temperature at time of placement to satisfy maximum allowable temperature by one or more of the following:

i) Addition of cold water with a subsequent addition of cement to maintain proper water-cement ratio.

Tanks or trucks used for storing or transporting water to be insulated or painted white. Mechanical refrigeration may be used to reduce water temperatures.

ii) Addition of crushed, shaved, or chipped ice directly into the mixer with a subsequent addition of cement to maintain proper water-cement ratio. Continue mixing until ice is completely melted.

iii) Other approved methods.

w) Placing concrete in water.

1) Only when authorized, use concrete mix with minimum 6.5 sacks cement per cubic yard of concrete.

2) Forms, cofferdams, or caissons to be sufficiently tight to prevent water current passing through space in which concrete is being deposited.

3) Pumping water not permitted during placing, nor until concrete with tremie, closed bottom-dump bucket, or other approved method, to avoid free fall through water.

4) Do not disturb concrete after depositing, and maintain horizontal layers at all times.

5) Use watertight tube 10-inches or less in diameter for tremie and constructed, so that bottom can be sealed and opened after it is in place and fully charged with concrete.

6) Support tremie to allow easy movement horizontally to cover work area and vertically to control concrete flow.

7) Stop flow by lowering tremie.

8) Capacity of bottom-dump buckets not less than one-half cubic yard.

9) Lower bucket or tremie gradually and carefully to rest upon concrete already placed and raise very slowly during upward travel, intent being to maintain still water at point of discharge and to avoid agitating mixture.

10) Pour concrete continuously until work is completed.

x) Placing Concrete on Ground

1) Place concrete in footings after depth and character of foundation is observed.

2) Place footing concrete upon seal slabs after caissons or cofferdams are free from water and seal surface cleaned.

3) Locate pumps or bailing equipment in sump outside of forms.

4) Immediately before placing concrete, moisten subgrade to decrease absorption of moisture, if seal slab or waterproofing not required.

5) With prior authorization, side forms in dry excavation may be omitted.

6) Place column concrete monolithically unless otherwise provided.

H. Curing Concrete

1. Keep forms tight against concrete, or remove an start curing operations.

2. Length of Curing

a) Cure concrete for six consecutive curing days.

b) Cure high-early-strength concrete for three consecutive curing days.

c) Cure bridge slabs and top slabs of direct traffic culverts for 10 consecutive curing days.

3. Definition of Curing Day

a) "Curing day" is any calendar day during in which the temperature, taken in the shade and away from artificial heat, is above 50° F for at least 19 hours (or colder days if satisfactory provisions are made to maintain the temperature at all surfaces of the concrete above 40° F for the entire 24-hour day).

b) Required curing period begins when all concrete therein has attained initial set.

4. Curing Methods

a) Water Curing: Keep all exposed concrete surfaces wet continuously for required curing time.

1) Place wet cotton mats as soon as possible after surface has hardened sufficiently to prevent damage to concrete.

2) Weight mats down to provide continuous contact with all concrete surfaces.

3) Use overlapping water sprays or sprinklers that keep all unformed surfaces continuously wet.

4) Use minimum 2-inches clean, granular material kept wet at all times or minimum 1-inch depth of water.

5) Provide dam or similar procedure to retain water or saturated sand.

b) Membrane Curing

1) Deliver curing compound in original containers showing name of compound, manufacturer, and batch number.

2) Spray compound, using pressure-tank type spraying equipment, and keep thoroughly mixed during application.

3) Apply in single, uniform coating at rate of coverage recommended by manufacturer, but not less than 1 gallon per 180 square feet of area.

4) Apply to walls immediately after form removal or after first rubbing, as applicable.

5) Apply on slabs immediately after finishing or after excess moisture has disappeared.

6) Keep in place and protect against abrasive action for 10 days to obtain curing equivalent to a 6-day moist curing.

7) Protect against any traffic and apply protective coating no sooner than 24 hours after application of membrane curing compound.

8) Immediately repair any damage to membrane.

9) Do not use on surface to receive first rubbing with No. 16 carborundum stone, surfaces to be painted, or to which waterproofing material or liquid floor hardener is to be applied, and surfaces on which additional concrete is to be placed.

10) Use on surfaces which cannot be cured satisfactorily with mats, when so directed.

I. Removal of Forms and Falsework

1. Remove forms from surface to receive rubbed finish when concrete has attained adequate strength to prevent damage, and remove only as rapidly as rubbing operation progresses.

2. Rewet wood forms or form lining left in place longer than 24 hours as required to keep them moist.

3. Remove forms and falsework from portions of structures that do not require rubbed finish, after the following number of curing days:

a) Forms for falsework under slabs, beams or girders - 7 days.

b) Forms for walls, columns and piers - 2 days.

4. If cold weather continues below 40° F, form and falsework may be removed at the end of a period of calendar days equal to twice the number of curing days specified.

J. Defective Work: Any defective work discovered after form removal to be repaired or replaced immediately at Contractor's expense.

K. Concrete Surface Finish: For concrete having no special finish indicated, remove ties, fill holes, and remove fins and rough edges.

1. Monolithic Finish

a) Finish slabs, platforms, and steps monolithically between joints.

b) Set screeds prior to concrete placement, and make sufficiently rigid to withstand impact of concrete being placed.

c) Tamp concrete thoroughly to force coarse aggregate away from surface of slab, then float to secure hard surface.

d) Provide wood float finish, except use steel-trowel finish for building and pump station floor slabs, and elsewhere as indicated on Plans, unless otherwise directed.

e) "Dusting" floor surfaces with dry material not permitted.

f) Round edges at all expansion joints with suitable jointing or edging tools.

2. Linseed Oil Treatment

a) Unless otherwise shown on Plans, upper surfaces of bridge roadway slab only to receive a linseed oil treatment.

b) Material to consist of boiled linseed oil and mineral spirits for ambient temperature range above 40° F. Boiled linseed oil and kerosene may be used for ambient temperature range above 70° F. Ship materials combined in a mixture containing a minimum of 50 percent and a maximum of 70 percent boiled linseed oil by volume, and to meet the following:

1) Boiled Linseed Oil per ASTM D260-61 Type 1.

2) Mineral Spirits per ASTM D235-77.

3) Kerosene per Federal Specification VV-K-211d.

c) Broom, air blast, or clean by other approved means the surface, to remove laitance, oil, or grime accumulation, which may retard or prevent absorption of the mixture by concrete. Concrete surface to be dry and ambient temperature to be above 40° F at time of application. Do not apply treatment earlier than 14 days after concrete placement when moist curing is used.

d) Unless otherwise shown on Plans, apply material in two stages at the rate of 40 square yards per gallon for the first stage, and approximately 67 square yards per gallon for the second stage, for a total coverage of approximately 25 square yards per gallon. Do not make second application until 24 hours after first application.

Make application with herbicide, insecticide, or similar type spray machine equipment with a spray bar. In isolated cases, make application using a hand-operated pressure pump equipped with spray nozzle.

e) Traffic not permitted on treated surfaces for minimum of 24 hours per final application.

L. Exposed Aggregate Panels

1. Forms for raised panels to be sandblasted may be removed on the day following concrete placement (about 18 hours). Continue curing after sandblasting.

2. Immediately after form removal, sandblast to a depth of from 3/8-inch to 5/8-inch.

3. Protect smooth surfaces adjacent to sandblasted panels during sandblasting.

4. Coarse aggregate for raised panels range from Standard No. 4 to 1½-inch gradation.

5. Exposed aggregate sandblasted surfaces are to receive a coat of Prime-A-Pell 200 as manufactured by Chemproke Corp., Garland, Texas, or equivalent. Preparatory work, application, and precautions in strict compliance with manufacturer's recommendations.

M. Rub-Finished Surfaces

1. General: Rub-finish exposed vertical and battered surfaces from 6-inches below ground surface or from 6 inches below normal water level to top, except for small plinths and similar structures which extend less than 12-inches above finished grade.

2. Procedure

a) Start rubbing operations when concrete has attained adequate strength for form removal (about 18 hours after concrete placement). Continue curing afterwards.

b) Do necessary pointing as forms are removed.

c) Remove forms only as rubbing progresses in order to prevent rapid hardening of surface to be rubbed.

d) After pointing has set, wet surface with brush and give first surface rubbing with No. 16 carborundum stone or equal.

e) Rub sufficiently to bring surface to paste and to produce smooth dense surface without irregularities.

f) Do not add cement to form surface paste.

g) Spread or brush material, which has been ground to paste, uniformly over surfaces and allow to take reset.

h) Do not rub chamfered corner in first rubbing.

i) Complete first rubbing within 36 hours after completion of concrete placement.

j) For final acceptance, clean surfaces of structure and give final finish rubbing with No. 30 carborundum stone or equal.

k) After rubbing, strip surfaces with brush and allow mortar on surface to take reset; then wash surface with clean water.

l) Leave structure with clean, neat, and uniform appearing finish.

N. Paint Type and Grout Finishes: When specified on Plans or by Special Provision, the following alternative procedures to rubbing apply.

1. Adhesive Grout Coating

a) Perform first rub to eliminate rough surfaces, then give surface a coating of latex-base adhesive grout of approximately 1/8-inch thickness.

b) Apply grout by rubbing with sponge rubber float or similar applicator.

c) Mix to be one part latex-base adhesive, two parts white cement, two parts natural cement, two parts fine masonry sand, and sufficient water to produce desired consistency and color.

2. Paint Type Coating

a) Perform first rub to eliminate rough surfaces before applying paint-type coating as specified in Paragraph 2.M.

b) Furnish sample of coating selected, for approval, before application to concrete surfaces.

O. Patching and Filling Holes

1. Tie and Bolt Holes

a) Fill holes with cement mortar to which has been added white cement so that patches will not appear darker than adjacent concrete surface.

b) Use mortar as dry as possible and pack into holes.

c) Fill holes, entirely through concrete, with nonshrinking grout from inside structure with a pressure gun or other device that will force mortar through to outside face.

d) Strike off excess mortar flush and finish surface to make filled holes as inconspicuous as possible.

2. Honeycomb and Minor Defects

a) Patch slight honeycomb and minor defects in concrete with cement mortar mixed one part cement to two parts fine aggregate. Match color of adjacent concrete.

b) Repair area by cutting out unsatisfactory material by chipping or other approved methods and replace with new concrete, securely keyed and bonded to old concrete, and finish so as to make joints as inconspicuous as possible. Use stiff mixture and thoroughly tamp into place.

P. Waterstops

1. Secure complete embedment of waterstop into concrete.

2. Make waterstops continuous by heat sealing at splices as recommended by manufacturer. Miter waterstops at directional changes, and butt weld straight splices.

3. Place concrete around splice only after inspection.

Q. Grouting

1. Headworks

a) Prepare slab to receive grout using bonding agent specified in Paragraph 2.01.H in accordance with manufacturer's recommendation.

b) Use grout mixture of one part Portland cement and three parts sand by weight.

c) Surface receiving bonding agent shall be free of dirt, grease, and other foreign substances before placement of bonding agent.

d) Placing Grout

1) Do not deposit large quantities at one point.

2) Use clarifier mechanism operated by hand only for final screeding.

3) Do not allow grout to build up in front of mechanism greater than three inches.

2. For Setting New Equipment

a) Use nonshrinking grout as specified in Paragraph 2.01.F.

b) Blow out bolt holes.

c) Chip concrete to obtain firm bond.

d) Set grout forms true, level, tight, and well braced.

e) Assemble equipment to be grouted before grouting.

f) Clean baseplates and all items to be embedded and set in final position.

g) Shim equipment bases for easy removal of shims.

h) Moisten area to receive grout.

i) Do not mix more grout than can be placed in 20 minutes.

j) Place grout from one end or side only to avoid excessive air entrapment and assure good compaction.

k) Work and rod grout continuously while it is being placed.

l) After grout has attained full strength, remove shims.

m) Replace grout damaged by shim removal with like material.

n) Steel trowel exposed grout, and protect exposed area from drying out rapidly.

o) Do not stress items embedded in grout, and do not operate equipment for 36 hours after grout is placed.

3. Other Grouting

a) For general purposes, use mixture of one part Portland cement and two parts sand by weight.

b) If space to be grouted is one inch or less in thickness and cannot be tamp grouted, use a mixture of one part Portland cement and one part sand by weight.

c) If space to be grouted is large, use original concrete mixture.

d) For grout to be tamped, use stiff mixture produced by prolonged mixing.

e) To obtain stiff grout, mix mortar using amount of water required to thoroughly mix ingredients, then continue mixing without additional water until grout is stiff enough to be compacted by tamping when placed.

f) For grouting blockouts, embedded pipes, and similar items, use nonshrinking grout as per Paragraph 2.01.F of this specification.

R. Cleanup: Clean up area and remove excess material, dismantled forms and falsework, and debris during construction; and clean area completely and thoroughly after completion of the work herein described.

END OF SECTION

Section 03151

JOINTS IN CONCRETE STRUCTURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Waterstops and similar joints in concrete structures intended to retain water or withstand hydrostatic pressure.

1.02 UNIT PRICES

A. No separate payment will be made for joints under this Section. Include payment in unit price for structural concrete.

B. Refer to Section 01270 - Measurement and Payment for unit price procedures.

1.03 REFERENCES

A. ASTM A 775 - Standard Specification for Epoxy-Coated Reinforcing Steel Bars.

B. ASTM C 920 - Specification for Elastomeric Joint Sealants.

C. ASTM D 412 - Test Methods for Rubber Properties in Tension.

D. ASTM D 624 - Test Method for Rubber Property - Tear Resistance.

E. ASTM D 638 - Test Method for Tensile Properties of Plastics.

F. ASTM D 746 - Test Method for Brittleness Temperature of Plastics and Elastomers by Impact.

G. ASTM D 747 - Test Method for Apparent Bending Modulus of Plastics by Means of a Cantilever Beam.

H. ASTM D 1056 - Specification for Flexible Cellular Materials - Sponge or Expanded Rubber.

I. ASTM D 1752 - Specification for Preformed Sponge Rubber and Cork Expansion Joint Fillers for Concrete Paving and Structural Construction.

J. ASTM D 2000 - Specification for Rubber Products in Automotive Applications.

K. ASTM D 2240 - Test Method for Rubber Property - Durometer Hardness.

L. ASTM D 2241 - Specification for PVC Tubing.

M. Federal Specification SS-S-210A - Sealing Compound, Preformed Plastic for Expansion Joints and Pipe Joints.

N. Federal Specification TT-S-0227E(3) Sealing Compound, Elastomeric Type, Multi-Component, for Caulking, Sealing, and Glazing Buildings and Other Structures.

O. U.S. Army Corps of Engineers Specification CRD-C 572 PVC Waterstop.

1.04 DEFINITIONS

A. The following definitions refer to concrete joints in water-retaining structures. Unless otherwise indicated, all such joints shall have a waterstop or sealant groove to prevent water penetration at the joint.

B. Construction Joint: The joint or surface between two concrete pours, produced by placing fresh concrete in contact with a hardened concrete surface.

1. A bond breaker may or may not be used, as indicated.

2. Reinforcing steel is continuous through the joint, unless otherwise indicated.

C. Contraction Joint: A joint similar to a construction joint, but intended to accommodate concrete shrinkage and similar movement.

1. A bond breaker is always used.

2. Reinforcing steel is held back 4-1/2 inches from the joint surface, and sleeved dowels are used so pours can move apart, unless otherwise indicated.

D. Expansion Joint: A joint similar to a construction or contraction joint, but intended to accommodate both expansion and contraction.

1. Compressible joint filler is placed against the hardened concrete, to form and separate the second pour so pours can move together or apart.

2. A centerbulb waterstop and joint sealant are used to fill the gap, unless otherwise indicated.

3. Reinforcing steel is held back, and sleeved dowels are used to allow and control movement, unless otherwise indicated.

E. Control Joint: A groove cut or formed in the face of a single pour, producing a weaker plane more likely to crack; used in an attempt to control locations of normal shrinkage cracks.

1. Joint sealant is used to fill the groove.

2. Reinforcing steel is continuous, since the pour is monolithic.

1.05 SUBMITTALS

A. Submit under provisions of Section 01330 – Submittal Procedures.

B. Product Data: Information sufficient to indicate compliance with Contract Documents, including manufacturer's descriptive literature and specifications.

C. Shop Drawings: Indicate type, size, and location of each joint in each structure, and installation details.

D. Samples: For extrusions, submit 6-inch lengths. For molded or fabricated items, submit whole items. Submit 6-inch beads for sealants and 6-inch square samples for coatings, on appropriate substrates.

E. Quality Control Submittals: Submit manufacturer's instructions and recommendations for storage, handling and installation including material safety data sheets, and, where specified, test reports certified by an independent testing laboratory or the manufacturer, and manufacturer's certification that products furnished comply with Contract Documents.

1.06 QUALITY ASSURANCE

A. Waterstop Inspection: Notify City Engineer to schedule inspection at least 24 hours prior to work involving waterstop installation or fabrication of waterstop field joints.

B. Defects include but are not limited to the following:

1. Offsets at joints greater at any point than 1/16 inch or 15 percent of material thickness, whichever is less.

2. Exterior cracks at joints due to incomplete bond, which are deeper at any point than 1/16 inch or 15 percent of material thickness, whichever is less.

3. At any point, any combination of offsets or exterior cracks resulting in a net reduction in the cross-sectional area of the waterstop greater than 1/16 inch or 15 percent of material thickness at any point, whichever is less.

4. Misalignment of joint resulting in misalignment of the waterstop in excess of 1/2 inch in 10 feet.

5. Porosity in the welded joint as evidenced by visual inspection.

6. Bubbles or inadequate bond which can be detected with a pen knife. If, while probing the joint with the point of a pen knife, the knife breaks through the outer portion of the weld into a bubble, the joint is defective.

C. Field Joint Samples: Prior to use of the waterstop material in the field, fabricate and submit for review a sample of a fabricated mitered cross and a tee constructed of each size or shape of material to be used. Fabricate samples so material and workmanship represent fittings to be furnished. Field samples of fabricated fittings (crosses, tees, etc.) will be selected at random by the City for testing by a laboratory at City's expense; they shall have a tensile strength across the joints equal to at least 600 psi when tested in accordance with ASTM D 638. Contractor shall pay cost of failed tests and retesting required by failures.

D. Construction Joint Sealant: Prepare adhesion and cohesion test specimens, as specified, at intervals of 5 working days while sealants are being installed.

E. Sealant material shall show no signs of adhesive or cohesive failure when tested in accordance with the following procedure in laboratory and field tests:

1. Prepare sealant specimen between 2 concrete blocks (1 inch by 2 inches by 3 inches); spacing between the blocks shall be 1 inch. Use coated spacers (2 inches by 1-1/2 inches by 1/2 inch)

to ensure sealant cross-sections of 1/2 inch by 2 inches with a width of 1 inch.

2. Cast and cure sealant according to manufacturer's recommendations except that curing period shall be not less than 24 hours.

3. Following curing period, widen the gap between blocks to 1-1/2 inches. Use spacers to maintain this gap for 24 hours prior to inspection for failure.

F. Sealant Installer: A competent waterproofing specialty contractor, approved by sealant manufacturer, having a record of successful performance in similar installations. Before beginning work, sealant manufacturer's representative shall instruct installer's crew in proper method of application.

1.07 WARRANTY

A. Provide a written warranty covering entire sealant installation against faulty and incompatible materials and workmanship, and agreeing to repair or replace defective work at no additional cost to the City, for a period of 5 years.

1.08 DELIVERY, STORAGE AND HANDLING

A. Deliver, store and handle materials in accordance with manufacturer's printed instructions.

B. Store waterstops to permit free circulation of air around waterstop material.

PART 2 P R O D U C T S

2.01 EPA POTABLE CLASSIFICATION

A. All joint materials shall be materials that reach acceptability for use in potable water systems no later than 30 days after installation, as classified by the Environmental Protection Agency.

2.02 PVC WATERSTOPS

A. Extrude from virgin polyvinyl chloride elastomer. Use no reclaimed or scrap material. Submit waterstop manufacturer's current test reports and manufacturer's written certification that the material furnished meets or

exceeds Corps of Engineers Specification CRD-C572 and other specified requirements.

B. Flat Strip and Center-Bulb Waterstops: As detailed, and as manufactured by: Kirkhill Rubber Co., Brea, California; Water Seals, Inc., Chicago, Illinois; Progress Unlimited, Inc., New York, New York; Greenstreak Plastic Products Co., St. Louis, Missouri; or equal acceptable to the City Engineer, provided that at no place shall waterstop thickness be less than 3/8 inch.

C. Multi-Rib Waterstops: As detailed, and as manufactured by Water Seals, Inc., Chicago, Illinois; Progress Unlimited, Inc., New York, New York; Greenstreak Plastic Products Co., St. Louis, Missouri; or equal acceptable to the City Engineer. Use prefabricated joint fittings at intersections of ribbed-type waterstops.

D. Other Waterstops: When types of waterstops not listed above are indicated on the Drawings, they are subject to these specifications.

E. Waterstop Properties: When tested in accordance with specified standards, waterstop material shall meet or exceed the following requirements:

Physical Property, Sheet Material	Value	ASTM Standard
Tensile Strength-min (psi):	1750	D638, Type IV
Ultimate Elongation-min (percent):	350	D638, Type IV
Low Temp Brittleness-max (degrees F):	-35	D746
Stiffness in Flexure-min (psi):	400	D747
Accelerated Extraction (CRD-C572) -		
Tensile Strength-min (psi):	1500	D638, Type IV
Ultimate Elongation-min (percent):	300	D638, Type IV
Effect of Alkalies (CRD-C572) -		
Change in Weight (percent):	+0.25/-0.10	------
Change in Durometer, Shore A:	+5	D2240
Finished Waterstop -		
Tensile Strength-min (psi):	1400	D638, Type IV
Ultimate Elongation-min (percent):	280	D638, Type IV

2.03 JOINT SEALANT

A. Material: Polyurethane polymer designed for bonding to concrete which is continuously submerged in water. Use no material with an unsatisfactory history of bond or durability when used in joints of liquid-retaining structures.

B. Sealant Properties at 73 degrees F, 50 percent relative humidity:

1.	Work Life:	45 - 180 minutes
2.	Time to Reach 20 Shore A Hardness (at 77 degrees F, 200 gr quantity):	24 hours, maximum
3.	Ultimate Hardness (ASTM D 2240):	20 - 45 Shore A
4.	Tensile Strength (ASTM D 412):	200 psi, minimum
5.	Ultimate Elongation (ASTM D 412):	400 percent, minimum
6.	Tear Resistance (Die C ASTM D 624):	75 pounds per inch of thickness, minimum
7.	Color:	Light Gray

C. Polyurethane Sealants for Waterstop Joints in Concrete:

1. Sealant: 2-part polyurethane; when cured, sealant shall meet or exceed ANSI/ASTM C 920 or Federal Specification TT-S-0227 E(3) for 2-part material.

2. Vertical and overhead horizontal joints: Use only "non-sag" compounds meeting ANSI/ASTM C 920, Class 25, Grade NS, or Federal Specification TT-S-0227 E(3), Type II, Class A.

3. Plane horizontal joints: Self-leveling compounds meeting ANSI/ASTM C 920, Class 25, Grade P, or Federal Specification TT-S-0227 E(3), Type I. For joints subject to either pedestrian or vehicular traffic, use a compound providing non-tracking characteristics and having a Shore A hardness range of 35 to 45.

4. Primer: Use only compatible materials manufactured or recommended for the application by the sealant manufacturer, in accordance with the printed instructions and recommendations of the sealant manufacturer.

D. Acceptable Products: Polymeric Systems Inc. "PSI-270"; Pacific Polymers "Elastothane 227R"; Sika Corporation "Sikaflex 2C", or equal acceptable to the City Engineer.

E. Sealants for non-waterstop joints: Conform to Section 07920 - Sealants and Caulking.

2.04 MISCELLANEOUS MATERIALS

A. Bearing Pad: ASTM D 2000 neoprene, Grade 2 or 3, Type BC, tensile strength 1450 psi, 60 durometer hardness, unless otherwise indicated.

B. Neoprene Sponge: ASTM D 1056, Type 2C3-E1 closed-cell expanded neoprene.

C. Preformed Joint Filler: ASTM D 1752 Type I non-extruding type; neoprene sponge or polyurethane of firm texture, except as otherwise specified. Bituminous fiber type will not be permitted.

D. Control Joint Former: Continuous plastic insert strips with anchorage ribs located at the bottom and an enlarged upper portion that is readily removable without damage to the concrete, and is sized to form sealant groove. Size to extend to at least 1/4 slab depth.

E. Backing Rod: Extruded closed-cell polyethylene foam rod, compatible with joint sealant materials used, with a tensile strength not less than 40 psi, and compression deflection approximately 25 percent at 8 psi. Size: 1/8-inch larger in diameter than joint width, except use one-inch diameter rod for 3/4-inch wide joints.

F. Bond Breaker: "Super Bond Breaker" manufactured by Burke Company, San Mateo, California; "Select Cure CRB", manufactured by Select Products Co., Upland, California, or equal acceptable to the City Engineer. Bond breaker shall contain a fugitive dye so areas of application will be readily distinguishable.

G. Slip Dowels: Smooth epoxy-coated bars conforming to ASTM A 775.

H. PVC Tubing: ASTM D 2241, Schedule SDR 13.5.

2.05 RESILIENT WATERSTOP

A. Resilient waterstop, where called for on the Drawings, shall be either a bentonite or adhesive type material.

B. Bentonite Waterstop:

1. Material: 75 percent bentonite, mixed with butyl rubber-hydrocarbon containing less than 1.0 percent volatile matter, and free of asbestos fibers or asphaltics.

2. Manufacturer's rated temperature ranges: For application, 5 to 125 degrees F; in service, -40 to 212 degrees F.

3. Cross-sectional dimensions, unexpanded waterstop: One inch by 3/4 inch.

4. Provide with adhesive backing capable of producing excellent adhesion to concrete surfaces.

C. Adhesive Waterstop:

1. Adhesive waterstop shall be at least 2 inches in diameter and shall be Synko-Flex preformed plastic adhesive waterstop by Synko-Flex Products, Inc., or equal. The waterstop shall meet or exceed requirements of Federal Specification SS-S-210A.

2. The adhesive waterstop shall be supplied wrapped completely by a two part protective paper.

3. The adhesive waterstop material shall have independent laboratory tests verifying that the material seals joints in concrete against leakage when subjected to a minimum of 30 psi water pressure for at least 72 hours.

4. Primer, to be used on hardened concrete surfaces, shall be provided by the same manufacturer as the waterstop material.

PART 3 EXECUTION

3.01 INSTALLATION

A. Embed waterstops in concrete across joints as shown. Waterstops shall be continuous for the extent of the joint; make splices necessary to provide such continuity in accordance with manufacturer's instructions. Support and protect waterstops during construction operations; repair or replace waterstops damaged during construction.

B. Install waterstops in concrete on one side of joints, leaving other side exposed until the next pour. When a waterstop will remain exposed for 2 days or more, shade and protect the exposed waterstop from direct rays of the sun during the entire exposure and until the exposed portion of the waterstop is embedded in concrete.

3.02 SPLICES IN WATERSTOPS

A. Splice waterstops by heat-sealing adjacent waterstop sections in accordance with the manufacturer's printed instructions.

1. Do not damage material by heat sealing.

2. Splice tensile strength: At least 60 percent of unspliced material tensile strength.

3. Maintain continuity of waterstop ribs and tubular center axis.

B. Butt end-to-end joints of 2 identical waterstop sections may be made in the forms during placement of waterstop material.

C. Prior to placement in formwork, prefabricate all waterstop joints involving more than 2 ends to be joined together, an angle cut, an alignment change, or the joining of 2 dissimilar waterstop sections, allowing not less than 24-inch long strips of waterstop material beyond the joint. Upon inspection and approval by the City Engineer, install prefabricated waterstop joint assemblies in formwork, and butt-weld ends of the 24-inch strips to the straight-run portions of waterstop in the forms.

D. Where a centerbulb waterstop intersects and is joined to a non-centerbulb waterstop, take care to seal the end of the centerbulb, using additional PVC material if needed.

3.03 JOINT CONSTRUCTION

A. Setting Waterstops:

1. Correctly position waterstops during installation. Support and anchor waterstops during progress of the work to ensure proper embedment in concrete. Locate symmetrical halves of waterstops equally between concrete pours at joints, with center axis coincident with joint openings. Thoroughly work concrete in joint vicinity for maximum density and imperviousness.

2. Flat-strip waterstop: Prevent folding over by concrete during placement. Unless otherwise shown, hold waterstops in place with wire ties on 12-inch centers passed through the waterstop edge and tied to reinforcing steel.

a. Horizontal waterstops (with flat face in vertical plane): Hold in place by fastening upper waterstop edge to continuous supports.

b. Horizontal waterstops (with flat face in horizontal plane): Work concrete under waterstops by hand to eliminate air and rock pockets.

3. Place centerbulb waterstops in expansion joints centered on joint filler material.

4. Where a waterstop in a vertical wall joint does not connect with any other waterstop, and is not intended to be connected to a waterstop in a future concrete placement, terminate the waterstop 6 inches below the top of the wall.

B. Joint Location: Unless specifically noted otherwise, provide construction joints at 25-foot maximum spacing for concrete construction. Where joints are shown spaced greater than 40 feet apart, provide additional joints to maintain the 25-foot maximum spacing. Submit joint locations for review by the City Engineer.

C. Joint Preparation: Prepare surfaces in accordance with Section 03310 - Structural Concrete. Unless otherwise indicated, bonding is required at horizontal concrete joints in walls. Except on horizontal wall construction joints, wall-to-slab joints, or where otherwise shown or specified, at joints where waterstops are required, coat the joint face of the first pour with bond breaker as specified.

D. Replacement of Defective Field Joints: Replace waterstop field joints showing evidence of misalignment, offset, porosity, cracks, bubbles, inadequate bond or other defects with products and joints complying with Contract Documents.

E. Construction Joint Sealant:

1. In water-bearing floor slabs and elsewhere where indicated, provide construction joints with tapered grooves filled with construction joint sealant. Leave groove- forming material in place until time grooves are cleaned and filled with joint sealant. After removing groove forms, remove laitance and fins and sand-blast the grooves. Allow grooves to dry thoroughly, then blow out, immediately prime surfaces, place bond-breaker tape in bottom of groove and fill with construction joint sealant. Use no sealant without a primer. Completely fill sealant grooves. Thoroughly clean areas designated to receive sealant, as specified for tapered grooves, prior to sealant application.

2. Mix and install primer and sealant in accordance with manufacturer's printed instructions and recommendations. Do not coat sides of sealant groove with bond breaker, curing compound or other substance which would interfere with proper sealant bond. Allow at least 7 days for sealant to achieve final cure before filling structure with water.

3. Thoroughly and uniformly mix 2-part catalyst-cured material.

4. Remove and replace improperly cured sealants after the manufacturer's recommended curing time; thoroughly sandblast the groove to remove all traces of uncured or partially-cured sealant and primer, then re-prime and re-seal with specified sealant.

F. Resilient Waterstop:

1. Install resilient waterstop in accordance with manufacturer's instructions and recommendations except as otherwise indicated and specified.

2. When requested by the Project Manager, provide technical assistance by manufacturer's representative in the field at no additional cost to the City.

3. Use resilient waterstop only where complete confinement by concrete is provided; do not use in expansion or contraction joints.

4. Where resilient waterstop is used in combination with PVC waterstop, lap resilient waterstop over PVC waterstop a minimum of 6 inches and place in contact with the PVC waterstop. Where crossing PVC at right angles, melt PVC ribs to form a smooth joining surface.

5. At the free top of walls without connecting slabs, stop the resilient waterstop and grooves (where used) 6 inches from the top in vertical wall joints.

6. Bentonite Waterstop:

   a. Locate bentonite waterstop as near as possible to the center of the joint and extend continuous around the entire joint. Minimum distance from edge of waterstop to face of member: 5 inches.

b. Where thickness of the concrete member to be placed on the bentonite waterstop is less than 12 inches, place waterstop in grooves at least 3/4 inch deep and 1-1/4 inches wide formed or ground into the concrete. Minimum distance from edge of waterstop placed in groove to face of member: 2.5 inches.

c. Do not place bentonite waterstop when waterstop material temperature is below 40 degrees F. Waterstop material may be warmed so that it remains above 40 degrees F during placement but means used to warm it shall in no way harm the material or its properties. Do not install waterstop where air temperature falls outside manufacturer's recommended range.

d. Place bentonite waterstop only on smooth and uniform surfaces; grind concrete smooth if necessary to produce satisfactory substrate, or bond waterstop to irregular surfaces using an epoxy grout which completely fills voids and irregularities beneath the waterstop material. Prior to installation, wire brush the concrete surface to remove laitance and other substances that may interfere with bonding of epoxy.

e. In addition to the adhesive backing provided with the waterstop, secure bentonite waterstop in place with concrete nails and washers at 12-inch maximum spacing.

7. Adhesive Waterstop:

a. Thoroughly clean the concrete surface on which the waterstop is to be placed with a wire brush and coat with primer.

b. If the surface is too rough to allow the waterstop to form a complete contact, grind to form an adequately smooth surface.

c. Install the waterstop with the top protective paper left in place. Overlap joints between strips a minimum of 1 inch and cover back over with the protective paper.

d. Do not remove protective paper until just before final formwork completion. Concrete shall be placed immediately. The time that the waterstop material is uncovered prior to concrete placement shall be minimized and shall not exceed 24 hours.

G. Control Joints:

1. Where indicated, form in slabs by sawcutting, preformed plastic

inserts or other means acceptable to City Engineer. Minimum insert or sawcut: 1/4 slab depth.

2. Perform sawcutting during the curing period as soon as possible after concrete has reached its final set, has attained sufficient strength to support sawcutting operations without damage, and while it remains fully saturated.

3. Leave the removable portion of plastic inserts in place and protect sawcuts against damage and intrusion of foreign material until the end of the curing period and until concrete has dried sufficiently to allow sealant installation.

4. Sealant Installation: Blow foreign material from formed or sawcut space. Insert a foam backer rod to form a sealant depth equal to the width of the space but not less than 3/8 inch. Install sealant as specified elsewhere in the Contract Documents.

END OF SECTION

Section 03211

REINFORCING STEEL

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Structural concrete reinforcement and grouting of reinforcement dowel bars into hardened concrete.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Measurement for reinforcing steel installed as extra work is on a per-pound basis.

3. Refer to Section 01270 - Measurement and Payment for unit price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

1.03 REFERENCES

A. ACI 315 - Details and Detailing of Concrete Reinforcement.

B. ACI 318 - Building Code Requirements for Reinforced Concrete.

C. ASTM A 36 - Standard Specification for Structural Steel.

D. ASTM A 82 - Standard Specification for Steel Wire, Plain, for Concrete Reinforcement.

E. ASTM A 185 - Standard Specification for Steel Welded Wire Fabric, Plain, for Concrete Reinforcement.

F. ASTM A 497 - Standard Specification for Steel Welded Wire Fabric, Deformed, for Concrete Reinforcement.

G. ASTM A 615 - Standard Specification for Deformed and Plain Billet-Steel Bars for Concrete Reinforcement.

H. ASTM A 675 - Standard Specification for Steel Bars, Carbon, Hot-Wrought, Special Quality, Mechanical Properties.

I. ASTM A 775/A 775M - Standard Specification for Epoxy-Coated Reinforcing Steel Bars.

J. ASTM C 881 - Specification for Epoxy-Resin-Base Bonding Systems for Concrete.

K. AWS D 1.4 - Structural Welding Code - Reinforcing Steel.

L. WRI - Manual of Standard Practice for Welded Wire Fabric.

M. CRSI MSP-1 - Manual of Standard Practice.

1.04 SUBMITTALS

A. Conform to Section 01330 – Submittal Procedures.

B. Shop Drawings:

1. Submit shop drawings detailing reinforcement fabrication, bar placement location, splices, spacing, bar designation, bar type, length, size, bending, number of bars, bar support type and other pertinent information, including dimensions. Provide sufficient detail for placement of reinforcement without use of Contract Drawings. Information shall correspond directly to data listed on bill of materials.

2. Use of reproductions of Contract Drawings by Contractor, Subcontractor, erector, fabricator or material supplier in preparation of shop drawings (or in lieu of preparation of shop drawings) signifies acceptance by that party of information shown thereon as correct, and acceptance of obligation to pay for any job expense, real or implied, arising due to errors that may occur thereon. Remove references to Design Engineer, including seals, when reproductions of Contract Drawings are used as shop drawings.

3. Detail shop drawings in accordance with ACI 315, Figure 6.

4. Submit shop drawings showing location of proposed additional construction joints as required under Section 03055 - Concrete Structures, and obtain approval of Engineer, prior to submitting reinforcing steel shop drawings.

C. Bill of Materials: Submit with shop drawings.

D. Product Data:

1. Mechanical Bar Splices: Submit manufacturer's technical literature, including specifications and installation instructions.

2. Epoxy grout proposed for anchoring reinforcing dowels to hardened concrete: Submit manufacturer's technical literature including recommended installation procedures.

E. Certificates:

1. Submit steel manufacturer's certificates of mill tests giving properties of steel proposed for use. List manufacturer's test number, heat number, chemical analysis, yield point, tensile strength and percentage of elongation. Identify proposed location of steel in work.

2. Foreign-manufactured reinforcing bars shall be tested for conformance to ASTM requirements by a certified independent testing laboratory located in United States. Certification from any other source is not acceptable. Submit test reports for review. Do not begin fabrication of reinforcement until material has been approved.

1.05 HANDLING AND STORAGE

A. Store steel reinforcement above ground on platforms, skids or other supports. Protect reinforcing from mechanical injury, surface deterioration and formation of excessive, loose or flaky rust caused by exposure to weather. Protect epoxy-coated reinforcing from formation of any amount of rust.

1.06 QUALITY ASSURANCE

A. Notify Resident Project Representative at least 48 hours before concrete placement so that reinforcement may be inspected, and errors corrected, without delaying Work.

PART 2 PRODUCTS

2.01 MATERIAL

A. Reinforcing Bars: Deformed bars conforming to ASTM A 615, grade as indicated on Drawings, except column spirals and those shown on Drawings to be smooth bars. Where grade is not shown on Drawings, use Grade 60.

B. Smooth Bars: Where indicated on Drawings, use smooth bars conforming to ASTM A 36; ASTM A 615, Grade 60; or ASTM A 675, Grade 70.

C. Column Spirals: Bars conforming to ASTM A 615, Grade 60, or wire conforming to ASTM A 82.

D. Epoxy-Coated Deformed Bars, Column Spirals and Smooth Bars: Conform to ASTM A 775/A 775M.

E. Welded Wire Fabric:

1. Welded Smooth Wire Fabric: Conform to ASTM A 185.

2. Welded Deformed Wire Fabric: Conform to ASTM A 497.

3. Provide wire size, type and spacing as shown. Where type is not shown on Drawings, use welded smooth wire fabric.

4. Furnish welded wire fabric in flat sheets only.

F. Tie Wire: 16-1/2 gage or heavier annealed steel wire. Use plastic-coated tie wire with epoxy-coated reinforcing steel.

G. Bar Supports: Provide chairs, riser bars, ties and other accessories made of plastic or metal, except as otherwise specified. Use bar supports and accessories of sizes required to provide required concrete cover. Where concrete surfaces are exposed to weather, water or wastewater, provide plastic accessories only; do not use galvanized or plastic-tipped metal in such locations. Provide metal bar supports and accessories rated Class 1 or 2 conforming to CRSI MSP-1 Manual of Standard Practice. Use epoxy-coated bar supports with epoxy-coated reinforcing bars.

H. Slabs on Grade: Provide chairs with sheet metal bases or provide precast concrete bar supports 3 inches wide, 6 inches long, and thick enough to allow required cover. Embed tie wires in 3-inch by 6-inch side.

I. Mechanical Bar Splices:

1. Conform to ACI 318; use where indicated on Drawings.

a. Compression splices shall develop ultimate stress of reinforcing bar.

b. Tension splices shall develop 125 percent of minimum yield point stress of reinforcing bar.

2. Regardless of chemical composition of steel, any heat effect shall not adversely affect performance of reinforcing bar.

J. Welded Splices:

1. Provide welded splices where shown and where approved by the Engineer. Welded splices of reinforcing steel shall develop a tensile strength exceeding 125 percent of the yield strength of the reinforcing bars connected.

2. Provide materials for welded splices conforming to AWS D1.4.

K. Epoxy Grout: High-strength rigid epoxy adhesive, conforming to ASTM C 881, Type IV, manufactured for purpose of anchoring dowels into hardened concrete and the moisture condition, application temperature and orientation of the hole to be filled. Unless otherwise shown, depth of embedment shall be as required to develop the full tensile strength (125 percent of yield strength) of dowel, but not less than 12 diameters.

2.02 FABRICATION

A. Bending: Fabricate bars to shapes indicated on Drawings by cold bending. Bends shall conform to minimum bend diameters specified in ACI 318. Do not straighten or rebend bars. Fabricate epoxy-coated reinforcing steel to required shapes in a manner that will not damage epoxy coating. Repair any damaged epoxy coating with patching material conforming to Item 4.4 of ASTM A 775/A 775M.

B. Splices:

1. Locate splices as indicated on Drawings. Do not locate splices at other locations without approval of Engineer. Use minimum number of splices located at points of minimum stress. Stagger splices in adjacent bars.

2. Length of lap splices: As shown on Drawings.

3. Prepare ends of bars at mechanical splices in accordance with splice manufacturer's requirements.

C. Construction Joints: Unless otherwise shown, continue reinforcing through construction joints.

D. Bar Fabrication Tolerances: Conform to tolerances listed in ACI 315, Figures 4 and 5.

E. Standard Hooks: Conform to the requirements of ACI 318.

F. Marking: Clearly mark bars with waterproof tags showing number of bars, size, mark, length and yield strength. Mark steel with same designation as member in which it occurs.

PART 3 EXECUTION

3.01 PREPARATION

A. Clean reinforcement of scale, loose or flaky rust and other foreign material, including oil, mud or coating that will reduce bond to concrete.

3.02 INSTALLATION

A. Placement Tolerances: Place reinforcement within tolerances of Table 03210A at the end of this Section. Bend tie wire away from forms to maintain the specified concrete coverage.

B. Interferences: Maintain 2-inch clearance from embedded items. Where reinforcing interferes with location of other reinforcing steel, conduit or embedded items, bars may be moved within specified tolerances or one bar diameter, whichever is greater. Where greater movement of bars is required to avoid interference, notify Engineer. Do not cut reinforcement to install inserts, conduit, mechanical openings or other items without approval of Engineer.

C. Concrete Cover: Provide clear cover measured from reinforcement to face of concrete as listed in Table 03210B at the end of this Section, unless otherwise indicated on Drawings.

D. Placement in Forms: Use spacers, chairs, wire ties and other accessory items necessary to assemble, space and support reinforcing properly. Provide accessories of sufficient number, size and strength to prevent deflection or displacement of reinforcement due to construction loads or concrete placement. Use appropriate accessories to position and support bolts, anchors and other embedded items. Tie reinforcing bars at each intersection, and to accessories. Blocking reinforcement with concrete or masonry is prohibited.

E. Placement for Concrete on Ground: Support bar and wire reinforcement on chairs with sheet metal bases or precast concrete blocks spaced at approximately 3 feet on centers each way. Use minimum of one support for each 9 square feet. Tie supports to reinforcing bars and wires.

F. Vertical Reinforcement in Columns: Offset vertical bars by at least one bar diameter at splices. Provide accurate templates for column dowels to ensure proper placement.

G. Splices:

1. Do not splice bars, except at locations indicated on Drawings or reviewed shop drawings, without approval of Engineer.

2. Lap Splices: Unless otherwise shown or noted, Class B, conforming to ACI 318-89, Section 12.15.1. Tie securely with wire prior to concrete placement, to prevent displacement of splices during concrete placement.

3. Mechanical Bar Splices: Use only where indicated on Drawings or approved by the Engineer. Install in accordance with manufacturer's instructions.

   a. Couplers located at a joint face shall be of a type which can be set either flush or recessed from the face as shown. Seal couplers prior to concrete placement to completely eliminate concrete or cement paste from entering.

   b. Couplers intended for future connections: Recess 1/2 inch minimum from concrete surface. After concrete is placed, plug

coupler and fill recess with sealant to prevent contact with water or other corrosive materials.

c. Unless noted otherwise, match mechanical coupler spacing and capacity to that shown for the adjacent reinforcing.

H. Construction Joints: Place reinforcing continuous through construction joints, unless noted otherwise.

I. Welded Wire Fabric: Install wire fabric in as long lengths as practicable. Unless otherwise indicated on Drawings, lap adjoining pieces at least 6 inches or one full mesh plus 2 inches, whichever is larger. Lace splices with wire. Do not make end laps midway between supporting beams, or directly over beams of continuous structures. Offset end laps in adjacent widths to prevent continuous laps. Conform to WRI - Manual of Standard Practice for Welded Wire Fabric.

J. Field Bending: Shape reinforcing bent during construction operations to conform to Drawings. Bars shall be cold-bent; do not heat bars. Closely inspect reinforcing for breaks. When reinforcing is damaged, replace, Cadweld, or otherwise repair, as directed by Engineer. Do not bend reinforcement after it is embedded in concrete.

K. Epoxy-coated Reinforcing Steel: Install in accordance with Paragraph 3.02J, Field Bending, and in a manner that will not damage epoxy coating. Repair damaged epoxy coating with patching material as specified in Paragraph 2.02A, Bending.

L. Field Cutting: Cut reinforcing bars by shearing or sawing. Do not cut bars with cutting torch.

M. Welding of reinforcing bars is prohibited, except where shown on Drawings.

3.03 GROUTING OF REINFORCING AND DOWEL BARS

A. Use epoxy grout for anchoring reinforcing and dowel steel to existing concrete in accordance with epoxy manufacturer's instructions. Drill hole not more than 1/4 inch larger than steel bar diameter (including height of deformations for deformed bars) in existing concrete. Just before installation of steel, blow hole clean of all debris using compressed air. Partially fill hole with epoxy, using enough epoxy so when steel bar is inserted, epoxy grout will completely fill hole around bar. Dip end of steel bar in epoxy and twist bar while inserting into partially-filled hole.

Table 03210A
REINFORCEMENT PLACEMENT TOLERANCES

PLACEMENT	TOLERANCE IN INCHES
Clear Distance -	
To formed soffit:	-1/4
To other formed surfaces:	"1/4
Minimum spacing between bars:	-1/4
Clear distance from unformed surface to top reinforcement -	
Members 8 inches deep or less:	"1/4
Members more than 8 inches deep but less than 24 inches deep:	-1/4, +1/2
Members 24 inches deep or greater:	-1/4, +1
Uniform spacing of bars (but the required number of bars shall not be reduced):	"2
Uniform spacing of stirrups and ties (but the required number of stirrups and ties shall not be reduced):	"1
Longitudinal locations of bends and ends of reinforcement -	
General:	"2
Discontinuous ends of members:	"1/2
Length of bar laps:	-1-1/2
Embedded length -	
For bar sizes No. 3 through 11:	-1
For bar sizes No. 14 and 18:	-2

Table 03210B
MINIMUM CONCRETE COVER FOR REINFORCEMENT

SURFACE	MINIMUM COVER IN INCHES
Slabs and Joists -	
Top and bottom bars for dry conditions -	
No. 14 and No. 18 bars:	1-1/2
No. 11 bars and smaller:	1
Formed concrete surfaces exposed to earth, water or weather; over, or in contact with, sewage; and for bottoms bearing on work mat, or slabs supporting earth cover -	
No. 5 bars and smaller:	1-1/2
No. 6 through No. 18 bars:	2
Beams and Columns -	
For dry conditions -	
Stirrups, spirals and ties:	1-1/2
Principal reinforcement:	2
Exposed to earth, water, sewage or weather -	
Stirrups and ties:	2
Principal reinforcement:	2-1/2
Walls -	
For dry conditions -	
No. 11 bars and smaller:	1
No. 14 and No. 18 bars:	1-1/2
Formed concrete surfaces exposed to earth, water, sewage or weather, or in contact with ground -	
Circular tanks with ring tension:	2
All others:	2
Footings and Base Slabs -	
At formed surfaces and bottoms bearing on concrete work mat:	2
At unformed surfaces and bottoms in contact with earth:	3
Over top of piles:	2
Top of footings -- same as slabs	

END OF SECTION

Section 03310

STRUCTURAL CONCRETE

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Cast-in-place normal-weight structural concrete and mass concrete.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Measurement for extra structural concrete is on cubic-yard basis, measured in place. Payment includes related work performed in accordance with related sections.

3. Refer to Section 01270 - Measurement and Payment for unit price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

1.03 REFERENCES

A. ACI 301 - Specifications for Structural Concrete for Buildings.

B. ACI 304.2R - Placing Concrete by Pumping Methods

C. ACI 305R - Hot Weather Concreting.

D. ACI 306.1 - Standard Specification for Cold Weather Concreting.

E. ACI 309R - Guide for Consolidation of Concrete.

F. ACI 318 - Building Code Requirements for Reinforced Concrete.

G. ACI 350R - Environmental Engineering Concrete Structures.

H. ASTM C 31 - Standard Practice for Making and Curing Concrete Test Specimens in the Field.

I. ASTM C 33 - Standard Specification for Concrete Aggregates.

J. ASTM C 39 - Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens.

K. ASTM C 42 - Standard Method of Obtaining and Testing Drilled Cores and Sawed Beams of Concrete.

L. ASTM C 88 - Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate.

M. ASTM C 94 - Standard Specifications for Ready-Mixed Concrete.

N. ASTM C 127 - Standard Test Method for Specific Gravity and Absorption of Coarse Aggregate.

O. ASTM C 131 - Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.

P. ASTM C 136 - Sieve Analyses of Fine and Coarse Aggregates.

Q. ASTM C 143 - Standard Test Method for Slump of Hydraulic Cement Concrete.

R. ASTM C 150 - Standard Specification for Portland Cement.

S. ASTM C 157 - Test Method for Length Change of Hardened Hydraulic Cement Mortar and Concrete.

T. ASTM C 172 - Standard Practice for Sampling Freshly Mixed Concrete.

U. ASTM C 173 - Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method.

V. ASTM C 192 - Method of Making and Curing Concrete Test Specimens in the Laboratory.

W. ASTM C 231 - Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method.

X. ASTM C 260 - Standard Specification for Air-Entraining Admixtures for Concrete.

Y. ASTM C 330 - Standard Specification for Lightweight Aggregates for Structural Concrete.

Z. ASTM C 494 - Standard Specification for Chemical Admixtures for Concrete.

AA. ASTM C 535 - Standard Test Method for Resistance to Degradation of Large-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.

AB. ASTM C 567 - Standard Test Method for Unit Weight of Structural Lightweight Concrete.

AC. ASTM C 1064 - Standard Test Method for Temperature of Freshly Mixed Portland Cement Concrete.

AD. Concrete Plant Manufacturer's Bureau (CPMB), Plant Mixer Manufacturers Division: Concrete Plant Mixer Standards.

AE. National Ready-Mixed Concrete Association (NRMCA): Certification of Ready-Mixed Concrete Production Facilities (checklist with instructions).

AF. John Wiley and Sons, Interscience Publishers Division, "Encyclopedia of Industrial Chemical Analysis," Vol. 15, Page 230 (alkalinity test procedure).

1.04 DEFINITIONS

A. Mass Concrete: Concrete sections 4 feet or more in least dimension.

B. Hot Weather: Any combination of high air temperature, low relative humidity and wind velocity tending to impair quality of fresh or hardened concrete or otherwise resulting in abnormal properties.

C. Cold Weather: Period when, for more than 2 successive days, mean daily temperature is below 40 degrees F.

1.05 SUBMITTALS

A. Conform to Section 01330 – Submittal Procedures.

B. Mill Certificates: Required for bulk cement.

C. Design Mixes:

1. Submit test data on proposed design mixes for each type of concrete in the Work, including each class, and variations in type, source or quantity of material. Include type, brand and amount of cementitious materials; type, brand and amount of each admixture; slump; air content; aggregate sources, gradations, specific gravity and absorption; total water (including moisture in aggregate); water/cement ratio; compressive strength test results for 7 and 28 days; and shrinkage tests for Class A and D concrete at 21 or 28 days of drying.

2. Submit abrasion loss and soundness test results for limestone aggregate.

3. Testing of aggregates, including sieve analysis, shall be performed by a certified independent testing laboratory. Tests shall have been performed no earlier than 3 months before Notice to Proceed.

4. Provide standard deviation data for plant producing concrete. Data shall include copies of laboratory test results and standard deviation calculated in accordance with ACI 318, Item 5.3.1. Laboratory tests shall have been performed within past 12 months. When standard deviation data is not available, comply with ACI 318, Table 5.3.2.2.

5. Review and acceptance of mix design does not relieve Contractor of responsibility to provide concrete of quality and strength required by these Specifications.

D. Admixtures: Submit manufacturer's technical information, including following:

1. Air-Entraining Admixture: Give requirements to control air content under all conditions, including temperature variations and presence of other admixtures.

2. Chemical Admixtures: Give requirements for quantities and types to be used under various temperatures and job conditions to produce uniform, workable concrete mix. Submit evidence of compatibility with other admixtures and cementitious materials proposed for use in design mix.

E. High-range Water Reducer (Superplasticizer): When approved for use by Engineer, submit manufacturer's technical information and instructions for use of superplasticizer. Superplasticizer will not be added at ready-mix plant. When superplasticizer will be added at job site, submit proposed plan for measuring and adding superplasticizer to concrete mix at job site, and establish dosing area on site with holding tanks and metering devices. Identify portions of Work on which superplasticizer is proposed for use.

F. Hot and Cold Weather Concreting: Submit, when applicable, proposed plans for hot and cold weather concreting. Review and acceptance of proposed procedure will not relieve Contractor of responsibility for quality of finished product.

G. Project Record Drawings: Accurately record actual locations of embedded utilities and components which are concealed from view.

1.06 QUALITY ASSURANCE

A. Provide necessary controls during evaluation of materials, mix designs, production and delivery of concrete, placement and compaction to assure that the Work will be accomplished in accordance with Contract Documents. Maintain records of concrete placement. Record dates, locations, quantities, air temperatures, and test samples taken.

B. Code Requirements: Concrete construction for buildings shall conform to ACI 318. Concrete construction for water and wastewater treatment and conveying structures shall conform to ACI 318 with modifications by ACI 350R, Item 2.6. Where this Specification conflicts with ACI 318 or ACI 350R, this Specification governs.

C. Testing and Other Quality Control Services:

1. Concrete testing required in this section, except concrete mix design, limestone aggregate test data, and testing of deficient concrete, will be performed by an independent commercial testing laboratory employed and paid by the Owner in accordance with Section 01454 – Testing Laboratory Services.

2. Provide material for and cooperate fully with Owner's testing laboratory technician in obtaining samples for required tests.

3. Standard Services: The following testing and quality control services will be provided by Owner in accordance with Section 01454 – Testing Laboratory Services:

a. Verification that plant equipment and facilities conform to NRMCA "Certification of Ready-Mix Concrete Production Facilities".

b. Testing of proposed materials for compliance with this Specification.

c. Review of proposed mix design submitted by Contractor.

d. Obtaining production samples of materials at plants or stockpiles during work progress and testing for compliance with this Specification.

e. Strength testing of concrete according to following procedures:

(1) Obtaining samples for field test cylinders from every 50 cubic yards and any portion less than 50 cubic yards for each mix design placed each day, according to ASTM C 172, with each sample obtained from a different batch of concrete on a representative, random basis. Selecting test batches by any means other than random numbers chosen before concrete placement begins is not allowed.

(2) Molding four specimens from each sample according to ASTM C 31, and curing under standard moisture and temperature conditions as specified in Sections 7(a) and (b) of ASTM C 31.

(3) Testing two specimens at 7 days and two specimens at 28 days according to ASTM C 39, reporting test results averaging strengths of two specimens. However, when one specimen evidences improper sampling, molding or testing, it will be discarded and remaining cylinder considered test result. When high-early-strength concrete is used, specimens will be tested at 3 and 7 days.

f. Air content: For each strength test, determination of air content of normal weight concrete according to ASTM C 231.

g. Slump: For each strength test, and whenever consistency of concrete appears to vary, conducting slump test in accordance with ASTM C 143.

h. Temperature: For each strength test, checking concrete temperature in accordance with ASTM C 1064.

i. Lightweight concrete: For each strength test, or more frequently when requested by Engineer, determination of air content by ASTM C 567 and unit weight by ASTM C 567.

j. Monitoring of current and forecasted climatic conditions to determine when rate of evaporation, as determined by Figure 2.1.5 of ACI 305R, will produce loss of 0.2 pounds of water, or more, per square foot per hour. Testing lab representative will advise Contractor to use hot weather precautions when such conditions will exist during concrete placement, and note on concrete test reports when Contractor has been advised that hot weather conditions will exist.

k. Class A and D Concrete Shrinkage Tests: Performance of drying shrinkage tests for trial batches as follows:

(1) Preparation and Testing of Specimens: Compression and drying shrinkage test specimens will be taken in each case from the same concrete sample; shrinkage tests will be considered a part of the normal compression tests for the project. 4-inch by 4-inch by 11-inch prisms with an effective gage length of 10 inches, fabricated, cured, dried and measured in accordance with ASTM C 157, modified as follows:

(a) Wet curing: Remove specimens from molds at an age of 23 hours "1 hour after trial batching and immediately immerse in water at 70 degrees F "3 degrees F for at least 30 minutes;

(b) Measure within 30 minutes after first 30 minutes of immersion to determine original length (not to be confused with "base length");

(c) Then submerge in saturated limewater, at 73 degrees F "3 degrees F, for 7 days;

(d) Then measure at age 7 days to establish "base length" for drying shrinkage calculations ("zero" days drying age);

(e) Calculate expansion (base length expressed as a percentage of original length);

(f) Immediately store specimens in a temperature- and humidity-controlled room maintained at 73 degrees F, +3 degrees F and 50 percent +4

percent relative humidity, for the remainder of the test.

(g) Measure to determine shrinkage, expressed as percentage of base length. Compute the drying shrinkage deformation of each specimen as the difference between the base length (after 2 curing days, or zero days drying age) and the length after drying at each test age. Compute the average drying shrinkage deformation of the specimens to the nearest 0.0001 inch at each test age. If the drying shrinkage of any specimen departs from the average of that test age by more than 0.0004 inch, disregard the results obtained from that specimen. Report results of shrinkage tests to the nearest 0.001 percent of shrinkage.

(h) Report shrinkage separately for 7, 14, 21, and 28 days of drying after 7 days of moist curing.

4. Additional Testing and Quality Control Services: The following will be performed by an independent commercial testing laboratory employed and paid by the Owner in accordance with Section 01454 – Testing Laboratory Services, when requested by Engineer.

a. Checking of batching and mixing operations.

b. Review of manufacturer's report of each cement shipment and conducting laboratory tests of cement.

c. Molding and testing reserve 7-day cylinders or field cylinders.

d. Conducting additional field tests for slump, concrete temperature and ambient temperature.

e. Alkalinity Tests: For concrete used in sanitary structures, one test for each structure. Perform alkalinity tests on concrete covering reinforcing steel on the inside of the pipe or structure in accordance with "Encyclopedia of Industrial Chemical Analysis," Vol. 15, page 230.

5. Contractor shall provide the following testing and quality control services:

   a. Employ an independent commercial testing laboratory, acceptable to Owner, to prepare and test design mix for each class of concrete for which material source has been changed.

   b. Notify commercial testing laboratory employed by Owner 24 hours prior to placing concrete.

6. Testing of deficient concrete in place:

   a. When averages of three consecutive strength test results fail to equal or exceed specified strength, or when any individual strength test result falls below specified strength by more than 500 psi, strength of concrete shall be considered potentially deficient and core testing, structural analysis or load testing may be required by Engineer.

   b. When concrete in place proves to be deficient, Contractor shall pay costs, including costs due to delays, incurred in providing additional testing and analysis services provided by the Engineer, or the independent commercial testing laboratory selected by the Owner.

   c. Replace concrete work judged inadequate by core tests, structural analysis or load tests at no additional cost to the Owner.

   d. Core Tests:

      (1) Obtain and test cores in accordance with ASTM C 42. Where concrete in structure will be dry under service conditions, air dry cores (temperature 60 to 80 degrees F, relative humidity less than 60 percent) for 7 days before test; test dry. Where concrete in structure will be more than superficially wet under service conditions, test cores after moisture conditioning in accordance with ASTM C 42.

      (2) Take at least three representative cores from each member or area of concrete in place that is considered potentially deficient. Location of cores shall be determined by Engineer so as to least impair strength of

structure. When, before testing, one or more cores shows evidence of having been damaged during or after removal from structure, replace the damaged cores.

(3) Concrete in area represented by core test will be considered adequate when average strength of cores is equal to at least 85 percent of specified strength, and when no single core is less than 75 percent of specified strength.

(4) Patch core holes in accordance with Section 03350 - Concrete Finishing.

e. Structural Analysis: When core tests are inconclusive or impractical to obtain, Engineer may perform additional structural analysis at Contractor's expense to confirm safety of structure.

f. Load Tests: When core tests and structural analysis do not confirm safety of structure, load tests may be required, and their results evaluated, in accordance with ACI 318.

g. Testing by impact hammer, sonoscope, probe penetration tests (Windsor probe), or other nondestructive device may be permitted by Engineer to determine relative strengths at various locations in structure, to evaluate concrete strength in place, or for selecting areas to be cored. However, such tests, unless properly calibrated and correlated with other test data, shall not be used as basis for acceptance or rejection of structure's safety.

1.07 STORAGE AND HANDLING OF MATERIALS

A. Cement: Store cement in weather tight buildings, bins or silos to provide protection from dampness and contamination and to minimize warehouse set. When there is any doubt as to expansive potential of shrinkage-compensating cements because of method or length of storage and exposure, laboratory test cement before use.

B. Aggregate: Arrange and use aggregate stockpiles to avoid excessive segregation or contamination with other materials or with other sizes of like aggregates. Build stockpiles in successive horizontal layers not exceeding 3 feet in thickness. Complete each layer before next is started.

C. Fine Aggregate: Before using, allow fine aggregate to drain until uniform moisture content is reached.

D. Admixtures: Store admixtures to avoid contamination, evaporation or damage. For those used in form of suspensions or nonstable solutions,

provide suitable agitating equipment to assure uniform distribution of ingredients. Protect liquid admixtures from freezing and other temperature changes which would adversely affect their characteristics.

E. Lightweight Aggregates: Uniformly predampen lightweight aggregates as necessary to prevent excessive variations in moisture content. Allow predampened aggregates to remain in stockpiles, under continuous fog spray, for minimum of 24 hours before use. Provide adequate drainage in stockpile areas to eliminate excess water and accumulation of contaminated fines.

PART 2 PRODUCTS

2.01 MATERIALS

A. Cement:

1. Use same brand of cement used in concrete mix design. Use only one brand of each type in each structure, unless otherwise indicated on Drawings.

2. Portland Cement: ASTM C 150, Type I or Type II, gray in color. Use Type III only when specifically authorized by Engineer in writing. Use Type II, including the requirements of Table 2, in construction of liquid-containing structures and cooling towers, unless shown otherwise on Drawings.

B. Admixtures:

1. Do not use calcium chloride, thiocyanate or admixtures containing more than 0.05 percent chloride ions.

2. Air-Entraining Admixtures: ASTM C 260, compatible with other admixtures used.

3. Chemical Admixtures: Polymer type, nonstaining, chloride-free admixtures conforming to ASTM C 494, Type A, C, D or E.

4. High-Range Water Reducer (Superplasticizer): ASTM C 494, Type F or G, compatible with and by the same manufacturer as other admixtures.

C. Mixing Water: Use clean, potable water, free from harmful amounts of oils, acids, alkalis or other deleterious substances, meeting requirements of ASTM C 94.

D. Aggregates: Use coarse aggregate from only one source, and fine aggregate from only one source, for exposed concrete in any single structure.

1. Coarse Aggregate: Gravel, crushed gravel or crushed limestone conforming to ASTM C 33.

2. Fine Aggregate: Natural sand complying with ASTM C 33.

3. Limestone aggregate shall conform to ASTM C 33 and the following additional requirements: Clean, hard, strong and durable particles free of chemicals and coatings of silt, clay, or other fine materials that may affect hydration and bond of cement paste. Select crushed limestone: High-calcium limestone (minimum 95 percent CaCO3 and maximum 3.5 percent MgCO3) with maximum Los Angeles Abrasion loss of 38 percent, when tested in accordance with ASTM C 131 or ASTM C 535. Test aggregate for soundness in accordance with ASTM C 88; maximum loss shall not exceed 18 percent after 5 cycles of magnesium sulfate test.

4. Maximum size of coarse aggregate:

   a. Normal weight concrete, except as noted below: 1-1/2 inches.

   b. Formed members 6 inches or less in least dimension: 1/5 least dimension.

   c. Slabs: 1/3 depth of slab.

   d. Drilled shafts: 1/3 clearance between reinforcing steel, but not greater than 3/4 inch.

   e. Concrete fill, seal slabs and bonded concrete topping in clarifiers: 3/8 inch.

5. Coarse aggregate for lightweight concrete: ASTM C 330. Grading limits: 3/4 inch to No. 4.

6. Abrasive Aggregate: Conform to requirements of Section 03350 - Concrete Finishing.

E. Calcium Chloride: Not permitted.

F. Evaporation Retardant: Masterbuilders "Confilm", Euclid "Eucobar", or equal.

G. Miscellaneous Materials:

1. Bonding Agent: Two-component modified epoxy resin.

2. Vapor barrier: 6 mil clear polyethylene film of type recommended for below-grade application.

3. Non-shrink grout: premixed compound consisting of non-metallic aggregate, cement and water-reducing and plasticizing agents; capable of developing minimum compressive strength of 2,400 psi in 48 hours and 7,000 psi in 28 days.

2.02 CONCRETE MIX

A. Objective: Select proportions of ingredients to produce concrete having proper placability, durability, strength, appearance, and other specified properties.

B. Mix Design: Employ and pay an independent commercial testing laboratory, acceptable to Owner, to prepare and test mix designs for each type of concrete specified. Proportion mix design ingredients by weight. Submit mix designs and test results for approval.

1. During the trial batches, aggregate proportions may be adjusted by the testing laboratory using two coarse aggregate size ranges to obtain the required properties. If one size range produces an acceptable mix, a second size range need not be used. Such adjustments shall be considered refinements to the mix design and shall not be the basis for extra compensation to the Contractor. Concrete shall conform to the requirements of this Section, whether the aggregate proportions are from the Contractor's preliminary mix design, or whether the proportions have been adjusted during the trial batch process. Prepare trial batches using the aggregates, cement and admixtures proposed for the project. Make trial batches large enough to obtain 3 drying shrinkage test specimens and 6 compression test specimens from each batch. Shrinkage testing is required only for Class A and D concrete.

2. Determine compressive strength by testing 6-inch diameter by 12-inch high cylinders, made, cured and tested in accordance with ASTM C 192 and ASTM C 39. Test 3 compression test cylinders at 7 days and 3 at 28 days. Average compressive strength for the 3 cylinders tested

at 28 days for any given trial batch shall be not less than 125 percent of the specified compressive strength.

3. Perform sieve analysis of the combined aggregate for each trial batch according to of ASTM C 136. Report percentage passing each sieve.

4. In mix designs for Class A and D concrete, fine aggregate shall not exceed 41 percent of total aggregate by weight.

C. Shrinkage Limitations, Class A and D Concrete

1. Maximum concrete shrinkage for specimens cast in the laboratory from the trial batch: 0.036 percent as measured at 21-day drying age, or 0.042 percent at 28-day drying age. Use for construction only mix designs that meet trial batch shrinkage requirements. Shrinkage limitations apply only to Class A and D concrete.

2. Maximum concrete shrinkage for specimens cast in the field shall not exceed the trial batch maximum shrinkage requirement by more than 25 percent.

3. If the required shrinkage limitation is not met during construction, take any or all of the following actions, at no additional cost to the Owner, for securing the specified shrinkage requirements: Changing the source or aggregates, cement or admixtures; reducing water content; washing of aggregate to reduce fines; increasing the number of construction joints; modifying the curing requirements; or other actions designed to minimize shrinkage or its effects.

D. Selecting Ingredient Proportions for Concrete:

1. Proportion concrete mix according to ACI 301, Chapter 3.

2. Establish concrete mix design by laboratory trial batches prepared by independent testing laboratory, or on basis of previous field experience in accordance with provisions of ACI 318, Item 5.3; however, minimum cement content for each class of concrete shall not be less than specified.

3. Concrete mix design data submitted for review shall have average 28-day compressive strength calculated in accordance with ACI 318, Item 5.3.2.1. When data is not available to determine standard deviation in accordance with ACI 318, Item 5.3.1, average 28-day strength of mix design shall conform to ACI 318, Table 5.3.2.2.

E. Water-Cement Ratios:

1. Maximum allowable water-cement ratios shall be as follows:

   a. Concrete for liquid-containing structures: 0.41.

   b. Concrete subjected to brackish water, salt spray or deicers: 0.40.

   c. All other concrete: 0.53.

2. Superplasticizer may be added to maintain specified maximum water-cement ratios. Include free water in aggregate in water-cement ratio computations.

F. Adjustment of Mix Proportions: After sufficient data becomes available during construction, mix may be adjusted upon approval of Engineer, in accordance with ACI 318, Item 5.5; however, minimum cement content for each class of concrete shall not be less than specified.

G. Entrained Air: Air-entrain all concrete except drilled shafts. Total air content in accordance with ASTM C 173: 4 to 6 percent.

H. Consistency, Workability, and Slump:

1. The quantity of water in a batch of concrete shall be just sufficient, with a normal mixing period, to produce concrete which can be worked properly into place without segregation, and which can be compacted by vibratory methods as specified, to give the desired strength, density, impermeability and smoothness of surface. Change the quantity of water as necessary, with variations in the nature or moisture content of the aggregates, to maintain uniform production of a desired consistency. Determine the consistency of the concrete in successive batches by slump tests in accordance with ASTM C 143. Slumps shall be as follows:

Concrete Type	Minimum Slump	Maximum Slump
Portland Cement Concrete:	2"	4"
Concrete to be dosed with superplasticizer:	1"	3"
Normal Weight Concrete after dosing with superplasticizer:	4"	8"
Drilled Shaft Concrete:	4"*	8"

* Minimum slump where drilled shafts are cast in temporary casings: 5 inches.

2. Specified slump shall apply at time when concrete is discharged at job site. Perform slump tests to monitor uniformity and consistency of concrete delivered to job site; however, do not use as basis for mix design. Do not exceed water-cement ratios specified.

I. Admixtures: Proportion admixtures according to manufacturer's recommendations. Use of accelerator is permitted when air temperature is less than 40 degrees F. Use of retarder is permitted when temperature of placed concrete exceeds 65 degrees F.

J. High-Range Water Reducers (Superplasticizers): Use superplasticizer to improve workability of concrete or delay hydration of cement, in accordance with requirements and recommendations of product manufacturer and approved submittals.

K. Concrete Classification and Strength:

1. Strength: Conform to values for class of concrete indicated on Drawings for each portion of Work. Requirements are based on 28-day compressive strength. If high early-strength concrete is allowed, requirements are based on 7-day compressive strength.

2. Classification:

Class (Normal-weight)	Minimum 28-Day Compressive Strength (psi)	Minimum Cement Content Pounds per Cubic Yard
Concrete for Structures Containing Water or Wastewater		
A	4000	564 (6 Sacks)
B	1500	329 (3-1/2 Sacks)
C	3000	470 (5 Sacks)
D	5000	658 (7 Sacks)
H	4500	611 (6-1/2 Sacks)

Class (Normal-weight)	Minimum 28-Day Compressive Strength (psi)	Minimum Cement Content Pounds per Cubic Yard
Concrete for Buildings, Slabs on Grade and Miscellaneous Structures		
AB	4000	Not Applicable
BB	1500	Not Applicable
CB	3000	Not Applicable
DB	5000	Not Applicable

Class (Light-weight)	Minimum 28-Day Compressive Strength (psi)	Minimum Cement Content Pounds per Cubic Yard
E	3000	Not Applicable
F	4000	Not Applicable
G	5000	Not Applicable

3. Maximum size aggregate for Class H concrete: 3/8 inch. Maximum size aggregate for all other normal-weight concrete: 1-1/2 inches, except as specified in Paragraph 2.01D.4.

4. When required strength is not obtained with minimum cement content as specified, add cement, lower water-cement ratio or provide other aggregates as necessary.

5. In addition to conforming to specified strength, lightweight concrete must be within specified unit weight limits. Maximum air-dry unit weight is 118 pounds per cubic foot; minimum is 110 pounds per cubic foot unless shown otherwise on Drawings. Determine air-dry unit weight in accordance with ASTM C 567. Correlate air-dry unit weight with fresh unit weight of the same concrete as a basis for acceptance during construction.

L. Use of Classes of Concrete:

1. Use classes of concrete as indicated on the Drawings and in other specifications.

2. Liquid-containing structures: If not otherwise indicated, use the following classes for structures containing water or wastewater and for utility applications in the locations described:

a. Class A: All reinforced concrete and where not otherwise defined.

b. Class B: Unreinforced concrete used for plugging pipes, seal slabs, thrust blocks and trench dams, unless indicated otherwise.

c. Class H: Fill and topping. Where concrete fill thickness exceeds 3 inches in the majority of a placement and is not less than 1.5 inches thick, Class A concrete may be used.

3. All other structures: If not otherwise indicated, use the following classes in the locations described:

a. Class AB: All reinforced concrete and where not otherwise defined.

b. Class CB: Duct banks; see Section 16402 - Underground Duct Banks for additional requirements.

c. Class BB: Unreinforced concrete fill under structures.

2.03 MIXING NORMAL WEIGHT CONCRETE

A. Conform to ACI 301, Chapter 7.

B. Ready-Mixed Concrete:

1. Measure, batch, mix and transport ready-mixed concrete according to ASTM C 94. Plant equipment and facilities shall conform to NRMCA "Certification of Ready Mixed Concrete Production Facilities".

2. Provide batch tickets with information specified in ASTM C 94. Deliver batch ticket with concrete and give to Owner's on-site testing laboratory representative.

C. Batch Mixing at Site:

1. Mix concrete in batch mixer conforming to requirements of CPMB "Concrete Plant Mixer Standards". Use mixer equipped with suitable charging hopper, water storage tank and water measuring device. Batch mixer shall be capable of mixing aggregates, cement and water into uniform mass within specified mixing time, and of discharging mix without segregation. Operate mixer according to rated capacity and

recommended revolutions per minute printed on manufacturer's rating plate.

2. Charge batch into mixer so some water will enter before cement and aggregates. Keep water running until one-fourth of specified mixing time has elapsed. Provide controls to prevent discharging until required mixing time has elapsed. When concrete of normal weight is specified, provide controls to prevent addition of water during mixing. Discharge entire batch before mixer is recharged.

3. Mix each batch of 2 cubic yards or less for not less than 1 minute and 30 seconds. Increase minimum mixing time 15 seconds for each additional cubic yard or fraction of cubic yard.

4. Keep mixer clean. Replace pick-up and throw-over blades in drum when they have lost 10 percent of original depth.

D. Admixtures:

1. Charge air-entraining and chemical admixtures into mixer as solution using automatic dispenser or similar metering device. Measure admixture to accuracy within + 3 percent. Do not use admixtures in powdered form.

2. Two or more admixtures may be used in same concrete, provided that admixtures in combination retain full efficiency and have no deleterious effect on concrete or on properties of each other. Inject admixtures separately during batching sequence.

3. Add retarding admixtures as soon as practicable after addition of cement.

E. Temperature Control:

1. When ambient temperature falls below 40 degrees F, keep as-mixed temperature above 55 degrees F to maintain concrete above minimum placing temperature.

2. When water or aggregate has been heated, combine water with aggregate in mixer before cement is added. Do not add cement to mixtures of water and aggregate when temperature of mixture is greater than 100 degrees F.

3. In hot weather, maintain temperature of concrete below maximum placing temperature. When necessary, temperature may be lowered

by cooling ingredients, cooling mixer drum by fog spray, using chilled water or well-crushed ice in whole or part for added water, or arranging delivery sequence so that time of transport and placement does not generate unacceptable temperatures.

4. Submit hot weather and cold weather concreting plans for approval.

2.04 MIXING LIGHTWEIGHT CONCRETE

A. Determining Absorption of Aggregates: Mixing procedures vary according to total absorption by weight of lightweight aggregates. Determine total absorption by weight before predamping in accordance with ASTM C 127.

B. Ten Percent or Less Absorption: Follow same requirements as for mixing normal-weight concrete when preparing concrete made with low-absorptive lightweight aggregates having 10 percent or less total absorption by weight. To be low-absorptive, aggregates must absorb less than 2 percent additional water in first hour after mixing.

C. More Than 10 Percent Absorption: Batch and mix concrete made with lightweight aggregates having more than 10 percent total absorption by weight, as follows:

1. Place approximately 80 percent of mixing water in mixer.

2. If aggregates are pre-dampened, add air-entraining admixture and all aggregates. Mix for minimum of 30 seconds, or 5 to 10 revolutions of truck mixer.

3. When aggregates have not been predampened, mix aggregates and water for minimum of 1 minute and 30 seconds, or 15 to 30 revolutions of truck mixer. Then add air-entraining admixture and mix for additional 30 seconds.

4. Then, in the following sequence, add specified or permitted admixtures (other than air-entraining agent), all cement, and mixing water previously withheld.

5. Complete mixing using procedures for normal-weight concrete.

2.05 MASS CONCRETE

A. Do not use high early-strength cement (Type III) or accelerating admixtures.

B. Use high-range water-reducing admixture (superplasticizer) to minimize water content and cement content.

C. Specified water-reducing retarding admixture may be required to prevent cold joints when placing large quantities of concrete, to permit revibration of concrete, to offset effects of high temperature in concrete or weather, and to reduce maximum temperature or rapid temperature rise.

2.06 EQUIPMENT

A. Select equipment of size and design to ensure continuous flow of concrete at delivery end. Conform to following equipment and operations requirements.

B. Truck mixers, agitators and manner of operation: Conform to ASTM C 94. Use of non-agitating equipment for transporting concrete is not permitted.

C. Belt conveyors: Configure horizontally, or at a slope causing no segregation or loss. Use approved arrangement at discharge end to prevent separation. Discharge long runs without separation into hopper.

D. Chutes: Metal or metal-lined (other than aluminum). Arrange for vertical-to-horizontal slopes not more than 1 to 2 nor less than 1 to 3. Chutes longer than 20 feet or not meeting slope requirements may be used if concrete is discharged into hopper before distribution.

E. Do not use aluminum or aluminum-alloy pipe or chutes for conveying concrete.

PART 3 EXECUTION

3.01 SPECIAL CONSIDERATIONS

A. Concreting Under Water: Not permitted except where shown otherwise on Drawings or approved by Engineer. When shown or permitted, deposit concrete under water by methods acceptable to the Engineer so fresh concrete enters mass of previously-placed concrete from within, causing water to be displaced with minimum disturbance at surface of concrete.

B. Protection from Adverse Weather: Unless adequate protection is provided or Engineer's approval is obtained, do not place concrete during rain, sleet, snow or freezing weather. Do not permit rainwater to increase mixing water or to damage surface finish. If rainfall occurs after placing operations begin, provide adequate covering to protect Work.

3.02 PREPARATION OF SURFACES FOR CONCRETING

A. Earth Surfaces:

1. Under interior slabs on grade, install vapor barrier. Lap joints at least 6 inches and seal watertight with tape, or sealant applied between overlapping edges and ends. repair vapor barrier damaged during placement of reinforcing and inserts with vapor barrier material; lap over damaged areas at least 6 inches and seal watertight.

2. Other Earth Surfaces: Thoroughly wet by sprinkling prior to placing concrete, and keep moist by frequent sprinkling up to time of placing concrete thereon. Remove standing water. Surfaces shall be free from standing water, mud and debris at the time of placing concrete.

B. Construction Joints:

1. Definition: Concrete surfaces upon or against which concrete is to be placed, where the placement of the concrete has been interrupted so that, in the judgement of the Engineer, new concrete cannot be incorporated integrally with that previously placed.

2. Interruptions: When placing of concrete is to be interrupted long enough for the concrete to take a set, use forms or other means to shape the working face to secure proper union with subsequent work. Make construction joints only where acceptable to the Engineer.

3. Preparation: Give horizontal joint surfaces a compacted, roughened surface for good bond. Except where the Drawings call for joint surfaces to be coated, clean joint surfaces of laitance, loose or defective concrete and foreign material by hydroblasting or sandblasting (exposing aggregate), roughen surface to expose aggregate to a depth of at least 1/4 inch and wash thoroughly. Remove standing water from the construction joint surface before new concrete is placed.

4. After surfaces have been prepared cover approximately horizontal construction joints with a 3-inch lift of a grout mix consisting of Class A concrete batched without coarse aggregate; place and spread grout uniformly. Place wall concrete on the grout mix immediately thereafter.

C. Set and secure reinforcement, anchor bolts, sleeves, inserts and similar embedded items in the forms where indicated on Contract Drawings, shop drawings and as otherwise required. Obtain Engineer's acceptance before

D. concrete is placed. Accuracy of placement is the sole responsibility of the Contractor.

E. Place no concrete until at least 4 hours after formwork, inserts, embedded items, reinforcement and surface preparation have been completed and accepted by the Resident Project Representative. Clean surfaces of forms and embedded items that have become encrusted with grout or previously-placed concrete before placing adjacent concrete.

F. Casting New Concrete Against Old: Where concrete is to be cast against old concrete (any concrete which is greater than 60 days of age), thoroughly clean and roughen the surface of the old concrete by hydro-blasting or sandblasting (exposing aggregate). Coat joint surface with epoxy bonding agent following manufacturer's written instructions, unless indicated otherwise. Unless noted otherwise, this provision does not apply to vertical wall joints where waterstop is installed.

G. Protection from Water: Place no concrete in any structure until water entering the space to be filled with concrete has been properly cut off or diverted and carried out of the forms, clear of the work. Deposit no concrete underwater. Do not allow still water to rise on any concrete until concrete has attained its initial set. Do not allow water to flow over the surface of any concrete in a manner and at a velocity that will damage the surface finish of the concrete. Pumping, dewatering and other necessary operations for removing ground water, if required, are subject to Resident Project Representative review.

H. Corrosion Protection: Position and support pipe, conduit, dowels and other ferrous items to be embedded in concrete construction prior to placement of concrete so there is at least a 2 inch clearance between them and any part of the concrete reinforcement. Do not secure such items in position by wiring or welding them to the reinforcement.

I. Where practicable, provide for openings for pipes, inserts for pipe hangers and brackets, and setting of anchors during placing of concrete.

J. Accurately set anchor bolts and maintain in position with templates while they are being embedded in concrete.

K. Cleaning: Immediately before concrete is placed, thoroughly clean dirt, grease, grout, mortar, loose scale, rust and other foreign substances from surfaces of metalwork to be in contact with concrete.

3.03 HANDLING, TRANSPORTING AND PLACING CONCRETE

A. Conform to applicable requirements of Chapter 8 of ACI 301 and this Section. Use no aluminum materials in conveying concrete.

B. Rejected Work: Remove concrete found to be defective or non-conforming in materials or workmanship. Replace rejected concrete with concrete meeting requirements of Contract Documents, at no additional cost to the Owner.

C. Unauthorized Placement: Place no concrete except in the presence of the Resident Project Representative. Notify the Resident Project Representative in writing at least 24 hours before placement of concrete.

D. Placement in Wall Forms:

1. Do not drop concrete through reinforcing steel.

2. Do not place concrete in any form so as to leave an accumulation of mortar on form surfaces above the concrete.

3. Pump concrete or use hoppers and, if necessary, vertical ducts of canvas, rubber or metal (other than aluminum) for placing concrete in forms so it reaches the place of final deposit without separation. Free fall of concrete shall not exceed 4 feet below the ends of pump hoses, ducts, chutes or buggies. Uniformly distribute concrete during depositing.

4. Do not displace concrete in forms more than 6 feet in horizontal direction from place where it was originally deposited.

5. Deposit in uniform horizontal layers not deeper than 2 feet; take care to avoid inclined layers or inclined construction joints except where required for sloping members.

6. Place each layer while the previous layer is still soft. Rate of placement shall not exceed 5 feet of vertical rise per hour.

7. Provide sufficient illumination in form interior so concrete at places of deposit is visible from the deck or runway.

E. Conveyors and Chutes: Design and arrange ends of chutes, hopper gates and other points of concrete discharge in the conveying, hoisting and placing system so concrete passing from them will not fall separated into whatever receptacle immediately receives it. Conveyors, if used, shall be of a type acceptable to the Resident Project Representative. Do not use chutes longer than 50 feet. Slope chutes so concrete of specified consistency will readily

flow. If a conveyor is used, it shall be wiped clean by a device operated in such a manner that none of the mortar adhering to the belt will be wasted. All conveyors and chutes shall be covered.

F. Placement of Slabs: In hot or windy weather, conducive to plastic shrinkage cracks, apply evaporation retardant to slab after screeding in accordance with manufacturer's instructions and recommendations. Do not use evaporation retardant to increase water content of the surface cement paste. Place concrete for sloping slabs uniformly from the bottom of the slab to the top, for the full width of the placement. As work progresses, vibrate and carefully work concrete around slab reinforcement. Screed the slab surface in an up-slope direction.

G. Concrete Temperature: When placed, not more than 90 degrees F nor less than 55 degrees F for sections less than 12 inches thick, nor less than 50 degrees for all other sections. Do not heat concrete ingredients to a temperature higher than that necessary to keep the temperature of the mixed concrete, as placed, from falling below the specified minimum temperature. When concrete temperature is 85 degrees F or above, do not exceed 60 minutes between introduction of cement to the aggregates and discharge. When the weather is such that the concrete temperature would exceed 90 degrees F, employ effective means, such as pre-cooling of aggregates and mixing water, using ice or placing at night, as necessary to maintain concrete temperature, as placed, below 90 degrees F.

H. Cold Weather Placement: Conform to ACI 306.1 - Standard Specification for Cold Weather Concreting, and the following.

1. Remove snow, ice and frost from surfaces, including reinforcement, against which concrete is to be placed. Before beginning concrete placement, thaw the subgrade to a minimum depth of 6 inches. Warm reinforcement and embedded items to above 32 degrees F prior to concrete placement.

2. Maintain concrete temperature above 50 degrees F for at least 3 days after placement.

3.04 PUMPING OF CONCRETE

A. If pumped concrete does not produce satisfactory results, in the judgement of the Resident Project Representative, discontinue pumping operations and proceed with the placing of concrete using conventional methods.

B. Pumping Equipment: Use a 2-cylinder pump designed to operate with only one cylinder if one is not functioning, or have a standby pump on site during pumping.

C. The minimum hose (conduit) diameter: Comply with ACI 304.2R.

D. Replace pumping equipment and hoses (conduits) that do not function properly.

E. Do not use aluminum conduits for conveying concrete.

F. Field Control: Take samples for slump, air content and test cylinders at the placement (discharge) end of the line.

3.05 CONCRETE PLACEMENT SEQUENCE

A. Place concrete in a sequence acceptable to the Engineer. To minimize effects of shrinkage, place concrete in units bounded by construction joints shown. Place alternate units so each unit placed has cured at least 7 days for hydraulic structures, or 3 days for other structures, before contiguous unit or units are placed, except do not place corner sections of vertical walls until the 2 adjacent wall panels have cured at least 14 days for hydraulic structures and 7 days for other structures.

B. Level the concrete surface whenever a run of concrete is stopped. To ensure straight and level joints on the exposed surface of walls, tack a wood strip at least 3/4-inch thick to the forms on these surfaces. Carry concrete about 1/2 inch above the underside of the strip. About one hour after concrete is placed, remove the strip, level irregularities in the edge formed by the strip with a trowel and remove laitance.

3.06 TAMPING AND VIBRATING

A. Thoroughly settle and compact concrete throughout the entire depth of the layer being consolidated, into a dense, homogeneous mass; fill corners and angles, thoroughly embed reinforcement, eliminate rock pockets and bring only a slight excess of water to the exposed surface of concrete during placement. Use ACI 309R Group 3 immersion-type high-speed power vibrators (8,000 to 12,000 rpm) in sufficient number and with sufficient (at least one) standby units. Use Group 2 vibrators only when accepted by the Resident Project Representative for specific locations.

B. Use care in placing concrete around waterstops. Carefully work concrete by rodding and vibrating to make sure air and rock pockets have been

eliminated. Where flat-strip type waterstops are placed horizontally, work concrete under waterstops by hand, making sure air and rock pockets have been eliminated. Give concrete surrounding the waterstops additional vibration beyond that used for adjacent concrete placement to assure complete embedment of waterstops in concrete.

C. Concrete in Walls: Internally vibrate, ram, stir, or work with suitable appliances, tamping bars, shovels or forked tools until concrete completely fills forms or excavations and closes snugly against all surfaces. Do not place subsequent layers of concrete until previously-placed layers have been so worked. Provide vibrators in sufficient numbers, with standby units as required, to accomplish the results specified within 15 minutes after concrete of specified consistency is placed in the forms. Keep vibrating heads from contact with form surfaces. Take care not to vibrate concrete excessively or to work it in any manner that causes segregation of its constituents.

3.07 PLACING MASS CONCRETE

A. Observe the following additional restrictions when placing mass concrete.

1. Use specified superplasticizer.

2. Maximum temperature of concrete when deposited: 70 degrees F.

3. Place in lifts approximately 18 inches thick. Extend vibrator heads into previously-placed layer.

3.08 REPAIRING SURFACE DEFECTS AND FINISHING

A. Conform to Section 03350 - Concrete Finishing.

3.09 CURING

A. Conform to Section 03390 - Concrete Curing.

3.10 PROTECTION

A. Protect concrete against damage until final acceptance by the Owner.

B. Protect fresh concrete from damage due to rain, hail, sleet or snow. Provide such protection while the concrete is still plastic and whenever such precipitation is imminent or occurring.

C. Do not backfill around concrete structures or subject them to design loadings until all components of the structure needed to resist the loading are complete and have reached the specified 28-day compressive strength, except as authorized otherwise by the Engineer.

END OF SECTION

Section 03341

CONCRETE: MISCELLANEOUS MATERIALS

PART 1 GENERAL

1.01 DESCRIPTION

The materials listed in this section shall meet the standards as stated below.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Refer to Section 01270 – Measurement and Payment for Unit Price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

PART 2 PRODUCTS

2.01 MATERIALS

A. Premolded Expansion Joint Filler

ASTM Standard D 1752, Type II, unless otherwise specified.

B. Non-Shrink Grout

"Embeco" as manufactured by Master Builders Company, Sikadur 42 by Sika Corp., Five Star Grout by U.S. Grout Corp., or approved equal.

C. Membrane Curing Compound

Resin base compound, ASTM Standard C 309, Type 1, with light red tint of fugitive dye.

D. Cotton Mats for Curing

Use cotton mats that uniformly contain at least three-fourths of a pound of cotton filler per square yard with Osnaburg covering cloth weighing not less than 6 ounces per square yard. The mats shall have 6-inch wide peripheral flaps for overlaps.

E. Integral Concrete Coloring

"Sonobrite" as manufactured by L. Sonneborn and Sons, Inc., "Staybrite" as manufactured by W. R. Grace & Company, or approved equal.

F. Polyethylene Film

Use polyethylene film of .006-inch (6 mils) minimum thickness with high-impact strength rating.

G. Expansion Bolts

Phillips Red Head Wedge Anchors as manufactured by Phillips Drill Company, Hilti Stainless Steel "Kwik Bolt" Anchors as manufactured by Hilti Corp. or approved equal.

PART 3 EXECUTION (NOT USED)

END OF SECTION

Section 03350

CONCRETE FINISHING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Repairing surface defects.

B. Finishing concrete surfaces including both formed and unformed surfaces.

C. Sealing concrete surfaces.

D. Installation of concrete fill and installation of concrete topping in bottoms of clarifiers and thickeners.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Refer to Section 01270 – Measurement and Payment for Unit Price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

1.03 REFERENCES

A. ASTM C 144 - Standard Specification for Aggregate for Masonry Mortar.

B. ASTM C 881 - Specification for Epoxy-Resin-Base Bonding Systems for Concrete.

C. ASTM C 1059 - Standard Specification for Latex Agents for Bonding Fresh to Hardened Concrete.

D. ASTM D 4587 - Conducting Tests on Paint and Related Coatings and Materials Using a Fluorescent UV-Condensation Light-and Water-Exposure Apparatus.

E. ASTM E 1155 - Standard Test Method for Determining Floor Flatness and Levelness Using the F Number System.

1.04 SUBMITTALS

A. Conform to Section 01330 - Submittal Procedures

B. Submit manufacturer's technical literature on the following products proposed for use. Include manufacturer's installation and application instructions and, where specified, manufacturer's certification of conformance to requirements and suitability for use in the applications indicated.

A. Floor hardener.

B. Sealer.

C. Epoxy floor topping.

D. Epoxy penetrating sealer.

E. Latex bonding agent.

F. Epoxy adhesive.

G. Abrasive aggregate.

H. Evaporation retardant.

PART 2 P R O D U C T S

2.01 MATERIALS

A. Sealer/Dustproofer (VOC Compliant): Water-based acrylic sealer; non-yellowing under ultraviolet light after 200-hour test in accordance with ASTM D 4587. Conform to local, state and federal solvent emission requirements.

B. Epoxy Floor Topping: Two-component epoxy resin meeting ASTM C 881 Type III, resistant to wear, staining and chemical attack, blended with granite, sand, trap rock or quartz aggregate, trowel-applied over concrete floor. Topping thickness, 1/8 inch; color, gray.

C. Abrasive Aggregate for Nonslip Finish: Fused aluminum oxide grit, or crushed emery aggregate containing not less than 40 percent aluminum oxide and not less than 25 percent ferric oxide. Material shall be factory graded, packaged,

rustproof and nonglazing, and unaffected by freezing, moisture and cleaning materials.

D. Epoxy Penetrating Sealer: Low-viscosity, two-component epoxy system designed to give maximum penetration into concrete surfaces. Sealer shall completely seal concrete surfaces from penetration of water, oil and chemicals; prevent dusting and deterioration of concrete surfaces caused by heavy traffic; and be capable of adhering to floor surfaces subject to hydrostatic pressure from below. Color, transparent amber or gray; surface, nonslip.

E. Latex Bonding Agent: Non-redispersable latex base liquid conforming to ASTM C 1059. When used in water and wastewater treatment structures, bonding agent shall be suitable for use under continuously submerged conditions. Conformance and suitability certification by manufacturer is required.

F. Bonding Grout: Prepare bonding grout by mixing approximately one part cement to one part fine sand meeting ASTM C 144 but with 100 percent passing No. 30 mesh sieve. Mix with water to consistency of thick cream. At Contractor's option, a commercially-prepared bonding agent used in accordance with manufacturer's recommendations and instructions may be used. When used in water and wastewater treatment structures, bonding agent shall be suitable for use under continuously submerged conditions. Conformance and suitability certification by manufacturer is required. Submit manufacturer's technical information on proposed bonding agent.

G. Patching Mortar:

1. Make patching mortar of same materials and of approximately same proportions as concrete, except omit coarse aggregate. Substitute white Portland cement for part of gray Portland cement on exposed concrete in order to match color of surrounding concrete. Determine color by making trial patch. Use minimum amount of mixing water required for handling and placing. Mix patching mortar in advance and allow to stand. Mix frequently with trowel until it has reached stiffest consistency that will permit placing. Do not add water.

2. Proprietary compounds for adhesion or specially formulated cementitious repair mortars may be used in lieu of or in addition to foregoing patching materials provided that properties of bond and compressive strength meet or exceed the foregoing and color of surrounding concrete can be matched where required. Use such compounds according to manufacturer's recommendations. When used in water and wastewater treatment structures, material shall be

suitable for use under continuously submerged conditions. Conformance and suitability certification by manufacturer is required.

H. Epoxy Adhesive: Two-component, 100 percent solids, 100 percent reactive compound developing 100 percent of strength of concrete, suitable for use on dry or damp surfaces. Epoxy used to inject cracks and as a binder in epoxy mortar shall meet ASTM C 881, Type VI. Epoxy used as a bonding agent for fresh concrete shall meet ASTM C 881, Type V.

I. Non-shrink Grout: See Section 03600 - Structural Grout.

J. Spray-Applied Coating: Acceptable products are Thoro System Products "Thoroseal Plaster Mix" or equal. Color: Gray.

K. Concrete Topping: Class H concrete with 3/8-inch maximum coarse aggregate size, as specified in Section 03310 - Structural Concrete.

L. Concrete Fill: Class H concrete with 3/8-inch maximum coarse aggregate size, (Class C where fill thickness exceeds 3 inches throughout a placement), as specified in Section 03310 - Structural Concrete.

M. Evaporation Retardant: Confilm, manufactured by Master Builders; Eucobar, manufactured by Euclid Chemical Company; or equal.

PART 3 EXECUTION

3.01 AGGREGATE CONCEALMENT

A. Unless indicated otherwise on Drawings or approved by Engineer, all surfaces to be finished shall be free of exposed aggregate.

3.02 REPAIRING SURFACE DEFECTS

A. Defective Areas: Repair immediately after removal of forms. Remove honeycombed and other defective concrete down to sound concrete but in no case to a depth less than one inch. Make edges of cuts perpendicular to concrete surface. Thoroughly work bonding grout into the surface with a brush as that the entire surface is covered. Alternatively, a proprietary bonding agent may be used. Use bonding agent in accordance with manufacturer's instructions. While bonding coat is still tacky, apply premixed patching mortar. Thoroughly consolidate mortar into place and strike off to leave patch slightly higher than surrounding surface. To permit initial shrinkage, leave undisturbed for at least 1 hour before final finishing. Keep patched area damp for 7 days. Alternatively, a proprietary cementitious repair mortar may be used and placed in accordance with manufacturer's

instructions. Do not use metal tools in finishing patches in formed walls which will be exposed.

B. Tie Holes: Patch holes immediately after removal of forms. After cleaning and roughening with a wire brush on a rotary drill, thoroughly dampen tie hole and fill solid with patching mortar. Taper tie holes shall have the plug, specified in Section 03055 – Concrete Structures, driven into the hole to the center of the wall before grouting. Completely fill taper tie holes with patching mortar except that non-shrink grout shall be used for all walls in contact with soil or liquid. On wall faces exposed to view, fill the outer 2 inches of the taper tie hole with patching mortar blended to match adjacent concrete.

C. Cracks: Repair cracks in excess of 0.01 inch by pressure injection of moisture-insensitive epoxy-resin system. Submit proposed material and method of repair for approval prior to making repairs.

D. Structural Repair: When required, make structural repairs after prior approval of Engineer as to method and procedure, using specified epoxy adhesive or approved epoxy mortar.

3.03 FINISHING OF FORMED SURFACES

A. Unfinished Surfaces: Finish is not required on surfaces concealed from view in completed structure by earth, ceilings or similar cover, unless indicated otherwise on Drawings.

B. Rough Form Finish:

1. No form facing material is required on rough form finish surfaces.

2. Patch tie holes and defects. Chip off fins exceeding 1/4 inch in height.

3. Rough form finish may be used on concrete surfaces which will be concealed from view by earth in completed structure, except concealed surfaces required to have smooth form finish, as shown on Drawings.

C. Smooth Form Finish:

1. Form facing shall produce smooth, hard, uniform texture on concrete. Use plywood or fiberboard linings or forms in as large sheets as practicable, and with smooth, even edges and close joints.

2. Patch tie holes and defects. Rub fins and joint marks with wooden blocks to leave smooth, unmarred finished surface.

3. Provide smooth form finish on the wet face of formed surfaces of water-holding structures, and of other formed surfaces not concealed from view by earth in completed structure, except where otherwise indicated on Drawings. Walls that will be exposed after future construction, at locations indicated on Drawings, shall have smooth form finish. Smooth form finish on exterior face of exterior walls shall extend 2 feet below final top of ground elevation. Exterior face of all perimeter grade beams shall have smooth form finish for full depth of grade beam.

D. Rubbed Finish:

1. Use plywood or fiberboard linings or forms in as large sheets as practicable, and with smooth, even edges and close joints.

2. Remove forms as soon as practicable, repair defects, wet surfaces, and rub with No. 16 carborundum stone or similar abrasive. Continue rubbing sufficiently to bring surface paste, remove form marks and fins, and produce smooth, dense surface of uniform color and texture. Do not use cement paste other than that drawn from concrete itself. Spread paste uniformly over surface with brush. Allow paste to reset, then wash surface with clean water.

3. Use rubbed finish at locations indicated on Drawings, except where rubbed finish is indicated for a wall which will be containing a liquid, use spray-applied coating.

E. Spray-applied Coating: At Contractor's option, in lieu of rubbed finish, spray-applied coating may be applied after defects have been repaired and fins removed. Remove form oil, curing compound and other foreign matter that would prevent bonding of coating. Apply coating in uniform texture and color in accordance with coating manufacturer's instructions.

F. Related Unformed Surfaces: Tops of piers, walls, bent caps, and similar unformed surfaces occurring adjacent to formed surfaces shall be struck smooth after concrete is placed. Float unformed surfaces to texture reasonably consistent with that of formed surfaces. Continue final treatment on formed surfaces uniformly across unformed surfaces.

3.04 HOT WEATHER FINISHING

A. When hot weather conditions exist, as defined by Section 03310 - Structural Concrete and as judged by the Engineer, apply evaporation retardant to the surfaces of slabs, topping and concrete fill placements immediately after each step in the finishing process has been completed.

3.05 FINISHING SLABS AND SIMILAR FLAT SURFACES TO CLASS A, B, AND C TOLERANCES

A. Apply Class A, B, and C finishes at locations indicated on Drawings.

B. Shaping to Contour: Use strike-off templates or approved compacting-type screeds riding on screed strips or edge forms to bring concrete surface to proper contour. See Section 03055 – Concrete Structures for edge forms and screeds.

C. Consolidation and Leveling: Concrete to be consolidated shall be as stiff as practicable Thoroughly consolidate concrete in slabs and use internal vibration in beams and girders of framed slabs and along bulkheads of slabs on grade. Consolidate and level slabs and floors with vibrating bridge screeds, roller pipe screeds or other approved means. After consolidation and leveling, do not permit manipulation of surfaces prior to finishing operations.

D. Tolerances for Finished Surfaces: Check tolerances by placing straightedge of specified length anywhere on slab. Gap between slab and straightedge shall not exceed tolerance listed for specified class.

Class	Straightedge Length in Feet	Tolerance in Inches
A	10	1/8
B	10	1/4
C	2	1/4

E. Raked Finish: After concrete has been placed, struck off, consolidated and leveled to Class C tolerance, roughen surface before final set. Roughen with stiff brushes or rakes to depth of approximately 1/4 inch. Notify Engineer prior to placing concrete requiring initial raked surface finish so that acceptable raked finish standard may be established for project. Protect raked, base-slab finish from contamination until time of topping. Provide raked finish for following:

1. Surfaces to receive bonded concrete topping or fill.
2. Steep ramps, as noted on Drawings.
3. Additional locations as noted on Drawings.

F. Float Finish:

1. After concrete has been placed, struck off, consolidated and leveled, do not work further until ready for floating. Begin floating when water

sheen has disappeared, or when mix has stiffened sufficiently to permit proper operation of power-driven float. Consolidate surface with power-driven floats. Use hand floating with wood or cork-faced floats in locations inaccessible to power-driven machine and on small, isolated slabs.

2. After initial floating, re-check tolerance of surface with 10-foot straightedge applied at not less than two different angles. Cut down high spots and fill low spots to Class B tolerance. Immediately re-float slab to a uniform, smooth, granular texture.

3. Provide float finish at locations not otherwise specified and not otherwise indicated on Drawings.

G. Trowel Finish:

1. Apply float finish as previously specified. After power floating, use power trowel to produce smooth surface which is relatively free of defects but which may still contain some trowel marks. Do additional troweling by hand after surface has hardened sufficiently. Do final troweling when ringing sound is produced as trowel is moved over surface. Thoroughly consolidate surface by hand troweling operations.

2. Produce finished surface free of trowel marks, uniform in texture and appearance and conforming to Class A tolerance. On surfaces intended to support floor coverings, remove defects which might show through covering by grinding.

3. Provide trowel finish for floors which will receive floor covering and additional locations indicated on Drawings.

H. Broom or Belt Finish:

1. Apply float finish as previously specified. Immediately after completing floated finish, draw broom or burlap belt across surface to give coarse transverse scored texture.

2. Provide broom or belt finish at locations indicated on Drawings.

3.06 FINISHING SLABS AND SIMILAR FLAT SURFACES TO "F-NUMBER SYSTEM" FINISH

A. Shaping to Contour: Use strike-off templates or approved compacting-type screeds riding on screed strips or edge forms to bring concrete surface to proper contour. Edge forms and screeds: Conform to Section 03055 – Concrete Structures.

B. Consolidation and Leveling: Concrete to be consolidated shall be as dry as practicable. Thoroughly consolidate concrete in slabs and use internal vibration in beams and girders of framed slabs and along bulkheads of slabs on grade. Consolidate and level slabs and floors with vibrating bridge screeds, roller pipe screeds or other approved means. After consolidation and leveling, do not manipulate surfaces prior to finishing operations.

C. Tolerances for Finished Surfaces: Independent testing laboratory will check floor flatness and levelness in accordance with Paragraph 3.12, Field Quality Control.

D. Float Finish:

1. After concrete has been placed, struck off, consolidated and leveled, do not work further until ready for floating. Begin floating when water sheen has disappeared, or when mix has stiffened sufficiently to permit proper operation of power-driven float. Consolidate surface with power-driven floats. Use hand floating with wood or cork-faced floats in locations inaccessible to power-driven machine and on small, isolated slabs.

2. Check tolerance of surface after initial floating with a 10-foot straightedge applied at not less than two different angles. Cut down high spots and fill low spots. Immediately refloat slab to uniform, smooth, granular texture to F_F20/F_L17 tolerance, unless shown otherwise on Drawings.

3. Provide "F-Number System" float finish at locations indicated on Drawings.

E. Trowel Finish:

1. Apply float finish as previously specified. After power floating, use power trowel to produce smooth surface which is relatively free of defects but which may still contain some trowel marks. Do additional trowelings by hand after surface has hardened sufficiently. Do final troweling when ringing sound is produced as trowel is moved over surface. Thoroughly consolidate surface by hand troweling operations.

2. Produce finished surface free of trowel marks, uniform in texture and appearance and conforming to an F_F25/F_L20 tolerance for slabs on grade and F_F25/F_L17 for elevated slabs, unless shown otherwise on Drawings. On surfaces intended to support floor coverings, remove defects, which might show through covering, by grinding.

3. Provide "F-Number System" trowel finish at locations indicated on Drawings.

3.07 BONDED CONCRETE TOPPING AND FILL

A. Surface Preparation:

1. Protect raked, base-slab finish from contamination until time of topping. Mechanically remove oil, grease, asphalt, paint, clay stains or other contaminants, leaving clean surface.

2. Prior to placement of topping or fill, thoroughly dampen roughened slab surface and leave free of standing water. Immediately before topping or fill is placed, scrub coat of bonding grout into surface. Do not allow grout to set or dry before topping or fill is placed.

B. Concrete Fill:

1. Where concrete fill intersects a wall surface at an angle steeper than 45 degrees from vertical, provide a 1.5-inch deep keyway in the wall at the point of intersection; size keyway so that no portion of the concrete fill is less than 1.5 inches thick. Form keyway in new walls; create by saw cutting the top and bottom lines and chipping in existing walls.

2. Apply wood float finish to surfaces of concrete fill.

3. Provide concrete fill at locations shown on Drawings.

C. Bonded Concrete Topping in Bottom of Clarifiers and Thickeners:

1. Minimum thickness of concrete topping: 1 inch. Maximum thickness when swept in by clarifier and thickener equipment: 3 inches.

2. Compact topping and fill by rolling or tamping, bring to established grade, and float. Topping grout placed on sloping slabs shall proceed uniformly from the bottom of the slab to the top, for the full width of the placement. Coat surface with evaporation retardant as needed between finishing operations to prevent plastic shrinkage cracks.

3. Screed topping to true surface using installed equipment. Protect equipment from damage during sweeping-in process. Perform sweeping-in process under supervision of equipment manufacturer's factory representative. After topping has been screeded, apply wood float finish. During finishing, do not apply water, dry cement or mixture of dry cement and sand to the surface.

4. As soon as topping or fill finishing is completed, coat surface with curing compound. After the topping is set and sufficiently hard in clarifiers and where required by the Engineer, fill the tank with sufficient water to cover the entire floor for 14 days.

5. Provide bonded concrete topping in bottom of all clarifiers and thickeners.

3.08 EPOXY PENETRATING SEALER

A. Surfaces to receive epoxy penetrating sealer: Apply wood float finish. Clean surface and apply sealer in compliance with manufacturer's instructions.

B. Rooms with concrete curbs or bases: Continue application of floor coating on curb or base to its juncture with masonry wall. Rooms with solid concrete walls or wainscots: Apply minimum 2-inch-high coverage of floor coating on vertical surface.

C. Mask walls, doors, frames and similar surface to prevent floor coating contact.

D. When coving floor coating up vertical concrete walls, curbs, bases or wainscots, use masking tape or other suitable material to keep a neat level edge at top of cove.

E. Provide epoxy penetrating sealer at locations indicated on Drawings.

3.09 EPOXY FLOOR TOPPING

A. Surfaces to receive epoxy floor topping: Apply wood float finish unless recommended otherwise by epoxy floor topping manufacturer. Clean surface and apply epoxy floor topping in compliance with manufacturer's recommendations and instructions. Thickness of topping: 1/8 inch.

B. Rooms with concrete curbs or bases: Continue application of floor coating on curb or base to its juncture with masonry wall. Rooms with solid concrete walls or wainscots: apply 2-inch-high coverage of floor coating on vertical surface.

C. Mask walls, doors, frames and similar surfaces to prevent floor coating contact.

D. When coving floor coating up vertical concrete walls, curbs, bases or wainscots, use masking tape or other suitable material to keep a neat level edge at top of cove.

E. Finished surface shall be free of trowel marks and dimples.

F. Provide epoxy floor topping at locations indicated on Drawings.

3.10 SEALER/DUSTPROOFER

G. Where sealer or sealer/dustproofer is indicated on Drawings, just prior to completion of construction, apply coat of specified clear sealer/dustproofing compound to exposed interior concrete floors in accordance with manufacturer's instructions.

3.11 NONSLIP FINISH

H. Apply float finish as specified. Apply two-thirds of required abrasive aggregate by method that ensures even coverage without segregation and re-float. Apply remainder of abrasive aggregate at right angles to first application, using heavier application of aggregate in areas not sufficiently covered by first application. Re-float after second application of aggregate and complete operations with troweled finish. Perform finishing operations in a manner that will allow the abrasive aggregate to be exposed and not covered with cement paste.

I. Provide nonslip finish at locations indicated on Drawings.

3.12 FIELD QUALITY CONTROL

J. Flatness and levelness of slabs and similar flat surfaces that are indicated on Drawings to receive "F-Number System" finish will be checked by independent testing laboratory employed by Owner in accordance with Section 01454 - Testing Laboratory Services.

K. Tolerances for "F-Number System" finished surfaces:

1. Floor tolerance shall be determined in accordance with ASTM E 1155.

2. Floor flatness and levelness tolerances:

a F_F defines maximum floor curvature allowed over 24 inches. Computed on the basis of successive 12-inch elevation differentials, F_F is commonly referred to as the "flatness F-Number."

b F_F = 4.57
Maximum difference in elevation, in decimal inches, between successive 12-inch elevation differences.

c F_L defines relative conformity of floor surface to horizontal plane as measured over 10-foot distance. F_L is commonly referred to as "levelness F-number."

d F_L = 12.5
Maximum difference in elevation, in inches, between two points separated by 10 feet.

3. Achieve specified overall slab tolerance. Minimum local tolerance (1/2 bay, unless otherwise designated by Engineer): 2/3 of specified tolerance.

4. Tolerance for floated finish: F_F20/F_L17, unless otherwise shown on Drawings.

5. Tolerance for troweled finish: F_F25/F_L20 for slabs on grade, and F_F25/F_L17 for elevated slabs, unless otherwise shown on Drawings.

3.13 CURING

L. Conform to requirements of Section 03390 - Concrete Curing.

END OF SECTION

Section 03390

CONCRETE CURING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Curing of structural concrete.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this Section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Refer to Section 01270 – Measurement and Payment for Unit Price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

1.03 REFERENCES

A. ACI 308 - Standard Practice for Curing Concrete.

B. ASTM C 171 - Standard Specifications for Sheet Materials for Curing Concrete.

C. ASTM C 309 - Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete.

D. ASTM D 44587 - Conducting Tests on Paint and Related Coatings and Materials Using a Fluorescent UV-Condensation Light-and Water-Exposure Apparatus.

1.04 DEFINITIONS

A. Mass Concrete: Concrete sections 4 feet or more in least dimension.

1.05 SUBMITTALS

A. Conform to Section 01330 - Submittal Procedures.

B. Product Data: Submit description of proposed curing method for concrete. When use of membrane-forming compound is proposed, submit manufacturer's technical information including material specifications, installation instructions and recommendations, and evidence that compound is satisfactory for intended application. State locations where curing compound will be used.

C. When membrane-forming compounds are to be used, submit certification by the manufacturer of compliance with specified requirements and compatibility with toppings, coatings, finishes, and adhesives to be applied.

PART 2 PRODUCTS

2.01 MATERIALS

A. Membrane-forming Curing Compound: Conform to ASTM C 309, Type 1D, and following requirements.

1. Minimum solids content: 30 percent.

2. Compound shall not permanently discolor concrete. When used for liquid- containing structures, curing compound shall be white-pigmented.

3. When used in areas that are to be coated, or that will receive topping or floor covering, material shall not reduce bond of coating, topping, or floor covering to concrete. Curing compound manufacturer's technical information shall state conditions under which compound will not prevent bond.

4. Conform to local, state and federal solvent emission requirements.

B. Clear Curing and Sealing Compound (VOC Compliant): Conform to ASTM C 309, Type 1, Class B, and the following requirements: 30 percent solids content minimum; non-yellowing under ultraviolet light after 500-hour test in accordance with ASTM D 4587. Sodium silicate compounds are not permitted. Conform to local, state and federal solvent emission requirements.

C. Sheet Material for Curing Concrete: ASTM C 171; waterproof paper, polyethylene film or white burlap-polyethylene sheeting.

D. Curing Mats (for use in Curing Method 2): Heavy shag rugs or carpets, or cotton mats quilted at 4 inches on center; 12 ounce per square yard minimum weight when dry.

E. Water for curing: Clean and potable.

PART 3 EXECUTION

3.01 CURING PROCEDURES

A. Comply with ACI 308 and the requirements specified herein. Protect freshly-deposited concrete from premature drying and excessively hot or cold temperatures. Maintain minimal moisture loss and relatively constant temperature during time necessary for hydration of cement and proper hardening of concrete.

B. Unformed Surfaces: For concrete surfaces not in contact with forms, use one of following procedures immediately after completion of placement and finishing.

1. Ponding or continuous sprinkling.

2. Absorptive mat or fabric kept continuously wet.

3. Sand or other covering kept continuously wet.

4. Continuous steam bath (not exceeding 150 degrees F at surface of concrete).

5. Vapor mist bath.

6. Membrane-forming curing compound applied according to manufacturer's recommendations. After the curing compound has dried, wet slab surfaces and cover with waterproof paper, polyethylene film, or white burlap-polyethylene sheeting after the application of the curing compound. Tape sheet seams together and provide sufficient weights to keep the sheeting in place. Wet the slab surface again if the sheeting becomes dislodged, and replace the sheeting.

7. Other moisture-retaining coverings as approved by Engineer.

C. Restrictions on Use of Curing Compounds: Unless curing compound manufacturer certifies that curing compound will not prevent bond to cured

surface, do not use curing compound on surfaces that will be rubbed or receive additional concrete, mortar, topping, terrazzo or other cementitious finishing materials, on slabs under resilient floors or built-up roofing, or on surfaces to be waterproofed, sealed, hardened or painted.

D. Curing and Sealing Compounds: At locations indicated, cure exposed interior slabs and troweled slabs receiving mastic-applied adhesives with specified clear curing and sealing compound in accordance with manufacturer's recommendations. Do not store materials directly on curing membranes. Use plywood to protect curing membrane from damage. Immediately repair membranes damaged by foot traffic or other operations.

E. Duration of Curing: Continue curing until cumulative number of days or fractions of days during which ambient temperature is above 50 degrees F has totaled 7. Continue curing of water-retaining structures for a total of 14 days. When high-early-strength concrete has been used, continue curing for total of 3 days. Prevent rapid drying at end of curing period.

F. Formed Surfaces: During the curing period keep wet steel forms heated by sun and wood forms in contact with concrete. When forms are to be removed during curing period, employ curing materials or methods immediately. Continue such curing for remainder of curing period.

G. Temperature:

1. Cold Weather. When mean daily temperature of atmosphere is less than 40 degrees F, maintain temperature of concrete between 50 and 70 degrees F for required curing period. When necessary, make arrangements for heating, covering, insulating or housing concrete work in advance of placement to maintain required temperature and moisture conditions. Prevent damage or injury due to concentration of heat. When combustion heaters are necessary in enclosed or protected area where concrete slabs are being placed, vent heaters.

2. Hot Weather. In advance of placement make arrangements for shading, fog spraying, sprinkling, ponding or installation of windbreaks or wet covering of light color. Take such protective measures as quickly as concrete hardening and finishing operations will allow.

3. Temperature Changes. Control so rate of change in temperature of concrete is as uniform as possible. Do not permit temperature change to exceed 5 degrees F in any one hour or 50 degrees F in any 24-hour period.

H. Protection from Mechanical Injury. During curing period, protect concrete from damaging mechanical disturbances, particularly load stresses, heavy shock, and excessive vibration. Protect finished concrete surfaces from damage

caused by construction equipment, materials or methods, and by rain or running water. Do not load self-supporting structures in a way that over stresses concrete.

3.02 CURING MASS CONCRETE

A. Observe the following additional restrictions when curing mass concrete.

1. Minimum curing period: 2 weeks.

2. When ambient air temperature falls below 32 degrees F, protect surface of concrete against freezing.

3. Do not use steam or other curing methods that will add heat to concrete.

4. Keep forms and exposed concrete continuously wet for at least the first 48 hours after placing, and whenever surrounding air temperature is above 90 degrees F during final curing period.

5. During 2-week curing period, provide necessary controls to prevent ambient air temperature immediately adjacent to concrete from falling more than 30 degrees F in 24 hours.

END OF SECTION

Section 05120

STRUCTURAL STEEL

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Work Included: Furnish all labor, materials, services, equipment and appliances required in conjunction with or property incidental to the furnishing, fabrication, delivery, and erection of structural steel complete, including, but not limited to, the following:

1. Structural steel columns, girders, beams, angles, steel plates, miscellaneous deck support angles, connections, and component parts.
2. Qualifications of welders.
3. Shop prime coat of paint and field touch-up painting.
4. Temporary construction bracing.
5. Fabrication/erection inspection and testing.

B. Extent of structural steel work is shown on the Drawings, including, notes and details to show sizes and locations of members, typical connections and type of steel required.

C. Include all supplementary parts and members necessary to complete the structural steel work, regardless of whether all such parts are definitely shown or specified, and furnish all such bolts, gussets, plates, etc., as may be required for the proper assembly of all items.

1.02 QUALITY CONTROL

A. Latest adopted edition of all standards referenced in this Section shall apply, unless noted otherwise. In case of conflict between these Contract Documents and a referenced standard, the Contract Documents shall govern. In case of conflict between these Contract Documents and the Building Code the more stringent shall govern.

B. Contractor shall furnish fabrication/erection inspection and testing of all welds in accordance with AWS D1 .1, Chapter 6. Submit records of inspections and tests to City's testing laboratory for their review.

C. Fabricator shall employ a competent technician, engineer or independent testing laboratory to inspect the fabrication work to ensure compliance with

the Contract Documents and shall identify such inspector to City's testing laboratory. Inspector shall examine in the shop all welding, bolting, painting, galvanizing, and straightness and alignment of fabricated members.

D. All materials, fabrication procedures and field erection are subject to verification inspection and testing, by the City's testing laboratory, in both shop and Held. Such inspections and tests will not relieve Contractor of his responsibility for providing materials and fabrication procedures in compliance with specified requirements. City reserves the right to use ultrasonic or radiographic inspection to verify the adequacy of all welds. Testing procedures and acceptance criteria shall be as specified in AWS D1 .1. Promptly remove and replace materials or fabricated components which do not comply.

E. Qualifications for Welding Work: Contractor shall be responsible for qualifying welding operators in accordance with the AWS "Standard Qualification Procedure." Provide certification, to City's testing laboratory, that welders to be employed in work have satisfactorily passed AWS qualification tests within previous 12 months. If recertification of welders is required, retesting will be Contractor's responsibility.

F. Qualifications of Welding Procedures: Contractor shall provide the testing laboratory with welding procedures which are to be used in executing this work. Welding procedures shall be qualified prior to use in accordance with AWS D1.1, Part B.

G. Comply with provisions of the following codes, Specifications and standards, in addition to the Building Code:

1. AISC, "Code of Standard Practice for Steel Buildings and Bridges," except that the following sentence in paragraph 4.2.1 shall not apply to this project: "This approval constitutes the City's acceptance of all responsibility for the design adequacy of any detail configuration of connections developed by the fabricator as part of his preparation of these shop drawings."
2. AISC, "Specification for Structural Steel Buildings," including the "Commentary" and Supplements thereto, as issued.
3. AISC, "Specifications for Structural Joints using ASTM A 325 or A 490 Bolts," approved by the Research Council on Structural Connections of the Engineering Foundation.
4. AWS D1 .1, "Structural Welding Code."
5. ASTM A 6, "Specifications for General Requirements for Delivery of Rolled Steel Plates, Shapes, Sheet Piling, and Bars for Structural Use."

6. Industrial Fasteners Institute, "Handbook on Bolt, Nut, and Rivet Standards."
7. Steel Structure Painting Council:
   1 Painting Manual, Volume 1, Good Painting Practice
   2 Painting Manual, Volume 2, Systems Specifications
8. Qualifications:
   1 Structural steel fabricator shall have not less than five years experience in the fabrication of structural steel for buildings and shall be currently certified under the AISC Qualify Certification Program for fabrication of Category I or higher structures. An otherwise qualified fabricator who is not a member of the AISC Quality Certification Program will be accepted if satisfactory evidence of qualifications is submitted prior to contract award. For non-certified fabricators, contractor shall submit a resume describing plant size, equipment, quality control procedures and personnel, and experience on comparable work in the last three years.
   2 Structural steel erector shall have not less than five years experience in the erection of structural steel.

1.03 DESIGN:

A. Connections:
   1. All structural steel beams, truss, and bracing connections not specifically detailed on the Drawings shall be designed by the Contractor, under the direct supervision of a Registered Professional Engineer, licensed in the State of Texas, to resist all the forces, and shall be shown in detail on the shop drawings.
   2. Connections shall be designed in accordance with the requirements in the AISC Manual of Steel Construction latest edition.

B. Substitutions: Substitutions of sections or modifications of details, or both, and the reasons therefore, shall be submitted with the shop drawings for approval. Submitted substitutions must be clearly identified and noted as such. Approved substitutions, modifications, and necessary changes in related portions of the work shall be coordinated by the fabricator and shall be accomplished at no additional cost to the City.

C. Responsibility for Errors: Fabricator shall be responsible for all errors of detailing, fabrications, and for the correct fitting of structural steel members.

D. Templates: Shall be furnished by fabricator with instructions for setting of anchor bolts and bearing plates.

1.04 SUBMITTALS:

A. Conform to requirements of Section 01330 – Submittal Procedures.

B. Product Data: Submit producer's or manufacturer's specifications and installation instructions, including laboratory test reports and other data, to show compliance with Specifications for the following products.

1. Structural steel primer paint.

C. Mill Certificates: Submit for the City's record certificates of mill analysis showing compliance with Specifications for the following products:
1. Structural steel (each type).
2. High-strength bolts (each type), including nuts and washers.

D. Shop Drawings:
1. Submit shop drawings prepared under the supervision of a Registered Professional Engineer, licensed in the State of Texas, including complete details and schedules for fabrication and shop assembly of members, erection plans, details, procedures, and diagrams showing sequence of erection. Include details of cuts, connections, camber, holes, and other pertinent data. Indicate welds by standard AWS symbols, and show size, length, and type of each weld. Shop drawings and erection drawings shall not be made by using reproductions of Contract Drawings.
2. Structural steel members for which shop drawings have not been reviewed shall not be fabricated. Architect's review shall cover general locations, spacings, and details of design. Omission from shop drawings of any materials required by the Contract Documents shall not relieve the Contractor of the responsibility of furnishing and installing such materials, even though such shop drawings may have been reviewed and returned.
3. Submit setting drawings, templates, and directions for installation of anchor bolts and other anchorages to be installed by other trades.

E. Certification: Submit evidence of current AISC plant certification (see "Qualifications").

1.05 PRODUCT DELIVERY, STORAGE, AND HANDLING:

A. Deliver anchor bolts and anchorage devices, which are to be embedded in cast-in-place concrete or masonry, in ample time to not delay that work.

B. Store materials to permit easy access for inspection and identification. Keep steel members off the ground, using pallets, platforms, or other supports. Protect steel members and packaged materials from corrosion and deterioration.

C. Do not store materials on structure in a manner that might cause distortion or damage to members or supporting structures. Repair or replace damaged materials or structures as directed.

D. Support cambered members during shipment and handling in a manner which will not result in loss of camber.

1.06 JOB CONDITIONS:

A. Coordinate erection of structural steel with work of other trades.
B. Do not install columns which have anchor bolts in concrete, until concrete members have attained their 28 day compressive strengths.

1.07 MEASUREMENT AND PAYMENT

A. No separate payment will be made for work under this section. Include payment in the Lump Sum Base Bid Price.

PART 2 P R O D U C T S

2.01 MATERIALS

A. Metal Surfaces, General: For fabrication of work which will be exposed to view, use only materials which are smooth and free of surface blemishes including pitting, seam marks, roller marks, rolled trade names, and roughness. Remove such blemishes by grinding, or by welding and grinding prior to cleaning, treating and application of surface finishes.

B. Steel:

1. Wide flange shapes ASTM A572-50 (50ksi yield).
2. Rolled Shapes, Plates, and Bars: ASTM A 36 (36 ksi yield).
3. Cold formed Steel Tubing: ASTM A 500, Grade B, (46,000 psi yield)
4. Steel Pipe: ASTM A 53, Type E or S, Grade B.

C. Bolts and Washers:

1. Bolts: Anchor bolts and erection bolts shall conform to ASTM A 307 and to the requirements for regular hexagon bolts and nuts of ANSI Standards B18.2.1 and B18.2.2.
2. High-strength bolts for connections shall conform to ASTM A 325 or ASTM A 490. Dimensions of bolt heads and nuts shall conform to requirements for heavy hexagon nuts of ANSI Standards B18.2.1 and B18.2.2.
3. Washers: Circular washers shall be flat and smooth, and shall conform to requirements of Type A washers in ANSI Standard B23.1. Beveled washers for "S" shapes and channels shall be square or rectangular, shall taper in thickness, and shall be smooth. Washers for use with high strength bolts shall be hardened.
4. Drilled anchor bolts shall be one of the following:
    a. Wej-it Bolt, Wej-it Corporation, Tulsa, Oklahoma
    b. Kwik Bolt, Hilti Fastening Systems, Tulsa, Oklahoma
    c. Trubolt, Ramset Fastening Systems, Paris, Kentucky

D. Welding electrodes shall conform to the requirements of the Specifications of the 'American Welding Society. Use E70 electrodes. For high-strength, low-alloy steel, provide electrodes, welding rods, and filler metals equal in strength and compatible in appearance with parent metal joined.

E. Primer Paint:
1. Standard shop coat of red oxide primer, meeting the requirements of "SSPC-Paint 13" or Federal Specification "TT-P-636," applied to a dry film thickness of 2.0 mils.

F. Zinc-coating: When galvanized steel is required, the zinc-coating shall conform to ASTM A 123. Zinc-coating for threaded products shall conform to ASTM A 153, Class C. Zinc-coating for sheet steel shall conform to ASTM A 591.

G. Cold galvanizing compound shall be "ZRC" cold galvanizing compound, as manufactured by ZRC Chemical Products, Quincy, Massachusetts.

2.02 FABRICATION

A. Shop Fabrication and Assembly:
1. Fabricate and assemble structural assemblies in the shop to greatest extent possible. Fabricate items of structural steel in accordance with AISC Specifications and as indicated on final shop drawings.
2. Provide camber in members where indicated. Specified camber applies at jobsite, just prior to erection, lying down flat so that member weight has no effect. Contractor shall take necessary precautions to prevent or compensate for camber loss during shipment. Measured camber in members up to 50'-0" long shall be within a tolerance of minus 1/2" to plus zero from the amount specified. For members greater than 50'-0" long, both positive and negative tolerance may increase 1/8" for every 10'-0" of length in excess of 50'-0". Members with a field measured camber outside of the specified tolerance shall be returned to the shop.
3. Properly mark and match-mark materials for field assembly. Fabricate for delivery sequence which will expedite erection and minimize field handling of materials.
4. Where finishing is required, complete assembly, including welding of units, before start of finishing operations. Provide finish surfaces of members exposed in final structure free of markings, burrs, and other defects.
5. Splicing of structural steel members is prohibited without prior approval of the Architect. Any member having a splice not shown and detailed on approved shop drawings shall be rejected.
6. Members in compression joints which depend on contact bearing shall have the bearing surfaces milled to a common plane. Members to be milled shall be completely assembled before milling.
7. Plates shall be free of gross internal discontinuities such as ruptures and delaminations. Plates shall comply with ASTM A 578, Level 1.

8. Mill tolerances: Comply with ASTM A 6.
9. Fabrication tolerances: Comply with AISC Code of Standard Practice.

B. Connections:

1. Weld or bolt shop connections, as indicated on the Drawings.
2. Bolt field connections, except where welded connections or other connections are indicated. Provide specified threaded fasteners for all principle bolted connections. Holes for bolted constructions shall be drilled or punched at right angles to member. The slope of surfaces under the bolt head and nut shall not exceed 1:20. Provide beveled washers where slopes exceed 1:20. Bolt holes shall have a diameter not greater than 1/16" larger than the nominal bolt diameter. Do not flame cut holes or enlarge by burning. Provide washers over all slotted holes in an outer ply.
3. High-strength Bolted Construction: Install high-strength threaded fasteners in accordance with AISC, "Specifications for Structural Joints using ASTM A 325 or A 490 Bolts," (RCRBSJ).
4. Welded Construction: Comply with AWS Structural Welding Code for procedures, appearance and quality of welds, and methods used in correcting welding work. Assemble and weld built-up sections by methods which will produce true alignment of axes without warp. Welds not specified shall be continuous fillet welds designed to develop the full strength of member. No combination of bolts and welds shall be used for stress transmission at the same face of any connections.
5. Clean completed welds prior to inspection. Slag shall be removed from all completed welds and the weld and adjacent base metal shall be cleaned by brushing or other suitable means. Tightly adherent splatter remaining after the cleaning operation is acceptable unless its removal is required for the purpose of nondestructive testing.
6. Base Plates: Hole sizes for anchor bolts may be oversized to facilitate erection as follows:

   Bolts 3/4" to 7/8" Diameter - 5/16" oversize
   Bolts 1" to 2" Diameter - 1/2" oversize
   Bolts over 2" Diameter - 1" oversize

Use oversize or plate washers under nut at all oversized holes in base plates. Washers must be large enough to cover the entire hole. Washer thickness shall be at least 1/8 of bolt diameter.

C. Holes for Other Work: Provide holes required for securing other work to structural steel framing and for passage of other work through steel framing members, as shown on final shop drawings. Provide threaded nuts welded to framing and other specialty items as indicated to receive other work. Cut, drill or punch holes perpendicular to metal surfaces. Do not flame cut holes or enlarge holes by burning. Drill holes in bearing plates.

D. Zinc-coating:

1. The Following Steel shall be Galvanized:
   a. As specified on drawings.

2.03 SHOP PAINTING

A. General: Shop Painting shall be coordinated with Section 09901 – Protective Coatings. Shop paint structural steel, except those members or portions of members to receive a galvanized coating and those members to be embedded in concrete or mortar. Paint embedded steel which is partially exposed, on exposed portions and initial 2" of embedded areas only.
   1. Do not paint surfaces which are to be welded.
   2. Do not paint surfaces which are scheduled to receive sprayed-on fireproofing.

B. Surface Preparation: After inspection and before shipping, clean steel work to be painted. Remove loose rust, loose mill scale, spatter, and slag or flux deposits. Clean steel in accordance with Steel Structures Painting Council (SSPC) as follows:
   1. SP-1, "Solvent Cleaning."
   2. SP-2, "Hand Tool Cleaning."
   3. SP-3, "Power Tool Cleaning."

C. Painting: Immediately after surface preparation, apply structural steel primer paint in accordance with manufacturers' instructions and at a rate to provide a uniform dry film thickness as specified. Use painting methods which result in full coverage of joints, corners, edges, and exposed surfaces.

PART 3 EXECUTION

3.01 INSPECTION:

A. Erector must examine areas and conditions under which structural steel work is to be installed, and notify Contractor of conditions detrimental to proper and timely completion of work.

3.02 ERECTION:

A. General Comply with AISC Specifications and Code of Standard Practice, and as herein specified

B. Temporary Shoring and Bracing:
   1. Provide adequate shoring and bracing to safely

withstand all loads to which the structure may be subjected during the construction process, including wind loads, dead loads, construction material, and equipment loads. Such bracing shall remain in place as long as required for safety.

2. As the erection progresses, make a sufficient number of permanent welded or bolted connections to withstand erection stresses and maintain stability.

3. The design of temporary shoring and bracing shall be the responsibility of the Contractor.

C. Temporary Planking: Provide temporary planking and working platforms, as necessary, to effectively complete the work.

D. Anchor Bolts: Furnish anchor bolts and other connectors required for securing structural steel to foundations and other in-place work. Furnish templates and other devices as necessary for presetting bolts and other anchors in accurate locations.

E. Setting Bases and Bearing Plates: Clean concrete and masonry bearing surfaces of bond-reducing materials and roughen to improve bond to surfaces. Clean bottom surface of base and bearing plates.

1. Set loose and attached base plates and bearing plates, for structural members, on wedges or other adjusting devices.

2. Tighten anchor bolts after supported members have been positioned and plumbed. Do not remove wedges or shims but, if protruding, cut off flush with edge of base or bearing plate prior to packing with grout.

F. Field Assembly:

1. Set structural frames accurately to lines and elevations indicated. Align and adjust various members forming a part of a complete frame or structure before permanently fastening. Clean bearing surfaces and other surfaces, which will be in permanent contact, before assembly. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.

2. Level and plumb individual members of structure within tolerances defined by AISC Code for Standard Practice, unless closer tolerances are required for proper fitting of adjoining or enclosing materials, in which case the most stringent shall apply.

3. Set horizontal members with their natural camber (or specified camber) up.

4. Establish required leveling and plumbing measurements on mean operating temperature of structure. Make allowances for the difference between temperature at time of erection

and mean temperature at which the structure will be when completed and in service.

5. Splice members only where indicated and accepted on final shop drawing.

6. Where parts cannot be assembled or fitted properly, as a result of errors in fabrication or of deformation due to handling or transportation, such condition shall be immediately reported to the Architect, along with proposed method of correction. The straightening of bends or warps shall be done by approved methods. Bent or damaged heat-treated parts will be rejected.

7. Fastening of splices in compression members shall be done after the abutting surfaces have been brought completely into contact.

G. Erection Bolts: On exposed welded construction, remove erection bolts, fill holes with plug welds and grind smooth at exposed surfaces. On non-exposed welded construction, erection bolts shall be tightened securely and left in place, or if removed, the holes shall be filled with plug welds.

H. Bolted Connections:

1. High-strength bolts shall be installed in conformance with the "Specifications for Structural Joints using ASTM A 325 or A 490 Bolts."

2. A 307 bolts and high-strength (A 325 and A 490) bolts noted to be "snug-tight" shall be tightened using a few impacts of an impact wrench or the full effort of a man using an ordinary spud wrench, bringing the plies into snug contact.

3. High-strength bolts which are not specifically designated to be "snug-tight" shall be tightened to provide at least the minimum tension shown in Table 4 of the "Specification for Structural Joints using ASTM A 325 and A 490 Bolts." Tightening shall be done by the turn-of-the-nut method, with direct tension indicators, or by properly calibrated wrenches.

4. Bolted parts shall fit solidly together when assembled. All joint surfaces shall be free of burrs, dirt and other foreign material that would prevent solid seating of the parts.

5. Bolts tightened by calibrated wrench or by torque control shall have a hardened washer under the element (nut or bolt head) turned in tightening.

6. Hardened washers shall be placed over slotted holes in an outer ply. Hardened beveled washers shall be used where outer face of bolted parts has a slope greater than 1:20 with respect to bolt axis.

I. Field Welding: Comply with AWS Structural Welding Code and AISC Specification for Structural Steel Buildings. Pay particular attention to surface preparation, preheating, sequence, and continuity of welds. Where heavy shapes are to be welded, comply with all special requirements contained in the AISC Specification and the AWS Structural Welding Code.

J. Comply with AISC Specifications for bearing, adequacy of temporary connections, alignment, and removal of paint on surfaces adjacent to field welds.

K. Do not enlarge unfair holes in members, by burning or by use of drift pins, except in secondary bracing members. Ream holes that must be enlarged to admit bolts.

L. Gas Cutting: Do not use gas cutting torches in field for correcting fabrication errors in structural framing. Cutting will be permitted only on secondary members which are not under stress, as acceptable to City. Finish gas-cut sections equal to a sheared appearance when permitted.

M. Touch-up Painting: Immediately after erection, clean field welds, bolted connections, and abraded areas of shop paint. Apply paint to exposed areas with same materials as used for shop paintings. Apply by brush or spray, to provide a minimum dry film thickness of 2.5 mils for each coat.

N. Touch-up Cold Galvanizing: Immediately after erection, touch-up areas of hot-dip galvanized members where galvanizing has been abraded during shipping and erection and areas where galvanized has been removed or damaged due to welding. Apply specified cold galvanizing compound in accordance with the manufacturer's instructions, to a minimum dry film thickness of 2.0 mils.

3.03 CLEANUP:

A. Clean up all debris caused by the work of this Section, keeping the area clean and neat at all times.

END OF SECTION

SECTION 06610

FIBERGLASS REINFORCED PLASTICS

PULTRUDED GRATING

PART 1 - GENERAL

1.01 SCOPE OF WORK

A. Furnish, fabricate (where necessary), and install all fiberglass reinforced plastic (FRP) items, with all appurtenances, accessories and incidentals necessary to produce a complete, operable and serviceable installation as shown on the Contract Drawings and as specified herein, and in accordance with the requirements of the Contract Documents.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Refer to Section 01270 – Measurement and Payment for Unit Price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

1.03 REFERENCE STANDARDS

ASTM D 635 Rate of Burning and/or Extent and Time of Burning of Self-Supporting Plastics in a Horizontal Position

ASTM D 732 Shear Strength of Plastics by Punch Tool

ASTM E 84 Surface Burning Characteristics of Building Materials

1.04 SUBMITTALS

A. Submittals shall conform to requirements of Section 01330 – Submittal

Procedures.

B. Submit manufacturer's shop drawings clearly showing material sizes, types, styles, part or catalog numbers, complete details for the fabrication of and erection of components including, but not limited to, location, lengths, type and sizes of fasteners, clip angles, member sizes, and connection details.

C. Submittal shall include manufacturer's published literature including structural design data, structural properties data, grating load/deflection tables, corrosion resistance tables, certificates of compliance, test reports as applicable, concrete anchor systems and their allowable load tables, and design calculations for systems not sized or designed in the contract documents.

D. The project manager may request sample pieces of each item specified herein for acceptance as to quality and color. Sample pieces shall be manufactured by the method to be used in the final installation.

1.05 QUALITY ASSURANCE

A. All items to be provided under this Section shall be furnished only by manufacturers having a minimum of five (5) years experience in the design and manufacture of similar products and systems. Additionally, if requested, a record of at least five (5) previous, separate, similar successful installations in the last five (5) years shall be provided.

B. Manufacturer shall offer a 1 year warranty on all FRP products against defects in materials and workmanship.

C. Manufacturer shall be certified to the ISO 9001-2000 standard.

D. Manufacturer shall provide proof of certification from at least two other quality assurance programs for its facilities or products (UL, DNV, ABS, USCG, AARR).

1.06 PRODUCT DELIVERY AND STORAGE

A. Delivery of Materials: Manufactured materials shall be delivered in original, unbroken pallets, packages, containers, or bundles bearing the label of the manufacturer. Adhesives, resins and their catalysts and hardeners shall be crated or boxed separately and noted as such to facilitate their movement to a dry indoor storage facility.

B. Storage of Products: All materials shall be carefully handled to prevent them from abrasion, cracking, chipping, twisting, other deformations, and other types of damage. Store items in an enclosed area and free from contact with soil and water. Store adhesives, resins and their catalysts and hardeners in dry indoor storage facilities between 70 and 85 degrees Fahrenheit (21 to 29 degrees Celsius) until they are required.

PART 2 - PRODUCTS

2.01 MANUFACTURER

A. Pultruded grating shall be Model I-3320 manufactured by Bedford Reinforced Plastics, Inc. or approved equal.

2.02 GENERAL

A. All FRP items furnished under this Section shall be composed of fiberglass reinforcement and resin in qualities, quantities, properties, arrangements and dimensions as necessary to meet the design requirements and dimensions as specified in the Contract Documents.

B. Fiberglass reinforcement shall be a combination of continuous roving, continuous strand mat, and surfacing veil in sufficient quantities as needed by the application and/or physical properties required.

C. Resins shall be VINYL ESTER with chemical formulations as necessary to provide the corrosion resistance, strength and other physical properties as required.

D. All finished surfaces of FRP items and fabrications shall be smooth, resin-rich, free of voids and without dry spots, cracks, crazes or unreinforced areas. All glass fibers shall be well covered with resin to protect against their exposure due to wear or weathering.

E. All pultruded structural shapes shall be further protected from ultraviolet (UV) light with 1) integral UV inhibitors in the resin and 2) a synthetic surfacing veil to help produce a resin rich surface.

F. All FRP products shall have a tested flame spread rating of 15 or less per ASTM E-84 Tunnel Test. Gratings shall also have a tested burn time of less than 30 seconds and an extent of burn rate of less than or equal to 10 millimeters per ASTM D635.

G. All grating clips shall be manufactured of Type 316SS (stainless steel).

2.03 PULTRUDED GRATING

A. Manufacture: Grating components shall be high strength and high stiffness pultruded elements having a maximum of 70% and a minimum of 60% glass content (by weight) of continuous roving and continuous strand mat fiberglass reinforcements. The finished surface of the product shall be provided with a surfacing veil to provide a resin rich surface which improves corrosion resistance

and resistance to ultraviolet degradation. Bearing bars shall be interlocked and epoxied in place with a two piece cross rod system to provide a mechanical and chemical lock. Cross rods should be below the walking surface of the grating. Gratings with cross rods that are flush with the walking surface are excluded.

B. Non-slip surfacing: Grating shall be provided with a silica sand grit bonded and baked to the top surface of the finished grating product.

C. Fire rating: Grating shall be fire retardant with a tested flame spread rating of 15 or less when tested in accordance with ASTM E84. Manufacturer may be required to provide certification of ASTM E84 test on grating panels from an independent testing laboratory. Test data shall be from full scale testing of actual production grating, of the same type and material supplied on the project. Test data performed only on the base resin shall not be acceptable.

D. Resin system: The resin system used in the manufacture of the grating shall be VINYL ESTER. Manufacturer may be required to submit corrosion data from tests performed on actual grating products in standard chemical environments. Corrosion resistance data of the base resin from the manufacturer is not a true indicator of grating corrosion resistance and shall not be accepted.

E. Color: Gray

F. Thickness: 2"

G. 1.5" load bar spacing; 12" with cross rod spacing on centers.

H. Load/Deflection: Grating shall meet manufacturers published safe recommended loadings with deflection not to exceed the following:

Uniform distributed load over a 42" span: 150 pounds per square foot, with a maximum deflection of 0.11".

2.04 GRATING FABRICATION

A. Measurements: Grating supplied shall meet the minimum dimensional requirements for openings to be covered. Verify measurements in field prior to fabricating the gratings by the manufacturer. Determine correct size and locations of required holes or cutouts from field dimensions before grating fabrication.

B. Layout: Each grating section shall be readily removable, except where indicated on drawings. Manufacturer to provide openings and holes where located on the contract drawings. Grating supports shall be provided at openings in the grating by contractor where necessary to meet load/deflection requirements specified herein. Grating openings which fit around protrusions (pipes, cables, machinery, etc.) shall be discontinuous at approximately the centerline of opening so each section of grating is readily removable.

C. Sealing: All shop fabricated grating cuts shall be coated with vinyl ester resin to provide maximum corrosion resistance. All field fabricated grating cuts shall be coated similarly by the contractor in accordance with the manufacturer's instructions.

D. Hardware: Type 316 stainless steel hold-down clips shall be provided and spaced at a maximum of four feet apart with a minimum of four per piece of grating, or as recommended by the manufacturer.

PART 3 - EXECUTION

3.01 INSPECTION

A. The grating shall be free from defects such as foreign inclusions, delamination, blisters, resin burns, air bubbles and pits.

3.02 INSTALLATION

A. Gratings shall be installed in accordance with manufacturer's assembly drawings and written instructions. Lock grating panels securely in place with hold-down fasteners as required. Field cut and drill fiberglass reinforced plastic products with carbide or diamond tipped bits and blades. Seal cut or drilled surfaces in accordance with manufacturer's instructions. Follow manufacturer's instructions when cutting or drilling fiberglass products or using resin products; provide adequate ventilation.

END OF SECTION

Section 09901S

PROTECTIVE COATINGS

The following supplements modify Section 09901 – Protective Coating. Where a portion of the Specification is modified or deleted by this Supplementary Specification, the unaltered portions of the Specification shall remain in effect.

2.03 SUBMERGED AND SEVERE SERVICE COATINGS SYSTEMS: Add the following Paragraph 2.03 J:

J. System 108 - 100% Solids, Isocyanate-Free, Solvent-Free, High Build Epoxy Coating for Wastewater applications only, to be spray applied in one or more coats to all interior surfaces of exposed concrete above the spring line or as otherwise detailed.

1. Product Characteristics:
   a. Product: 100% solids, solvent-free high-build epoxy system
   b. Product Type: amine cured epoxy
   c. VOC Content (ASTM D2584): 0%
   d. Compressive Strength, psi (ASTM D695): 10,500 (minimum)
   e. Tensile Strength, psi (ASTM D638): 4,500 (minimum)
   f. Flexural Strength, psi (ASTM D790): 7,500 (minimum)
   g. Adhesion to Concrete, psi/mode of failure (ASTM D4541/7234): 350 psi (minimum)/with substrate (concrete) failure
   h. Chemical Resistance, pH≥0.5 (ASTM G20): 60% Sulfuric Acid
2. In all cases the coating product(s) shall be applied to a minimum dry film thickness of 80 mils to surface profiles of CSP-4 to CSP-5 or 125 mils minimum DFT to surface profiles of CSP-6 or greater.
3. For resistance to ground water head pressure the coating shall be a minimum of 80 mils for depths up to 15' and 125 mils minimum for depths from 15' to 80'. For depths greater than 80' consult the coating manufacturer for recommendations.
4. Subsequent top-coating or additional coats of the coating product(s) shall occur within the product recoat window or 24 hours whichever is less. Additional surface preparation procedures will be required if this recoat window is exceeded.

END OF SUPPLEMENT

Approved by:

Eb Nass
Ebi Nassiri, P.E.
Assistant Director,
Wastewater Engineering Section,
Engineering and Construction Division

01/15/14
Date

Section 09904

PROTECTIVE COATINGS FOR
WASTEWATER WET WELLS

PART 1 - GENERAL

1.1 SUMMARY

A. This section provides requirements for furnishing labor, materials and equipment to prepare surfaces and to apply protective coatings to wastewater vaults, wet wells, and holding structures including lift stations and miscellaneous items.

B. The term "paint" as used in this section means the protective coatings specified. Other painting may be required in other sections of the specifications. All paint for concrete or metal surfaces shall be especially adapted for use around wastewater treatment plants and shall be applied in conformance with the manufacturer's published specifications.

C. All paint for final coats shall be fume resistant, compounded with pigments suitable for exposure to sewage gases, especially to hydrogen sulfide and carbon dioxide. Pigments shall be materials which do not tend to darken, discolor or fade due to the action of sewage gases. If a paint manufacturer proposes use of paint which is not designated "fume resistant" in its literature, it shall furnish full information concerning the pigments used in this paint and test data to demonstrate its color stability and chemical resistance.

1.2 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section unless specifically listed in Document 00410 – Bid Form. Therefore include cost for such work in contract unit prices for work of which it is a component part.

2. Measurement for protective coating to wet well, when included as a separate pay item, is on a lump sum basis for the complete protective coating system installed and in-place.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

1.3 REFERENCE STANDARDS

Work performed and materials used must comply with the requirements of the Steel Structures Painting Council's Vol. No. 1, "Good Painting Practices," and Vol. 2,

"Systems and Specifications," and these technical specifications. Where a conflict exists between these technical specifications and the Steel Structures Painting Council's specifications, these technical specifications govern.

A. Steel Structures Painting Council (SSPC) - Steel Structures Painting Manual.

1. SSPC-PA-1, Paint Application Specification.
2. SSPC-PA, Guide 3, A Guide to Safety Paint Applications.
3. SSPC-SP1, Solvent Cleaning.
4. SSPC-SP5, White Metal Blast Cleaning.
5. SSPC-SP6, Commercial Blast Cleaning.
6. SSPC-SP7, Brush-Off Blast Cleaning.
7. SSPC-SP10, Near-White Blast Cleaning.
8. SSPC-SP11, Power Tool Cleaning (with profile).
9. SSPC-SP2, Hand Tool Cleaning.

1.4 SUBSTITUTIONS

A. Wherever a product is designated by trade name with provision for an approved substitution, the product specified must be used unless a written request for substitution is submitted at least 7 days before the receipt of bids. The request for substitution must include the manufacturer's complete technical data sheets on the proposed product with a certified ingredients analysis signed by an officer of the manufacturer and sufficient information, including applicable case history information, for making a complete comparison between specified and proposed product.

B. Consideration will be given only to those products which have been used in wastewater treatment plant service for at least 5 years. The request for substitution must include a list of at least 10 applications in the Gulf Coast area where the product has been in continuous use for at least 5 years. Furnish the Owner's name, the Owner's Representative's name and the name of product used.

1.5 SUBMITTALS

A. Product Data and Shop Drawings. Submit product data, shop drawings, certificates and instructions on all protective coating items as specified herein and in accordance with Division 1 - General Requirements.

B. Certificates. Before beginning work, submit to the Project Manager a certificate from the paint supplier stating that sufficient paint has been purchased to provide the coatings specified in this section. List on the certificate the quantities and types of paint purchased. In addition, submit to the Project Manager a certificate from the blast cleaning abrasive supplier stating that sufficient abrasive has been purchased for the surface preparation specified in this section; list on the certificate the quantities and gradation purchased.

C. Product Data. Complete data on each type and kind of paint and primer shall be submitted to the Project Manager for review. Favorable review shall be obtained from the Project Manager before the paint is delivered to the job site. This procedure must be followed whether or not the paint that the Contractor proposes to use is named in the specifications. Submittal data shall show where and for what uses each paint product is to be used, with cross reference made to paragraphs of the specifications or the coating schedule. Data submitted on each type and kind of paint product shall include information to show that the product meets the detailed requirements of these specifications.

D. Manufacturer's Instructions. The manufacturer's published instructions, for use as a guide in specifying and applying the manufacturer's proposed paint, shall be submitted to the Project Manager. A manufacturer's paint will not be considered for use unless that manufacturer's published instructions meet the following requirements:

1. The instructions must have been written and published by the manufacturer for the purpose and with the intent of giving complete instruction for the use and application of the proposed paint in the locality and for the conditions for which the paint is specified or shown to be applied under this contract.

2. All limitations, precautions and requirements that may adversely affect the paint; that may cause unsatisfactory results after the painting application; or that may cause the paint not to serve the purpose for which it was intended, that is, to protect the covered material from corrosion, shall be clearly and completely stated in the instructions. These limitations and requirements shall include, but not be limited to, the following:

a. Surface preparation.

b. Methods of application.

c. Number of coats.

d. Thickness of each coat.

e. Total thickness.

f. Drying time of each coat, including primer.

g. Drying time of final coat before placing in service.

h. Time allowed between coats.

i. Primer required to be used.

j. Primers not permitted.

k. Use of a primer.

l. Compatible topcoats.

m. Thinner and use of thinner.

n. Weather limitations during and after application (temperature, humidity, wind velocity.).

o. Protection from sun.

p. Physical properties of paint, including solids content and ingredient analysis.

q. Cathodic dis-bonding limitations, if any.

r. Equipment settings (air cap, fluid tip, equipment pressure settings, etc.).

1.6 DELIVERY AND STORAGE

A. Delivery. Have paint delivered to the job site in original unopened containers.

B. Storage. Store materials in an approved location. Keep the storage area clean and repair any damage done. Remove oily rags, waste, or other fire hazards from buildings each night; take adequate precautions to avoid damage by fire. Place cloths and cotton waste which might constitute a fire hazard in metal containers or destroy at the end of each work day. Storage facilities shall meet City of Houston Fire Code Requirements.

1.7 MAINTENANCE MATERIAL

At the end of the project, the Contractor shall turn over to the Owner a gallon can of each type and color of coating used in the field application. The material shall be delivered in unopened labeled cans, just as it comes from the factory. If the manufacturer does not package the material in gallon cans, and in the case of special compounds, the materials shall be delivered in new gallon containers, properly closed with typed labels indicating brand, type, color, etc. Where multiple component materials are used, the Contractor shall supply an unopened kit of the necessary materials in the

manufacturer's smallest standard packaging size. The manufacturer's literature describing the materials and giving directions for their use shall be furnished in three bound copies. A typewritten inventory list shall be furnished at the time of delivery.

1.8 COATING SYSTEM COMPATIBILITY

The Contractor shall apply coating from only one manufacturer. Application of coating from more than one manufacturer will not be allowed.

PART 2 - PRODUCTS

2.1 COLOR SCHEDULE

Coordinate color selection with the Project Manger.

2.2 TEST EQUIPMENT

The following pieces of equipment will be used by the NACE certified inspector to determine film thickness and presence of flaws.

A. Mikrotest. Model DFG-100, 0-40 mils film thickness gauge including a set of U.S. Department of Commerce, Bureau of Standards Film Thickness Calibration Standards from 0-8 mils and 10-18 mils.

B. Tinker-Rasor. High-voltage flaw detector (holiday detector).

C. Clemtex Comparator. Surface anchor profile standard.

D. Textex Tape. Replicate tape.

PART 3 - EXECUTION

3.1 WORK CONDITIONS

A. Weather. No coating or painting shall be applied: 1) when the surrounding air temperature or the temperature of the surface to be coated or painted is below 50 F (10.0 C); 2) to wet or damp surfaces or in rain, snow, fog or mist; 3) when the temperature is less than 5 F (2.78 C) above the dew point; 4) when it is expected the air temperature will drop below 50 F (10.0 C) or less than 5 F (2.78 C) above the dew point within 8 hours after application of coating or paint. Dew point shall be measured by use of an instrument such as a Sling Psychrometer in conjunction with U.S. Department of Commerce Weather Bureau Psychrometric tables. If preceding conditions are prevalent, coating or painting shall be delayed or postponed until conditions are favorable. The day's coating or painting shall be completed in time to permit the film sufficient drying time prior to damage by atmospheric conditions. The weather

conditions shall be adhered to unless otherwise specified under individual coating systems.

B. Surface. If surfaces to be painted cannot be put in proper condition for painting by customary cleaning and abrasive operations, notify the Project Manager in writing or assume the responsibility for and rectify any unsatisfactory finish resulting from application to an unsatisfactory surface. Do not apply paint to a wet or damp surface.

C. Equipment. The Contractor's coating and painting equipment shall be designed for application of the materials specified and shall be maintained in good working order comparable to that described in printed instructions of the coating manufacturer. Clean equipment thoroughly before and after use with the appropriate cleaning solution indicated by the coating manufacturer. All gauges and controls on spray equipment shall be in proper working order at all times and the gauges must be operational and readable.

D. Warnings. Display caution signs in necessary areas advising of spray painting and warning against open flames.

3.2 SURFACE PREPARATION

A. Solvent Cleaning. Remove oil, grease, soil and other contaminants by use of solvents, emulsions, cleaning compounds, steam cleaning, or similar materials and methods which involve a solvent or cleaning action, in accordance with Steel Structures Painting Council Surface Protection Specifications (SSPC) SP-1.

B. Grinding. Remove weld splatter and rough edges and grind rough welds so that all surfaces are in proper condition, in the opinion of the Project Manger, to receive the specified coating.

C. Abrasive Blast Cleaning.

1. Use a source that provides compressed air, free of detrimental amounts of water and oil. The compressor shall, as a minimum, be capable of delivering a pressure at the blast nozzle of at least 90 psig; the blast nozzle shall be of the venturi type.

2. Abrasively clean only those areas that can be primed the same day or before any rust starts to form, whichever occurs first. Areas which are not painted the same day must be cleaned again on the day the prime coat is applied. Remove the abrasive material from surface by brush or industrial vacuum.

D. Power Tool Cleaning. Subject to review by the Project Manager, any above metalwork in which SP-6 or SP-10 cannot be accomplished shall be cleaned in

accordance with SSPC SP-3, Power Tool Cleaning, removing loose mill scale, loose rust, loose paint and other foreign matter.

E. Shop Priming. Where metalwork, equipment, valves and the like are shop primed, the primer used must be compatible with the coating system to be applied in the field. All information shall be furnished regarding the shop prime coat and, if not compatible with succeeding coats, in the opinion of the Project Manager, the shop prime coat shall be removed by abrasive blast cleaning or as otherwise recommended by the manufacturer.

F. Unknown or Non-compatible Materials. Items coated with an unknown paint system, or a primer or system which is not compatible with the specified system, shall be blast cleaned and recoated with the specified coating system at the job site. When abrasive blast cleaning is not feasible, the Contractor shall notify the Project Manager and request permission to apply a barrier coat over the unknown or non-compatible material. The proposed barrier coat must be recommended in writing by the paint system manufacturer and shall be approved by the Project Manager. Following application of the barrier coat, if permitted, the specified coating system shall be applied. Minimum dry film thickness shall be increased an amount equal to the barrier coat and unknown or non-compatible coats.

3.3 COATING APPLICATION

A. Manufacturer's Representative. The coating manufacturer will be responsible, through an authorized representative, to provide technical assistance to the paint contractor as needed.

B. Workmen. Employ workmen skilled in structural steel, piping, and mechanical equipment painting.

C. Materials.

1. Coating materials, abrasive, and equipment used in painting and abrasive cleaning are subject to inspection at any time by the Owner or his representative.

2. Remove blasting material and dust from the surface to be painted before paint application is begun.

D. General Application Requirements.

1. Prepare all surfaces to receive materials as required herein or as required by the coatings manufacturer. Clean surfaces to remove all foreign matter. Roughen surface as recommended by the coating manufacturer for proper adhesion of coating to the substrate.

2. Items to be attached to similar or dissimilar materials shall be back coated as specified for the exposed surfaces of those items. Mask or protect finished surfaces in area being coated. Remove, replace, and protect finished items adjacent to surfaces to be coated. Reinstall items when painting is complete.

3. Mix and apply materials in accordance with the manufacturer's printed instructions. Allow each succeeding coat to dry in accordance with manufacturer's printed instructions.

4. Include painting of engaged and free standing columns or similar items when painting walls.

5. Do not paint code required labels, (Underwriters Laboratories, Inc., Factory Mutual, or the like) or any equipment identification, performance ratings, name, or nomenclature plates. Remove any paint inadvertently applied to such items.

6. Protect adjacent walls, floors, and ceilings against splash or overspray. Remove materials from surfaces not designated to receive such materials.

7. Remove waste rags and coating debris on a daily basis. Keep storage spaces and work areas neat and clean.

E. Paint Coating Methods.

1. Double-lap all welds. Apply prime coat by brush to all weld areas; then apply prime coat to entire surface, including weld areas, by spray, roller or method selected.

2. Coat areas with a uniform film, free of sags, runs, or brush marks. Where multiple coats of paint are specified, apply each coat in a different color which complements the following coat and is different than the preceding coat. Each coat must be free of shadows and uniform in appearance.

3. Except where otherwise specified, thin paint only as necessary for workability of coating material in accordance with manufacturer's printed instructions. Use only an appropriate thinner as recommended by the paint manufacturer.

4. When paint is being applied to interior of wet well or any other closed areas, provide adequate ventilation.

5. Comply with recommendations of the paint manufacturer in regard to drying time for each coat, technique of spray application, ventilation, paint thinning, and safety precautions. The Contractor must fully inform all members of his field crew of these recommendations.

6. Where inspection shows that the specified thickness is not developed, apply additional coats in accordance with the manufacturer's surface preparation and cure schedule requirements to produce the required film thickness.

7. Repair and recoat improper applications as recommended by the manufacturer or as required by the Project Manager.

8. Factory finished items shall be protected against damage during transit, storage and erection. Damaged areas must be refinished as the original so that at the end of the project the finish on all items will be in perfect shape. The following items shall receive final finish at the factory, colors to be reviewed by the Project Manager.

   a. Electrical panels (to be factory painted ANSI No. 61 gray).

   b. Light fixtures.

   c. Pressure gauges.

   d. Instrumentation.

   e. Similar equipment with standard factory finish, subject to Project Manager's review.

9. The following items shall not be painted unless otherwise specified:

   a. Aluminum, brass, bronze, chrome, copper or stainless steel.

   b. Nameplates or serial numbers.

   c. Grease fittings.

   d. Valve operator stems.

   e. Buried or encased piping or conduit.

   f. Concrete floors and slabs not exposed to wastewater.

   g. Glass.

F. Cleaning. Upon completion of the work, remove all staging and scaffolding. Dispose of all used sand, containers and rubbish in a suitable manner. Remove paint spots, oil or stains on adjacent surfaces. Leave the entire job clean and acceptable.

3.4 COATING SCHEDULE

Coat each item listed below using the coating specified.

Item to be Coated	Coating System
Concrete Wastewater Structures, including Lift Station Wet Wells, junction boxes and miscellaneous structures.	Raven 405
	Warren Environmental Epoxy S-301-14
	Or approved equal, see City of Houston Approved Product list for approved wastewater coating systems for this application.
Non-concrete wet well items (i.e. piping, metal bracings, etc...)	See Section 09901 Protective Coatings

3.5 COATING SYSTEMS

A. Wet Well Coating

1. Surface Preparation

a. Surfaces shall be free of weld splatter. All welds shall be continuous.

b. Steel contaminated with soluble salts (i.e. chlorides and sulfates) develops rust-back rapidly at intermediate and high humidity. Therefore, these salts must be removed from the steel surface preferably before blast cleaning and by eliminating sources of recontamination during and after blast cleaning. A number of tests for soluble salts have been examined by SSPC, ASTM, the National Shipbuilding Research Program, and the International Organization for Standardization.

c. All loose scale, large deposits oil, grease, cutting oils, dirt and other contaminants shall be removed prior to abrasive blasting by washing with detergent and potable water, followed by a thorough rinsing with potable water.

d. The steel surfaces to be coated shall be abrasive blast cleaned. Blast air shall be free of oil and water.

e. Abrasive shall not be recycled.

f. Abrasive blasting shall not be performed when the air or steel temperature is below 40 deg F, when the relative humidity exceeds 80%, or when the steel is less than 5 deg F warmer than the dew point. The Contractor will

provide dehumidification, and/or temperature control as necessary to meet these conditions.

g. Blast cleaning shall be in accordance with SSPC-SP 5, White Metal Blast Cleaning for severe-duty immersion service of the coated areas. Blast cleaning for other surfaces shall be in accordance with SSPC-SP 10, Near White Blast Cleaning. Anchor profile shall be 2.5-5.0 mil and relative to the coating thickness specified.

h. Remove all blasting residues from the structure/vessel by means of vacuum cleaning plus, as appropriate, shovels, brooms, clean compressed air, vacuum cleaners and other dry extraction methods.

i. All surfaces should be inspected by the Inspector during and after preparation and before the coating is applied.

j. Quick setting high strength concrete with latex or curing agent additives cannot be used to re-profile the surface to be epoxy lined. Quickset cements can only be used as a spot repair to stop or slow down flowing water prior to chemical grouting to permanently stop infiltrating. Proper surface preparation procedures must be followed to ensure adequate bond strength to any surface to be coated. New cement must cure at least 30 days prior to coating.

2. Repair

a. Repair products shall be used to fill voids, pinholes, and other surface defects which may affect the performance or adhesion of the coating product(s).

b. Repair products shall be installed to minimum thickness as recommended within manufacturers published guidelines. Should structural repairs be necessary, these products shall be installed as specified by the Project Engineer.

c. Repair products shall be handled, mixed, installed and cured in accordance with manufacturer guidelines.

d. All repaired surfaces shall be inspected for cleanliness and suitability to receive the coating product(s). Additional surface preparation may be required prior to coating application.

e. Repair materials must be accepted and approved by the specifying engineer and must be compatible with the specified epoxy surfacing system. No cementations repair materials will be allowed. The

manufacturer will only approve 100% solid epoxy mastic repair materials to profile or build out deteriorated walls. The repair mortar and epoxy topcoat must share the same epoxy matrix to ensure a bonded weld at the molecular leveling order to prevent migration of bacteria and sewer gasses throughout the monolithic system.

3. APPLICATION

a. Application procedures shall conform to the recommendations of the coating product(s) manufacturer, including environmental controls, product handling, mixing, application equipment and methods.

b. Spray equipment shall be specifically designed to accurately ratio and apply the coating product(s) and shall be in proper working order.

c. Contractors must meet minimum requirements for coating manufacturer's qualification prior to application which may include any certifications and references as part of any quality assurance and warranty from the manufacturer.

d. Before spraying any coating, all welds, grooves, pits, other rough areas, difficult-to-spray areas, and other areas as specified shall be striped. Striping can be accomplished by spray application in accessible areas; and, hand-mixing product or spray followed by scrub-striping with a good-quality bristle brush in difficult-to-spray areas.

e. Prepared surfaces shall be coated by spray application of the coating product(s) described herein to a minimum wet film thickness of 250 mils. Thicknesses shown is for general purposes only, each project should be evaluated independently and thickness of system determined upon product, service environment, protection and restoration requirements:

f. Subsequent topcoating or additional coats of the coating product(s) shall occur within the product's recoat window. Additional surface preparation procedures will be required if this recoat window is exceeded.

g. Coating product(s) shall interface with adjoining construction materials throughout the structure to effectively seal and protect substrates. Procedures and materials necessary to effect this interface shall be as recommended by the coating product(s) manufacturer.

h. Apply coating to all exposed surfaces within wet well, except wet well bottom/floor. Concrete surfaces to receive protective coating includes wet

well wall, ceiling, baffels, pony walls, and other miscellenous concrete structures and/or features withing wet well. Also apply protective coating the exposed concrete surface on vertical sections of hatch and/or other wet well openings.

3.6 PIPE PAINTING AND IDENTIFICATION

A. All pipelines in the project which are exposed to view, above suspended ceilings, or exposed above grade, and all exterior lines shall be identified by color and signs. Each pipeline shall be identified by a color complying with the coating schedule of colors and further identified by applied markers, see Section 09901 Protective Coatings.

B. Pipes which are exposed in areas requiring protective coatings shall be coated in accordance with the specifications for protective coating. Other pipes shall be painted in accordance with the specifications for decorative painting.

C. Pipes shall be coated in the number of coats and type of material specified for protective coating and decorative painting. Base coats for pipeline painting may be the same neutral color. Each succeeding base coat shall be a slightly different color. The final coat shall comply with the pipe identifying color schedule.

D. Pipeline identification markers shall be applied to all pipes, whether coated or uncoated.

E. Identify all pipelines with applied signs or markers at 15-foot centers, at both sides of penetrated walls or floors, adjacent to valves, at connected equipment, at branch fittings, and in congested pipe layouts.

F. Color Code Schedule.

Paint piping and associated items with colors complying with the coating schedule of colors and further identified by applied markers, see Section 09901 Protective Coatings.

3.7 INSPECTION AND TESTING

A. Inspection.

1. The Contractor shall provide OSHA-approved staging, scaffolding and lighting as required to permit proper inspection as outlined in these specifications.

2. Surface preparation, coating application and repairs are subject to inspection by the Owner. The standards published by the Steel Structures Painting Council, especially SSPC-VISL-635, Pictorial Surface, shall be used as guides for acceptance or rejection of the cleaning, painting or coating application.

Particular attention will be given hard-to-reach areas, bolted connections, supports, anchor bolts and threaded joints.

3. A magnetic-type dry film thickness gauge, and an electrical holiday detector shall be used to determine the acceptability of the paint application. Calibration of the magnetic thickness gauge shall be done on the site using the U.S. Department of Commerce, Bureau of Standard Film Thickness Calibration Standards.

4. Give sufficient notice in advance of coating applications so that the following inspections can be performed:

a. Examination and approval of surface preparation prior to any coating.

b. Examination and approval of each coat prior to application of the next coat.

c. Inspection of the completed coating for runs, overspray, roughness, and any evidence of improper application.

d. Direction or observation of testing.

B. Testing.

1. Testing shall be performed by NACE certified inspector and Contractor shall bear expenses of such testing.

2. The Contractor shall be responsible to remedy failure of any paint system to pass a test.

3. The following tests shall be conducted:

a. Dry film thickness shall be tested after each coat of interior and exterior paint has been applied, and after final coat of the exterior system has been applied to the pump, motor, piping, concrete structure and appurtenances. A test will be made for every 25 square feet of surface and at locations designated by the inspector and Project Manager.

b. All paint systems will be tested for holidays after the final coat has been applied.

END OF SECTION

Section 09917

CORROSION PROTECTIVE COATING SYSTEM

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Application of a corrosion protective coating system to existing junction boxes, manholes and/or sanitary sewer pipe, as depicted on the plans.

1.02 RELATED SECTIONS

A. Section 02427- Plastic Liner for Large Diameter Concrete Sewer and Structures

B. Section 02555 – Manhole Rehabilitation

C. Section 03931 -Concrete Repair and Rehabilitation

D. Section 09918- Grouted in Place Lining of Sewers and Manholes with Profiled PVC

1.03 UNIT PRICES

A. No separate payment will be made for protective coatings unless specifically listed in Document 00410- Schedule of Unit Price Work. Include payment for protective coatings in unit prices for items to which coatings are applied.

B. Measurement for protective coatings, when included as a separate pay item, is on a square-foot basis for completed protective coating systems.

C. Refer to Section 01270 - Measurement and Payment for unit price procedures.

1.04 PERFORMANCE REQUIREMENTS

A. Provide the corrosion protective coating systems specified in this section and apply this coating in accordance with the manufacturer's recommendations.

B. The completed coating system shall coat the junction box and/or manhole with a corrosion protective coating to prevent deterioration from contact with sewage, hydrogen sulfide and other corrosive compounds within the wastewater stream.

C. Upon project completion, the Contractor shall provide a certification that the corrosion protective coating was applied in accordance with the procedures recommended by the manufacturer.

1.05 REFERENCES

A. ASTM D638- Standard Test Method for Tensile Properties of Plastics.

B. ASTM D790- Standard Test Methods for Flexural Properties of Unreinforced and Reinforced Plastics and Electrical Insulating Materials.

C. ASTM D695- Standard Test Method for Compressive Properties of Rigid Plastics.

D. ASTM D4541 -Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers.

E. ASTM D2584- Standard Test Method for Ignition Loss of Cured Reinforced Resins.

F. ASTM D2240- Durometer Standard Test Method for Rubber Property-Durometer Hardness.

G. ASTM D543 - Standard Practices for Evaluating the Resistance of Plastics to Chemical Reagents.

H. ASTM C109- Standard Test Method for Compressive Strength of Hydraulic Cement Mortars.

I. ASTM C579- Standard Test Methods for Compressive Strength of Chemical- Resistant Mortars, Grouts, Monolithic Surfacings and Polymer Concretes.

J. ASTM D4414 - Standard Practices for Measurement for Wet Film Thickness by Notch Gages.

K. ASTM E84- Surface Burning Characteristics of Building Materials

L. NACE - Published Standards of National Association of Corrosion Engineers (NACE International), Houston, TX.

1.06 SUBMITTALS

A Make submittals in accordance with Section 01330- Submittal Procedures and Section 01340- Shop Drawings, Product Data, and

Samples.

B. Submit the following information at least 30 days prior to corrosion protective coating work:

1. Coating Manufacturer's Information: For each coating system to be used, submit the following data:

a. Coating Manufacturer's data sheet for each product proposed, including statements on the suitability of the material for the intended use.

b. Technical and performance information that demonstrates compliance with the system performance and material requirements.

c. Coating Manufacturer's instruction and recommendations on surface preparation and application.

d. Colors available for each product, where applicable.

e. Compatibility of shop and field applied coats, where applicable.

f. Material Safety Data Sheet for each product used.

C. Samples

1. Submit color samples of coating materials on 8 1/2-inch by 11-inch sheet metal or heavy cardstock. Have each sheet completely coated over its entire surface with one coating material, type, and color.

2. Provide two sets of color samples to match each color selected by the City Engineer from the manufacturer's standard color sheets. If custom-mixed colors are indicated, prepare color samples using color formulations prepared to match the color samples furnished by the City Engineer.

1.07 QUALIFICATIONS

A Where corrosion protective coatings are to be applied by a subcontractor (Applicator), employ and Applicator who possesses a valid state license as required for performance of coating work called for in this Specification.

B. Submit five (5) recent references which show that the coating Applicator has previous successful experience with the indicated or

comparable coating systems in the last three (3) years. Include the name, address, and the telephone number for the owner of each installation for which the coating Applicator provided the protective coating.

C. The coating Applicator has been manufacturer certified, trained and approved in the handling, mixing and application of the products to be used.

D. Certification that the equipment to be used for applying the products has been manufactured or approved by the coating manufacturer and the coating · Applicator personnel have been trained and certified for proper use of the equipment.

E. Approved Equal Submittal: In order to be considered as an equal product, said product will have to meet the minimum physical properties of the approved products as referenced in Paragraph 2.02, as measured by the applicable ASTM standards referenced in Paragraph 1.05. Testing results must be performed and presented by a third-party testing laboratory.

Equal products must be submitted to the City Engineer for approval. A coating Applicator that has been trained and certified by the manufacturer must install all products.

1.08 ENVIRONMENTAL REQUIREMENTS

A Ventilate area where coating is being applied. Post and enforce "NO SMOKING OR OPEN FLAME" signs until coating has cured.

B. Provide lighting level of 80-foot candles (860 1x) measured mid-height at substrate surface.

C. Restrict worker access and construction traffic from area where coating is being applied or is curing.

1.09 WARRANTY

A Contractor shall extend the standard one (1) year materials and installation warranty nine (9) additional years to a total of Ten (10) years for the coating material used in the rehabilitation of Manholes, Junction Boxes and Sanitary Sewer Pipe.

B. Warranty Inspection

1. A warranty inspection may be conducted during the eleventh month following completion of corrosion protective coating. The Contractor and a representative of the coating material manufacturer shall attend this inspection.

2. The City Engineer may, by written notice to the Contractor, reschedule the warranty inspection to another date within the one-year warranty period, or may cancel the warranty inspection altogether. Cancellation of the warranty inspection does not relieve the Contractor of his responsibilities under the Contract Documents.

3. Repair defective work discovered during the warranty inspection in accordance with these Specifications.

PART 2 PRODUCTS

2.01 EXISTING PRODUCTS

A. Standard Portland cement or new concrete (not quick setting high strength cement) must be well cured prior to application of the epoxy coating. Generally, 28 days is adequate cure time for standard Portland. If earlier application is desired, compressive or tensile strength of the concrete can be tested to determine if acceptable cure has occurred. (Note: Bond strength of the coating to the concrete surface is generally limited to the tensile strength of the concrete itself.)

B. Patching and repair materials shall be 100% solids, solvent free Epoxy Grout formulated for Epoxy Top Coating compatibility to provide smooth surface profile for Top Coating. Project specific submittals and procedures should be provided including application, cure time and surface preparation procedures which permit optimum bond strength with the Epoxy Coating.

C. Remove existing coatings prior to application of the new Epoxy Coating. Applicator is to maintain strict adherence to applicable NACE and SSPC recommendations with regard to proper surface preparation and compatibility with existing coatings.

D. Protective coating System must meet the minimum standards of "System 108", See Supplementary Specification 09901S

2.02 COATING CRITERIA

A. Compatibility: In any coating system, use only approved and compatible materials from a single source and manufacturer.

B. Containers: Supply coating material in sealed containers that plainly show the designated name, formula or specification number, batch number, color, date of manufacture, and name of manufacturer, all plainly legible at the time of use.

C. Colors: Use color and shades of colors of all coats of coatings as selected by the City Engineer. Make each coat of a slightly different shade to facilitate inspection of surface coverage of each coat. The City Engineer will select finish colors from the manufacturer's standard color samples.

D. Thickness: Coating thickness shall be designed for hydrostatic loading.

E. Substitute or Equal Products:

1. To establish equality under Section 01630- Product Substitution Procedures, furnish satisfactory documentation from the manufacturer of the proposed substitute product that the material meets the indicated requirements and is equivalent or better in the following properties:

   a. Resistance to abrasion and physical damage.

   b. Resistance to chemical attack.

   c. Life expectancy.

   d. Ability to recoat in future.

   e. Solids content by volume.

   f. Dry film thickness per coat.

   g. Compatibility with other coatings.

   h. Suitability for the intended service.

   i. Temperature limitations in service and during application.

   j. Type and quality of recommended undercoats and topcoats.

k. Ease of application.

l. Ease of repairing damaged areas.

m. Stability of colors.

2. For substitutions, submit protective coating materials which are standard products produced by recognized manufacturers who are regularly engaged in production of such materials for essentially identical service conditions. Where requested, provide the City Engineer with the names of not less than ten successful applications of the proposed manufacturer's products which comply with these requirements.

2.03 COATING PRODUCT

A. Contractor shall use City of Houston Approved Products List for rehabilitation and corrosion protection of existing Junction Boxes, Manholes, Sanitary Sewer Pipe (at selected locations indicated on the Contract Drawings) and corrosion protection of proposed RCP manhole risers.

2.04 REPAIR MATERIALS

A. Repair materials shall be used to fill voids, structurally reinforce and/or rebuild surfaces, etc. as determined necessary by the City Engineer and coating Applicator. Repair materials must be compatible with the specified coating and shall be applied in accordance with the manufacturer's recommendations.

B. The following products may be accepted and approved as compatible repair basecoat materials for epoxy topcoating for use within the specifications.

1. 100% solids, solvent-free epoxy grout specifically formulated for epoxy topcoating compatibility. The epoxy grout manufacturer shall provide instruction for trowel or spay application and for epoxy topcoating procedures.

2. Factory blended, rapid setting, high early strength, fiber reinforced, non- shrink repair motor that can be trowelled or pneumatically spay applied may be approved if specifically formulated to be suitable for epoxy topcoating. Such repair mortars should not be used unless their manufacturer provides information as to its suitability for topcoating with an epoxy coating. Project specific submittals should be provided including application, cure time, and surface preparation procedures which permit optimum bond strength with the epoxy

coating.

2.05 CORROSION PROTECTIVE COATING

A. 100% solids, solvent-free two-component epoxy resin system thixotropic in nature and filled with select fillers to minimize permeability and provide sag resistance acceptable to these specifications:

Product Type	**Amine cured epoxy**
Color	Blue, White or Light Grey
Solids Content (vol %)	100
Mix Ratio	3:1 or as required by System
Compressive Strength, psi	11,000
Tensile Strength, psi	4,500
Tensile Elongation,%	4
Flexural Strength, psi	7,500
Hardness, Type D	88
Bond Strength – Concrete >	Tensile Strength of Concrete
Chemical Resistance: Severe Municipal Sewer: Successful Pass:	 All types of service Sanitation District of L.A. County Coating Evaluation Study

PART 3 EXECUTION

3.01 MANUFACTURER'S SERVICES

A. Require the coating manufacturer to furnish a qualified technical representative to visit the project site for technical support as may be necessary to resolve field problems attributable or associate with manufacturer's products.

B. For submerged and severe service coating systems, require the coating manufacturer to furnish the following services:

1. At least 8 hours of on-site instruction on the proper surface preparation, use, mixing, application, and curing of the coating system.

2. Observe action of the start of surface preparation, mixing, and application of the coating materials for each coating system by the manufacturer's representative.

3.02 WORKMANSHIP

A. Use skilled craftsmen and experienced supervision.

B. Apply corrosion protective coating to produce an even film of uniform thickness. Give special attention to edges, corners, crevices, and joints. Ensure thorough cleaning and an adequate thickness of coating material. Apply corrosion protective coatings to produce finished surfaces free from runs, drop, ridges, waves, laps, brush marks, and variations in color, texture, and finish. Effect complete hiding so that the addition of another coat would not increase the hiding. Give special attention to ensure that edges, corners, crevices, welds, and similar areas receive a film thickness equivalent to adjacent areas. Protect installations by use of drop cloths or other precautionary measures.

C. If surfaces are damaged, clean, repair, and refinish to original condition.

3.03 EXAMINATION

A. All structures to be coated shall be readily accessible to the coating Applicator.

B. Appropriate actions shall be taken to comply with local, state, and federal regulatory and other applicable agencies with regard to environment, health and safety.

C. Any active flows shall be dammed plugged or diverted as required to ensure that the liquid flow is maintained below the surfaces to be coated. Flows should be totally plugged and/or diverted when coating the invert. All extraneous flows into the manhole or vaults at or above the area coated shall be plugged and/or diverted until the epoxy has set hard to the touch.

D. Installation of the corrosion protective coating shall not commence until the concrete substrate has properly cured in accordance with these specifications.

E. Temperature of the surface to be coated should be maintained between 40 degree F and 120 degree F during application. Prior to and during application, care should be taken to avoid exposure of direct sunlight or other intense heat source to the structure being coated.

3.04 STORAGE, MIXING, AND THINNING OF MATERIALS

A Manufacturer's Recommendations: Unless otherwise indicated, strictly comply with the coating manufacturer's printed recommendations and instructions for thinning, mixing, handling, applying, and protecting its coating materials, for preparation of surfaces for coating, and for all other procedures relative to coating.

B. Use corrosion protective coating materials within the manufacturers recommend shelf life.

C. Storage and Mixing: Store coating materials under conditions recommended by the Material Safety Data Sheets. Keep coating materials thoroughly stirred, strained and with uniform consistency during application. Do not mix coatings of different manufacturers.

3.05 SURFACE PREPARATION

A Applicator shall inspect all specified surfaces prior to surface preparation. Applicator shall notify the City Engineer of any noticeable disparity in the surfaces which may interfere with the proper preparation or application of the repair material and/or corrosion protective coating.

B. Applicator shall perform all surface preparation and corrosion protective coating installation.

C. All contaminants including: oils, grease, incompatible existing coatings, waxes, form release, curing compounds, efflorescence, sealers, salts, or other contaminants shall be removed. All concrete or mortar that is not sound or has been damaged by chemical exposure shall be removed to a

sound concrete surface or replaced.

D. Surface preparation method(s) should be based upon the conditions of the substrate, service environment and the requirements of the repair materials and/or corrosion protective coating to be applied. Surfaces to receive repair materials and/or corrosion protective coating shall be cleaned and abraded to produce a sound surface with adequate profile and porosity to provide a strong bond between the repair materials and/or corrosion protective coating and the substrate.

E. Infiltration shall be stopped by using a material which is compatible with the repair materials and is suitable for topcoating with the corrosion protective coating.

F. All surfaces should be inspected by the Inspector during and after preparation and before the repair material is applied.

3.06 PREPARATION FOR COATING

A. Cleaning and Touch--up: Clean- and prepare surfaces to receive corrosion protective coatings using water blasting or abrasive blasting in accordance with the manufacturer's recommendations. Examine surfaces to be coated. Correct surface defects before application of any coating material. Touch up marred or abraded spots on shop-primed and on factory-finished surfaces prior to coating application. Verify that surfaces to be coated are dry and free of visible dust.

B. Protection of Surfaces Not to be Coated: Protect surfaces which are not to receive corrosion protective coatings during surface preparation, cleaning, and coating operations.

C. Remove, mask or otherwise protect hardware, grease fittings, machined surfaces, nameplates on machinery, and other surfaces not to be coated. Provide drop cloths to prevent coating materials from falling on or marring adjacent surfaces. Protect the working parts of mechanical and electrical equipment from damage during surface preparation and coating operations. Mask openings in motors to prevent entry of coating or other materials.

D. Do not damage adjacent work during blast cleaning operations. Conduct spray operations under carefully controlled conditions. Promptly repair any damage to adjacent work or adjoining property occurring from blast cleaning or coating operations.

E. Protection of Coated Surfaces: Coordinate cleaning and coating so that dust and other contaminants from the cleaning process will not fall on we, newly-coated surface.

3.07 APPLICATION OF REPAIR MATERIALS

A. Areas where structural steel has been exposed or removed shall be repaired in accordance with the Contract Drawings or manufacturer's recommendations.

B. Repair materials shall meet the specifications herein. The materials shall be trowel or spray applied utilizing proper equipment on to specified surfaces. The material thickness shall be specified according to manufacturer's recommendations.

C. Cementitious repair materials shall be trowelled to provide a smooth surface with an average profile equivalent to coarse sandpaper to optimally receive the corrosion protective coating. No bug holes or honeycomb surfaces should remain.

D. The repair material shall be permitted to cure according to manufacturer recommendations. Curing compounds should not be used unless approved for compatibility with the specified corrosion protective coating.

E. After abrasive blast and leak repair is performed, all surfaces shall be inspected for remaining laitance prior to corrosion protective coating application. Any evidence of remaining contamination or laitance shall be removed by additional abrasive blast, shotblast, or other approved method. If repair materials are used, refer to these specifications for surface preparation. Areas to be coated must also be prepared in accordance with these specifications after receiving a cementitious repair material and prior to application of the corrosion protective coating.

F. All surfaces should be inspected by Inspector during and after preparation and before the corrosion protective coating is applied

3.08 APPLICATION OF CORROSION PROTECTIVE COATING

A Application procedures shall conform to the recommendations of the corrosion protective coating manufacturer, including material handling, mixing, environmental controls during application, safety, and spray equipment.

B. The spray equipment shall be specifically designed to accurately ratio and apply the specified corrosion protective coating materials and shall be regularly maintained and in proper working order.

C. The corrosion protective coating material must be spray applied by a

Certified Applicator of the corrosion protective coating manufacturer.

D. Specified surfaces shall be coated by spray application of a moisture tolerant, solvent-free, 100% solids, corrosion protective coating as further described herein. Spay application shall be a minimum wet and dry thickness as defined below with a minimum of two coats:

Composite System: ½" minimum approved cementitious base repair mortar plus 100 mils epoxy topcoat

E. If necessary, subsequent topcoating or additional coats of the corrosion protective coating should occur as soon as the basecoat becomes tack free, but no later than the recoat window for the specified products. Additional surface preparation procedures will be required if this recoat window is exceeded.

F. Fiberglass woven-roving fabric may be rolled into the resin or chopped glass spray applied with the resin for added tensile and flexural strength where desired. Sloped surfaces of the floor may be made non-skid by broadcasting aluminum oxide or silica sand into the surface prior to gelation.

3.09 CURING OF COATS

A. Maintain curing conditions in accordance with the recommendations of the coating material manufacturer and this Section, whichever is the most stringent. Complete curing before placing the coating systems into service.

B. In the case of enclosed areas, force air ventilation using heated air if necessary, may be required until the coatings have fully cured.

C. Forced Air Ventilation of Enclosed Hydraulic Structures: Forced air ventilation is required for the application and curing of coatings on the interior surfaces of enclosed hydraulic structures. During application and curing periods, continuously exhaust air from the lowest level of the structure using portable ducting. After interior coating operations have been completed, provide a final curing period for a minimum of 10 days, operating the forced air ventilation system continuously.

3.10 SHOP AND FIELD INSPECTION AND TESTING

A. Give the City Engineer a minimum of 3 days advance notice of the start of any field surface preparation work or coating application work.

B. Perform surface preparation and coating applications in the presence of the City Engineer, unless the City Engineer has granted prior approval to perform such Work in his absence.

C. Inspection by the City Engineer, or the waiver of inspection of any particular portion of the work, does not relieve the Contractor of his responsibility to perform the Work in accordance with these Specifications.

D. Erect and move scaffolding where requested by the City Engineer to facilitate inspection. Provide additional illumination to light areas to be inspected.

E. Inspection Devices: Until final acceptance of coating, furnish inspection devices in good working condition for the detection of holidays and measurement of dry-film thickness of corrosion protective coatings. Make dry - film thickness gauges available for the City Engineer's use while coating is being done, until final acceptance of such coatings. Provide the services of a trained operator of the holiday detection devices until the final acceptance of such coatings. Operate holiday detection devices in the presence of the City Engineer.

F. During application, Applicator shall regularly perform and record corrosion protective coating thickness readings with a wet film thickness gauge, such as those available through Paul N. Gardner Company, Inc. meeting ASTM D4414 - Standard Practice for Measurement of Wet Film Thickness of Organic Coatings by Notched Gauges, to ensure a monolithic coating and uniform thickness during application. A minimum of three readings per 200 square foot area shall be recorded. Applicator will submit all documentation on thickness readings to Inspector on a daily basis when coating application occurs.

G. Applicator shall perform holiday detection on all surfaces coated with the corrosion protective coating in the presence of Inspector. After the corrosion protective coating has set hard to the touch, surfaces shall first be dried, an induced holiday shall then be made on to the coated concrete surface and shall serve to determine the minimum/maximum voltage to be used to test the coating for holidays at that particular area. The spark tester shall be initially set at 100 volts per 1 mil (25 microns) of film thickness applied but may be adjusted as necessary to detect the induced holiday (refer to NACE RP0188-99). All detected holidays shall be marked and repaired by abrading the coating surface with grit disk paper or other hand tooling method. After abrading and cleaning, additional corrosion protective coating material can be hand applied to the repair area. All touch-up/repair procedure shall follow the corrosion protective coating manufacturer's recommendations.

H. A minimum of 10% of the total surface area or structures coated may be subjected to adhesion (bond) testing per this section at the option of the City

Engineer. Measurement of bond strength of the corrosion protective coating to the substrate may be examined in accordance with ASTM D4541. Any areas detected to have inadequate bond strength shall be evaluated by the City Engineer. Further bond tests may be performed in that area to determine the extent of potentially deficient bonded area and repairs shall be made by Applicator in strict accordance with manufacturer's recommendations.

I. A final visual inspection shall be made by the Inspector and Applicator. Any deficiencies in the finished coating shall be marked and repaired by Applicator according to the procedures set forth herein.

J. The municipal sewer system may be put back into non-severe operational service as soon as the final inspection has taken place. Consult corrosion protective coating manufacturer for further recommendations.

END OF SECTION

Section 11311

SUBMERSIBLE WASTEWATER PUMPS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Submersible sewage pumps complete and operational with motors, control equipment and accessories as shown and specified.

B. Coordination:

1. Review installation procedures under other Sections and coordinate with the Work related to this Section.

2. Coordinate pumps and motors with electrical work as specified in Division 16, Electrical.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Refer to Section 01270 – Measurement and Payment for Unit Price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

1.03 REFERENCES

A. Reference Standards: Comply as a minimum with applicable provisions and recommendations of the following:

1. American National Standards Institute (ANSI)

2. American Society for Testing and Materials (ASTM)

3. Anti-Friction Bearing Manufacturers Association (AFBMA)

4. Hydraulic Institute.

5. Institute of Electrical and Electronic Engineers (IEEE)

6. National Electric Code (NEC)

7. National Electrical Manufacturers Association (NEMA)

8. Steel Structures Painting Council (SSPC)

1.04 PERFORMANCE REQUIREMENTS

A. Furnish and install the submersible, non-clog wastewater pumps capable of handling raw unscreened sewage in accordance with these Specifications and as shown on the Drawings.

B. Number of pumps, minimum and maximum operating capacities, TDH, and other pump design data is tabulated on the Drawings.

1. Woodway #1 Lift Station Pump No. 1 through No. 3 shall be a constant speed submersible pump which meets the following design and performance requirements:

a. Service: raw sewage.

b. Flow at maximum head: 1120 gpm at 64.19 feet TDH.

c. Mid-point flow and head: 1200 gpm at 60.82 feet TDH.

d. Flow at minimum head: 1300 gpm at 54.73 feet TDH.

e. Minimum shutoff head: 132.6 feet.

f. Maximum horsepower: 35 HP.

g. Run-Out Head: 9.35 feet.

h. Electrical requirements: 460V/3 PH/60 Hz.

i. Motor speed: 1760 rpm

j. Motor Efficiency at full load 90%

k. Pump Efficiency at rated speed 64.2 %

l. Discharge diameter: 8 inches

C. Pumps shall be designed for continuous operation without cavitation within the specified operating range. The pump shall have a minimum hydraulic efficiency of 65 percent at the rated capacity. The NPSHR at the maximum operating capacity shall not exceed 30 feet.

1.05 SUBMITTALS

A. Submit shop drawings and product data under provisions of Section 01330 - Submittal Procedures.

B. Submit a list of not less than 5 installations where pumping equipment of the type and approximate size specified has been in successful operation for at least 5 years.

C. Submit locations of the nearest permanent service headquarters of the pump and motor manufacturer for the size of pump and motor submitted.

D. Submit descriptive literature, including a cross-sectional view of each pump and motor combination, which indicates materials of construction, weights, principal dimensions and other important details.

E. Submit certified characteristic curves showing the head-capacity relationship, brake horsepower, NPSH requirements, pump efficiency (ratio of the water horsepower to brake horsepower) and pump speed. The curves shall be complete for the entire range of operation from shutoff to minimum head conditions. Submit manufacturer's calculation of radial and thrust bearing L-10 life at the head and flow indicated on the Drawings.

F. If the proposed pumping equipment is supplied with electrical equipment and components of larger capacity than specified or shown on the Contract Documents, the shop drawings for the equipment listed in the following Sections shall be submitted in the same package as the shop drawings submitted for this Section.

1. Section 16111 - Conduit, for conduit related to the submersible wastewater pump only.

G. Manufacturer's Certifications:

1. Submit manufacturer's certification that he has carefully examined the Contract Documents in detail, including the arrangement and conditions of proposed electrical, mechanical and structural systems affecting the performance of the pumping equipment units, and the

detailed requirements of manufacturing and subsequent installation of the pumping equipment units.

2. Submit manufacturer's certification that there are no omissions, ambiguities or conflicts in the Contract Documents or in the pumping station piping layout that affects the pumping unit, as shown on the Drawings, which have not already been clarified in writing.

3. Submit manufacturer's certification that the running amperes of the motor will not exceed the nameplate rating of the motor under all expected operating conditions.

4. Submit manufacturers certification that spare parts, seals, bearings, o-rings and power cable shall be available locally for models to be supplied.

5. Submit manufacturer's certification that motors are explosion proof and labeled so, approved by Underwriters Laboratories (UL) or Factory Mutual (FM).

H. Record Drawings: Submit record drawing under provisions of Section 01785 - Project Record Documents.

I. Factory Tests: Submit 3 copies of certified test reports to the City Engineer for review.

1. The pump manufacturer shall perform the following inspections and tests on each pump before shipment:

   a. Impeller, motor rating and electrical connections shall first be checked for compliance to the customer's purchase order.

   b. A motor and cable insulation test for moisture content or insulation defects shall be made.

   c. Prior to submergence, the pump shall be run dry to establish correct rotation and mechanical integrity.

   d. Each pump shall be run submerged in water.

   e. After running pump submerged in water, retest motor and cable insulation.

2. If tests do not meet performance specifications, Contractor shall correct deficiencies to provide the specified performance.

3. A written report stating the foregoing steps have been done must be supplied with each pump at the time of shipment. This report must be approved by the City Engineer prior to payment.

J. Operation and Maintenance Data: Submit operation and maintenance data under provisions of Section 01782 - Operations and Maintenance Data.

1.05 QUALITY ASSURANCE

A. All materials used shall be new, of high grade, and with properties best suited to the work required.

B. Manufacturer's Qualifications:

1. Pumping equipment provided under this Section shall be a standard product in regular production by manufacturers whose products have proven reliable in similar service for at least 5 years.

2. Manufacturer shall satisfy the City Engineer that it is capable of the following:

a. Providing local (within 50 miles of the limits of the City of Houston) factory trained personnel to service the pumps and allied equipment when needed within a 48 hour period.

b. Providing all needed spare parts for the pumps within a 48-hour period.

3. Provide a written manufacturer's certification that spare parts, seals, bearings, o-rings and power cable shall be available locally for models to be supplied.

C. Coordination Responsibility

1. In order to ensure equipment compatibility, one manufacturer shall be responsible for providing all submersible wastewater pumping equipment, including pump and motor, access frame and guides.

2. The Contractor shall name a pump manufacturer, who will have responsibility for the function of the complete system in accordance with the intent of these Specifications. The named manufacturer shall be experienced in similar work.

3. Contractor shall retain overall responsibility for equipment coordination, installation, testing and operation.

D. Substitution. The engineering design is based on a certain manufacturer's equipment. If the Contractor's choice of equipment is approved but requires modifications to plant, equipment or piping for installation, the Contractor is responsible for submitting revised engineering design and drawings to make the proposed equipment compatible with the project, at no additional cost to the City.

1.06 DELIVERY, STORAGE AND HANDLING

A. Deliver equipment to site, all store and protect equipment under provisions of Section 01610 - Basic Product Requirement.

B. Store all equipment off the ground in enclosed shelter.

C. The pump cable end shall be sealed with a high quality protective covering to make it impervious to moisture or water seepage from submersion or other causes prior to electrical installation.

1.07 EVALUATION AND SELECTION

A. The City reserves the right to select any equipment which is deemed to be in its best interest.

1.08 WARRANTY

A. Provide warranty under provisions of Section 01770 - Closeout Procedures.

B. Pump manufacturer shall furnish to the City a warranty written expressly from the manufacturer to the City of Houston, covering workmanship and material for 5 years or 10,000 hours of operation under normal use and service. The warranty shall cover 100 percent of parts and labor for at least one full year. The warranty period shall commence on the day of initial operation for City's beneficial use. Warranty shall be in printed form and previously published as the manufacturer's Standard Warranty for all similar units manufactured. Pumps repaired under warranty will be returned to the job site freight pre-paid.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

A. Through shop drawing submittals, the following named manufacturers will be considered, provided the submitted equipment meets the specified requirements and system operating conditions:

1. Fairbanks-Morse
2. Flygt Pumps, Inc.
3. KSB Pumps, Inc.

B. Listing as an acceptable manufacturer will not relieve the manufacturer from conforming to Contract Specifications.

2.02 PUMP CONSTRUCTION

A. Casing

1. Major pump components shall be of fine grained gray cast iron, ASTM A48, Class 30 or better, with smooth surfaces devoid of blow holes and other irregularities. Surfaces coming into contact with sewage, other than stainless steel shall be protected by an approved sewage resistant coating.

2. Mating surfaces where watertight sealing is required shall be machined and fitted with nitrile rubber o-rings. Fitting shall be such that sealing is accomplished by metal-to-metal contact between machined surfaces. This will result in controlled compression of nitrile rubber o-rings without the requirement of a specific torque limit. No secondary sealing compounds, rectangular gaskets, elliptical o-rings, grease or other devices shall be used.

3. Pump suction flange shall be drilled to ANSI standard, class 125.

B. Power Cable

1. The cable entry water seal design shall preclude specific torque requirements to ensure a watertight and submersible seal. The cable entry shall be sealed by an elastomer grommet, epoxy potting material, or a combination of both. The cable entry sealing system shall provide strain relief for the terminal connections and allow access to the terminal connections without adversely affecting the integrity or function of the seal system.

2. Cables shall be oil, grease and abrasion resistant, and meet applicable standards. The outer jacket shall be polyurethane or other material equally suitable for immersion in wastewater.

3. Cables shall be capable of operating on either 230 volt or 460 volt, 3 phase service and under continuous submergence without loss of watertight integrity to a depth of 65 feet.

4. No parallel power cables are acceptable unless they are size #1/0 or larger.

5. Motors 7.5 HP and over shall have reconnectable terminal blocks. All leads shall be numbered.

C. Submersible Motor

1. The pump motor shall be a NEMA Design B squirrel-cage, induction, shell type design, housed in an oil-filled or air-filled watertight chamber. The stator winding and stator leads shall be insulated with moisture resistant Class F insulation which will resist a temperature of 155 degrees C (311 degrees F). The use of bolts, pins or other fastening devices requiring penetration of the stator housing shall be rejected. The rotor bars and short circuit rings shall be of aluminum. The motor shall be designed for continuous duty, capable of sustaining a minimum of 15 starts per hour, evenly spaced. The pump/motor shall be capable of operating at liquid temperature of 104 degrees F per FM requirements-without overheating or operating in the service factor. Motor shall be non-overloading over the entire range of the operating curve within the nameplate HP. A performance chart shall be provided showing curves for torque, current, a minimum service factor of 1.15, input/output kw and efficiency.

2. The motor shall be UL listed or FM approved as explosion-proof, suitable for NEC Class I, Division 1, Group C and D environments.

3. Each unit shall be provided with an adequately designed cooling system totally self-contained with no external mechanical devices. Pumps shall be designed to operate continuously with the fluid level at the top of the pump volute.

4. Maximum motor speed shall be 1200 rpm for pumps with discharge diameter greater than or equal to 6-inches.

5. For sizes 20 HP and smaller, the motor shall be equipped with dual voltage connections for 230/460 volts.

6. Thermal sensors shall be used to monitor stator temperatures. The stator shall be equipped with 3 thermal switches, embedded in the end coils of the stator winding (one switch in each stator phase). These shall be used in conjunction with and supplemental to external motor overload protection and wired to the control panel.

7. For motor sizes larger than 100 HP, an independent thermal switch shall be included to monitor the lower motor bearing temperature.

8. The pump shall be equipped with moisture sensors in the oil-filled seal chamber to indicate seal leakage. Motors larger than 20 HP shall be equipped with a leakage sensor to detect water in the stator chamber.

D. Shaft: Each pump shaft shall be one piece of AISI type 420 stainless steel, or heat-treated carbon steel C 1035 protected by a stainless steel shaft sleeve. The shaft shall be of sufficient diameter to assure rigid support of the impeller and to prevent excessive vibration at all speeds.

E. Pump Seal: Each pump shall be provided with a tandem mechanical shaft seal system. The upper seal of the tandem set of seals shall operate in an oil chamber located just below the stator housing. This set shall contain one stationary tungsten-carbide ring and one positively driven rotating carbon (or better) ring, and functions as an independent secondary barrier between the pumped liquid and the stator housing. The lower seal of the tandem set of seals functions as the primary barrier between the pumped liquid and the oil housing. This set shall consist of a stationary ring and a positively driven rotating ring both of which shall be silicon carbide or tungsten carbide. Shaft seals without positively driven rotating members or conventional double mechanical seals containing either a common single or double spring action between upper and lower seal faces shall not be acceptable.

F. Bearings: Bearings shall be permanently lubricated ball or roller type rated in accordance with AFBMA for an L-10 duty life of at least 80,000 hours at the rated capacity.

G. Impeller:

1. The impeller shall be of fine grained gray cast iron, Class 30 or better, dynamically or statically balanced, double shrouded non-clogging design having a long thrulet without acute turns. The impeller shall be capable of handling 3 inch minimum diameter solids, fibrous materials, heavy sludge and other matter found in normal sewage application. The impeller hub shall be accurately fitted and mechanically secured to the motor shaft.

2. The volute shall be of a single piece, concentric or non-concentric design, and shall have smooth fluid passages large enough at all points to pass any size solids which can pass through the impeller. The volute bottom shall be of a suction bell design for pumps with 12-inch discharge and larger.

3. A replaceable wear ring shall be installed to provide efficient sealing between the volute and impeller. The wear rings shall consist of AISI Series 300 or better heat-treated stainless steel. For pumps 10 HP and below the pump shall be equipped with brass or nitrite rubber volute wear ring only.

2.03 ACCESSORIES

A. Access Frames and Covers

1. Halliday Products Series H2R, U.S. Foundry Series AHD or AHS, or approved equal.

2. For watertight service, Halliday Products Series H2W, U.S. Foundry Series THD or THS, or approved equal.

3. Aluminum access frames and covers shall be provided by the pump supplier. Fasteners, hinges and other hardware shall be type 316 stainless steel.

4. The frame shall be extruded aluminum with an integral seat and anchor flange. Door leafs shall be 1/4-inch thick aluminum floor plate reinforced to H-20 live load with 30 percent impact factor per AASHTO specifications.

5. The access door shall be equipped with a flush cast aluminum drop handle which does not protrude above the cover surface and an automatic hold open arm with a red vinyl release grip, that automatically holds the door in a 90 degree open position utilizing a

stainless steel pin at the point where the door meets the hold open arm.

6. Hinges shall be stainless steel with stainless steel tamperproof hardware. Doors shall be equipped with a stainless steel, watertight slamlock with a threaded aluminum plug, removable outside handle and an inside release handle. The slamlock must latch onto a stainless steel catch bolted to the frame.

7. Doors shall also include a recessed padlock assembly that consists of a cast aluminum enclosure that is sized to restrict access by bolt cutters, a stainless steel staple for a padlock and a hinged stainless steel cover which does not protrude above cover surface.

8. Doors shall be equipped with stainless steel spring operators for lift assist and to retard downward motion. All parts of the spring operator shall be stainless steel or aluminum and to ensure visual inspection. Spring operators shall be open type. The spring operators shall be engineered and installed so that in the event of slamlock failure the door will remain closed. The force required to open any one door leaf shall be a minimum of 5 pounds and a maximum of 20 pounds.

9. Apply bituminous paint on all areas that come in contact with concrete.

10. Exposed frame and door surfaces shall be painted dark green as approved by the City Engineer.

11. A written 10-year material and/or workmanship warranty on all components shall be provided.

B. Pump Guide System: Pump manufacturer shall provide a guide rail system complying with the following requirements:

1. Type 316 stainless steel rails, replaceable without man entry into the wet well.

2. Lower bracket integral with pump support/discharge fitting.

3. Type 316 stainless steel upper bracket bolted to access cover frame.

4. Intermediate brackets as shown on the Drawings, if required.

C. Bolts, Studs and Nuts

1. All bolts, studs and nuts shall have American National form right-hand machine cut threads which shall be in conformity with the current ANSI

B1.1, "Screw Threads", Coarse Thread Series, unless otherwise specified.

2. Bolt heads and nuts shall be semi-finished and shall be in conformity with ANSI B18.2, "Wrench-Head Bolts and Nuts and Wrench Openings", Heavy Series, unless otherwise specified. All nuts shall be hexagonal in shape.

3. Anchor bolts, flange bolts, studs and nuts shall be Type 316 stainless steel in conformity with ASTM A276.

2.04 PUMP PROTECTION SYSTEM

A. Manufacturer shall furnish a complete pump monitoring and protection system consisting of an intrinsically safe solid state monitoring system to be installed in the motor starter cubicle, and independent probes integral to the pump/motor wired to a sealed cable entry terminal box for connection of submersible control cables.

B. Monitoring unit shall be solid state, intrinsically safe system designed for mounting within the motor starter cubicle. Monitoring system shall accept inputs from the sensors specified and shall output independent contacts which close to alarm each condition, or separate independent output terminals suitable for direct connection to interposing relays for alarm contact development. Provide a separate N.C. alarm contact, rated at 120V, 5A inductive, which opens on any failure. Monitor system shall be suitable for operation from a 24VAC unregulated, unlimited power supply. Provide any additional equipment or appurtenances required to provide current and voltage limited intrinsically safe installation as specified. The monitoring system shall accept separate isolated N.O. contacts which close to indicate pump running and to reset after pump trip.

C. Sensors shall be independently wired to the monitoring system. Provisions for the following sensors for each pump:

1. Stator leak (one required).

2. Stator temperature for pumps over 100 HP (one per phase, field test and connect to highest reading obtained).

3. Bearing temperature (one required).

2.05 SHOP PAINTING

A. Pump motor size up to 100 HP.

1. Pump Exterior:

a. Pre-treatment.

b. Primer. One coat of alkyd resin primer, 1.6 mils minimum.

c. Finish. Chloric rubber paint, 2.4 mils minimum.

2. Machine Finished Surfaces:

a. Machined parts are cleaned to remove all dirt and grease.

b. Cleaning is done so as not to affect primer or deteriorate adherence to finish paint.

c. Storage and transport is carried out in such a way that rust attack on machined surfaces does not occur.

d. At assembly, surfaces are coated with a corrosion preventive paint.

B. Pump motor size greater than 100 HP.

1. Pump Exterior:

a. Pre-treatment. Sandblast cleaning and removal of all oil and dust.

b. Primer. One coat of alkyd resin primer, 1.6 mils minimum.

c. Finish coat. Two coats of chloric rubber paint, 2.1 mils each coat.

2. Machine finished surfaces:

a. Machined parts are cleaned to remove all dirt and grease.

b. Cleaning is done so as not to affect primer or deteriorate adherence to finish paint.

c. Storage and transport is carried out in such a way that rust-attack on machined surfaces does not occur.

d. At assembly, surfaces are coated with a corrosion preventive paint.

PART 3 EXECUTION

3.01 INSTALLATION

A. Installation of the pumping equipment shall conform to the manufacturer's instructions and recommendations and reviewed shop drawings.

B. Field Tests:

1. Each pump will be subjected to a 6-hour field operational test before acceptance as follows:

a. The unit under test shall be properly installed in the wet well, firmly upon its discharge connection after determination of (a) proper service voltage is being supplied and (b) proper rotation of the impeller. No cooling by forced or circulated air shall be allowed.

b. Capacity Test: On four occasions, wet well shall be filled with liquid to an elevation sufficient to allow each single pump to operate for 3 minutes, independent of the control regime. Time required to pump down known volume shall be measured as evidence of each pump's capacity. All portions of the force main must have been constructed and tested prior to this test.

c. Snore Tests: Snore is defined as that state when the pump is alternately pumping liquid and air and usually occurs when the pump pumps the liquid down to expose its inlet. The unit(s) under test shall be submerged with just enough liquid to accomplish "snore" and allowed to run two times for 10 minutes minimum.

C. Start-up Data: Contractor shall complete and submit the start-up records and maintenance data sheets.

END OF SECTION

Section 13440

PUMP STATION CONTROL SYSTEM

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Programmable logic controllers (PLCs), remote input/output (I/O) units, Human Machine Interface (HMI), and programmer.

1.02 REFERENCES

A. National Electrical Manufacturers Association (NEMA).

1. NEMA ICS 1 - General Standards for Industrial Control and Systems.
2. NEMA ICS 2 - Standards for Industrial Control Devices, Controllers and Assemblies.
3. NEMA ICS 3 - Industrial Systems.
4. NEMA ICS 6 - Enclosures for Industrial Controls and Systems.
5. NEMA ST 1 - Standard for Specialty Transformers (Except General Purpose Type).

B. Instrument Society of America (ISA).

C. Underwriters Laboratories, Inc. (UL).

D. Factory Mutual (FM).

E. Institute of Electrical and Electronic Engineers (IEEE).

F. National Fire Protection Association (NFPA). ANSI/NFPA 70 - National Electrical Code (NEC).

G. Joint Industrial Council (JIC).

H. American National Standards Institute (ANSI).

1.03 SUBMITTALS

A. Submit product data, shop drawings and samples (if samples are requested by the City Engineer) under provisions of Section 01330 - Submittal Procedures.

1. Submit in complete packages grouped to permit review of related items as outlined in these specifications.

2. Bind submittals in three-ring binders with complete indexing and tab dividers. Completely tag and label equipment information to correspond with Drawings.

3. Review of Submittals will be for conformance to Contract Documents and for application to specified functions.

B. Product Data: Submit descriptive product literature including manufacturer's specifications for each component specified.

C. Shop Drawings: Indicate layout and mounting of completed assemblies and systems, interconnecting piping and cabling, dimensions, weights, external power and communication connections and programming information.

1. Panel, Console and Cabinet Information.

a. Layout drawings, including the following:

1) Front, rear, end and plan views to scale.

2) Dimensional information.

3) Tag numbers and functional names of components mounted in and on panels, consoles or cabinets.

4) Product information on panel components.

5) Nameplate locations and legends, including text, letter sizes and colors to be used.

6) Location of anchoring connections and holes.

7) Location of external wiring and piping connections.

8) Mounting and installation details.

9) Proposed layouts and sizes of graphic display panels.

b. Wiring and piping diagrams, including the following:

1) Name of panel, console or cabinet.

2) Wiring sizes and types.

3) Piping and tubing sizes and types.

4) Terminal strip numbers.

5) Color coding for each wire and color coding legend.

6) Functional name and manufacturer's designation of components to which wiring and piping are connected.

c. Electrical control schematics in accordance with JIC standards.

d. Plan showing equipment layout in each area.

2. Field Wiring and Piping/Tubing Diagrams

a. Wiring and piping/tubing sizes and types.

b. Terminal strip, device terminal and wire numbers.

c. Color coding.

d. Designation of conduits in which wiring is to be located.

e. Location, functional name and manufacturer's designation of items to which wiring or piping are connected.

f. Point-to-point wiring diagrams identifying every termination point and connection.

3. Instrumentation Diagrams

a. Prepare instrument loop diagrams for analog and digital displays, and control and I/O loop diagrams, using ISA standard symbols in accordance with ISA Standard S5.4. Drawings shall follow the format in Attachment C and include the following:

1) Instrument tag numbers.

2) Functional name, manufacturer's name, product name and model or catalog number of each item.

3) Location of each item.

b. Submit loop diagrams, wiring diagrams, PLC and control schematics on 4.7 GB DVD, formatted as AutoCAD files using the latest release of AutoCAD current and available on bid date, or any subsequent version. Identify diagrams, schematics and other files with computer-printed labels affixed to each diskette. Leave at least 200,000 bytes free space available on each DVD.

c. In addition, submit such diagrams and schematics laser-printed on 8.5-inch x 11-inch paper. Use lettering and numerals of at least 1/16-inch nominal height.

4. Programmable Controller System I/O Loop Wiring Diagrams

a. Prepare drawings on a module-by-module basis. Include the following information:

1) Rack numbers, module types and slot numbers, module terminal point numbers, and location and identification of intermediate panel and field terminal block and strip numbers to which I/O wiring and power supply wiring is connected. Identify power supply circuit numbers and ratings.

2) Wiring sizes, types, wire numbers and color coding.

3) Designation of conduits in which field I/O wiring is to be run.

4) Locations, functional names, tag numbers and manufacturer's names and model numbers of panel and field devices and instruments to which I/O wiring is connected. Label wiring and cables at both ends and within junction and terminal boxes. Use sleeve-type plastic wire markers covered with clear heat-shrink labels, or machine-printed permanent ink heat-shrink labels by Brady or approved equal.

b. For each drawing, submit one reproducible hardcopy and one copy on 4.7 GB DVD, formatted as AutoCAD files using the latest release of AutoCAD current and available on bid date, or any subsequent version. Identify diagrams, schematics and other files with computer-printed labels affixed to each diskette. Leave at least 200,000 bytes free space available on each DVD.

c. In addition, submit such diagrams and schematics laser-printed on 11 x 17 inch paper. Use lettering and numerals of at least 1/16 inch nominal height.

5. System Programming Information

   a. At least six weeks prior to substantial completion, submit detailed programming information consisting of ladder logic and proposed program code, complete input, output, relay, register and controller identification labels, memory allocation table, and written description of program operation.

   b. Ladder logic diagrams shall contain a written descriptive note for each line of program code describing the function and logic of that line.

   c. Submit documents in hard copy and as computer-readable files 4.7 GB DVD. Leave at least 200,000 bytes free space available on each DVD. PLC, HMI, MPR, VFD and all other operational, installation and application related programs required necessary by the City of Houston with the installation shall be submitted in native programming language files.

D. Quality Control Submittals

1. Factory Test Reports: If specified, submit 6 copies.

2. Testing Procedures: Submit testing procedures proposed to verify input, output, loop and register operations, system logic verification, and spare memory capacity. Testing procedures shall detail, as a minimum, verification of required functions as follows:

   a. Verification of pump start, pump stop, and well level alarm outputs by simulation of analog signals representing pump level.

   b. Verification of each discrete input via external manually-operated switch.

   c. Verification of each analog input by connection of external analog indicator in input loop.

   d. Verification of each analog output by connection of external analog indicators.

   e. Verification of communications system by hardwire connection via modem and wiring to a similar unit. Demonstrate operation and status monitoring of each register specified for external monitoring.

   f. Verification of spare memory capacity by hard copy printout of

full memory bit map after successfully demonstrating that system logic, inputs, outputs and communications features are fully installed and operational.

g. Test and verify system with external devices required to simulate field connections connected simultaneously for a full system test.

h. Reconnecting external devices to verify portions of the systems at a time is not acceptable.

3. Certificates: Under provisions of Section 01450 - Contractor's Quality Control, submit manufacturers' certificates that equipment and systems meet or exceed specified requirements.

4. Instructions: Submit manufacturer's installation instructions for each component specified.

5. Field Reports: Submit 6 copies of Manufacturer's Installation Inspection, Field Calibration and Field Testing Reports.

6. Site Acceptance:

E. Operations and Maintenance (O&M) Data.

1. Submit operation and maintenance data notebook in accordance with Section 01782 - Operations and Maintenance Data.

2. Information and drawings submitted must reflect the final installed condition. Revise documents requiring updates following testing and start-up.

3. In addition to the content specified in Section 01782 - Operation and Maintenance Data, provide the following information:

a. Name, address and telephone number of the control system supplier's local service representative.

b. Complete list of supplied system hardware parts with full model numbers referred to system part designations, including spare parts and test equipment provided.

c. Copy of approved submittal information and system shop drawings as specified in Paragraph 1.3, Submittals, with corrections made to reflect actual system as tested, delivered and installed at the site. Provide half-size blackline reproductions of all shop drawings larger than 11 inches x 17

inches.

d. Complete up-to-date system software documentation.

e. Original copies of manufacturer's hardware, unprotected software, installation, assembly and operations manuals for the programmable controller and data communication system, single loop and multi-loop controllers and other control system components. In addition to hard copy versions, provide all manuals in PDF format on 4.7 GB DVD.

f. Instructions for PLC replacement adjustment, and preventive maintenance procedures and materials.

g. Control system description and system operation sequence instructions.

h. For each major system/subsystem, in separate binders, submit PLC ladder logic programming documentation (fully annotated of each network headers, logical elements, control descriptions), PLC I/O schematics, control and loop diagrams, electrical drawings, system description, operation instructions and files on 4.7 GB DVD.

F. Project Record Documents

1. Submit record documents under provisions of Section 01785 - Project Record Documents.

2. Revise system shop drawings, software documentation and other submittals to reflect system as installed. Accurately record locations of controller cabinets and input and output devices connected to system. Include interconnection wiring and cabling information and terminal block layouts on rite in the rain all weather writing paper in a suitable drawing pocket installed inside the controller cabinet door.

3. Insert half-size blackline prints of wiring diagrams applicable to each control panel in a clear plastic envelope and store in a suitable print pocket or holder inside each control panel.

1.04 QUALITY ASSURANCE

A. Manufacturer's Qualifications: Manufacturer shall be a company specializing in manufacturing products specified in this Section, having proven compatibility with the City's existing facilities and at least 5 years of documented experience. The company shall maintain service facilities within 100 miles of the City of Houston.

B. System Integrator / Panel shop Qualifications: System Integrator / Panel shop shall be a company specializing in installation of products specified in this Section, having proven experience with the City's existing facilities and at least 5 years of documented record. The company shall maintain service facilities within 100 miles of the City of Houston.

1.05 DELIVERY, STORAGE AND HANDLING

A. Deliver products to site in factory-sealed containers. Store and protect products under provisions of Section 01610 - Basic Product Requirements.

B. Check for damage upon receiving products on site.

C. Store products in a clean, dry area; maintain temperature in accordance with NEMA ICS 1.

1.06 ENVIRONMENTAL REQUIREMENTS

A. Maintain temperature above 32 degrees F and below 104 degrees F during and after installation of products.

B. Maintain area free of dirt and dust during and after installation of products.

C. Provide temporary heating and air conditioning units and equipment required to maintain environmental conditions specified for control and MCC panels.

1.07 MAINTENANCE SERVICE

A. Provide manufacturer's maintenance services for programmable logic controllers for one year from Date of Substantial Completion without additional cost to the City.

PART 2 P R O D U C T S

2.01 PROGRAMMABLE LOGIC CONTROLLER (PLC)

Manufacturer and Product: Siemens Model S7-315-2PN/DP; with integral Ethernet, the latest version at the time of delivery, or approved equal

B. Description: Modular Programmable Controller and Removable 2 MB Micro Memory Card.

C. Service Conditions

1. Temperature: 32 to 140 degrees F, horizontally installed.

2. Humidity: 5 to 95 percent, non-condensing.

3. Electromagnetic Compatibility: Noise suppression to EN 50082-2, Noise emission to EN50081-2.

4. Vibration: IEC 68, Part 2-6/10 to 58 Hz.

5. Shock: IEC 68, Part 2-27/half-sine: 15 g peak, 11 milliseconds.

D. Configuration

1. Processor Rack: Include processor, power supply, micro memory card, communication modules, and input/output modules with front connectors.

2. Expansion Unit: Include interface module, power supply, communication module, input/output modules, front connectors and necessary connection cables.

3. Mounting Rail: Provide passive mounting rail for processor, power supply, communication, and input/output modules.

E. Processor Unit

1. Integrated Memory: Internal 256 KB minimum

2. Execution Time, Bit Operations: 0.1 microseconds.

3. Execution Time, Word Operations: 0.2 microseconds.

4. Execution Time, Fixed Point Arithmetic: 2 microseconds.

5. Execution Time, Floating Point Arithmetic: 3 microseconds.

6. Ports: See 2.01.H

7. Storage Memory: Micro Memory Card, minimum 2 MB.

F. Power Supply

1. Input: 85-132/170-264 VAC, switch-selectable.

2. Output: 24 VDC, 5-amp.

3. Mounting: On PLC Mounting Rail.

4. Front Panel: Green status LED, On/Off Switch, Input Voltage Selector.

5. Output Terminations: Screw terminations with connector to PLC CPU, plus additional terminations for wiring to other control system 24 VDC needs.

G. Input/Output Units

1. Spare Input/Output Capacity: At least 25 percent spare capacity of each I/O type installed.

2. Discrete Input Characteristics: 16 points; 24 volts DC.

3. Analog Input Characteristics: 8 channels for configurable in groups of 2, 4 to 20 milliamperes DC.

4. Discrete Output Characteristics: 16 points; Relay.

5. Analog Output Characteristics: 8 channels, 4 to 20 milliamperes DC.

H. Communication Interfaces for Remote Lift Station or Plant On-Site Lift Station:

1. Profibus-DP: Integral to CPU, master/slave, capable up to 12 Mbit/sec, configured in standard PLC programming environment. Supports Profibus-DP Master, Profibus-DP Slave, MPI with programmer, HMI and S7 communications.

2. Ethernet Interface: Integral to CPU, 10/100 Mbps with automatic speed detection, supports open TCP/IP, PLC programming, HMI communications, ST Communications, Profinet CBA and Pronet IO-Controller.

3. Ethernet Switch (Wastewater Treatment Plant applications): Managed Industrial Ethernet Switch to be mounted in control panel and connected to PLCs with Ethernet interface.

I. Ethernet Networking (Wastewater Treatment Plant applications)

1. Industrial Ethernet Switch: Managed Industrial Ethernet Switch to be mounted in control panel and connected to PLCs with Ethernet interface.

   a. Fiber Optic Networks: SCALANCE X204-2

1) Manufacturer and Model: Siemens X204-2

2) Electrical Ports: Four RJ45, 10/100 Mbps, Connectors latch to housing for strain relief.

3) Optical Ports: Two female ST pairs, 100 Mbps

4) Fiber Topology: Bus, Star, and Ring

5) Power: Redundant 24 VDC

6) Mounting: Standard DIN rail, PLC Rail

7) Diagnostic LEDs: Power, Link Status, Communications

8) Housing: Metal

9) Include C-Plug Configuration Plug

b. Copper-Only Networks: SCALANCE X208

1) Manufacturer and Model: Siemens X208

2) Electrical Ports: Eight RJ45, 10/100 Mbps, Connectors latch to housing for strain relief.

3) Power: Redundant 24 VDC

4) Mounting: Standard DIN rail, PLC Rail

5) Diagnostic LEDs: Power, Link Status, Communications

6) Housing: Metal

7) Include C-Plug Configuration Plug

2. Industrial Ethernet Cable, Copper, for Runs Outside Control Panels

a. Manufacturer and Model: Siemens Energy & Automation, 6XV1-840-2AH10

b. Style: Industrial Ethernet Fast Connect (FC) Standard Cable

c. Type: Four-wire, shielded

d. Jacketing: Green PVC Sheath, 6.5 +/- 0.4 mm OD

e. Temperature: -40 to 70 deg. C operating, transport and storage

f. Include Stripping Tool: Siemens Energy & Automation, 6GK1-901-1GA00

3. Industrial Ethernet Connectors, Copper

a. Manufacturer and Model: Siemens Energy & Automation 6GK1-901-1BB10-2AA0 (straight) or 6GK1-902-1BB20-2AA0 (90-degree)

b. Permissible Cable: Industrial Ethernet FastConnect Cable

c. Installation: Insulation Displacement via simple cable insertion and housing closure

d. Strain relief: Via quarter-turn locking mechanism

e. Housing: Metal with metal spring clip

4. Industrial Ethernet and Profibus Cable, Fiber Optic

a. Manufacturer and Model: Optical Cable Corp)

b. Fibers: 6 multimode fibers minimum, 25% spare pairs minimum, 62.5/125 graded index

c. Type: Tight-Buffered, Riser-Rated, Multi-fiber Breakout-Grade Cable

d. Jacketing: Indoor/outdoor PVC outer jacket, Color-coded subcables protected to permit direct field termination without patch boxes, jumpers, splices, etc.

e. Primary Fiber Buffer: 500 micron acrylate buffer over each optical fiber

f. Secondary Fiber Buffer: 900 micron elastomeric tight buffer over each optical fiber

g. Connectors: ST, Factory-terminated or field-installed and tested

h. Diameter: 9.5 mm (0.37 in)

i. Tensile Load Rating: 270 lbs. long-term, 670 lbs. short-term (installation)

j. Minimum Bend Radius: 3.7" under long-term tensile load, 7.4" under installation load

k. Temperature: -40 to 85 deg. C operating

5. Industrial Ethernet and Profibus Fiber Optic Patch Panel

a. Manufacturer :

1) Panduit

2) Black Box

3) 3M

4) Leviton

5) Corning

b. Design: Metal box with latching door covering two chambers

c. Connectors: Populated 6-packs with ST connectors

d. Mounting: Wall mount

e. Minimum 12 ports and up to 24 ports.

6. Industrial Ethernet, Wireless Access Point

a. Manufacturer and Model: Siemens Energy & Automation SCALANCE W788-1PRO or W788-2PRO

b. Radio Networks: Single (-1PRO) or Dual (-2PRO) depending on project requirements

c. WLAN Standards: IEEE 802.11b/g, IEEE 802.11a/h

d. Data Security: WEP, WPA2/IEEE 802.11i with AES and TKIP, EAP-TLS, EAP, TTLS, EAP-PEAP, EAP-MD5, EAP-MSChapv2, MAC Filter, Admin Password

e. Degree of Protection: IP65

Ethernet Interface: IE Hybrid Socket (IP65); RJ45 Connection

f. External Antenna Connections: Two (or four for Dual) R-SMA

with included Omnidirectional Direct-Mounted Removable Antennas

g. External Antennas: As needed, Siemens ANT-79X selected for necessary Antenna Gain at installed frequency

h. Lightning Protection: Include LP798-1PRO Lightning Protector on cable to external antenna

i. Power: 24VDC, Redundant

j. Operating Temperature: -20 to 60 deg C

k. Include C-Plug Configuration Plug

7. Industrial Ethernet, Wireless Client Module

a. Manufacturer and Model: Siemens Energy & Automation SCALANCE W740-1PRO

b. WLAN Standards: IEEE 802.11b/g, IEEE 802.11a/h

c. Data Security: WEP, WPA2/IEEE 802.11i with AES and TKIP, EAP-TLS, EAP, TTLS, EAP-PEAP, EAP-MD5, EAP-MSChapv2, MAC Filter, Admin Password

d. Degree of Protection: IP65

e. Ethernet Interface: IE Hybrid Socket (IP65); RJ45 Connection

f. External Antenna Connections: Two (or four for Dual) R-SMA with included Omnidirectional Direct-Mounted Removable Antennas

g. External Antennas: As needed, Siemens ANT-79X selected for necessary Antenna Gain at installed frequency

h. Lightning Protection: Include LP798-1PRO Lightning Protector on cable to external antenna

i. Power: 24VDC, Redundant

j. Operating Temperature: -20 to 60 deg C

k. Include C-Plug Configuration Plug

J. Profibus Networking

1. Profibus Cable, Copper

   a. Manufacturer and Model:

1. Siemens Energy & Automation, 6XV1-830-0EH1

2. Beldon, 3079A

   b. Style: Profibus Fast Connect (FC) Standard Cable

   c. Type: Two-wire, shielded

   d. Jacketing: Purple PVC Sheath, 8.0 +/- 0.4 mm OD

   e. Include Stripping Tool:

1 Siemens Energy & Automation, 6GK1-905-6AA00

2. Phoenix Contact, PSM-STRIP-FC/PROFIB

2. Profibus Connector, Copper

   a. Manufacturer and Model:

1. Siemens Energy & Automation, 6ES7-972-0BA50-0XA0

2. Helmholz, 700-972-0BA50/-0FA50

   b. Cable Outlet: 90-degree, dual cable path

   c. Terminating Resistor: Integrator resistor combination, slide switch enabled

   d. Interfaces: DB9F connector and four insulation displacement terminals

K. Wireless I/O

1. Wireless I/O System

   a. Manufacturer and Model: Phoenix Contact RAD-ISM-900-XD-BUS

   b. Design: Modular, Expandable, DIN-Rail mounting, Multi-Point to Point

   c. I/O Capacity: Up to 33 analog or 66 discrete in one direction

d. Module Capacity: Up to 8 I/O modules per master transceiver

e. Slave Capacity: Up to 8 Slave Transceivers per master transceiver

f. Configuration: Rotary Switch on modules, No programming

2. Wireless I/O Transceiver

a. Radio Signal: Frequency Hopping Spread Spectrum (FHSS) over 902-928 KHz ISM band, License-free, 1W

b. Integral I/O: Two Discrete Inputs, Two Relay Outputs, One Analog Input, One Analog Output

c. Signal Status: RF Link Status Relay

d. Antenna Included: 3" ¼-wave Whip Antenna with 6-ft of RG174 Cable, With L-Bracket

e. Antenna Connection: MCX

f. Power: 9-30 VDC

3. Wireless I/O Expansion Modules

a. 8-pt DC Discrete Input, RAD-IN-8D

b. 8-pt Relay Output, RAD-OUT-8D-REL

c. 4-pt Analog Input, RAD-IN-4A-I

d. 4-pt Analog Output, RAD-OUT-4A-I

e. Combination, 2DI / 2RO / 1AI / 1AO, RAD-IN+OUT-2D-1A-I

4. Wireless I/O Antennas

a. External Antennas: As needed, Phoenix Contact antennas and cables selected for necessary Antenna Gain

b. Lightning Protection: Include CN-UB-280DC-BB Lightning Protector on cable to external antenna

L. Programming, Software and Programming Equipment

1. Configure system and program for operation as specified in this Section.

2. System Software: Siemens Step 7 software will be loaned by City for utilization by contractor on this project. Contractor to supply any other software or interfaces and cables needed to support equipment supplied on this project.

3. Control Program: A generic lift Station PLC Control Program will be provided by Wastewater Operations. Contractor shall provide necessary programming modifications and enter the required variable parameters to provide a complete functional and integrated system. Contractor shall customize the generic software to meet site-specific conditions. The system shall be fully tested to be operational prior to substantial completion.

4. Control Program Data Sheet: Contractor shall complete and submit Lift Station Data Sheet to Control Program Librarian designated by City of Houston. System I/O list shall be submitted with Data Sheet to the City of Houston two weeks prior to the 7-day test where communication can be verified by the Control Center. (Refer to Attachment 13440 A and B)

5. Programmer (City of Houston Wastewater Plant applications only): HP ZBook Mobile Workstation or equivalent current model, new, submitted in the original package including manuals having at least the following features as minimum:

   a. Operating system: Genuine Windows 7 Professional 64

   b. Processor: Intel Core i7-4700MQ Processor (2.4 GHz, 4MB L3 cache)

   c. Memory: 8GB 1600 MHz DDR3L SDRAM.

   d. Hard drive: 750 GB 7200 rpm SATA, 32GB MSATA SSD

   e. Optical drive: DVD-ROM; DVD+-RW SuperMulti DL LightScribe; Blue-ray R/RE DVD+/-RW SuperMulti DL

   f. Display: 15.6 diagonal LED-backlight HD anti-glare

   g. Graphics: NVDIA Quadro FX 1800M graphics with 1 GB dedicated GDDR5 video memory.

   h. I/O Ports: External – 3USB 2.0, 2USB 3.0, 1eSATA, 1 external VGA monitor, 1 Display Port, 1 1394a, 1 stereo microphone in,

1 stereo headphone/line-out, 1 AC power, 1 RJ-11, 1 RJ-45, 1 docking connector, 1 secondary battery connector.

i. Slots: 1 Express Card/54, 1 Smart Card Reader, 1 Secure Digital.

j. Network interface: Integrated Intel Gigabit Network Connection (10/100/1000 NIC).

k. Wireless: HP Mobile Broad (powered by Gobi) with GPS; Intel Centrino Ultimate-N 6300 (3x3) 802.11 a/b/g/n; HP Integrated Module with Bluetooth 2.1 Wireless Technology.

l. Energy Efficiency: ENERGY STAR

m. Battery: HP Long Life 8-cell (68 WHr) Li-Ion

n. Power supply: External 150-watt Smart AC adapter; External 120-Watt Smart AC adapter; External 90-watt Smart AC adapter; HP Fast Charge

o. Security management: Standard – Integrated Smart Card Reader, HP ProtectTools, TPM Embedded Security Chip 1.2, Enhanced Pre-Book Security, HP Spare Key (require initial user setup), HP Disk Sanitizer, Enhanced Drive Lock, drive Encrption for HP ProtectTools, Credential Manager for HP ProtectTools, File Sanitizer for HP Protect Tools

p. Warranty: HP services offers limited 3-year standard parts and labor onsite, next business day warranty, and toll-free 7 x 24 hardware technical phone support; 1-year limited warranty on primary battery. On-site service and warranty upgrades are also available.

q. Preinstalled Microsoft Windows in latest versions currently available that are compatible with HMI software.

r. Programming cable and adapter for PLC programming.

s. Compaq Workstation carrying case (overall size 18"x13"x5").

M. Spare Capacity: Provide at least 25 percent spare rack space, and 25 percent spare I/O's configured, wired, terminated, and identified as such, but not used in program.

N. Provide at least 25% of each PLC module furnished as spare parts. Minimum spare parts will include the following for each type furnished:

1. One discrete input, of each type.
2. One discrete output, of each type.
3. One analog input, of each type.
4. One analog output, of each type.
5. One PLC power supply, of each type.
6. One CPU with Profibus-DP and Ethernet ports.
7. One Ethernet Switch where applicable

O. Connect PLC inputs/outputs including analog inputs through snap-on isolated fused terminal blocks.

P. Separate the AC and control signals from DC and loop signals by at least 6 inches. Provide a barrier between AC and DC within the raceways.

2.02 LOCAL WORK STATION

A. General

1. Manufacturer and Model: Siemens Energy & Automation, TP900 touch panel.
2. Display: 9.0" 800 x 480 TFT LCD Touch Panel.
3. Keyboard: Numeric / Alphabetic Entry.
4. Memory: 12 MB.
5. Memory Card: Two MMC/SD combination slot
6. Operating System: Windows CE
7. Ports: One RS 422/485, USB, Ethernet RJ-45
8. Power: 24 VDC.
9. Certifications: IP65 / NEMA 4 / FM Class I, Division 2 when mounted.
10. Configuration: A generic Lift Station HMI Configuration will be provided by Wastewater Operations. Contractor shall provide necessary modifications and enter the required variable parameters to

provide a complete functional and integrated system. Contractor shall customize the generic software to meet site-specific conditions. The system shall be fully tested to be operational prior to substantial completion.

11. Configuration Software: Configuration software not including cable will be loaned by City for utilization by contractor on this project. Contractor to supply any other software needed to support equipment supplied on this project.

12. Provide necessary cables and connectors to communicate between Operator Panel and PLC processor. Following is a list of sample displays to be provided:

    a. Display 1: Name/Address.

    b. Display 2: Screen Listing.

    c. Display 3 to 5: Pumps 1 to 3 Status Alarms (to be extended where more pumps used).

    d. Display 6: PLC I/O health Status.

    e. Display 7: Wet Well Level Set points.

    f. Display 8: Wet Well Level Readings.

    g. Display 9: 7-day level trends

13. Supply configuration software, latest version, and download cable.

14. Note: Pump Information and necessary status points shall be configured as needed. All configurations shall be performed by the contractor.

PART 3 EXECUTION

3.01 SYSTEM DESCRIPTION

A. Level Measurement System: Equip pump station with two independent well level measurement systems, each system consisting of a submersible transmitter and associated cable and installation mounting hardware to provide a 4-20 mA loop signal proportional to well level and recorder as indicated on the Drawings.

B. Installation: Fabricate and install stilling well for each submersible transmitter.

1. Support Hardware: Provide mounting hardware shown on the Drawing Z0C01 for supporting 6" Schedule 80 PVC inside support to guide each transmitter cable and cord.

2. Support cable: 1/4 inch stainless steel 316 cable to support and hold transmitter.

3. Access manhole: Provide access manhole where the transmitter can easily be removed, installed, and maintained.

C. Primary Pump Control-Constant Speed Pump used for 2, 3, 4, 5, and 6 pump that are the same ratings

1. PLC shall monitor the primary level measurement system and control a PLC output to energize a relay to start / stop pumps at a preselected well levels a indicated on the Drawings.

2. The primary control system shall monitor a NO contact which closes when tl pump is running and shall totalize pump running time and store last 100 entries.

3. The primary control system shall provide first-on first-off alternate sequencing of pump starts.

4. The primary control system shall provide a numerical sequencer to sequenc available pumps.

5. The primary control system shall monitor a NO contact which closes when the HOA switch for each pump is in auto.

6. Stagger start times by 10 seconds between pump lead/lag stages to prevent pumps starting at the same time. It responses to a pump signal to run command not confirmed within 20 seconds (through auxiliary feedback, motor amperage report or level indication) shall remove that pump from service and the pump sequence, but transfer the command signal to the next available pump in the same sequence.

7. Phase failure, overload, high temperature, and seal leak (primary mode only), alarms shall cause a pump to stop in either Primary or Back-up mode. Alarm conditions shall keep the pump out of service and shall only be reset through the control panel push-button switch. In power failure condition, control shall automatically operate pumps in primary or back up mode when power is restored without local or remote alarm reset.

8. If a period of 8 hours expires with no pump sequence rotation (one pump running and more than one pump available), the control shall stop the lead pump and rotate the sequence.

9. Provide remote start, stop, and alarm reset capabilities.

10. Low level alarm shall cut all pumps off.

11. The primary control system shall test and select the functioning transmitter to control pumps in the primary mode (PLC).

D. Secondary Pump Control

1. Accomplish via back up pump controller specified in section 13446. Pump controls and alternations shall be performed by back up pump control. PLC shall provide a discrete output to select PLC mode of operation, and an independent discrete output for watchdog relay. Upon detection of a failure via the watchdog relay or selecting backup control via PLC, pump control shall be switched from PLC mode to backup mode.

2. Automatic switchover from PLC to backup mode shall also be initiated under the following conditions: When both transmitters fail (under range, 4 milliamps or less), when PLC I/O fails (control status bit tests), or when high level alarm is activated when no pump is running.

3. Provide manual selector switch for PLC and backup mode.

4. Provide hardware timer for backup control system to stagger pump starts (add time cubes to pump start relays).

5. Allow 30 seconds for an automatic rollover to backup system for failure conditions to be true before a transfer takes place. System shall transfer to primary (PLC) when there is no fault and no pump running, or manual selector switch (toggle PLC/backup selector switch).

E. Primary Pump Control-Dry Weather wet weather 5, and 6 pump that are the same ratings

12. PLC shall monitor the primary level measurement system and control a PLC output to energize a relay to start / stop pumps at a preselected well levels as indicated on the Drawings.

13. The primary control system shall monitor a NO contact which closes when the pump is running and shall totalize pump running time.

14. PLC shall provide first-on first-off alternate sequencing of pump starts.

15. Provide a numerical sequencer to sequence available pumps (when

HAND-OFF-AUTO switches are set in AUTO position). When three pumps are available (switches are in AUTO), local pump controller (LPC) shall select Pump No. 1 as lead pump, Pump No. 2 as lag pump, and Pump No. 3 as lag 2 pump. For dry weather/wet weather designs(dual discharge), provide two separate sequencers to alternate dry weather pumps independently from wet weather pumps (one sequencer to alternate dry weather pumps and another to alternate wet weather pumps).

16. The contractors shall develop a single set point level control algorithm when a variable speed drive is used for controlling one or all the pumps. This algorithm will provide the starting, stopping, alternation and load sharing for all pumps.

17. Stagger start times by 10 seconds between pump lead/lag stages to prevent pumps starting at the same time. It responses to a pump signal to run command not confirmed within 20 seconds (through auxiliary feedback, motor amperage report or flow indication) shall remove that pump from service and the pump sequence, but transfer the command signal to the next available pump in the same sequence.

18. Phase failure, high temperature, and seal leak (primary mode only), alarms shall cause a pump to stop in either Primary or Back-up mode. Alarm conditions shall keep the pump out of service and shall only be reset through the control panel push-button switch. In power failure condition, control shall automatically operate pumps in primary or back up mode when power is restored without local or remote alarm reset.

19. If a period of 8 hours expires with no pump sequence rotation (one pump running and more than one pump available), the control shall stop the lead pump and rotate the sequence.

20. Provide remote start, stop, and alarm reset capabilities.

21. Low level alarm shall cut all pumps off.

22. The PLC shall test and select the functioning transmitter to control pumps in the primary mode (PLC).

F. Secondary Pump Control

6. Accomplish via back up pump controller specified in section 13446. Pump controls and alternations shall be performed by back up pump control. PLC shall provide a discrete output to select PLC mode of operation, and an independent discrete output for watchdog relay. Upon detection of a failure via the watchdog relay or selecting backup control via PLC, pump control shall be switched from PLC mode to backup mode.

7. Automatic switchover from PLC to backup mode shall also be initiated under the following conditions: When both transmitters fail (under range, 4 milliamps or less), when PLC I/O fails (control status bit tests), or when high level alarm is activated when no pump is running.

8. Provide manual selector switch for PLC and backup mode.

9. Provide hardware timer for backup control system to stagger pump starts (add time cubes to pump start relays).

10. Allow 30 seconds for an automatic rollover to backup system for failure conditions to be true before a transfer takes place. System shall transfer to primary (PLC) when there is no fault and no pump running, or manual selector switch (toggle PLC/backup selector switch).

G. Pump Status and Alarm Monitoring: PLC shall monitor NO contacts which close to indicate the following:

1. Pump status for each pump.

2. Auto status for each pump.

3. Alarm for each pump.

4. UPS alarm.

5. Station undervoltage/phase failure alarm.

6. Intrusion alarm (control building or control panel).

H. Pump Controls: PLC shall provide an NO contact which closes and provides 120VAC to drive the following discrete pump control outputs:

1. Watchdog relay.

2. PLC/backup control mode select.

3. Start/stop for each pump.

4. Reset for each pump.

5. High/low level alarms.

I. Pump Station Monitoring: Arrange PLC to monitor both wet well level transmitters to indicate pump station alarms or status.

J. Communications: PLC shall be capable of full two-way communications with the City of Houston Central Control facility. Communications shall have the capability to transmit all station and pump status and alarms, well levels, PLC status and additional information indicated in the Drawings, and shall receive pump start/stop Set points, alarm Set points and miscellaneous data via City of Houston SCADA software package and protocol. Provide necessary hardware and software required to implement the communications system as part of pump station control system work. Programming and modifications required at the City of Houston Central Control facility will be performed by the City of Houston. The project SE shall be responsible for coordinating and performing the communication testing.

K. Modem Watchdog: On systems with modems, provide watchdog timer in PLC to confirm regular communication polls from SCADA. If no communications is detected within 10 minutes, power down and restart the modem to reset. Power to modem shall be wired through an interposing relay connected to a PLC discrete output.

3.02 INSTALLATION

A. Install in accordance with manufacturer's instructions and Drawings. Provide sufficient clearance for calibration and maintenance access.

B. Do not install products until major construction is complete and building interior is enclosed and heated.

C. Connect input and output devices as shown on Drawings.

D. Provide complete programming, testing and verification of the programmable controller and associated inputs and outputs, including work required to interface with the existing City of Houston system.

3.03 MANUFACTURER'S FIELD SERVICES

A. Prepare and start systems under provisions of Section 01755 - Starting Systems.

3.04 DEMONSTRATION

A. Provide systems demonstration under provisions of Section 01770 - Closeout Procedures.

B. Demonstrate operation and programming of controller. Provide 2 sessions of 4 hours of instruction each for 4 persons, to be conducted at project site with manufacturer's representative.

C. System demonstration shall include the following:

1. Complete verification of field wiring.

2. Complete verification of system software.

3. Demonstration of functionality of each discrete input and output by simulation of actual field device action.

4. Demonstration of functionality of each analog input and output by actual variations in the process variable (e.g. well level, etc.).

5. Complete demonstration of each alarm by simulation of actual field device action.

6. Complete demonstration and verification (status/alarm points) of 2-way communication with City of Houston Central Monitoring Facility.

3.05 TRAINING (City of Houston projects only.)

A. Provide engineering and programming schools preferably at the Houston offices of the PLC manufacturer or distributor or at the manufacturer's factory, as specified below. This training shall be performed by fully-qualified and manufacturer-certified training personnel who can clearly illustrate experience in teaching previous courses. Obtain approval from the Owner's representative for training facility and course outline before scheduling training.

A. If such training is provided somewhere other than Houston, then the system supplier shall provide coach airfare (weekday travel), motel expenses ($95.00/day/person), rental cars ($50.00/day/2 people), and meal allowances $35.00/day/person) for selected City personnel for the duration of the schools.

B. Schedule classes at the City of Houston's convenience. The supplier should not assume that the City's personnel will attend these courses in a continuous and sequential manner. When training is submitted in voucher form, it shall be valid for a minimum of 2 years at no extra cost to the City.

D. Training shall consist of the following as a minimum:

1. PLC basic/advanced programming/maintenance (5 days): Two people for remote lift station.

2. PLC basic/advanced programming/maintenance (5 days): four people for WWTP on-site lift station.

END OF SECTION

1.01 Section 13441

1.02 SCADA SOFTWARE ENGINEERING
SECURITY AND QUALITY REQUIREMENTS

PART 2 GENERAL

2.01 PURPOSE:

A. The Wastewater Operations Automation and Electrical Support Service Group maintains this document for the communication of the requirements of the SCADA software used for the control and monitoring of the wastewater facilities. These requirements are intended to address three related areas: 1) SCADA Homeland Security Requirements, 2) Texas Engineering Practice Act, 3) COH Wastewater SCADA system quality requirements:

1. According to the National Strategy for Homeland Security wastewater treatment facilities are part of the nation's critical infrastructure and the government agencies that are responsible shall take specific steps to improve SCADA security.

    a. Government agencies are required to "Establish policies to minimize the likelihood that organizational personnel will inadvertently disclose sensitive information regarding SCADA system design, operations, or security controls" and "Release data related to the SCADA network only on a strict, need-to-know basis, and only to persons/entities explicitly authorized to receive such information".

    b. In compliance with these Homeland Security requirements all SCADA related information is restricted to authorized personnel.

2. In compliance with Texas Engineering Practice Act (Article 3271a) and the recognition that SCADA software is an integral part of the electrical control of the wastewater facilities and is therefore within the jurisdiction of the act:

    a. All SCADA software related work shall be performed by a licensed engineering firm meeting the qualifications as specified in these requirements and referred to within as the Software Engineer (SE). The software produced for the project shall be stamped by SE in accordance with (Article 3271a §137.33 Sealing Procedures for engineering software).

3. Additionally, these requirements are to refine and perpetuate software engineering and software quality standards that will benefit the Wastewater Operation Branch in the areas of facility operations, maintenance, and facility construction projects:

    a. The requirements are intended to benefit facility operations through encouraging SCADA standards of consistency in facility functionality and operation, improved process visibility, improved efficiency and control, lower operating costs and reduced potential permit violations. The SCADA standardization also addresses improved technical support and ease of maintenance.

    b. These requirements specify SCADA related issues in construction, deliverables and qualifications that will help ensure the availability and quality of SCADA system integration.

    c. SCADA related software integration activities have been identified as a key point of quality control for construction projects. The SE shall subcontract directly to the general contractor and shall perform an independent assessment of the SCADA related work of the other subcontractors and equipment suppliers to ensure complete system and software integration within the facility per the construction specification and wastewater SCADA design guidelines.

PART 3 SCOPE

3.01 The requirements defined in this document apply to wastewater facility SCADA software including system control, monitoring and integration. The scope includes new and existing facility construction projects where new SCADA software is required or where the existing SCADA software is modified.

A. SCADA software activities shall be performed only by the pre-approved SE and include: PLC programming, HMI configuration and graphics development, historical logging software application and report generation, network configuration and programming.

B. Manufactured packaged subsystems with pre-engineered software may be specifically excluded if specified in that subsystem equipment specification, that the system shall be shipped with the software as a fully functional unit. The system PLC and HMI hardware and software application shall meet the requirements for SCADA integration and software documentation. The packaged system provider shall deliver all software to SE as soon as possible for the purpose of review and integration.

C. These requirements apply to all SCADA security related activities including configuration of servers, workstations and network equipment.

PART 4 SOFTWARE ENGINEERING REQUIREMENTS

4.01 The SE shall perform the software engineering functions as required within the scope section meeting the requirements within.

A. The SE shall use the wastewater standards for SCADA software engineering and Homeland Security in all work performed.

1. The SE shall identify and communicate omissions and required modifications to these standards.

2. Details on these standards are restricted to authorized personnel only according to the Homeland Security requirements and are not included in these requirements. The pre-approved SE is authorized for access to these standards.

4.02 The SE shall provide the SCADA related submittals as defined in the submittals section.

A. The SE shall perform the work required to complete the required SCADA software submittals.

B. The SE shall review and report on the SCADA related submittals of the project subcontractors and equipment providers.

4.03 The SE shall assist the project team including; the engineer, the wastewater operations and equipment suppliers with the SCADA integration issues.

A. The SE shall attend project meetings as required by the project team.

B. The SE shall assist the project team with functional test of the system.

1. This may include providing project related process data from the SCADA system.

PART 5 SUBMITTALS

5.01 Within 30 days of the notice to proceed the SE shall submit a letter of SE qualifications specifically addressing each item of qualification as defined in these requirements.

A. Include the SE professional engineering firm licensed number and date of issuance.

B. Include a statement addressing the awareness of the Homeland Security concerns and intention to restrict the dissemination of security sensitive SCADA network information to those who are authorized by the COH and require the information in the support of this project.

5.02 Within 90 days of the notice to proceed the SE will submit the Software Engineering Manual (Preliminary Report).

A. Include the software conventions for the use in the HMI development.

B. Include diagrams and schedules for all network devices associated with the process control and monitoring for the facility/facilities.

C. Include the interfaces for the City SCADA network.

D. Identify every network component (new and existing).

E. The Software Engineering Manual will be updated for the final O&M.

5.03 The SE will submit letters of software and network integration compatibility to be included in all the control related submittals.

A. Included but not limited to: PLCs, network devices, computers, HMI devices.

B. Include deviations from City standards and the construction specifications for electrical control drawings and tag naming conventions.

C. Include deviations from the submitted Software Engineering Preliminary Report.

D. Include the manufacturer supplied package systems with control panels.

E. The SE shall distribute monthly a Software Engineering Integration Schedule highlighting software and system integration progress and issues.

5.04 Factory demonstration test confirmation report

A. After the required factory demonstration test the SE shall submit a report confirming the related software and network compatibility.

5.05 Field Acceptance Functional Test

A. Shall be completed prior to performance and reliability testing.

B. Field Acceptance Functional Test Submittals shall include:

1. Field Acceptance Functional Test Plan Submittal.

2. Description of plan for testing field devices.

3. Description of plan for function test and system integration of each subsystem.

4. Field Acceptance Functional Test Schedule shall be submitted after the acceptance of the test plan submittal.

5. Field Acceptance Functional Test plan completion report shall be submitted.

5.06 Updated Software Engineering Manual (Final Version)

A. Update and submit a singled CD with all related SCADA software.

B. Control and network components.

C. Inventory of software components.

D. Network device configuration documentation.

E. Software Engineering documentation.

F. PLC and HMI software shall be documented using the product development tool.

G. Software shall be stamped as required in Texas Engineering Practice Act (Article 3271a §137.33 Sealing Procedures) with the date, the engineers name, the PE designation with license number.

H. The SE will collect and submit all software and network device configuration programs and data developed for the project.

PART 6 SOFTWARE ENGINEER (SE) QUALIFICATIONS

6.01 The Wastewater Operations Automation and Electrical Support Services group has set forth these qualifications for performing all SCADA related software activities for the wastewater facilities as defined in these requirements.

6.02 The SE shall be pre-approved by Automation and Electrical Support Services section for Wastewater Operations no later than seven (7) days prior to the project bid opening date for construction projects.

6.03 Specific qualifications for pre-approved SE:

A. The SE shall be a Texas Registered Professional Engineering firm with a minimum of five (5) years of licensed history with the software engineering of the control systems for advanced wastewater treatment processes.

B. The SE shall be experienced with the software application development packages which are used as standards for Wastewater Operations including a minimum five (5) years of software engineering experience with Wonderware Archestra and G.E. IFIX HMI application development packages and Siemens PLCs.

C. The SE shall demonstrate a minimum of five (5) years of continuous Cisco Advanced Security expertise. This ensures the SE has the required expertise to configure, secure and maintain the SCADA system network for applicable projects (excluding stand-alone control system at the lift stations and small plants where only a single PLC is installed).

D. The SE shall have errors and omissions insurance with coverage in the amount of $1,000,000.00 (aggregate).

E. The SE shall have an existing office, within the City of Houston, and shall maintain that office for the duration of the warranty and extended software service requirement.

F. To ensure effectiveness and objectivity in the review and reporting of SCADA related integration issues, the SE shall be an independent entity and provide only software engineering services for the construction projects. Additional scope of automation and electrical services may be provided as required by the owner. The services may include, but not limited to network diagram development, efficiency and optimization program and application implementation, data dictionary design guideline development.

END OF SECTION

Section 13446

PRIMARY INSTRUMENTATION DEVICES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Telephone modems, pump controllers, submersible transmitters, level recorder, power meter, control power transformers, phase/voltage monitor relay, terminal blocks, surge protections, and accessories for use with lift station instrumentation.

1.02 REFERENCES AND STANDARDS

A. NEMA ICS 1 - General Standards for Industrial Controls and Systems.

B. NEMA ICS 2 - Standards for Industrial Control Devices, Controllers and Assemblies.

C. NEMA ICS 3 - Industrial Systems.

D. NEMA ICS 6 - Enclosures for Industrial Controls and Systems.

E. NFPA 70 - National Electrical Code (NEC).

F. Underwriters Laboratories, Inc. (UL).

G. ANSI B40.1 - Gauges, Pressure Indicating Dial Type Elastic Element.

1.03 SUBMITTALS

A. Comply with Section 01330 - Submittal Procedures.

B. Submit shop drawings indicating layout of completed assemblies, interconnecting cabling, dimensions, weights and external power requirements.

C. Submit product data for each component specified.

D. Submit manufacturer's certificate that all equipment meets or exceeds specified requirements. Submit manufacturer's installation instructions.

1.04 PROJECT RECORD DOCUMENTS

A. Submit record documents under provisions of Section 01770 - Closeout Procedures.

B. Accurately record actual locations of controller cabinets and input and output devices connected to system. Include interconnection piping, wiring and cabling information, and terminal block layouts in controller cabinets.

C. During drawing submittal phase, submit detailed programming information consisting of ladder logic and line code of proposed program, and complete input, output, relay, register and controller identification labels.

D. Submit factory testing procedures proposed to verify input, output, PID loop and register operations, system logic verification, and spare memory capacity.

1.05 OPERATION AND MAINTENANCE DATA

A. Submit operation in accordance with Section 01782 - Operations and Maintenance Data.

1.06 QUALIFICATIONS

A. Manufacturer: A company specializing in manufacturing the products specified in this Section having at least 3 years documented experience maintaining service facilities within 100 miles of project and having proven compatibility with existing City wastewater facilities. Like devices shall be of the same Manufacturer.

1.07 REGULATORY REQUIREMENTS

A. Conform to requirements of ANSI/NFPA 70 (NEC).

B. Furnish products listed and classified by Underwriters Laboratories, Inc., as suitable for the purpose specified and shown; install in accordance with UL requirements.

1.08 DELIVERY, STORAGE AND HANDLING

A. Deliver products in factory-sealed containers. Store, handle and protect products under provisions of Section 01610 - Basic Product Requirements.

B. Upon delivery, inspect products for damage.

C. Store products in clean, dry area; maintain temperature in compliance with NEMA ICS 1.

1.09 ENVIRONMENTAL REQUIREMENTS

A. Maintain temperature above 32 degrees F and below 104 degrees F during and after installation of products.

B. Maintain area free of dirt and dust during and after installation of products.

PART 2 PRODUCTS

2.01 TELEPHONE/ETHERNET MODEMS (City of Houston projects only)

A. Manufacturer and Model:

1. Spectrum Controls, Webport 2005, WP26204.

2. Cisco 891 series integrated services router.

3. Approved equal.

B. Integrated V.92 analog modem

1. Operating Modes: Dial-up Modem, 2-wire Half/Full Duplex Transmission Speed: 300 baud to 56 kbaud.

C. Integrated IP Router.

D. Integrated Ethernet switch with a minimum of 4 Ethernet Ports: RJ45, Shielded, 10/100 Mbps.

E. Minimum of 1 Telephone Port: RJ12, Shielded.

F. Power: 24 VDC (10.8-30VDC) or 120 VAC.

G. Mounting: Standard DIN Rail or desk top.

2.02 PUMP CONTROLLERS

A. Manufacturer:

1. DCC, Universal Pump Control (UPC) Model 11436-H for up to four pump control or approved equal.

B. Display: 0-30' LED bar graphs for level reading and level set point and four character display.

C. Alternation: Built-in first-on first-off sequence for up to four pumps.

D. Level simulation: Front-face mounted level simulation switch with spring return to normal.

E. Input signal: Two 4-20 mA signals.

F. Power: 24 VDC

G. Interface: 2 RS-232 serial ports that uses "Modbus" protocol for SCADA support.

H. Control: 4 variable or single speed pumps.

I. 5 to 6 Pumps operation: Includes standard variations listed A-H above.

a. Dual isolated inputs: Primary fail, Secondary resumes.

b. 5th pump turns on by channel 5 upper set point, off by channel no. 4 lower set point.

c. 6th pump turns on by channel 5 lower set point, off by channel no. 4 lower set point.

J. 7 Pumps operation: Includes standard variations listed A-H above.

a. (2) 11346-H controllers required.

b. Single 4-20ma input

c. First unit has isolated 4-20ma module in 4th location

d. for level in 2nd unit, staggered channel set points.

K. 8 Pumps operation: Includes standard variations listed A-H above.

a. (2) 11346-H controllers required

b. Each has an external 4-20ma input signal

c. Staggered set points for pump on/off

L. For 5-8 Pumps operation: Contact DCC Manufacture at 800-335-5219

2.03 SUBMERSIBLE PRESSURE TRANSMITTERS

A. Manufacturer:

1. Endress and Hauser: Model FMX167-A2B FE1C7.

2. Blue Ribbon: Model Birdcage 01 (15, 30 psi)

3. AMETEK: Model 575P

4. Dwyer: PBLT2 series

B. Description: Solid-state two-wire submersible electronic differential pressure transmitter with 4-20 mA output proportional to input pressure.

C. Range: 0-30 feet range, or as required by wet well depth, with +/- 0.3 % accuracy and 0.5% max temperature across calibrated span.

D. Power: Loop-powered, 24 VDC

E. Spare Unit: Provide a spare unit in addition to the unit installed.

F. Transmitters to be calibrated to match the chart recorder range.

G. Warranty: 18 months minimum from the time acceptance by City.

2.04 LEVEL RECORDER

A. Manufacturer: Foxboro Model 740R (740RA-A3300) or approved equal.

B. Description: Digital circular, 7-day-pen recorder, 2-pin 4-20 mA signals, display indicator, one-year supply of 0-30 foot range or sized to match wet well depth.

C. Display: Brilliant 2-line 20-characters per line.

D. Input: Two 4-20 mA signals.

E. Accuracy: Display (+/- 0.1% of input span), recording (+/- .25% of input span), supply voltage (less than 0.025% of span within +/- 10% of reference operating supply voltage).

2.05 POWER MONITOR: (City of Houston plant on-site lift station only or as need for large capacity site.)

A. Manufacturer: Siemens Energy & Automation PAC4200, or approved equal.

B. Measurements: Voltage (L-L, L-N, 3-ph Avg), Current (Per Phase, 3-ph Avg), Apparent Power, Active Power, Power Factor, Frequency, 6 Limit Values.

C. Harmonics Monitoring: 3rd to 31st

D. Load Curve Recording: 40 days with 15-minute measuring period, Fixed block or rolling block

E. Event Recording: At least 4000 events with priority control and selectable warning levels

F. Clock: Real-time clock with calendar

G. Display: Backlit LCD.

H. Configuration: Via front panel or with Sentron PowerConfig Software supplied with unit

I. Communications: Profibus-DP to PLC via Expansion Module.

J. Digital Inputs and Outputs: One multifunctional input, One multifunctional output.

K. Certifications: cULus, CE, C-Tick, GOST.

L. Temperature Ratings: -10 to 55 deg. C operating.

M. Power: 95 to 240 VAC

2.06 CONTROL POWER TRANSFORMERS

A. Transformer: NEMA ST 1 machine tool transformer with isolated secondary winding.

B. Power Rating: 250 VA or 200 percent power requirement, whichever is greater.

C. Voltage Rating: 480/240 volt primary, 120 volt secondary, single phase.

2.07 PHASE/VOLTAGE MONITOR RELAY

A. Manufacturer, Product: Diversified Electronics Inc.; Model PBD Series or approved equal.

B. Description: All three phases monitored individually for preselected under and over voltage limit phase loss, phase unbalance, phase reversal, frequency shift and phase shift. Automatic reset after adjustable release delay when line conditions return to normal.

C. Indicators: LED indicators for under and over voltage limit.

D. Output Rating: DPDT, 3 amps resistive at 600 VAC.

E. Phase Sequence: ABC.

F. Sampling Time: 2 seconds.

G. Spare Unit: In addition to the unit installed, furnish one spare phase/voltage monitor relay.

2.08 TERMINAL BLOCKS

A. Manufacturers

1. Bussmann.
2. Phoenix Contact.
3. General Electric Company.
4. Weidmuller.
5. Allen Bradley.

B. Substitutions: Comply with Section 01630 - Product Substitution Procedures.

C. Terminal Blocks: Provide isolated fused snap-on type terminal blocks.

D. Power Terminals: Unit construction type with closed back and tubular pressure screw connectors, rated 600 volts.

E. Signal and Control Terminals: Modular construction type suitable for channel mounting with tubular pressure screw connectors; 300 volt rating.

F. Provide color-coded (green/yellow) ground bus terminal block, with each connector bonded to enclosure.

2.09 CONTROL SWITCHES AND INDICATOR LIGHTS

A. Manufacturers

1. Automatic Timing and Controls Company.
2. Eaton Corporation.
3. Eagle Signal Company.
4. General Electric Company.
5. Schneider Electric
6. Allen Bradley.

7. Siemens

B. Substitutions: Comply with Section 01630 - Product Substitution Procedures.

C. Control Switches

1. Contacts: NEMA ICS 2; at least two Form C contact sets.

2. Contact Ratings: NEMA ICS 2; 120V, 10 ampere inductive.

3. Selector Switch Operators: NEMA ICS 2; heavy-duty, oil-tight, NEMA 4 multi-position rotary selector switch.

4. Push-button Operator: NEMA ICS 2; heavy-duty oil-tight NEMA 4 unguarded and lockable type; black for start, red for stop.

D. Indicator Lights: Red for run, amber or yellow for alarm, green for control mode; LED, oil-tight, 100,000-hour rated life expectancy; rated voltage approximately 125 percent of nominal 120 VAC operating voltage. To be push-to-test type.

2.10 CONTROL RELAYS

A. Contacts: Three Form C contact sets (3PDT).

B. Rating: 120 volt, 10 ampere inductive.

C. Coil Voltage: 120 volt, 60 Hz AC.

D. Socket: DIN Rail, Include hold-down clip.

E. Features: 11-pin tube socket relay base, external color-coded test button, mechanical and electrical status indications, impact-resistant thermoplastic case.

F. Manufacturer: Turck, Siemens, or equal approved by end user.

G. Spare Units: In addition to units installed, furnish 2 spare units.

2.11 TIME DELAY RELAYS

A. Contacts: Three Form C contact sets (3PDT).

B. Contact Ratings: DPDT Class; 120 volt 10 ampere inductive.

C. Coil Voltage: 120 volt 60 Hz AC.

D. Socket: Turck S3B with coding system, label and label holder (11-pin).

E. Description: Control relay as specified above in Paragraph 2.04, with added Time Cube Module as manufactured by Turck, Inc.; series CT3, with on or off delay, as indicated.

F. Features: DIP switch-selectable timing ranges of 0.2 to 3 seconds, 0.8 to 12 seconds, 0.1 to 1.5 minutes and 0.8 to 12 minutes; externally-adjustable graduated time dial; solid-state digital timing system.

G. Spare Units: In addition to units installed, furnish 2 spare units.

2.12 ACCESSORIES

A. Plastic Raceway: Plastic slotted wireway with snap-on locking covers.

B. Manufacturer

6. Anixter Bros., Inc.

7. Delaware Industries, Inc.

8. Panduit Corp.

9. Iboco

PART 3 EXECUTION

3.01 INSTALLATION

A. Furnish complete enclosure, factory tested and ready for installation and field termination.

B. Terminate wiring with spade lugs at terminal strips corresponding to designations on Drawings.

C. When not installed in plastic wireways, such as along back of door, neatly bundle and support air tubing and internal panel wiring with self-adhesive nylon clips. Provide adequate slack for proper door operation without damage to wiring or tubing.

D. Identification: Identify system components in accordance with Section 16195 - Wiring and Conduit Identification.

1. Identify conductors and termination points (device and relay terminals).

2. Identify transmitters, switches and devices with stainless steel tags.

3. Provide nameplates for panel-mounted devices and instruments as shown on drawings.

3.02 SYSTEM TESTING

A. Perform system testing as required by individual component Sections. Calibrate and adjust components for proper operation. Submit 6 copies of Manufacturer's Installation Inspection, Field Calibration and Field Testing Reports. Replace components found to be defective.

END OF SECTION

Section 13471

CONTROL CABINET ENCLOSURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Indoor and outdoor control cabinets for Lift Station instrumentation.

1.02 REFERENCES

A. NEMA 250 - Enclosures for Electrical Equipment (1000 Volts Maximum).

B. ANSI/NFPA 70 - National Electrical Code (NEC).

C. Underwriters Laboratories, Inc. (UL).

D. Factory Mutual (FM).

E. Occupational Safety and Health Administration (OSHA).

F. American National Standards Institute (ANSI).

1.03 SUBMITTALS

A. Conform to Section 01330 - Submittal Procedures.

B. Product Data: Provide manufacturer's product literature and specifications.

C. Manufacturer's Instructions: Indicate application conditions and limitations of use stipulated by product testing agency specified under Paragraph 1.04, Regulatory Requirements. Include instructions for storage, handling, protection, examination, preparation, installation, and starting of product.

1.04 REGULATORY REQUIREMENTS

A. Conform to requirements of ANSI/NFPA 70 (NEC).

B. Furnish products listed and classified by Underwriters Laboratories, Inc., as suitable for purpose specified and shown; install in accordance with UL requirements

1.05 EXTRA MATERIALS

A. Provide two keys for each cabinet; key locks as directed by City Engineer to operate in current City of Houston master keying system.

B. Insert half-size blackline prints on rite in the rain all weather writing paper model 8511 of the complete wiring diagrams, schematics, and loop diagrams applicable to each control panel in a clear plastic envelope and store in a suitable print pocket or holder inside each control panel.

PART 2 P R O D U C T S

2.01 MANUFACTURERS

A. Acceptable Manufacturers

1. Rittal, Corporation
2. Hoffman Engineering.
3. Hammond Manufacturing
4. The EMF Company.
5. Rose Enclosure.
6. Weigman Company.
7. N.E.M.A. Enclosure Mfg. Co.

B. Substitutions: Comply with Section 01630 - Product Substitutions and Procedures.

2.02 INDOOR CONTROL CABINETS (City of Houston Projects only)

A. Enclosure: NEMA 250, Type 12; if requested by City Engineer, obtain Underwriters Laboratory, Inc. approval after completion.

B. Enclosure Size: As indicated on Drawings; or, if not indicated, at least 72 inches high by 20 inches deep by 48 inches wide, or larger, as required to mount equipment indicated to U.L. Standards.

C. Backboard for mounting terminal blocks and components: 12 gauge steel, finished in white enamel.

D. Fronts: Steel pan-type doors with concealed stainless steel hinges, held closed by stainless steel 3-point latch operable by pistol-grip handle.

E. Provide solid metal barriers to separate compartments containing control wiring operating at less than 50 volts from power wiring.

F. Clean surfaces to remove dirt and corrosion residue. Phosphatize for corrosion protection. Prime with two coats, and finish with one coat, of factory-applied textured polyurethane, minimum 5 mils thickness, color as selected by City Engineer from manufacturer's standard colors.

G. Panel Construction: Provide panel stiffeners and bracing. Fully gasket doors. Weld seams and grind smooth.

H. Conduit Entrances: Bottom entry unless otherwise indicated on Drawings.

I. Material: Minimum 12 gauge steel.

J. Finish: Enamel; gray outside, white inside.

K. Provide convenience outlets and internal fluorescent lighting, as shown on Drawings.

L. Nameplates: On the outside of each cabinet's inner door, provide motor data nameplate information for each pump motor; copy all information exactly as shown on each motor nameplate. Provide engraved laminated plastic nameplates; black letters with white background; fasten to outside of cabinet door of each motor starter section with stainless steel screws. Provide nameplates for all devices within panel.

M. Install wiring in open-slot plastic wiring duct.

N. On indoor panels install a 4-inch passive vent in the side near the top and near the bottom of an adjacent side panel. These vents shall have removable filters to resist dust and insect entry.

2.03 OUTDOOR CONTROL CABINETS

A. Enclosures: NEMA 3 type 5052-H32 aluminum with 0.125 inch thickness 5052-H32 aluminum back panel for mounting components. If requested by City Engineer, obtain inspection and approval by Underwriters Laboratory, Inc., after installation of control system in cabinet.

B. Enclosure Size: As indicated on Drawings, or if not indicated, at least 72 inches high by 48 inches wide by 36 inches deep, or larger, as required to accommodate equipment and as indicated in UL standards.

C. Material: Exterior and interior enclosure doors, shelves and component enclosures: Fabricate of 14 gauge type 316 stainless steel or 0.125 inch thick type 5052-H32 aluminum.

D. Doors: Stainless steel pan-type construction, with full-length stainless steel piano hinge (for stainless steel or aluminum). Equip exterior door with padlock, heavy-duty locking pistol-grip handles and 3-point latching mechanism of the draw roller type (0.750 inch minimum diameter rollers). Handles shall be 3/4 inch minimum diameter stainless steel. Equip interior doors with flush quarter-turn closure devices. Equip interior and exterior doors with neoprene gaskets.

E. Provide rain shield with 1 inch drip lip for outdoor cabinets to protect against direct sun radiation and rainfall. Design shield to provide 3-1/2 feet of cover front and back and 6 inches of cover on the sides. Design shield shall have a 1-inch open panel door clearance. Shielding material: Type 316 stainless steel or type 5052-H32 aluminum.

F. Nameplates: On the outside of each cabinet's inner door, provide motor data nameplate information for each pump motor; copy all information exactly as shown on each motor nameplate. Provide engraved laminated plastic nameplates; black letters with white background; fasten to outside of cabinet door of each motor starter section with stainless steel screws. Provide nameplates for all devices within panel.

G. In each cabinet section, provide a 120V convenience outlet and a switched 40 watt minimum fluorescent light fixture, with 0 degrees F ballast in each section.

H. Inside and outside of cabinet shall be smooth and free from burrs.

I. If aluminum cabinet, hinges shall be .090 inch thick minimum, aluminum, and shall have .250 inch diameter stainless steel hinge pin. Hinge leaves shall not be exposed externally when door is closed.

J. NEMA 4X enclosures shall have all bolt holes gasketed.

K. A divider of same material and thickness as the cabinet shall be added to divide electrical components and wiring from instrumentation and pneumatic components and wiring.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that surface and job conditions are ready for construction; report unsatisfactory conditions to the City Engineer. Do not proceed with work until unsatisfactory conditions have been corrected.

3.02 INSTALLATION

A. Transport, handle and install products in accordance with manufacturer's instructions.

B. Install on prepared pads. Anchor securely at each corner. Shim and grout as required to form a watertight seal.

C. Install cabinet fronts plumb.

D. Field-cut bottom conduit entrance openings for outdoor cabinets. Seal removable plates with silicone sealant.

E. Install ground rod and equipment ground conductor.

F. Install separate instrument ground lug and ground conductor; connect to common station ground grid.

G. Mount devices to allow removal and reinstallation without backboard removal. Use stainless steel mounting hardware.

H. Except for nameplate fasteners, mounting or other hardware shall not penetrate panel exterior.

I. Exterior panels: Mount with stainless steel anchor bolts and ground to the station ground field. Install and test ground field to provide maximum 5 ohm resistance to ground in accordance with Section 16170 - Grounding and Bonding.

J. Provide door restraints for outer and inner doors to positive lock and hold doors open at 115 degrees minimum.

K. Label all wires with heat shrink markers per Section 16195.

END OF SECTION

Section 15050

BASIC MECHANICAL MATERIALS AND METHODS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Basic mechanical requirements specifically applicable to Division 15 Sections, in addition to Division 1 - General Requirements.

1.02 REFERENCES

A. ANSI: American National Standards Institute.

B. ARI: American Refrigeration Institute.

C. ASHRAE: American Society of Heating Refrigeration and Air Conditioning Engineers.

D. ASME: American Society for Mechanical Engineers.

E. ASTM: American Society for Testing and Materials.

F. AWWA: American Water Works Association.

G. MSS: Manufacturer's Standardization Society of the Valve and Fitting Industry.

H. NEMA: National Electrical Manufacturers' Association.

I. NFPA: National Fire Protection Association.

J. SMACNA: Sheet Metal and Air Conditioning Contractors' National Association.

K. UL: Underwriters' Laboratories, Inc.

1.03 SUBMITTALS

A. Submit under provisions of Section 01330 - Submittal Procedures.

B. Submittals as specified in individual sections.

C. Submit shop drawings and product data grouped to include complete submittals of related systems, products, and accessories in a single submittal.

D. Mark dimensions and values in units to match those specified.

1.04 REGULATORY REQUIREMENTS

A. Conform to applicable City of Houston Building Code for the Pump Station Control Building.

B. Fire Protection: Conform to National Fire Prevention Association Code.

C. Plumbing: Conform to National Plumbing Code.

D. Obtain permits, and request inspections from authority having jurisdiction on of this Project.

1.05 PROJECT/SITE CONDITIONS

A. Install Work in locations shown on Drawings, unless prevented by Project conditions.

B. Prepare drawings showing proposed rearrangement of Work to meet Project conditions, including changes to Work specified in other Sections. Obtain permission of City Engineer before proceeding.

1.06 SEQUENCING AND SCHEDULING

A. Construct Work in sequence under provisions of Section 01325 - Construction Schedule.

PART 2 P R O D U C T S - Not Used

PART 3 E X E C U T I O N - Not Used

END OF SECTION

Section 15053

PUMP STATION PIPING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Piping for pump station wet well and valve vault, as shown on the Drawings.

1.02 REFERENCES

A. ANSI A21.10, AWWA C110 - Ductile Iron Fittings 3 in. through 48 in., for water and other liquid.

B. ANSI B36 - Stainless Steel Pipe.

C. AWWA C151 - Ductile Iron Pipe, centrifugally cast in metal molds or sand-lined molds for water or other liquids.

D. ANSI A21.15, AWWA C115 - Flanged Ductile Iron Pipe with Threaded Flanges.

E. ANSI B16.1 Ductile Iron Pipe Flanges and Flanged Fittings.

F. AWWA C111, ANSI A21.11 - Rubber Gasket Joints.

G. AWWA C600 - Hydrostatic Testing.

H. AWWA C606 - Grooved and Shouldered Joints.

I. ANSI B1.1 Screw Threads.

J. ASTM A193 - Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service.

K. ASTM A194 - Carbon and Alloy-Steel Nuts for Bolts for High-Pressure and High-Temperature Service.

1.03 SUBMITTALS

A. Submit shop drawings and product data under provisions of Sections 01330 – Submittal Procedures and Section 15050 - Basic Mechanical Materials and Methods.

B. Submit detailed drawings on pipe, joints, gaskets, fittings, flange coupling adapters, and appurtenances.

C. Submit shop drawings indicating dimensions, layout of piping, elevations, intersections, connections, support system, etc.

D. Submit manufacturer's Certification of Compliance with ANSI, AWWA and other Standards listed herein.

E. Submit description of proposed testing methods, procedures and apparatus and test reports for each system.

1.04 QUALITY ASSURANCE

A. Manufacturer's Qualifications

1. Piping and appurtenances provided under this Section shall be the standard product in regular production by manufacturers whose products have proven reliable in similar service for at least 5 years.

2. Insofar as possible all piping and appurtenances of the same specific type shall be the product of one 1 manufacturer.

1.05 DELIVERY, STORAGE AND HANDLING

A. Have products delivered, stored and protected under provisions of Section 01610 – Basic Product Requirements.

PARTS 2 P R O D U C T S

2.01 MATERIALS

A. Ductile Iron Pipe: AWWA C151, Class 53 minimum.

1. Fittings: AWWA C110

2. Joints: AWWA C115, with threaded flanges and rubber gaskets.

3. Bolts, studs and nuts: ASTM A-316 stainless steel.

4. Flanges: Same material as pipe and screwed onto the pipe in accordance with ANSI B16.1. Use screwed-on flanges attached to the pipe by the pipe manufacturer or pipe manufacturer's authorized fabricator.

5. After flange attachment, have flange and pipe re-faced so that the end of the pipe is even with the face of the flange and both are perpendicular to the axis of the pipe.

6. All flanged joints shall be hydrostatically tested after fabrication to a pressure rating of 300 psi minimum. All flanged joints shall be marked (Tested at 300 psi) and notarized certification papers supplied to the purchaser.

7. Align bolt holes on both flanges at the end of each piece of pipe.

8. Where cap screws or stud bolts are required, incorporate tapped holes for such cap screws or stud bolts in the flanges.

9. Interior Lining: Use one of the following interior lining systems.

   a. Nominal 40 mils (35 mils minimum) virgin polyethylene complying with ASTM D1248, heat fused to interior of pipe.

   b. Nominal 40 mils (35 mils minimum) polyurethane, such as Corro-pipe II by Madison Chemicals, or Polythane by U.S. Pipe.

   c. Approved equal.

10. Exterior Coating: Coat pipe in accordance with Section 09901 - Protective Coatings.

11. Performance: Use pipes and fittings designed for an internal working pressure range of -10 to +150 psi.

B. Wall Pipes: Ductile iron flanged with water stop collar.

1. Ductile iron water stop collar to be welded on the wall pipe prior to installation of the interior lining.

2. Interior Lining: As specified for pipe in paragraph 2.01A.9.

3. Bolts, studs and nuts: Type 316 stainless steel.

C. Flanged Coupling Adapter:

1. Type: Ductile iron; Romac Industries, Style FCA501, Dresser Style 128, or approved equal.

2. Interior Lining: As specified for pipe in paragraph 2.01A.9, or heat-fused epoxy coating complying with AWWA C213.

3. Bolts, studs and nuts: Type 316 stainless steel

D. Grooved Couplings: Grooved couplings conforming to AWWA C606 may be used for exposed piping outside of the wet well.

1. Manufacturers: Gustin-Bacon, Victualic Style 31 (flexible or rigid).

2. Bolts and Nuts: Type 316 Stainless Steel.

3. Gaskets: Flush seal type, compatible with the fluid, according to the manufacturer's recommendations.

4. Pipe Wall Thickness: Wall thickness of grooved piping shall conform to the coupling manufacturer's recommendations to suit the highest expected pressure.

5. Equipment Connections: Equipment connections shall be rigid-type grooved couplings unless thrust restraint is provided by other means.

6. Require the manufacturer to verify correct choice and installation of couplings, gaskets, and workmanship to assure correct installation.

E. Air Release Piping: Schedule 40, ANSI B36 stainless steel with ANSI B1.20.1 threaded joints.

PART 3 EXECUTION

3.01 INSTALLATION

A. Check dimensions shown on the Drawings prior to installation of Work. Notify the City Engineer promptly of any conflicts or errors.

B. Run pipe lines straight and true in alignment, grade and location as shown on the Drawings.

C. Install piping through walls and floors as shown on the Drawings.

3.02 PIPE IDENTIFICATION LABELS

A. Label piping as follows:

1. Identify all piping with plastic sleeve snap-on markers equivalent to Seton Name Plate "Setmark" or approved equal with 3/4-inch letters on pipe sizes to 4-inch and 2-inch letters on pipe sizes 5-inches and larger, or approved equal.

2. Locate at each valve, each branch take-off, and at each side of floor or wall through which pipe passes.

3. Not more than one label is required every 12 feet if adjacent label is visible.

4. Place labels on all lines.

3.03 TESTING

A. Flush pipes clean. Tighten connections to stop any visible leaks.

B. Test piping in accordance with Section 4-Hydrostatic Testing, AWWA C600.

C. Test piping to a pressure of 150 percent of the maximum possible discharge pressure of the pumps.

3.04 PAINTING

A. Paint pipe in accordance with Section 09901 - Protective Coatings.

END OF SECTION

Section 15126

VALVES FOR SEWAGE SERVICE

PART 1. GENERAL

1.01. DESCRIPTION

A. Scope: This section provides requirements for furnishing and installing valves for sewage service. Plans show location, end connections, and special requirements.

B. QUALITY ASSURANCE

1. Factory Tests: Test all valves hydrostatically to manufacturer's published standard.

2. Marking: Cast size and working pressure on bodies.

3. Submittals: Submit the following in accordance with Contract Documents.
   a. Shop Drawings: For valves 6-inches and larger, or for valves with special accessories. Show materials and construction details.
   b. Operation and maintenance data.

4. Products Protection: Ship with flange protectors on flanges.

1.02 MEASUREMENT AND PAYMENT

A. Unit Prices

1. No separate payment will be made for work performed under this section. Include cost of such work in contract unit prices for work of which it is a component part.

2. Refer to Section 01270 – Measurement and Payment for Unit Price procedures.

B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment of work in this Section is included in total Stipulated Price.

PART 2. PRODUCTS

A. Plug Valves

1. General
   a. Non-Lubricated
   b. Minimum Pressure Rating - 50 psig
   c. Manufacturer - Dezurik or Pratt.

2. Construction

   a. Bodies: ASTM A126-91, Class "B" cast iron per AWWA C507-91, Section 3.2 and C504-87, Section 3.1. Zinc plate all exposed nuts, bolts, etc., except for buried service. Furnish stainless steel bolting for buried service. Cast working pressure and valve size on body.
   b. Plug: ASTM A126-91, Class "B" cast iron with resilient plug facings of neoprene.
   c. Seats: Raised, corrosion-resistant alloy per AWWA C507-91, Section 3.5, and AWWA C504-87, Section 3.2.3.
   d. Shaft Bearings: Replaceable, stainless steel, sleeve-type in upper and lower journals per AWWA C507-91, Section 3.2.4, and AWWA C504-87, Section 3.6.
   e. Shaft Seals: Per AWWA C507-91, Section 3.2.6, and C504-87, Section 3.7.
   f. Valve Hardware
      1) Above Ground Service: Zinc plate nuts, bolts, springs, and washers.
      2) Submerged/Buried Service: Stainless steel nuts, bolts, springs, and washers.
   g. Coating: Exterior of valve to be shop primed with a coating compatible with finish coat for application shown in Section 09901 - Protective Coatings.

   h. Operators

      1) Exposed Service

         Manual operators to be lever or worm gear equipped with extension stems (if necessary), with the lever wrench, hand wheel, and/or floor stands as shown on Plans. Valves 8-inches and larger to be gear operated with adjustable open position stop.

Gear to be enclosed in ASTM A126 cast iron housing and running in lubricant. Provide seals on all shafts. Support operator shaft and quadrant on permanently lubricated bearings.

2) Buried Service

Valves with operators for submerged/buried service to be water proof. Units to have gaskets on valve and operator covers and water tight seals on shafts. Valves to be gear operated with totally enclosed gear with adjustable open position stop. Unit to be equipped with valve box, extension rod pinned to valve operator, couplings, and operating nut extended to within 6-inches of top of valve box.

B. Check Valves

1. Full Body, Swing Check Valve
   a. General
      1) Valves to be drip tight in closed position.
      2) Minimum pressure rating - 150 psi.
      3) Valves to be closing with side mount lever and weight.
      4) Manufacturer: APCO Series 6100 or Pratt or approved equal.

   b. Construction
      1) Body: Cast Iron, Bronze Mounted, ASTM A126, GR.B.
      2) Disc: Cast Iron, ASTM A126, GR B with disc ring.
      3) Body Seat: Stainless Steel, Series 316 SS or CF8M.
      4) Seat Retainer Ring: Series 316 SS or CF8M .
      5) Exposed Bolting : Series 304 SS.
      6) Flanges: ANSI Class 125 flat faced.
      7) Shaft: One Piece, Heat treated 17-4 PH Stainless steel, extending through both sides of valve body to relieve internal axial forces.
      8) Coating: Exterior of valve to be shop primed with a coating compatible with finish coat for application shown in Section 09901 - Protective Coatings.
      9) Valves 2" – 8" to have single lever, weight, and air cushion. 10" and larger to have double lever, weight and Oil Cushion.
      10) Valves 6" and larger to have 3 stage closing by means of a timing valve.

11) Cylinder mounting to have pivot action top and bottom with a double clevis connection.

12) Cylinders to be totally enclosed. Rubber boots are not considered totally enclosed.

2. Wafer Body, Swing Check (To be supplied only when called specifically on Plans)

a. General
1) Valves to be drip tight in closed position.
2) Minimum pressure rating - 150 psig.
3) Manufacturer: Valve and Primer.

b. Construction
1) Valve Bodies: Cast iron. Plain faced, wafer design, threaded lug-type, to fit between ANSI Class 125 flanges.
2) Hinge and Pin: AISI Type 316 stainless steel.
3) Seat: AISI Type 316 stainless steel.
4) External Spring: Adjustable
5) Disc: AISI Type 316 stainless steel.
6) "O" Rings: Buna "N".
7) Shaft: AISI Type 316 stainless steel.
8) Coating: Exterior of valve to be shop primed with a coating compatible with finish coat for application shown in Section 09901 – Protective Coatings.

C. Knife Gate Valves

1. General
a. Valves to be bonnet less knife gate type and wafer face-to-face flanged connections, round port, and resilient seat.
b. Valves to have drip tight shutoff.
c. Valves 24-inch and smaller to be rated for 150 psig. Larger valves to be rated at 125 psig.
d. Manufacturer: Valves meeting these specifications shall be furnished by: Dezurik Series L, Figure 825, Red Valve Series G.

2. Materials and Construction
a. Body: AISI Type 304 stainless steel or cast iron with AISI Type 304 stainless steel lining.
b. Stem, Gate, Gate Guides, Gate Jams, and Seat Ring: AISI Type 304 stainless steel.

c. Yoke Sleeve: Acid-resistant bronze.
d. Flanges: Drilled and tapped to ANSI 125/150-pound standard.
e. Seat: Neoprene, replaceable.
f. Coating: Exterior of valve to be shop primed with a coating compatible with finish coat for application shown in Section 09901 - Protective Coatings.
g. Operators:
   1) 2 to 20-Inches: Hand wheel operator.
   2) 24-Inches and Larger: Bevel Gear Operator with weather-proof enclosure and grease-packed gear case and packing boxes.

3. Design Features
   a. Include supporting ribs between flanges.
   b. Valves to 24-inch size to have raised face seat with relieved area around seat to prevent jamming.
   c. Gate to have knife edge and both sides finished ground.

PART 3. EXECUTION

A. Installation

1. Install valves and specialties in accordance with manufacturer's written instructions to permit intended performance.

2. Eccentric plug valves shall be installed according to the following:
   a. Position the valves with the stem in the horizontal direction.
   b. In horizontal pipelines, position the valves so that the plug swings upward when opening to permit flushing of solids.
   c. Orient the valves to prevent the valve bodies from filling up with solids when closed; however, orient the valves such that the pressure differential forces the plug against the seat in cases where the pressure differential across a closed valve will exceed 25 psi.

END OF SECTION

Section 16010

BASIC ELECTRICAL REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Basic requirements specifically applicable to the work of Division 16 - Electrical Requirements.

B. The Contractor shall furnish equipment, materials, and labor for assembly and installation plus check-out and start-up of the complete electrical system as shown on the Drawings and stipulated in the Specifications.

1.02 REFERENCES

A. As a minimum requirement, the electrical system shall be constructed in accordance with:

1. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), No. 70 - National Electrical Code (NEC).At the time of this publication all electrical work / installations are based on the 2014 addition of the NEC. However the contractor shall provide all electrical work / installations based on the current addition of the NEC adopted by the City of Houston.

2. City of Houston Building Code.

3. Other applicable Codes and Standards as referenced in other Master Specifications.

B. Comply with local, county, state and federal regulations and codes in effect as of date of purchase.

C. Equipment of foreign manufacture must meet U.S. codes and standards.

D. Equipment and materials shall conform to requirements of specification and to the criteria provided in data sheets for the project.

1.03 QUALITY ASSURANCE

A. Product Conformance Certificate and Quality Assurance Release. Submit an overall conformance certificate for electrical components signed by the person responsible for product quality. Specifically identify the purchased material or equipment by project name and

location, purchase order number, supplements, and item number where applicable, including materials and services provided by others. Indicate that all requirements have been met and identify any approved deviations.

B. Field Inspection

1. Electrical work shall be inspected and approved by the local code inspectors, the wastewater inspectors, and the Project Manager prior to starting the 7-day test or scheduling training.

2. Contractor shall give a minimum of two days notice to the Inspectors that the installation is ready for inspection and two days notice to the Project Manager.

3. Concealed work shall be inspected and approved by code inspectors and wastewater inspectors before it is covered:

   a. Conduit with stub-ups, underground in duct banks before concrete is poured.

   b. Conduit in slabs, walls and ceilings, complete with boxes.

4. Electrical equipment and materials shall be inspected upon arrival by the Project Manager for compliance with specifications.

1.04 SITE CONDITIONS

A. Take the following site conditions into consideration when fabricating, erecting, installing and wiring electrical equipment under this contract:

1. Plant Location Houston, Texas

2. Plant Type and Size

3. Plant Site Elevation

4. Seismic Zone Zone 0

5. Wind Velocity 90 mph

6. Temperature, Min./Max.:

- Coldest Winter Month High 60 degrees F Low 41 degrees F
- Warmest Summer Month High 94 degrees F Low 73 degrees F

- Lowest Expected 11 degrees F
- Highest Expected 107 degrees F

7. Rainfall:

   - Annual 45 inches
   - Design 3.4 inches/hour, 8.4 inches/24 hours

8. Design Relative Humidity: 98%
9. Station Barometric Pressure:

   - Average Annual 29.5 inches Hg Absolute.

10. Utility Water Systems: Design Pressure Design Temp.

    - River Water _____PSI_____ _____degrees F
    - Well Water _____PSI_____ _____degrees F
    - City Water _____PSI_____ _____degrees F

11. Electric Power Supply Characteristics (Available to Contractor):

	Voltage	Phase	Hz	Wire	Delta or Wye
1					
2					
3					

PART 2 PRODUCTS

2.01 COMPONENT DESIGN

A. Components utilized in the construction of the material or equipment shall be of the latest proven design, new and in current production. Do not use obsolete components or components to be phased out of production.

2.02 FACTORY INSPECTION

A. Provide free access with prior notice for the Project Manager at all times to the shop where the material or equipment is being fabricated or tested. Provide reasonable facilities for inspection, witnessing tests, and examining

records. Give 7-days notice prior to starting tests which are scheduled for factory inspection.

PART 3 E X E C U T I O N

3.01 PREPARATION

A. Verify dimensions and ratings of equipment and materials to ensure proper fit and performance.

3.02 INSTALLATION

A. Install equipment and materials in accordance with the Drawings and manufacturer's written instructions. If field conditions necessitate changes in electrical installation, obtain approval from the City Engineer.

B. Conductor voltage drop shall not exceed 2 percent for feeders and 3 percent for branch circuits.

3.03 DEMONSTRATION

A. Test the electrical system to specification requirements and to demonstrate correct installation and operation of equipment. O & M Manual shall be furnished prior to testing for reference during testing and corrections for final O & M.

B. Before 7-days test, demonstrate the system to the wastewater inspectors and the Project Manager. Show the system to be fully operational. All alarms, safeties, and communication points to central and locally must operate in both full-automatic and back-up modes. Use fresh water in the test medium.

C. Operate the system continuously for a period of 7 days in full automatic, without failure, to qualify as acceptable. "Failure" is considered any problem that requires correction by process control instructions, maintenance personnel, such as: high or low water level, any motor alarm, power failure, phase failure, communication failure, PLC failure, process control software failure, requiring rewriting or transducer failure. This would exclude conditions not under the control of Contractor, such as: evident lightning strikes, 25-year rains, local power utility power failure longer than the specified duration of service. Failures due to uncontrollable situations would allow the 7-day test to continue, as soon as test conditions are restored and the City Engineer is notified.

D. The existing station shall remain in service during this test.

END OF SECTION

Section 16060

ELECTRICAL DEMOLITION

PART 1 GENERAL

2.01 SECTION INCLUDES

A. Electrical demolition.

2.02 REFERENCES

A. Temporary wiring of systems to maintain operation of facilities while undergoing modifications and demolition shall be provided in accordance with:

1. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), No. 70 - National Electrical Code (NEC), Article No. 590 - Temporary Wiring

2. City of Houston Electrical Code.

2.03 SUBMITTALS

A. Annotate existing drawings to sequence the demolition of systems, equipment removal and temporary hook-ups.

B. Schedule with Project Manager for required shut-downs to accommodate system demolition and installation of temporary facilities.

2.04 QUALITY ASSURANCE

A. Verify field measurements and circuiting arrangements are as shown on Drawings.

B. Verify that abandoned wiring and equipment serve only abandoned facilities.

C. Demolition drawings are based on casual field observation and existing record documents. Report discrepancies to City Engineer before disturbing existing installation.

D. By beginning demolition, installer accepts existing conditions and warrants that he will maintain service to equipment and items not scheduled or indicated for removal, and that he will return to the City all items and systems in good operating condition.

PART 2 PRODUCTS

2.01 MATERIALS AND EQUIPMENT

A. Materials and equipment for patching and extending work: As specified in individual Sections.

2.02 DESIGN AND CONSTRUCTION

A. The temporary electrical wiring and facilities shall be designed and constructed in strict compliance with NEC - Article No. 590 and the City of Houston Electrical Code.

PART 3 EXECUTION

3.01 PREPARATION

A. Disconnect electrical systems in walls, floors, and ceilings scheduled for removal.

B. Coordinate utility service outages with utility company to provide continuous service to operating equipment.

C. Provide temporary wiring and connections to maintain existing systems in service during construction. When work must be performed on energized equipment or circuits, notify City of Houston Utility Operations and get approval. Use personnel experienced in such operations.

D. Existing Electrical Service: Maintain existing system in service until new system is complete and ready for service. Disable system only to make switchovers and connections. Obtain permission from the City Engineer at least one week before partially or completely disabling system. Minimize outage duration.

E. Adding Load to Existing Electrical System: Perform a load analysis to assure that the existing power distribution system (MCC, service, conductors, panel, breakers, feeders, branch circuits, etc.) is not overloaded if additional load is added to existing equipment.

F. Existing electrical conduit and wire may not be reused to feed new equipment except by written authorization from the City of Houston.

3.02 DEMOLITION AND EXTENSION OF EXISTING ELECTRICAL WORK

A. Remove, relocate, and extend existing installations to accommodate new construction.

B. Remove abandoned wiring to source of supply.

C. Remove exposed abandoned conduit, including abandoned conduit above accessible ceiling finishes. This includes all associated support and

anchoring systems. Cut conduit flush with walls and floors, and patch surfaces.

D. Disconnect abandoned outlets and remove devices. Remove abandoned outlets if conduit servicing them is abandoned and removed. Provide blank cover for abandoned outlets which are not removed.

E. Disconnect and remove abandoned panelboards and distribution equipment.

F. Disconnect and remove electrical wire, conduits, devices and equipment serving utilization equipment that has been removed.

G. Repair adjacent construction and finishes damaged during demolition and extension work. Repairs to include matching material type and color.

H. Maintain access to existing installations which remain active. Modify installation or provide access panel as appropriate. Cut abandon conduits in floors or slabs flush to surface, fill with concrete and path to match surface type and color.

I. Extend existing installations using materials and methods as specified for new work.

3.03 DISPOSAL AND SALVAGE

A. Salvage electrical and instrumentation equipment and wiring size four and larger removed from existing facilities for City's reuse.

B. Material and equipment which can be reused or salvaged remains the property of the City of Houston. Equipment to be retained by the City of Houston shall be delivered to a specified location by the Contractor.

C. Materials and equipment which cannot be reused or salvaged will be removed and disposed by the Contractor.

3.04 CLEANING AND REPAIR

A. Clean and repair existing materials and equipment which remain or are to be reused.

B. Panelboards: Clean exposed surfaces and check tightness of electrical connections. Replace damaged circuit breakers and provide closure plates for vacant positions. Provide typed circuit directory showing revised circuiting arrangement.

3.05 INSTALLATION

A. Install relocated materials and equipment under the provisions of Section 02220 - Demolition.

B. Electrical installations and materials shall conform to the current issue of the following standard and codes: American National Standards Institute/National Fire Protection Association (ANSI/NFPA), No. 70 - National Electrical Code (NEC), City of Houston Electrical Code, and material and workmanship.

C. All material shall be free of defects and in safe working condition which will meet electrical classification and functional requirements.

D. Testing shall be made during the course of construction or at the completion of the job. These tests shall be made by the electrical contractor. The contractor shall furnish all test equipment.

E. The job will not be complete until work has been inspected and trial startup has been successfully completed.

END OF SECTION

Section 16111

CONDUIT, FITTINGS, AND BODIES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Conduit, fittings, and bodies.

1.02 REFERENCES

A. American National Standards Institute (ANSI):

1. ANSI C 80.1 - Rigid Steel Conduit - Zinc Coated.

2. ANSI C 80.4 - Fittings for Rigid Metal Conduit.

B. American Society for Testing and Materials (PVC Coated Conduit)

1. ASTM D149-09 – Standard test method for dielectric breakdown voltage and dielectric strength of solid electrical insulating materials at commercial power frequencies.

2. ASTM D1735-08 – Standard practice for testing water resistance of coatings using water fog apparatus.

3. ASTM D2247-11 – Standard practice for testing water resistance of coatings in 100% relative humidity.

4. ASTM D2240-05 (2010) – Standard test method for rubber property – durometer hardness.

5. ASTM D1308-02 (2007) – Standard test method for effect of household chemicals on clear and pigmented organic finishes.

6. ASTM D638-10 – Standard test method for tensile properties of plastics.

7. ASTM D746-07 – Standard test method for brittleness temperature of plastics and elastomers by impact.

8. ASTM D1151-00 (2006) – Standard practice for effect of moisture and temperature on adhesive bonds.

9. ASTM D870-09 – Standard practice for testing water resistance of coatings using water immersion.

10. ASTM G152-06 – Standard practice for operating open flame carbon arc light apparatus for exposure of non-metallic materials.

11. ASTM G153-04 (2010) – Standard practice for operating enclosed carbon arc light apparatus for exposure of non-metallic materials.

12. ASTM D3359-09e2 – Standard test methods for measuring adhesion by tape test.

13. ASTM D4585-07 – Standard practice for testing water resistance of coatings using controlled condensation.

C. ASTM B571-97 (2008)e1 – Standard practice for qualitative adhesion testing of metallic coatings

D. Federal Specifications:

1. W-C-58 C - Conduit Outlet Boxes, Bodies Aluminum and Malleable Iron.

2. W-C-1094 - Conduit and Conduit Fittings Plastic, Rigid.

3. WW-C-566 C - Flexible Metal Conduit.

4. WW-C-581 D - Coatings on Steel Conduit.

E. National Electrical Manufacturers Association (NEMA):

1. NEMA RN 1 - Polyvinyl-Chloride Externally Coated Galvanized Rigid Steel Conduit and Electrical Metallic Tubing.

2. NEMA TC 2 - Electrical Plastic Tubing (EPT) and Conduit (EPC-40 and EPC-80).

3. NEMA TC 3 - PVC Fittings for Use with Rigid PVC Conduit and Tubing.

F. National Fire Protection Association (NFPA), ANSI/NFPA 70 - National Electrical Code (NEC).

G. Underwriters' Laboratories (UL):

1. UL 1 - Flexible Metal Electrical Conduit.

2. UL 6 - Rigid Metal Electrical Conduit.

3. UL 514 B - Fittings for Conduit and Outlet Boxes.

4. UL 651 - Schedule 80 Rigid PVC Conduit.

5. UL 651 A - Type EB and A Rigid PVC Conduit and HDPE Conduit.

6. UL 886 - Electrical Outlet Boxes and Fittings for Use in Hazardous Locations.

H. City of Houston Electrical Code.

1.03 SUBMITTALS

A. Make submittals following Section 01330 - Submittal Procedures:

1. Manufacturer's cut sheets, catalog data.

2. Installation, terminating and splicing procedure.

3. Instruction for handling and storage.

4. Dimensions and weight of products.

5. Code compliance certificate.

6. Conformance certificate.

1.04 QUALITY ASSURANCE

A. Rigid steel conduit shall pass the bending, ductility, and thickness of zinc coating test described by ANSI C 80.1.

B. Flexible conduit shall pass the tension, flexibility, impact, and zinc coating test described by UL 1.

C. Nonmetallic conduit and fittings shall pass the test requirements of NEMA TC 2, UL 65and 651 A and Federal Specification W-C-1094 A.

D. The PVC coated conduit must be listed by UL with both the zinc coating and PVC coating each serving as primary coatings by itself under UL6.

1.05 DELIVERY STORAGE AND HANDLING

A. Package conduit in 10-foot bundles maximum with conduit and coupling thread protectors suitable for indoor and outdoor storage. Package fittings in manufacturer's standard quantities and packaging suitable for indoor storage. Package plastic-coated rigid conduit,

fittings, and bodies in such a manner as to protect the coating from damage during shipment and storage.

B. Store conduit above ground on racks to prevent corrosion and entrance of debris.

C. Protect plastic conduit from sunlight.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Rigid Steel Conduit:

1. Allied Tube and Conduit.
2. Triangle Wire and Cable, Inc.
3. Wheatland Tube Company.

B. PVC Coated Steel Conduit:

1. Occidental Coating Company (O-Cal Blue).
2. Robroy Industries, Inc.
   a. Rob-Roy Red
   b. Plasti-Bond Red
   c. Perma-Cote Green
   d. Calbond

C. PVC Rigid Conduit:

1. Cantex.
2. Carlon Industries, Inc.
3. Atkore

D. Conduit Fittings and Bodies:

1. Appleton Electric.
2. Crouse-Hinds.

3. Hubbell - Killark Manufacturing Company.

4. O-Z/Gedney.

E. Liquidtight Flexible Conduit:

1. Anamet, Inc.

2. Electriflex Company.

3. Triangle Wire and Cable, Inc.

2.02 MATERIALS AND EQUIPMENT

A. Design Conditions. Use electrical conduit, fittings, and bodies designed for service in areas as specified in Section 16010 - Basic Electrical Requirements and this section to form a continuous support system for power, control, and instrument cables or any combination thereof.

B. Conduit and Fittings:

1. Rigid Steel Conduit and Fittings.

a. Rigid steel conduit and rigid steel conduit bends, nipples, and bodies shall be hot-dipped galvanized and shall comply with the latest ANSI C 80.1, UL 6, Federal Specification WW-C-581 D, and NEC Article 346-15.

b. Mild steel tubing shall be used for conduit, nipples, and couplings, and shall be free of defects on both the inner and outer surfaces.

c. Fittings and bodies and covers for rigid steel conduit shall be steel or cast-iron and shall comply with ANSI C 80.4, UL 514 B, and Federal Specification W-C-58 C.

2. PVC-Coated Rigid Steel Conduit and Fittings

a. PVC-coated conduit, fittings, bodies, and covers shall conform in all respects to NEMA RN 1 (Type A). Rigid steel galvanized conduit and fittings shall conform to Federal Specifications WW-C-581 D and ANSI C 80.1.

b. The PVC coated conduit must be listed by UL with both the zinc coating and the PVC coating each serving as primary coatings by itself under UL6. Conduit bodies shall conform to UL 514 B and Federal Specification

W-C-58 C. PVC-coated fittings for general service locations must be UL listed with the PVC as the primary corrosion protection. Provide sufficient coating for touch-up after installation.

c. Condulet covers shall have encapsulated stainless steel thumb screws.

d. Condulets and covers shall be of malleable iron or ferroalloy material before coating.

e. Urethane coating shall be a minimum of 2 mil thickness on the interior of the conduit and the interior of fittings, condulets, covers, and bodies.

f. Form 8 fittings shall have an o-ring molded with the coating of their covers. The fittings shall pass a UL observed pressure and vacuum test retaining 25" of vacuum and 17 PSI of pressure for a period of 80 hours.

2. Liquidtight Flexible Metal Conduit and Fittings

a. Use liquidtight flexible metal conduit manufactured in accordance with UL 1 and Federal specification WW-C-566 C.

b. Fittings used with liquidtight flexible metal conduit shall be the PVC-coated type. Thoroughly ground the conduit to the fittings and through the fittings to the box or enclosure to which it is attached.

c. Couplings and fittings for use in hazardous areas shall comply with UL 886, NEC Article 501 & 502, and Federal Specification W-C-586 C.

3. PVC Conduit and Fittings. Use PVC conduit, bends, and fittings, which comply with NEMA TC 2, W-C-A, and NBC Article 347-17 for above ground installation. Underground installations refer to 16402. Conduit shall be Schedule 80.

PART 3 EXECUTION

3.01 PREPARATION

A. Ensure that the conduit system to be installed is sized properly for the cable and wire requirements.

B. Verify the actual physical conduit route from the conduit plan drawings and prepare the conduit support system.

C. Verify the equipment locations to which the conduit will be connected and determine detail requirements for connections.

3.02 INSTALLATION

A. Install PVC-coated conduits in all outdoor locations, inside valve vaults and wet wells, lift station drypits, areas that are not air-conditioned, and in all other corrosive and wet environments. Install PVC-coated conduit in strict accordance with manufacturer's instructions. Use installers certified by the manufacturer.

B. Install rigid galvanized steel (RGS) conduits in dry, inside, air-conditioned locations only.

C. Install PVC conduits in reinforced duct banks or encased in concrete slabs. For stub-ups, use PVC coated rigid steel elbows as required in Section 16402.

D. Run exposed conduit parallel or perpendicular to walls, ceilings or main structural members. Group multiple conduits together where possible. Conduit shall not interfere with the use of passageways, doorways, overhead cranes, monorails, equipment removal areas or working areas. In no case shall conduit routing present a safety hazard, trip hazard, or interfere with normal plant operating and maintenance procedures. A minimum overhead clearance of 8 feet shall be maintained in passageways. All conduits installed across walkways shall have concrete or aluminum trip plates installed.

E. Installation and support of conduit shall be from steel or concrete structures in accordance with the standard detail drawings. Furnish necessary conduit straps, clamps, fittings and support for the conduit in accordance with the standard details.

F. Identify conduit at termination points like MCC, light fixtures, control panels, receptacles, panels, and junction boxes.

G. Not more than 3 equivalent 90 degree bends will be permitted between outlets. Provide bonded expansion fittings at building expansion joints.

H. Install conduit runs so that they are mechanically secure, mechanically protected from physical harm, electrically continuous, and neat in appearance. The interiors of conduit shall provide clean, smooth raceways through which conductors may be drawn without damage to the insulation. Make threaded connections wrench tight.

I. Cut conduit square with a power saw or a rotary type conduit cutter designed to leave a flat face. Do not use plumbing pipe cutters for cutting conduit. Ream the cut ends of conduit with a reamer, designed for the purpose to eliminate rough edges and burrs. Threads shall be cut with standard conduit dies providing 3/4-inch taper per foot, allowing the proper length so that joints and terminals may be made up tight and the ends of the conduit not deformed. Keep dies sharp and use a good quality threading oil continuously during the threading operation. Remove metal cuttings and oil from the conduit ends after the threads are cut and paint threads before connections are made. Use non-corrosive Carbozinc No. 11 as manufactured by the Carboline Company, coal tar enamel or zinc rich epoxy primer on the threads of steel conduit before connections are made.

J. Use strap wrenches only to tighten joints in plastic coated rigid steel conduit. Replace all conduit and fittings with damage to the plastic coating, such as cuts, nicks and threader chuck jaw marks. Use a solvent, or the same patching material to seal around the edges of conduit fitting covers.

K. Make changes in direction of conduit using elbows or fittings. Do not use pull boxes to make direction changes unless specifically designated otherwise.

L. Field fabricated bends shall be free of indentations or elliptical sections. The radius of the bend shall not be less than 6 times the smallest diameter of the raceway.

M. Protect all conduit terminations from mechanical injury. Prevent the entry of moisture and foreign matter into the conduit system by properly capping terminations.

N. Avoid trapped runs of conduit, if possible. When they are necessary, provide drainage using a "tee" condulet equipped with a drain. Conduit is likely to pass through areas with a temperature differential of 20 F or more. Seal penetrations with a proper seal fitting at the wall or barrier between such areas. For conduit passing through walls separating pressurized areas from non-pressurized areas, install sealing fittings at the wall on the non-pressurized side.

O. Fit all conduit crossing building or structure expansion joints with approved expansion fittings, except that fittings will not be required when conduit crossing an expansion joint is supported on trapeze hangers in such a way that at no time will the conduit be under stress due to expansion. Unless otherwise indicated on Drawings, install expansion fittings every 300 feet within a straight conduit run and where conduit crosses building expansion joints, using bonding straps

to ensure ground continuity. Bonding strap connections shall be protected by minimum 40 mils PVC coating.

P. Where rigid galvanized conduit terminates in sheet metal enclosures, fit the conduit with double locknuts and bushings. Sheet metal enclosures made of stainless steel or aluminum located outside or in any other wet, damp, or corrosive areas shall be furnished with PVC-coated threaded hubs. Restrict side penetrations to the lower one third of the enclosure. Where PVC-coated rigid conduit is used, PVC-coated rigid threaded hubs will be used.

Q. Provide flexible Liquidtight metallic conduit where necessary to allow for movement or to localize sound or vibration, at transformers, at motors and any other rotating equipment. Flexible metal conduit shall be used as fixture whips only.

R. Seal all openings or holes where conduits pass through walls or floors. When passing through a firewall or floor, use a fire-rated seal per the typical detail included in the Drawings. Certain walls, as indicated on the drawings, require environmental (air-tight) seals; seal as indicated on the Drawings.

S. Install explosion-proof seals according to N.E.C. requirements and in coordination with NFPA 820, in conduit runs crossing or entering hazardous classified areas (as shown on Drawings). Install type CSBE removable sealing fittings to seal pump cables between wet well and first junction box. If a junction box is not used, install the CSBE seals at the wet well and the control panel.

T. All transitions in PVC-coated conduit size shall be accomplished with PVC-coated RECs or manufactured reducing condulets. RE bushings shall not be used.

U. Parallel runs of conduit may be supported by structural steel racks. When two or more racks are arranged one above the other, provide vertical separation of not less than 12 inches between racks, unless otherwise indicated on Drawings. Space conduits on the racks at least enough to provide 1/4-inch clearance between hubs on adjacent conduits at terminations and to allow room for fittings.

V. Fill conduit racks no more than 75 percent of their capacity, providing usable space for future conduit. To ensure this, conduits leaving the rack horizontally shall be offset up or down so that future conduits may be installed in the space remaining. Construct conduit racks to permit access for wire or cable pulling at all pull points, even when future conduits are added to fill the racks.

W. Where conduit racks are supported on rods from beam clamps or by some other non-rigid suspension system, install rigid supports at no more than 50-foot intervals to give lateral stability to the rack.

X. Conduit racks or hangers must in no way interfere with machinery (or its operation), piping, structural members, process equipment, or access to anticipated future equipment. Refer to architectural, structural, equipment layout and piping drawings to ensure that this requirement is met. Label high voltage conduit with the circuit phase-to-phase voltage by means of a firmly attached tag or label of approved design at each conduit termination, on each side of walls or barriers pierced and at intervals not exceeding 200 feet along the entire length of the conduit.

Y. Support conduit sizes 2 inches and larger at spacings not exceeding 10 feet and conduit sizes 1-1/2 inches and smaller at spacings not exceeding 8 feet.

Z. The means of fastening conduit to supports shall be: by one hole malleable iron conduit straps secured by wood screws to wood and by bolts with expansion anchors to concrete or masonry; by "Korn" clamps or U-bolts to other surfaces. Use "clamp backs" when strapping conduits to walls, column faces, or other such surfaces.

AA. Support conduit runs with conduit clamps, hangers, straps and metal framing channel attached to structural steel members. Conduits of 1-1/2 inch size or less may be supported by one-hole conduit straps on concrete, tile or steel work, but for larger size conduit, 2-hole straps shall be used. Use clamps of galvanized malleable iron for rigid galvanized conduit and stainless steel for PVC-coated conduit. Metal framing channel straps used for PVC-coated conduit shall be type 316 stainless steel.

BB. Install conduits supported form building walls with at least 1/4-inch clearance from the wall to prevent the accumulation of dirt and moisture behind conduit.

CC. All Conduits embedded in concrete lift station deck shall be PVC-coated rigid.

END OF SECTION

Section 16120

600-VOLT BUILDING WIRE AND CABLE

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for 600-volt building wire and cable.

1.02 REFERENCES

A. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), NFPA 70 - National Electrical Code (NEC), Article 310 - Conductors for General Wiring

B. Underwriter's Laboratories (UL)

1. UL 83: Thermoplastic Insulated Wires and Cables

2. UL 1063: Machine Tool Wires and Cables

C. American Society for Testing and Materials (ASTM)

1. ASTM B 3: Soft or Annealed Copper Wires

2. ASTM B 8: Concentric-Lay-Stranded Copper Conductors, Hard, Medium Hard, Soft

D. Insulated Cable Engineers Association (ICEA), ICEA S-61-402: Thermoplastic-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-5)

E. City of Houston Electrical Code

1.03 SUBMITTALS

A. Make submittals following Section 01330 - Submittal Procedures.

1. Manufacturer's cut sheets, catalog data

2. Instruction for handling and storage

3. Dimensions and weight

4. Conformance certificate

1.04 QUALITY ASSURANCE

A. Tests.Cable shall meet all the requirements of Part 6 of ICEA S-61-402.

B. Conformance Certificate and Quality Assurance Release: Submit a conformance certificate signed by the person responsible for product quality. The certificate shall specifically identify the purchased material or equipment; such as by the project name and location, purchase order number, supplements, and item number where applicable, including materials and services provided by others. The certificate shall indicate that requirements have been met and identify any approved deviations.

1.05 DELIVERY, STORAGE AND HANDLING

A. Ship wire and cable on manufacturer's standard reel sizes unless otherwise specified. Where cut lengths are specified, mark reel footage accordingly. Each reel shall contain one continuous length of cable. Provide impact protection by wood lagging or suitable barrier across the traverse of the reel. Provide moisture protection by using manufacturer's standard procedure or heat shrinkable self-sealing end caps applied to both ends of the cable.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. American Insulated Wire Corporation

B. American Wire and Cable Company

C. General Cable Company

D. Southwire Company

E. Rome Cable Company

F. Triangle Wire and Cable, Inc.

2.02 MATERIALS AND EQUIPMENT

A. Design. Provide cable designated as THWN/THHN stranded single conductor type and UL 83 and UL 1063 listed, rated 600 volts and certified for continuous operation at maximum conductor temperature of 90 C in dry locations and 75 C in wet locations in conduit. MTW stranded will be used in

control panels.

B. Conductors. Provide conductors which are Class B, concentric stranded, annealed uncoated copper with physical and electrical properties complying with ASTM B 3 and ASTM B 8 and Part 2 of ICEA S-61-402.

C. Insulation.

1. Each conductor shall be PVC insulated and nylon jacketed to meet the requirements of Part 3 of ICEA S-61-402. The insulation thickness shall match the dimensions listed in Table 310.104(A) of the National Electrical Code (NEC) for type THHN/THWN wire.

2. Outdoor conductors installed in conduit exposed to sunlight shall be Type XHHW-2 stranded copper conductors, moisture, and heat resistant cross-linked polyethylene (XLP). Conductors shall meet or exceed UL Standard 44, Federal Specification A-A-59544, and requirements of the National Electrical Code. Type XHHW-2 meets and exceeds all construction requirements of ICEA S-95-658 (NEMA WC 70.

D. Wire Marking

1. Wire marking shall be in accordance with National Electrical Code (NEC) Article 310.120.

2. The printing method used shall be according to (NEC) 310.120(B).

E. The single conductor color coding shall be as follows:

System Voltage	A	B	C	Neutral
120/208 Volt 3Ph/4w	Black	Red	Blue	White
120/240 Volt 3Ph/4w	Black	Orange	Blue	White
277/480 Volt 3Ph/4w	Brown	Purple	Yellow	Grey
Motor Control	1 ..... Black 2 ..... Red 3 ..... Blue			
Ground	..... Green			

PART 3 EXECUTION

3.01 PREPARATION

A. Complete the cable raceway systems and underground duct banks before installing cables.

B. Verify sizing of raceways and pullboxes to ensure proper accommodation for the cables according to (NEC) minimum requirements or as specified on drawings.

C. Check the length of the cable raceway system against the length of cable on the selected reel.

D. Clean and swab conduits of foreign matter before cables are pulled.

3.02 INSTALLATION

A. Wiring Methods

1. Use wiring methods indicated on Drawings.

2. In general, use THHN/THWN stranded building wire for lighting, power and control wiring where conductors are enclosed in raceways like in above ground conduit system or in underground duct banks, or inside control panels.

3. Use XHHW-2 stranded building wire in outdoor areas power and control wire is in conduit exposed to direct sunlight. Refer to (NEC) 310.15(B)(3)(a)(5)(c) Exception.

4. Do not use solid conductors.

5. Use conductors not smaller than No. 12 AWG stranded for general lighting circuits.

6. Use conductors not smaller than No. 14 AWG stranded for control circuits, except when part of a multiconductor cable or internal panel wiring.

7. In general, do not splice conductors unless approved by the City Engineer.

8. Splices associated with taps for lighting and control circuits are allowed without approval.

9. Make splices in accessible junction boxes.

B. Single Conductor in Conduit and Ductbank

1. Install cables in accordance with the manufacturer's instructions and the National Electrical Code (NEC), Chapter 3- Wiring Methods and Materials. Do not exceed maximum wire tension, maximum insulation pressure and minimum bending radius.

2. Pull cables into conduits using wire pulling compounds approved by cable manufacturers to reduce friction. Lubricants must not be harmful to the conductor insulation. Mixtures containing soap or detergent shall not be used.

C. Single Conductor in Cable Tray

1. Do not install single conductor building wire and cable in cable tray.

2. For single conductor tray installation, see Section 16122 - 600 Volt Power Cable.

D. Preparation for Termination

1. Make 600-volt power cable terminations and splices with heat shrinkable sleeves and seals.

2. Terminal lugs and connectors for all sizes of conductors shall be crimp-on type.

3. For size 1/0 AWG and larger, crimp-on lugs shall have the long barrel with 2-hole tongues except in places where termination space is limited.

E. Tests

1. In general, test insulation integrity of the wiring system before terminating.

2. Make sure to disconnect sensitive electronic equipment before testing insulation.

3. Use a 600 VDC megohmmeter and perform the wire system insulation test in accordance with the operating instructions.

F. Termination. After the 600-volt wiring system has been tested with satisfactory results, reconnect wire.

END OF SECTION

Section 16121

600-VOLT CONTROL CABLE

PART 1 G E N E R A L

1.01 SECTION INCLUDES

A. 600-volt control cable.

1.02 REFERENCES

A. American Society for Testing and Materials (ASTM):

1. ASTM B 3 - Soft or Annealed Copper Wires.

2. ASTM B 8 - Concentric-Lay-Stranded Copper Conductors, Hard, Medium Hard, Soft.

3. ASTM B 33 - Tinned Soft or Annealed Copper Wire for Electrical Purposes.

4. ASTM B 174 - Bunch-stranded Copper Conductors for Electrical Conductors.

B. Institute of Electrical and Electronics Engineers (IEEE), IEEE 383-2.5: IEEE Standard for Type Test of Class IE Electric Cables, Field Splices, and Connections for Nuclear Power Generating Stations.

C. Insulated Cable Engineers Association (ICEA):

1. ICEA S-61-402 - Thermoplastic-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-5).

2. ICEA S-66-524 - Cross-Linked-Thermosetting-Polyethylene-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-7).

3. ICEA S-68-516 - Ethylene-Propylene-Rubber-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-8).

D. Underwriters' Laboratories (UL):

1. UL 44 - Rubber Insulated Wires and Cables.

2. UL 83 - Thermoplastic Insulated Wire and Cables.

E. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), No. 70 - National Electrical Code (NEC), Chapter No.3 - Wiring Methods and Materials, Article 725 - Class 1, Class 2, and Class 3 Remote Control, Signaling, and Power-Limited Circuits.

1.03 SUBMITTALS

A. Make submittals following Section 01330 - Submittal Procedures.

1. Completed engineer's data sheets.

2. Completed manufacturer's data sheets.

3. Manufacturer's cut sheets, catalog data.

4. Installation, terminating and splicing procedure.

5. Instruction for handling and storage.

6. Dimensions and weight.

7. Conformance certificate.

1.04 QUALITY ASSURANCE

B. Tests.

1. Cable shall be tested at the factory to confirm that the cable complies with requirements of Part 6 of ICEA S-61-402, S-66-524 or S-68-516. Refer to data sheet for additional test requirements.

2. Where applicable, the cable shall meet the requirements of the vertical tray flame test as described in IEEE 383-2.5.

1.05 DELIVERY STORAGE AND HANDLING

A. Ship cable on manufacturer's standard reel sizes, unless otherwise specified. Where cut lengths are specified, mark reel footage accordingly. Each reel shall contain one continuous length of cable. Reels shall be of the type specified on the data sheets. Provide impact protection by wood lagging or suitable barrier across the traverse of the reel. Provide moisture protection by

manufacturer's standard procedure or heat shrinkable self-sealing end caps applied to both ends of the cable.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

A. America Wire and cable Co.

B. Belden Division, Cooper Industries, Inc.

C. Okonite Company

D. Cablec Continental Cables Company

E. General Cable Company

F. Manhattan Electric Cable Corporation

2.02 MATERIALS AND EQUIPMENT

A. Design. Provide cable with the following design characteristics. The cable shall consist of multiple conductors. The cable assembly shall be UL listed, flame, oil and sunlight resistant, and certified for continuous operation at the temperature specified on the 600-Volt Control Cable Data Sheets in wet or dry locations while installed in underground duct, conduit, or cable tray. The number and size of conductors supplied in each cable shall correspond to the quantities specified on the 600-Volt Control Cable Data Sheets.

B. Conductors. Provide conductors which are concentric or bunch-stranded, annealed tinned copper with physical and electrical properties conforming to ASTM B 3, ASTM B 8 or ASTM B 33 or ASTM B 174 and Part 3 of ICEA S-61-402, S-66-524, or S-68-516 unless otherwise specified on the 600-Volt Control Cable Data Sheets.

C. Insulation. Each conductor shall be insulated as specified on the 600-Volt Control Cable Data Sheets complying to the requirements of Part 3 of ICEA S-61-402, S-66-524 or S-68-516. The average insulation thickness shall not be less than the dimensions shown in Section 3.2, Table 3-1 of ICEA S-61-402, S-66-524 or S-68-516 for 600 volt insulation unless otherwise specified on the 600-Volt Control Cable Data Sheets. The minimum insulation thickness shall not be less than 90 percent of the value given in the table.

D. Drain Wire. Provide drain wire Class B, seven-stranded, tin-coated copper in accordance with ASTM B 3, ASTM B 8, or ASTM B 33 and as specified on the 600-Volt Control Cable Data Sheets.

E. Shielding. Cable shielding shall consist of laminated, nonburning, mylar-backed aluminum tape applied helically around conductors with the aluminum side in continuous contact with the drain wire unless otherwise specified on the 600-Volt Control Cable Data Sheet. The tape shall be wrapped around the conductors with a 25 percent minimum overlap unless otherwise specified on the 600-Volt Control Cable Data Sheets.

F. Jacket.

1. When control cables are to be enclosed in conduit, ducts or in other raceway systems, the cables shall be of the non-metallic type and shall be covered by an overall nonmetallic jacket, as specified on the 600-Volt Control Cable Data Sheets, which complies with the requirements of Section 4.4 of ICEA S-66-524 or S-68-516, Section 4.3 of ICEA S-61-402, or Table 21-5 of Part 21 of UL 83.

2. Multi-conductor cables shall have a jacket thickness which complies with Table 4-7 of Part 4 of ICEA S-66-524, Table 4-5 of Part 4 of ICEA S-68-524, or Table 4-6 of Part 4 of ICEA S-61-402 unless otherwise specified on the 600-Volt Control Cable Data Sheets.

G. Armor. Where control cables are to be exposed, as in cable tray, cable channel or other cable support systems, the cables shall be protected by an interlocked metal tape armor made of galvanized steel which meets the requirements of paragraph 4.5 of ICEA S-68-516 or S-66-524 unless otherwise specified on the 600-Volt Control Cable Data Sheets. An over-all jacket shall be provided as specified in the Data Sheets.

H. Conductor Identification. Identify individual conductors by method as specified on the 600-Volt Control Cable Data Sheets in conformance with Appendix L of ICEA S-66-524, Part 5 of ICEA S-68-516, or Appendix I of ICEA S-61-402.

I. Cable Marking. Print cable marking information on the jacket of each cable at 2-foot intervals. Use a permanent printing method with a color sharply contrasting the jacket color. See the 600-Volt Control Cable Data Sheets for the minimum information required.

PART 3 EXECUTION

3.01 PREPARATION

A. When control wiring requires installation in cable tray and other cable support systems, use the 600-Volt Multiconductor Control Cable.

B. Complete cable raceway systems, underground duct banks, and cable support systems before installing cables.

C. Verify sizing of raceways and pullboxes to ensure proper accommodation for the cables.

D. Check the length of the cable raceway system against the length of cable on the selected reel.

E. Do not install or work on PVC insulated or jacketed cables in temperatures below 32 F.

F. Clean conduits of all foreign matter before cables are pulled in.

G. Provide at least 30 percent spare conductors.

3.02 INSTALLATION

A. Cable in Conduit and Ductbank.

1. Install cables in accordance with the manufacturer's instructions and the National Electrical Code (NEC), Article 725 - Class 1, Class 2, and Class 3 Remote Control, Signaling and Power Limited Circuits. Do not exceed maximum wire tension, maximum insulation pressure and minimum bending radius.

2. Pull cables into conduits using wire pulling compounds approved by cable manufacturers to reduce friction. Lubricants must not be harmful to the conductor insulation or cable jacket. Mixtures containing soap or detergent shall not be used.

B. Cable in Tray

1. Install armored cable in cable tray.

2. 600-Volt Tray rated Control Cable may be installed in cable tray with 600-volt Tray rated power cables.

3. Install cables in trays in a neat and orderly manner. Tie cables to the rungs at approximate 15-foot intervals by use of cable ties.

C. Termination

1. Do not splice conductors unless approved by the Project Manager. For termination use crimp-on type, ring tongue, non-insulated, tin-plated copper lugs.

2. Mark wiring on both ends with circuit numbers or loop tag numbers. Heat shrink wire markers after the ring tongue terminal has been installed. Extend the marker over the crimp-on base of the terminal.

D. Tests

1. Test insulation integrity and conductor continuity before connecting the cables.

2. Use a 500 VDC megohmmeter and perform the cable insulation test in accordance with the operating instructions.

E. Termination. After the 600-volt control cable has been tested with satisfactory results, terminate the cable at both ends to designated terminal points.

END OF SECTION

DATA SHEET 1 of 3

IDENTIFICATION

CLIENT _____ MANUFACTURER _____
PROJECT _____ MODEL NO. _____
JOB NO. _____ SIZE _____
PLANT LOCATION _____ SERIAL NO. _____
ITEM NO. _____ INQUIRY NO _____
SERVICE _____ P.O. NO. _____
NO. ITEMS REQUIRED _____

NOTE: [ ] INDICATES INFORMATION TO BE COMPLETED BY MANUFACTURER

OPERATING DATA

VOLTAGE _____ FREQUENCY _____ AMBIENT TEMP (°C) _____
INSTALLATION ENVIRONMENT _____

CONSTRUCTION

CONDUCTORS

SIZE (AWG or KCMIL): _____
ARRANGEMENT: _____ SINGLE CONDUCTOR __ OTHER _____
_____ MULTI-CONDUCTOR _____ NO. OF CONDUCTORS
MATERIAL: _____ BARE COPPER _____ TIN-COATED COPPER
_____ SOLID _____ STRANDED
SINGLE CONDUCTOR: _____ JACKETED _____ NON-JACKETED
MULTI-CONDUCTOR _____ JACKETED _____ NON-JACKETED (TRIPLEXED ONLY)
_____ ARMORED _____ ARMORED W/OUTER JACKET
_____ GROUND WIRES IN INTERSTICES: _____ COPPER _____ ALUMINUM
CONDUCTOR CLASS PER _____ ASTM STANDARD
SPECIAL REQUIREMENTS: _____

INSULATION

TYPE: _____ CROSS LINKED POLYETHYLENE _____ CHLOROSULFONATED POLYETHYLENE
_____ POLYVINYL CHLORIDE _____ ETHYLENE-PROPYLENE RUBBER
_____ POLYETHYLENE _____ OTHER _____
THICKNESS (MILS OR MM) _____
COLOR: _____
TEMPERATURE RATING: _____ 60°C - 75°C (WET-DRY) _____ 75°C - 90°C (WET-DRY)
_____ 90°C (WET-DRY) _____ OTHER _____
DRAIN WIRE: SIZE _____ STRANDED ___ SOLID _ BARE COPPER _____ TIN-COATED COPPER
SPECIAL REQUIREMENTS: _____

SHIELDING

TYPE SHIELDING: _____ BRAIDED _____ CONDUCTIVE PLASTIC
_____ CONDUCTIVE COTTON _____ SPIRAL-SERVED _____ CORRUGATED
_____ MYLAR FILM - ALUMINUM FOIL _____ POLYESTER FILM-ALUMINUM FOIL
_____ COPPER TAPE _____ OTHER _____
POLYESTER FILM-ALUMINUM LOCATION _____ INSIDE _____ OUTSIDE
_____ PAIR SHIELD ISOLATED
_____ SEPARATOR _____ FILLED

ITEM NO. _____

DATA SHEET 2 of 3

SHIELD COMBINATION

OVERSHIELD: _____ POLYESTER FILM ALUMINUM
_____ BRAID _____ SERVED _____ OTHER _____

BRAID SHIELD: _____ TYPE STRANDS _____% COVERAGE _____ TINNED
_____ BARE _ COPPER _____ ALUMINUM
_____ OTHER _____

OVERALL TYPE: _____ POLYESTER _____ PAPER OTHER: _____

JACKET

TYPE: _____ POLYVINYL CHLORIDE _____ POLYETHYLENE
_____ HEAVY DUTY NEOPRENE _____ CHLOROSULFONATED POLYETHYLENE
_____ **NYLON** _____ OTHER _____

THICKNESS (MILS OR MM) _____
COLOR: _____ BLACK _____ OTHER _____
SPECIAL REQUIREMENTS: _____

ARMORING

TYPE: _____ INTERLOCKED (POSITIVE) _____ OTHER _____
MATERIAL: _____ GALVANIZED STEEL _____ ALUMINUM
_____ OTHER _____
COVERING: _____ POLYVINYL CHLORIDE _____ OTHER _____
COLOR: _____ BLACK _____ OTHER _____
SPECIAL REQUIREMENTS: _____

MARKING

CONDUCTOR IDENTIFICATION

SINGLE CONDUCTOR: _____
MULTI-CONDUCTOR: _____

CABLE MARKING

REQUIRED: _____ MANUFACTURER _____ CONDUCTOR SIZE
_____ NO. OF CONDUCTORS _____ VOLTAGE RATING
_____ UL LABEL _____ NEC TYPE
_____ TEMPERATURE RATING _____ MONTH/YEAR OF MANUFACTURE
_____ INSULATION _____ FOOTAGE MARKERS
_____ OTHER _____

FACTORY TESTING/DOCUMENTATION

_____ PHYSICAL _____ _____ FLAME TESTS (PER IEEE 383 - 2.5)
_____
_____ ELECTRICAL _____ OTHER TESTS _____
_____ MEGGER
_____ OTHER _____

ITEM NO._____

DATA SHEET 3 of 3

QUALITY ASSURANCE

_____ NO ADDITIONAL REQUIREMENTS _____ ATTACHED SPECIFICATION _____

PACKAGING

_____ DOMESTIC _____ EXPORT

SHIPPING

REEL TYPE: _____ RETURNABLE _ NON-RETURNABLE _____ LENGTH PER REEL _____

ADDITIONAL REQUIREMENTS: _____

[ ]MANUFACTURER DATA

CABLE DIMENSION (O.D. IN.) _____ SHIPPING TIME _____
CABLE CROSS-SECTIONAL AREA _____ OTHER _____
CABLE WEIGHT (LBS/FT) _____
CABLE MIN BENDING RADIUS _____
TENSILE STRENGTH _____
GROSS WEIGHT/REEL (LBS) _____
TOTAL CUBIC FEET/REEL _____
SHORT CIRCUIT WITHSTAND CURVES _____
CABLE TESTING REQUIREMENTS _____

NOTES

TEM NO. _____

Section 16122

600-VOLT POWER CABLE

PART 1 GENERAL

1.01 SECTION INCLUDES

A. 600-volt power cable.

1.02 REFERENCES

A. American Society for Testing and Materials (ASTM).

1. ASTM B 3: Soft or Annealed Copper Wires.

2. ASTM B 8: Concentric-Lay-Stranded Copper Conductors, Hard, Medium Hard, Soft.

3. ASTM B 33: Tinned Soft or Annealed Copper Wire for Electrical Purposes.

B. Institute of Electrical and Electronics Engineers (IEEE), IEEE 383-2.5: IEEE Standard for Type Test of Class IE Electric Cables, Field Splices, and Connections for Nuclear Power Generating Stations.

C. Insulated Cable Engineers Association (ICEA).

1. ICEA S-61-402: Thermoplastic-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-5).

2. ICEA S-66-524: Cross-Linked-Thermosetting-Polyethylene-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-7).

3. ICEA S-68-516: Ethylene-Propylene-Rubber-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-8).

D. Underwriters' Laboratories (UL).

1. UL 44: Rubber Insulated Wires and Cables.

2. UL 83: Thermoplastic Insulated Wire and Cables.

E. National Fire Protection Association (NFPA), No. 70 - National Electrical Code (NEC), Chapter No.3 - Wiring Methods and Materials.

F. City of Houston Electrical Code.

1.03 SUBMITTALS

A. Make submittals following Section 01330 - Submittal Procedures:

1. Completed engineer's data sheets

2. Completed manufacturer's data sheets

3. Manufacturer's cut sheets, catalog data

4. Installation, terminating and splicing procedure

5. Instruction for handling and storage

6. Dimensions and weight

7. Conformance certificate.

1.04 QUALITY ASSURANCE

A. Tests.

1. Cable shall be tested at the factory to confirm that the cable complies with requirements of Part 6 of ICEA S-61-402, S-66-524 or S-68-516. Refer to data sheet for additional test requirements.

2. Where applicable, the cable shall meet the requirements of the vertical tray flame test as described in IEEE 383-2.5.

1.05 DELIVERY STORAGE AND HANDLING

A. Ship cable on manufacturer's standard reel sizes unless otherwise specified. Where cut lengths are specified, mark reel footage accordingly. Each reel shall contain one continuous length of cable. Reels shall be of the type specified on the data sheets. Provide impact protection by wood lagging or suitable barrier across the traverse of the reel. Provide moisture protection by manufacturer's standard procedure or heat shrinkable self-sealing end caps applied to both ends of the cable.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

A. American Insulated Wire Company

B. Cablec Continental Cables Company

C. General Cable Company

D. Okonite Company

E. Pirelli Cable Corporation

F. Rome Cable Corporation

G. Triangle Wire and Cable, Inc.

2.02 MATERIALS AND EQUIPMENT

A. Design. Provide cable with the following design characteristic. Cable shall be UL 44 or UL 83 listed, rated 600 volts and certified for continuous operation at the temperature as specified on the 600 Volt Power Cable Data Sheets while installed in underground duct, conduit, or cable tray. Cables shall be single-conductor or multi-conductor (with ground) as specified on the data sheets.

B. Conductors. Provide conductors which are Class B, concentric stranded, annealed copper coated, unless otherwise specified on the data sheets, with physical and electrical properties conforming to ASTM B 3, ASTM B 8 or ASTM B 33 and Part 2 of ICEA S-61-402, S-66-524, or S-68-516. The number and size of conductors supplied in each cable shall correspond to the quantities specified on the data sheets.

C. Insulation. Insulate each conductor as specified on the 600 Volt Power Cable Data Sheets to meet the requirements of Part 3 of ICEA S-61-402, S-66-524 or S-68-516. The insulation thickness shall match the dimensions listed in Section 3.2, Table 3-1 of ICEA S-61-402, S-66-524 or S-68-516, as specified on the data sheets.

D. Jacket.

1. When power cables are to be enclosed in conduit, ducts or in other raceway systems, multiconductor power cables shall be of the non-metallic type and shall be covered by an overall nonmetallic jacket as specified on the Data Sheets, which complies with the requirements of Section 4.4 of ICEA S-66-524 or S-68-516, Section 4.3 of ICEA S-61-402, or Table 21-5 of Part 21 of UL 83.

2. Single-conductor cables shall have a jacket thickness which meets the requirements of Table 4-4 of Part 4 of ICEA S-66-524, Table 4-2 of Part 4 of ICEA S-68-516, or Table 4-2 or 4-6 of Part 4 of ICEA S-61-402. Multi-conductor cables shall have a jacket thickness which complies with Table 4-7 of Part 4 of ICEA S-66-524, Table 4-2 of Part 4 of ICEA S-68-516, Table 4-5 of Part 4 of ICEA S-68-516, or Table 4-6 of Part 4 of ICEA S-61-402, unless otherwise specified on the data sheets.

E. Armor. When power cables are to be exposed in a cable tray, cable channel or other cable support systems, the multiconductor power cables shall be protected by an interlocked metal armor made of galvanized steel which meets the requirements of paragraph 4.5 of ICEA S-68-516 or S-66-524 unless otherwise specified on the data sheets. An over-all jacket shall be provided as specified in the data sheets.

F. Cable Marking. Print cable marking information on the overall cable jacket at 2-foot intervals. Use a permanent printing method and color sharply contrasting with the jacket color. Identify individual conductors as specified on the data sheets in conformance with Part 5 of ICEA S-61-402, S-66-524, and S-68-516.

PART 3 EXECUTION

3.01 PREPARATION

A. Complete cable raceway systems, underground duct banks, and cable support systems before installing cables.

B. Verify sizing of raceways and pullboxes to ensure proper accommodation for the cables.

C. Check the length of the cable raceway system against the length of cable on the selected reel.

D. Do not install or work on PVC insulated or jacketed cables in temperatures below 32 F.

3.02 INSTALLATION

A. Cable in Conduit and Ductbank.

1. Clean conduits of foreign matter before cables are pulled.

2. Install cables in accordance with the manufacturer's instructions and the National Electrical Code (NEC), Chapter 3 - Wiring Methods and Materials. Do not exceed maximum wire tension, maximum insulation pressure and minimum bending radius.

3. Pull cables into conduits using wire pulling compounds approved by cable manufacturers to reduce friction. Lubricants must not be harmful to the conductor insulation. Mixtures containing soap or detergent shall not be used.

B. Cable in Tray.

1. Install medium voltage (5 kv and 15 kv) and 600V cables in separate trays or separated cables by a barrier in a single tray in accordance with NEC 392.

2. Install cables in trays in a neat and orderly manner. Tie cables to the tray rungs at approximate 15-foot intervals by use of cable ties.

3. The number of multi conductors or cables rated 2000 volts or less shall be according to NEC 392.22.

4. Using cable ties, make a triplex of single conductors used for 3-phase systems. Install in cable tray in accordance with NEC 392.20(D).

C. Preparation for Termination.

1. Make up 600-volt power cable terminations and splices with heat shrinkable sleeves and seals.

2. Use crimp-on terminal lugs and connectors for all sizes of conductors.

3. Use crimp-on lugs with long barrel and 2-hole tongues, except in places where terminations space is limited.

D. Tests.

1. Before connecting the cables, test insulation integrity.

2. Use a 500 VDC megohmmeter and perform the cable insulation test in accordance with the operating instructions.

E. Termination.

1. After the 600-volt cable has been tested with satisfactory results, terminate the cable at both ends to designated terminal points.

2. Tighten connection bolts with a torque wrench to specified torque levels.

END OF SECTION

DATA SHEET 1 of 3

IDENTIFICATION

CLIENT _____ MANUFACTURER _____
PROJECT _____ MODEL NO. _____
JOB NO. _____ SIZE _____
PLANT LOCATION _____ SERIAL NO. _____
ITEM NO. _____ INQUIRY NO. _____
SERVICE _____ P.O. NO. _____
QUANTITY REQUIRED _____

OPERATING DATA

VOLTAGE _____ FREQUENCY _____ AMBIENT TEMP (°C) _____
INSTALLATION ENVIRONMENT _____

CONSTRUCTION

CONDUCTORS

SIZE (AWG or MCM): _____
ARRANGEMENT: _____ SINGLE CONDUCTOR OTHER _____
_____ MULTI-CONDUCTOR _____ NO. OF CONDUCTORS
MATERIAL: _____ COPPER _____ ALUMINUM _____ TINNED COPPER
_____ JACKETED _____ NON-JACKETED
_____ GROUND WIRES IN INTERSTICES: _____ COPPER _____ ALUMINUM
ASTM STANDARD: _____
SPECIAL REQUIREMENTS: _____

INSULATION

TYPE: ___CROSS-LINKED-THERMOSETTING-POLYETHYLENE ___CHLOROSULFONATED POLYETHYLENE
___ POLYVINYL CHLORIDE _____ ETHYLENE-PROPYLENE RUBBER
___ POLYETHYLENE _____OTHER _____
COLOR: _____
TEMPERATURE RATING: _____ 60°C - 75°C (WET-DRY) _____75°C - 90°C (WET-DRY)
_____ 90°C (WET-DRY) _____ OTHER _____
INSULATING RATING: _____ 100% _____ 133% _____ 173% _____ OTHER _____
ICEA STANDARD: _____
SPECIAL REQUIREMENTS: _____

JACKET

TYPE: _____ POLYVINYL CHLORIDE _____ POLYETHYLENE
_____ HEAVY DUTY NEOPRENE _____ CHLOROSULFONATED POLYETHYLENE
_____ NYLON _____ OTHER: _____
COLOR: _____ BLACK _____ OTHER: _____
ICEA STANDARD: _____
SPECIAL REQUIREMENTS: _____

ITEM NO. _____

600-VOLT POWER CABLE

DATA SHEET 2 of 3

ARMORING

TYPE: _____ INTERLOCKED (POSITIVE) _____ OTHER _____
MATERIAL: _____ GALVANIZED STEEL _____ ALUMINUM
_____ OTHER _____
COVERING: _____ POLYVINYL CHLORIDE _____ OTHER _____
COLOR: _____ BLACK _____ OTHER _____
ICEA STANDARD: _____
SPECIAL REQUIREMENTS: _____

MARKING

CONDUCTOR IDENTIFICATION

SINGLE CONDUCTOR: _____
MULTI-CONDUCTOR: _____

CABLE MARKING

REQUIRED: _____ MANUFACTURER _____ CONDUCTOR SIZE
_____ NO. OF CONDUCTORS _____ VOLTAGE RATING
_____ UL LABEL _____ NEC TYPE
_____ TEMPERATURE RATING _____ MONTH/YEAR MANUFACTURE
_____ OTHER _____

TESTING

_____ PHYSICAL _____ FLAME TESTS (PER IEEE 383 - 2.5)
_____ ELECTRICAL _____ OTHER TESTS _____
_____ MEGGER
_____ OTHER _____

QUALITY ASSURANCE

_____ NO ADDITIONAL REQUIREMENTS _____ ATTACHED SPECIFICATION _____

PACKAGING

_____ DOMESTIC _____ EXPORT

SHIPPING

REEL TYPE: _____ RETURNABLE _____ NON-RETURNABLE _____ LENGTH PER REEL _____

ADDITIONAL REQUIREMENTS: _____

ITEM NO. _____

DATA SHEET 3 of 3
MANUFACTURER DATA

2. CABLE DIMENSION (O.D. IN.) _____ SHIPPING TIME _____
3. CABLE CROSS-SECTIONAL AREA _____ OTHER _____
4. CABLE WEIGHT (LBS/FT) _____
5. CABLE MIN BENDING RADIUS _____
6. TENSILE STRENGTH _____
7. GROSS WEIGHT/REEL (LBS) _____
8. TOTAL CUBIC FEET/REEL _____
9. SHORT CIRCUIT WITHSTAND CURVES _____
10.
11. **NOTES**
12.
13.
14.
15.
16.
17.
18.
19.
20.
21.
22.
23.
24.
25.
26.
27.
28.
29.
30.
31.
32.
33.
34.
35.
36.
37.
38.
39.
40.
41.
42.
43.
44.
45.
46.
47.
48.
49.
50.

ITEM NO. _____

Section 16123

MEDIUM VOLTAGE POWER CABLE

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Medium voltage power cable.

1.02 REFERENCES

A. American Society for Testing and Materials (ASTM):

1. ASTM B 3: Soft or Annealed Copper Wires.

2. ASTM B 8: Concentric-Lay-Stranded Copper Conductors, Hard, Medium Hard, Soft.

3. ASTM B 33: Tinned Soft or Annealed Copper Wire for Electrical Purposes.

B. Institute of Electrical and Electronics Engineers (IEEE), IEEE 383-2.5: IEEE Standard for Type Test of Class IE Electric Cables, Field Splices, and Connections for Nuclear Power Generating Stations.

C. Insulated Cable Engineers Association (ICEA).

D. ICEA P-45-482: Short-Circuit Performance of Metallic Shielding and Sheaths of Insulated Cable.

E. ICEA S-66-524: Cross-Linked-Thermosetting-Polyethylene-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-7).

F. ICEA S-68-516: Ethylene-Propylene-Rubber-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-8).

G. Underwriters' Laboratories (UL), UL 1072: Medium-Voltage (Type MV) Solid-Dielectric Cables.

H. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), 70-National Electrical Code (NEC), Chapter No. 3 - Wiring Methods and Materials.

1.03 SUBMITTALS

A. Make submittals following Section 01330 - Submittal Procedures.

1. Completed engineer's data sheets
2. Completed manufacturer's data sheets.
3. Manufacturer's cut sheets, catalog data.
4. Name of electrical testing company to be employed.
5. Impulse voltage test record.
6. Installation, terminating, and splicing procedure.
7. Instruction for handling and storage.
8. Dimensions and weight.
9. Conformance certificate.

1.04 QUALITY ASSURANCE

A. Tests.

1. Cable shall be tested at the factory to confirm that the cable complies with requirements of Parts 2, 3, 4, and 5 of ICEA S-68-516 or S-66-524. Test methods shall comply with the requirements of Part 6 of ICEA S-68-516 or S-66-524.
2. Where applicable, the cable shall meet the requirements of the vertical tray flame test as described in IEEE 383-2.5.

B. Contractor shall employ an electrical testing company with minimum 10 years experience in testing industrial electrical equipment, to perform Megger and Hi Potential test on newly installed cables. Submit name and qualifications of the electrical testing company for review by City Engineer prior to testing cables.

1.05 DELIVERY STORAGE AND HANDLING

A. Ship cable on manufacturer's standard reel sizes unless otherwise specified. Where cut lengths are specified, mark reel footage accordingly. Each reel shall contain one continuous length of cable.

Reels shall be of the type specified on the data sheets. Provide impact protection by wood lagging or suitable barrier across the traverse of the reel. Provide moisture protection by manufacturer's standard procedure or heat shrinkable self-sealing end caps applied to both ends of the cable.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. American Insulated Wire Company

B. Cablec Continental Cables Company

C. General Cable Company

D. Okonite Company

E. Pirelli Cable Corporation

F. Rome Cable Corporation

G. Triangle Wire and Cable, Inc.

2.02 MATERIALS AND EQUIPMENT

A. Design. Provide cable with the following design characteristics. Cable shall be UL listed type MV-105 suitable for operation on a medium voltage (grounded or ungrounded) system. Provide cable rated 3 phase, 3 wire, 60 Hz with an insulation level and a continuous conductor temperature as specified on the data sheets. The conditions apply in wet or dry locations whether installed in underground duct or conduit. Use only 3-conductor cable and single-conductor cable size No. 1/0 and larger which are suitable for cable tray installation.

B. Conductors. Provide conductors which are bare, uncoated copper or tinned (See data sheet), class B stranded per ASTM B 3, ASTM B 8, and ASTM B 33 unless otherwise specified on the data sheets. Size conductors in conformance with at least the minimums given in Table 3.1 of ICEA S-68-516 or S-66-524. Provide the number and size of conductors supplied in each cable corresponding to the quantities specified on the data sheets.

C. Conductor Shielding. Use conductor with a shield composed of extruded semi-conducting compound or semi-conducting tape applied in accordance with the Part 2 of ICEA S-68-516 or S-66-524.

D. Insulation. Conductor insulation as specified on the data sheets, shall conform to the physical and electrical requirements of Part 3 of ICEA S-68-516 or S-66-524.

E. Insulation Shielding. Provide each insulated conductor with an insulation shield consisting of a nonmetallic covering located directly over the insulation and a nonmagnetic metal component directly over or embedded in the covering. The materials used in the insulation shield and the method of construction shall comply with Part 4 of ICEA S-68-516 or S-66-524 and UL-1072.

1. The short-circuit capacity of the conductor insulation shielding shall be the larger value of either the capacity defined in ICEA P-45-482 or that shown in the following table:

Shield Diameter Inches	Short-Circuit Amps for 8 Cycles	Short-Circuit Amps for 16 Cycles
1/2	1400	1000
3/4	2100	1500
1	2800	2000
1-1/4	3500	2500
1-1/2	4200	3000
1-3/4	5000	3500
2	5700	4000
2-1/4	6400	4500
2-1/2	7100	5000
2-3/4	7800	5500
3	8500	6000

F. Jacket. When medium voltage power cables are enclosed in conduit, duct or in other raceway systems, the cables shall be of the non-armored type with an overall nonmetallic jacket covering single- and 3-conductor cables as specified on the data sheets and conforming to the requirements of Part 4 of ICEA S-68-516 or S-66-524.

G. Armor. When medium voltage power cables are exposed in cable tray, cable channel or other cable support systems, the 3-conductor cables shall be protected by an interlocked metal armor made of galvanized steel or aluminum which meets the requirements of paragraph 4.5 of ICEA S-68-516 or S-66-524 (see data sheet).

H. Splice Kits. For 5 kv to 8.7 kv cable, use splice kits with a uniform cross-section, heat-shrinkable, high voltage splice system, such as Raychem HVS-803, or equal.

I. Marking. Mark the jacket of cables as required by paragraphs 201, 202, 203, and 204 of UL 1072, unless otherwise specified.

PART 3 EXECUTION

3.01 PREPARATION

A. Complete cable raceway systems, underground duct banks, and cable support systems before installing cables.

B. Verify sizing of raceways and pullboxes to ensure proper accommodation for the cables.

C. Check the length of the cable raceway system against the length of cable on the selected reel.

D. Do not install or work on PVC insulated or jacketed cables in temperatures below 32 F.

3.02 INSTALLATION

A. Cable in Conduit and Ductbank

1. Clean conduits of foreign matter before cables are pulled.

2. Install cables in accordance with the manufacturer's instructions and the National Electrical Code (NEC). Do not exceed maximum wire tension, maximum insulation pressure, and minimum bending radius.

3. Pull cables into conduits using wire pulling compounds approved by cable manufacturers to reduce friction. Lubricants must not be harmful to the conductor insulation. Mixtures containing soap or detergent shall not be used.

B. Cable in Tray

1. Provide medium voltage cable installation in trays per NEC 392.20(B).

2. Install cables in trays in a neat and orderly manner. Tie cables to tray rungs at approximate 15-foot intervals by use of cable ties.

C. Preparation for Termination

1. Do not splice medium voltage cable.

2. For 5 kv to 8.7 kv cable, use specified splice kits.

3. Make terminations of cables at switchgear and motors using preformed stress relief cones rated for phase-to-phase voltage.

4. Use crimp-on terminal lugs and connectors for all sizes of conductors.

5. Use crimp-on lugs with long barrel and 2-hole tongues, except in places where terminations space is limited.

D. Tests.

1. Before connecting the medium voltage cables, test insulation integrity.

2. Have qualified electrical testing company perform Megar and Hi Potential tests on newly-installed cables.

3. Use a 5 kv DC megohmeter and perform the cable insulation test in accordance with operating instructions.

4. Record test data for each cable test and report meggering test complete with signatures of the City Engineer or designated representative who witnessed the testing.

E. Termination.

1. After the cable has been tested with satisfactory results, terminate the medium voltage cable at both ends to designated terminal points.

2. Tighten connection bolts with a torque wrench to specified torque levels.

END OF SECTION

DATA SHEETS 1 of 3

IDENTIFICATION

CLIENT _____ MANUFACTURER _____
PROJECT _____ MODEL NO. _____
JOB NO. _____ SIZE _____
PLANT LOCATION _____ SERIAL NO. _____
ITEM NO. _____ INQUIRY NO. _____
SERVICE _____ P.O. NO. _____
NO. ITEMS REQUIRED _____

OPERATING DATA

VOLTAGE _____ FREQUENCY _____ AMBIENT TEMP (°C) _____
INSTALLATION ENVIRONMENT _____

CONSTRUCTION

CONDUCTORS

SIZE (AWG or MCM): _____
ARRANGEMENT: _____ SINGLE CONDUCTOR _____ OTHER
_____ MULTI-CONDUCTOR _____ NO. OF CONDUCTORS
MATERIAL: _____ COPPER _____ ALUMINUM _____ TINNED COPPER
SINGLE CONDUCTOR: _____ JACKETED _____ NON-JACKETED
MULTI-CONDUCTOR _____ JACKETED _____ NON-JACKETED (TRIPLEXED ONLY)
_____ ARMORED _____ ARMORED W/OUTER JACKET
_____ GROUND WIRES IN INTERSTICES: _____ COPPER _____ ALUMINUM
SHIELDING: _____ YES _____ NO
_____ EXTRUDED SEMI-CONDUCTING COMPOUND _____ SEMI-CONDUCTING
ASTM STANDARD: _____
SPECIAL REQUIREMENTS: _____

INSULATION

TYPE: _____ CROSS LINKED POLYETHYLENE _____ CHLOROSULFONATED POLYETHYLENE
_____ POLYVINYL CHLORIDE _____ ETHYLENE-PROPYLENE RUBBER
_____ POLYETHYLENE _____ OTHER _____
THICKNESS (MILS OR MM) _____
COLOR: _____
TEMPERATURE RATING: _____ 60°C - 75°C (WET-DRY) _____ 75°C - 90°C (WET-DRY)
_____ 90°C (WET-DRY) _____ OTHER _____
INSULATING RATING: _____ 100% _____ 133% _____ 173% _____ OTHER _____
SHIELDING: _____ YES ___ NO ___ EXTRUDED ___ TAPE
_____ HELICAL COPPER TAPES _____ HELICAL COPPER WIRES
_____ LONGITUDINAL DRAIN WIRES _____ BARE COPPER
_____ COATED BARE COPPER _____ OTHER: _____
ICEA STANDARD: _____
SPECIAL REQUIREMENTS: _____

ITEM NO. _____

DATA SHEETS 2 of 3

JACKET

TYPE: _____ POLYVINYL CHLORIDE _____ POLYETHYLENE
_____ HEAVY DUTY NEOPRENE _____ CHLOROSULFONATED POLYETHYLENE
_____ NYLON _____ OTHER _____
_____ _____ _____

THICKNESS (MILS OR MM) _____

COLOR: _____ BLACK _____ OTHER _____

ICEA STANDARD: _____

SPECIAL REQUIREMENTS: _____

ARMORING

TYPE: _____ INTERLOCKED (POSITIVE) _____ OTHER _____

MATERIAL: _____ GALVANIZED STEEL _____ ALUMINUM
_____ OTHER _____

COVERING: _____ POLYVINYL CHLORIDE _____ OTHER _____

COLOR: _____ BLACK _____ 5 & 8 KV YELLOW _____ 15 KV RED ____ 35 KV ORANGE
_____ OTHER _____

ICEA STANDARD: _____

SPECIAL REQUIREMENTS: _____

CABLE MARKING

REQUIRED:
_____ MANUFACTURER _____ CONDUCTOR SIZE
_____ NO. OF CONDUCTORS _____ VOLTAGE RATING
_____ UL LABEL _____ NEC TYPE
_____ TEMPERATURE RATING _____ MONTH/YEAR OF MANUFACTURE
_____ OTHER _____

CONDUCTOR IDENTIFICATION

SINGLE CONDUCTOR: _____

MULTI-CONDUCTOR: _____

FACTORY TESTING/DOCUMENTATION

_____ PHYSICAL _____ _____ FLAME TESTS (PER IEEE 383 - 2.5) _____

_____ ELECTRICAL _____ OTHER TESTS _____
_____ MEGGER
_____ OTHER _____

QUALITY ASSURANCE

_____ NO ADDITIONAL REQUIREMENTS _____ ATTACHED SPECIFICATION _____

PACKAGING

_____ DOMESTIC _____ EXPORT

SHIPPING

REEL TYPE: _____ RETURNABLE _____ NON-RETURNABLE _____ LENGTH PER REEL _____

ITEM NO. _____

DATA SHEETS 3 of 3

SHIPPING (Cont'd)

ADDITIONAL REQUIREMENTS: _____

MANUFACTURER DATA

CABLE DIMENSION (O.D. IN.) _____ SHIPPING TIME _____
CABLE CROSS-SECTIONAL AREA _____ OTHER _____
CABLE WEIGHT (LBS/FT) _____
TENSILE STRENGTH _____
GROSS WEIGHT/REEL (LBS) _____
TOTAL CUBIC FEET/REEL _____
SHORT CIRCUIT WITHSTAND CURVES _____
CABLE TESTING REQUIREMENTS _____

NOTES

ITEM NO. _____

Section 16125

THERMOCOUPLE EXTENSION CABLE

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for thermocouple extension cable.

1.02 REFERENCES

A. American Society for Testing and Materials (ASTM).

1. ASTM B3: Specification for Soft or Annealed Copper Wire.

2. ASTM B8: Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium Hard, Soft.

3. ASTM B33: Specification for Tinned Soft or Annealed Copper Wire for Electrical Purposes.

B. American National Standards Institute (ANSI), ANSI MC96.1: Temperature Measurement Thermocouples.

C. Institute of Electrical and Electronics Engineers (IEEE), IEEE 383-2.5: IEEE Standard for Type Test of Class IE Electric Cables, Field Splices, and Connections for Nuclear Power Generating Stations.

D. Insulated Cable Engineers Association (ICEA).

1. ICEA S-61-402: Thermoplastic-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-5).

2. ICEA S-66-524: Cross-Linked-Thermosetting-Polyethylene-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-5).

3. ICEA S-68-516: Ethylene-Propylene-Rubber-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy (NEMA WC-8).

4. American National Standards Institute/National Fire Protection NEC), Article 725, Class 1, Class 2, and Class 3 Remote-Controls, (Signaling, and Power-Limited Circuits).

5. Underwriters' Laboratories (UL), UL Subject 13: Listing Mark and Follow-up Inspection.

1.03 SUBMITTALS

A. Submit under the provisions of Section 01330 the following:

1. Completed engineer's data sheets from this specification or manufacturer's data sheets, cut sheets and catalog data.

2. Installation, terminating and splicing procedure (including bend radius and pulling tension data).

3. Instruction for handling and storage.

4. Dimensions and weight.

1.04 QUALITY ASSURANCE

A. Tests.

1. Cable shall be tested at the factory to confirm that the cable complies with requirements of this specification. Perform manufacturer's standard test and those listed in UL Subject 13.

2. Perform any additional tests specified on the Thermocouple Extension Cable Data Sheets.

3. Where applicable, the cable shall meet the requirements of the vertical tray flame test as described in IEEE 383-2.5.

4. Manufacturer shall perform any additional test and inspection required to ensure that cable meets requirements specified on the Thermocouple Extension Cable Data Sheets.

1.05 DELIVERY, STORAGE AND HANDLING

A. Ship cable on manufacturer's standard reel sizes unless otherwise specified. Where cut lengths are specified, mark reel footage accordingly. Each reel shall contain one continuous length of cable. Reels shall be of the type specified on the data sheets. Provide impact protection by wood lagging or suitable barrier across the traverse of the reel. Provide moisture protection by manufacturer's standard procedure or heat shrinkable self-sealing end caps applied to both ends of the cable.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

A. Alpha Wire Corporation

B. Belden Div., Cooper Industries, Inc.

C. Cablec Continental Cables Company

D. General Cable Company

E. Manhattan Electric Cable Corporation

F. Okonite Company

2.02 MATERIALS AND EQUIPMENT

A. Design. Provide cable with the following design characteristics. Cable is used to connect field-mounted thermocouples to temperature monitoring and recording devices. The cable assembly shall consist of individually insulated conductors covered by an overall jacket. The cable is intended for circuits in accordance with Article 725 of the National Electric Code and the Thermocouple Extension Cable Data Sheets. Install thermocouple extension cable in underground duct, conduit, or cable tray. The type of conductors, the number of pairs, and other requirements of each cable shall be specified on the Thermocouple Extension Cable Data Sheets.

B. Construction. Provide conductors made from metals matching the characteristics of the thermocouple and with wire size as specified on the Thermocouple Extension Cable Data Sheets. Select conductor with a calibrated tolerance which is within the standard or special limits of error defined in ANSI MC96.1 and as specified on the Thermocouple Extension Cable Data Sheets.

C. Insulation. The primary insulation of each conductor is specified on the Thermocouple Extension Cable Data Sheets. The physical and electrical properties of the insulation shall comply with the requirements of UL Subject 13.

D. Drain Wire. Provide drain wire which is Class B, seven-stranded or solid; and bare or tin-coated copper in accordance with ASTM B3, B8 or B33, and as specified on the Thermocouple Extension Cable Data Sheets.

E. Shielding. Provide shielding consisting of laminated, nonburning, mylar-backed aluminum tape applied helically around a twisted pair of conductors with the aluminum side in continuous contact with the drain wire unless otherwise specified on the Thermocouple Extension Cable Data Sheets.

F. Wrap the tape around the conductors with a 25 percent minimum overlap unless otherwise specified on the Thermocouple Extension Cable Data Sheets.

G. Jacket. The jacket used to cover single and multi-pair cables is specified on the Thermocouple Extension Cable Data Sheets. The physical and electrical properties of the jacket shall comply with the applicable requirements of UL Subject 13. The jacket thickness shall match the dimensions shown in Table 10 of UL Subject 13.

H. Single Pair Cables. Each pair shall consist of two individually insulated conductors with a drain wire, wrapped by a shield and covered by an overall jacket as specified on the Thermocouple Extension Cable Data Sheets.

I. Multi-Pair Cables. Multi-pair cables shall consist of the required number of electrically isolated, shielded, twisted, insulated pairs which are bundled together and covered by an overall shield and jacket as specified on the Thermocouple Extension Cable Data Sheets.

J. Armor or Barrier. Where requested, use thermocouple extension cables protected by an interlocked metal tape armor coating made of galvanized steel, which meets the requirements of paragraph 4.5 of ICEA S-68-516 or S-66-524 unless otherwise specified on the Thermocouple Extension Cable Data Sheets.

K. Conductor Identification. Use individual conductors in each cable which are color coded in accordance with Table 6 of ANSI MC96.1, and as specified on the Thermocouple Extension Cable Data Sheets.

L. Cable Marking. Print cable marking information on the jacket of each cable at 2-foot intervals. Use a permanent printing method with a color sharply contrasting the jacket color. See the Thermocouple Extension Cable Data Sheets for the minimum information required.

PART 3 EXECUTION

3.01 PREPARATION

A. Complete cable raceway systems, underground duct banks and cable support systems before installing cables.

B. Verify sizing of raceways and pullboxes to ensure proper accommodation for the cables.

C. Check the length of the cable raceway system against the length of cable on the selected reel.

D. Do not install or work on PVC insulated or jacketed cables in temperatures below 32 degrees F.

E. Clean conduits of foreign matter before cables are pulled.

3.02 INSTALLATION

F. Cable in Conduit and Duct Bank

1. Install cables in accordance with the manufacturer's instructions and NEC Article 725 - Class 1, Class 2, and Class 3 Remote-Control, Signaling and Power-Limited Circuit. Do not exceed maximum wire tension, maximum insulation pressure and minimum bending radius.

2. Pull cables into conduits using adequate lubrication to reduce friction. Lubricants must not be harmful to the conductor insulation.

3. Conduits carrying low level signal cables shall be PVC-coated rigid steel.

4. Use thermocouple leads that are continuous from instrument to thermocouple. Do not splice extension cable. Where junctions are unavoidable, make connections only on terminal blocks enclosed in suitable boxes. Generally, use such boxes only in installation involving a large number of thermocouples where multiconductor cable is applicable. Take care in locating such boxes in areas that have comparatively stable ambient temperature conditions. Avoid hot locations.

5. Do not install thermocouple leads in the same conduit or pull box with any other wiring.

6. Make the connection between thermocouple lead and rigid conduit by running cable in a flexible conduit forming a drip loop to prevent excessive moisture from entering the conduit system.

G. Cable in Tray. Install thermocouple extension cable in cable tray only when the tray is dedicated for this type cables and cables are approved for tray installation.

H. Termination

1. Do not splice conductors.

2. For shielded thermocouple cable, terminate the shield and ground it at one end only, preferably at the control panel end.

3. If splicing is required, maintain shield continuity by jumpering the ground shield across connection point where it is broken at junction boxes, or other splice points. Insulate these points from ground.

4. Mark wiring on both ends with circuit numbers or loop tag numbers. Heat shrink wire markers after the ring or fork terminal has been installed. Extend the marker over the crimp or base of the terminal.

END OF SECTION

DATA SHEET 1 of 4

IDENTIFICATION

CLIENT _____ MANUFACTURER _____
PROJECT _____ MODEL NO. _____
JOB NO. _____ SIZE _____
PLANT/LOCATION _____ SERIAL NO. _____
ITEM NO. _____ INQUIRY NO. _____
SERVICE _____ P.O. NO. _____
QUANTITY REQUIRED _____

NOTE: [ ] INDICATES INFORMATION TO BE COMPLETED BY SELLER

ENVIRONMENTAL CONDITIONS

TEMPERATURE RANGE: MAX _____ °C MIN _____ °C
INSTALLATION: _____ ENCLOSED _____ OUTDOORS _____ INDOORS
_____ UNDERGROUND UNDERWATER _____
EXPOSURE: _____ MOISTURE _____ DIRT _____ OZONE
_____ RADIATION ____CHEMICALS:(PLEASE LIST) _____
_____
SOILS: (PLEASE LIST) _____ELECTROSTATIC INTERFERENCE _____
ELECTROMAGNETIC INTERFERENCE DISTURBANCES _____RODENTS _____
OTHER: _____

PHYSICAL REQUIREMENTS

FLEXIBILITY: _____ VERY FLEXIBLE _____ FLEXIBLE _____ NOT CRITICAL
RESISTANCE TO: _____ ABRASION _____ IMPACT _____ CRUSH
_____ DEFORMATION _____ CUT THROUGH _____ COLD FLOW
TERMINATION METHOD: _____
ADDITIONAL REQUIREMENTS: _____

ELECTRICAL REQUIREMENTS

_____ CROSS TALK (ISOLATION IN DB AT FREQ)
_____ DC RESISTANCE (OHMS/1000 FT)
_____ VOLTAGE BREAKDOWN (VOLTS/MILL)
_____ INSULATION RESISTANCE (MEGOHMS/1000 FT)

ADDITIONAL REQUIREMENTS: _____

_____ CLASS I _____ CLASS II _____ CLASS III
_____ 600 VOLT _____ 150 VOLT _____ 300 VOLT
ADDITIONAL REQUIREMENTS: _____

THERMOCOUPLE EXTENSION CABLE

DATA SHEET 2 of 4

TYPE

DESIGN TEMPERATURE SCALE: _____ CELSIUS _____ FAHRENHEIT

_____ JX _____ KX _____ TX _____ EX

_____ SX _____ RX _____ BX

_____ OTHER _____

CONSTRUCTION

CONDUCTORS

SIZE (AWG): _____

_____ COPPER _____ STRANDED _____ SOLID

_____ LIMITS OF ERROR _____

ADDITIONAL REQUIREMENTS: _____

INSULATION

RUBBER: _____ SBR _____ NATURAL _____ SYNTHETIC ____ BUTYL _____ POLYBUTADIENE

_____ NEOPRENE _____ NBR _____ EPR/EPT ____CHLOROSULFONATED POLYETHYLENE _____ SILICONE

PLASTIC: _____ PVC _____ LOW-DENSITY POLYETHYLENE _____CELLULAR POLYETHYLENE

_____ TEFLON

_____ HIGH-DENSITY POLYETHYLENE _____ POLYPROPYLENE _____ POLYURETHANE

_____ NYLON _____ OTHER: _____

VOLTAGE RATING: _____ AC _____ DC WALLTHICKNESS _____

NUMBER OF CONDUCTORS: _____ NUMBER OF PAIRS: _____

NUMBER OF TRIADS: _____

LAY LENGTH PER INCH OF PAIRS: _____ LAY _____ TWIST-COATED

DRAIN WIRE: _____ SIZE _____ STRANDED _____ SOLID _____ BARE COPPER _____ TIN-COATEDCOPPF

COLOR _____

TEMPERATURE RATING: _____ 60° - 75°C (WET-DRY) _____75°C - 90°C (WET-DRY)

_____ 90°C (WET-DRY) _____105°C

OTHER: _____

SPECIAL REQUIREMENTS: _____

SHIELDING

TYPE SHIELDING: _____ BRAIDED _____ CONDUCTIVE PLASTIC

_____ CONDUCTIVE COTTON _____ SPIRAL-SERVED

_____ MYLAR FILM-ALUMINUM FOIL _____POLYESTER FILM-ALUMINUM FOIL

_____ OTHER: _____

POLYESTER FILM-ALUMINUM LOCATION _____ INSIDE _____ OUTSIDE_____ PAIR SHIELD ISOLATED

_____ SEPARATOR _____ FILTER

SHIELD COMBINATION

OVERSHIELD: _____ POLYESTER FILM-ALUMINUM

_____ BRAID _____SERVED

_____OTHER: _____

DATA SHEET 3 of 4

SHIELD COMBINATION (CONT)

BRAID SHIELD: _____ TYPE STRANDS _____% COVERAGE __ TINNED
_____ BARE _____COPPER _____ ALUMINUM
OVERALL TYPE: _____ POLYESTER _____ PAPER _____ OTHER: _____

SHIELD OVERLAP _____%

JACKET

TYPE: _____ POLYVINYL CHLORIDE _____ POLYETHYLENE
_____ HEAVY DUTY NEOPRENE _____ CHLOROSULFONATED POLYETHYLENE
_____ KAPTON _____ TEFLON
_____ NYLON _____ OTHER: _____

THICKNESS (MILS OR MM) _____
COLOR: _____ BLACK _____ OTHER:_____
SPECIAL REQUIREMENTS: _____

ARMOR OR BARRIER

TYPE: _____ INTERLOCKED (POSITIVE) OTHER: _____
_____ SERVED ARMOR _____ BONDED BARRIER
MATERIAL: _____ GALVANIZED STEEL _____ ALUMINUM
_____ OTHER: _____
COVERING: _____ POLYVINYL CHLORIDE _____ OTHER: _____
COLOR: _____ BLACK _____ OTHER: _____
SPECIAL REQUIREMENTS: _____

MARKING

CONDUCTOR IDENTIFICATION

SINGLE-CONDUCTOR: _____
MULTI-CONDUCTOR: _____

CABLE MARKING

REQUIRED: _____ MANUFACTURER _____ CONDUCTOR SIZE
_____ NO. OF CONDUCTORS _____ VOLTAGE RATING
_____ UL LABEL _____ NEC TYPE
_____ TEMPERATURE RATING _____ MONTH/YEAR OF MANUFACTURE
_____ OTHER: _____

FACTORY TESTING/DOCUMENTATION

_____ PHYSICAL _____ FLAME TESTS (SPECIFY STANDARDS)_____

_____ ELECTRICAL _____ OTHER TESTS:_____
_____ MEGGER
_____ OTHER:_____

DATA SHEET 4 of 4

QUALITY ASSURANCE

_____ NO ADDITIONAL REQUIREMENTS _____ ATTACHED SPECIFICATION _____

PACKAGING

_____ DOMESTIC _____ EXPORT

SHIPPING

REEL TYPE: _____ RETURNABLE _____ NON-RETURNABLE _____ LENGTH PER REEL _____

ADDITIONAL REQUIREMENTS: _____

MANUFACTURER DATA

CABLE DIMENSION (O.D. IN.) _____ SHIPPING TIME _____
CABLE CROSS-SECTIONAL AREA _____ OTHER _____
CABLE WEIGHT (LBS/FT) _____
CABLE MIN BENDING RADIUS _____
TENSILE STRENGTH _____
GROSS WEIGHT/REEL (LBS) _____
TOTAL CUBIC FEET/REEL _____
SHORT CIRCUIT WITHSTAND CURVES _____
CABLE TESTING REQUIREMENTS _____

NOTES

Section 16126

INSTRUMENTATION CABLE

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for instrumentation cable.

1.02 REFERENCES

A. The equipment in this specification shall be designed and manufactured according to latest revision of the following standards (unless otherwise noted):

1. NFPA 70 – National Electrical Code (NEC)

2. NEMA WC-5 – Thermoplastic-Insulated Wire and Cable for the Transmission and Distribution of Electrical Energy

3. ANSI/TIA/EIA 606A – Standard for telecommunications Infrastructure.

B. Underwriters' Laboratories (UL).

4. UL 44: Rubber Insulated Wires and Cables.

5. UL 83: Thermoplastic Insulated Wire and Cables.

1.03 SUBMITTALS

A. Submit the following under the provisions of Section 01330 – Submittal Procedures:

1. Completed engineer's data sheets from this specification or manufacturer's data sheets, cut sheets, and catalog data.

2. Installation, terminating and splicing procedure (including bending radius and pulling tension data).

3. Instruction for handling and storage.

4. Dimensions and weight.

1.04 QUALITY ASSURANCE

A. Tests

1. Cable shall be tested at the factory to confirm that the cable complies with requirements of ICEA Section 7.7.9 of S-66-524 or 7.5.9 of S-68-516. Refer to data sheet for additional test requirements.

2. Where applicable, the cable shall meet the requirements of the vertical tray flame test as described in IEEE 383-2.5.

1.05 DELIVERY, STORAGE AND HANDLING

A. Ship cable on manufacturer's standard reel sizes unless otherwise specified. Where cut lengths are specified, mark reel footage accordingly. Each reel shall contain one continuous length of cable. Reels shall be of the type specified on the data sheets. Provide impact protection by wood lagging or suitable barrier across the traverse of the reel. Provide moisture protection by manufacturer's standard procedure or heat shrinkable self-sealing end caps applied to both ends of the cable.

PART 2 P R O D U C T S

2.01 MANUFACTURERS

A. Alpha Wire Corporation

B. Belden Division, Cooper Industries, Inc.

C. Cablec Continental Cables Company

D. General Cable Company

E. Manhattan Electric Cable Corporation

F. Okonite Company

2.02 MATERIALS AND EQUIPMENT

A. Design. Provide cable with the following design characteristics. The cable shall consist of multiple conductors. The cable assembly shall be UL listed, flame, oil and sunlight resistant, and certified for continuous operation at the temperature specified on the Instrumentation Cable Data Sheets in wet or dry locations while installed in underground duct, conduit, or cable tray. The

number and size of conductors supplied in each cable shall correspond to the quantities specified on the Instrumentation Cable Data Sheets. Each conductor shall be individually insulated. Pairs and triads shall have conductors which are twisted together with a drain wire, shielded, and covered with a jacket. Multi-pair/triad cables shall consist of the required number of electrically isolated, shielded pairs or triads, which are bundled together and covered by an overall jacket as specified on the Instrumentation Cable Data Sheets.

B. Conductors. Provide conductors which are Class B, concentric stranded, annealed tinned copper whose physical and electrical properties comply with ASTM B3, B8 or B33 and Part 2 of ICEA S-61-402, S-66-524, or S-68-516, unless otherwise specified on the Instrumentation Cable Data Sheets.

C. Insulation. Each conductor shall be insulated as specified on the Instrumentation Cable Data Sheets in compliance the requirements of Part 3 of ICEA S-61-402, S-66-524, or S-68-516. The average insulation thickness shall not be less than the dimensions shown in Table 7-32 or 7.5.1 of ICEA S-66-524 or S-68-516 for 600-volt insulation unless otherwise specified on the Instrumentation Cable Data Sheets. The minimum insulation thickness shall not be less than 90 percent of the value given in the table.

D. Drain Wire. Provide drain wire which is Class B, seven-stranded, tin-coated copper in accordance with ASTM B3, B8, or B33 and as specified on the Instrumentation Cable Data Sheets. The drain wire shall not be less than two AWG sizes smaller than the insulated conductor's size, except for multiple pair triad drain wires, which shall not be less than the insulated conductor size.

E. Shielding. Provide shielding consisting of laminated, nonburning, mylar-backed aluminum tape applied helically around a twisted pair or triad with the aluminum side in continuous contact with the drain wire unless otherwise specified on the Instrumentation Cable Data Sheet. Wrap the tape around each twisted pair or triad with a 25 percent minimum overlap unless otherwise specified on the Instrumentation Cable Data Sheets.

F. Jacket. The physical and electrical properties of the jacket used to cover single or multi-pair or triad cables shall meet the requirements of section 7.7.7 or ICEA S-66-524 or section 7.5.6 of ICEA S-68-516. Jacket material is specified on the Instrumentation Cable Data Sheets. The jacket thickness shall be equal to the dimensions shown in Table 7-33 or 7.5.2 of ICEA S-66-524 or S-68-516. The jacket material is specified on the Instrumentation Cable Data Sheets. The jacket thickness shall be equal to the dimensions shown in Table 7-33 or 7.5.2 of ICEA S-66-524 or S-68-516.

G. Armor. Where requested, use instrumentation cables protected by an interlocked metal tape armor coating made of galvanized steel which meets the requirements of paragraph 4.5 of ICEA S-68-516 or S-66-524, unless otherwise specified on the Instrumentation Cable Data Sheets.

H. Conductor Identification. Use individual conductors in single-pair and single-triad cables which are color coded black and white; and black, white and red, respectively. Multi-pair-triad cables shall have one conductor in each pair or triad colored white, and all other conductors are color coded in sequence according to Table L-2 of Appendix 2 of ICEA S-66-524, and as specified on the Instrumentation Cable Data Sheets.

I. Cable Marking. Print cable marking information on the jacket of each cable at 2-foot intervals. Use a permanent printing method with color sharply contrasting the jacket color. See the Instrumentation Cable Data Sheets for the minimum information required.

PART 3 EXECUTION

3.01 PREPARATION

A. Complete cable raceway systems, underground duct banks and cable support systems before installing cables.

B. Verify sizing of raceways and pullboxes to ensure proper accommodation for the cables.

C. Check the length of the cable raceway system against the length of cable on the selected reel.

D. Do not install or work on PVC insulated or jacketed cables in temperatures below 32 degrees F.

E. Clean conduits of foreign matter before cables are pulled.

F. Provide at least 30 percent spare conductors or pairs.

3.02 INSTALLATION

A. Cable in Conduit and Ductbank

1. Install cables in accordance with the manufacturer's instructions and NEC Article 725 - Class 1, Class 2, and Class 3 Remote Control, Signaling and Power Limited Circuits. Do not exceed maximum wire tension, maximum insulation pressure and minimum bending radius.

2. Pull cables into conduits using adequate lubrication to reduce friction. Lubricants must not be harmful to the conductor insulation or cable jacket.

3. Conduits carrying low level signal cables shall be PVC-coated rigid steel.

B. Cable in Tray. Install instrument and signal cable in cable tray only when the tray is dedicated for this type cable and cables are approved for tray installation.

C. Termination

1. Do not splice conductors. For termination use crimp-on type ring tongue non-insulated tin plated copper lugs.

2. For shielded control cable, terminate the shield and ground it at one end only, preferably at the control panel end for instrument and communication cable and at the supply end for electronic power cables.

3. If splicing is required, maintain shield continuity by jumpering the ground shield across connection point where it is broken at junction boxes, or other splice points. Insulate these points from ground.

4. Mark wiring on both ends with circuit numbers or loop tag numbers. Heat shrink wire markers after the ring tongue terminal has been installed. Extend the marker over the crimp or base of the terminal.

D. Tests

1. Before connecting the cables, test insulation integrity and conductor continuity.

2. Use a 500 VDC megohmmeter and perform the cable insulation test in accordance with the operating instructions.

E. Termination. After the 600-volt cable has been tested with satisfactory results, the cable can be terminated at both ends to their designated terminal points.

END OF SECTION

DATA SHEET 1 of 4

IDENTIFICATION

CLIENT _____ MANUFACTURER _____
PROJECT _____ MODEL NO. _____
JOB NO. _____ SIZE _____
PLANT/LOCATION _____ SERIAL NO. _____
ITEM NO. _____ INQUIRY NO. _____
SERVICE _____ P.O. NO. _____
QUANTITY REQUIRED _____

NOTE: [ ] INDICATES INFORMATION TO BE COMPLETED BY MANUFACTURER

ENVIRONMENTAL CONDITIONS

TEMPERATURE RANGE: MAX _____ °C, MIN _____ °C
INSTALLATION: _____ ENCLOSED _____ OUTDOORS _____ INDOORS_____
_____ UNDERGROUND _____ UNDERWATER_____
EXPOSURE: _____ MOISTURE _____ DIRT _____ OZONE_____
_____ RADIATION _____ CHEMICALS:(PLEASE LIST) _____
SOILS: (PLEASE LIST) _____ ELECTROSTATIC INTERFERENCE _____
ELECTROMAGNETIC INTERFERENCE DISTURBANCES _____ RODENTS _____
OTHER: _____

PHYSICAL REQUIREMENTS

FLEXIBILITY: _____ VERY FLEXIBLE _____ FLEXIBLE _____ NOT CRITICAL
RESISTANCE TO: _____ ABRASION _____ IMPACT _____ CRUSH
_____ DEFORMATION _____ CUT THROUGH COLD FLOW
TERMINATION METHOD: _____

STRIPPABILITY: _____ MANUAL
_____ AUTOMATIC EQUIPMENT TYPE _____

ELECTRICAL REQUIREMENTS

_____ FREQUENCY (HZ) _____ CROSS TALK (ISOLATION IN DB AT FREQ)
_____ CURRENT (MILLIAMP) _____ DC RESISTANCE (OHMS/1000 FT)
_____ CAPACITANCE (PFD) _____ VOLTAGE BREAKDOWN (VOLTS/MILL)
_____ ATTENUATION (DB/100 FT) _____ INSULATION RESISTANCE (MEGOHMS/1000 FT)
ADDITIONAL REQUIREMENTS: _____

ITEM NO. _____

INSTRUMENTATION CABLE

DATA SHEET 2 of 4

CONSTRUCTION

CONDUCTORS

SIZE (AWG): ___
_____ COPPER _____ STEEL _____ TINNED
_____ BARE _____ SOLID _____ COPPER COATED
_____ STRANDED _____ SILVER COATED
NUMBER OF CONDUCTORS: _____ NUMBER OF PAIRS _____
NUMBER OF TRIADS _____
ADDITIONAL REQUIREMENTS: _____

INSULATION

RUBBER: _____ SBR _____ NATURAL _____ SYNTHETIC _____ BUTYL_POLYBUTADIENE
_____ NEOPRENE _____ NBR _____ EPR/EPT
_____ CHLORSULFONATED POLYETHYLENE _____ SILICONE
PLASTIC: _____ PVC ____ LOW-DENSITY POLYETHYLENE _____ CELLULAR POLYETHYLENE ___
TEFLON
_____ HIGH-DENSITY POLYETHYLENE _____ POLYPROPYLENE _____ POLYURETHANE
_____ NYLON _____ OTHER: _____
VOLTAGE RATING: _____ AC _____ DC WALL THICKNESS _____
LAY LENGTH PER INCH OF PAIRS: _____ LAY _____ TWIST
DRAIN WIRE: _____ SIZE ____ STRANDED __ SOLID _____ BARE COPPER _ TIN-COATED COPPER
COLOR _____
TEMPERATURE RATING: _____ 60° - 75°C (WET-DRY) __ 75°C - 90°C (WET-DRY)
_____ 90°C (WET-DRY) _____ OTHER: _____
SPECIAL REQUIREMENTS: _____

SHIELDING

TYPE SHIELDING: _____ BRAIDED _____ CONDUCTIVE PLASTIC
_____ CONDUCTIVE COTTON _____ SPIRAL-SERVED
_____ MYLAR FILM-ALUMINUM FOIL __POLYESTER FILM-ALUMINUM FOIL
_____ OTHER: _____
POLYESTER FILM-ALUMINUM LOCATION: _____ INSIDE _ OUTSIDE_____ PAIR SHIELD ISOLATED
_____ SEPARATOR _____ FILTER

SHIELD COMBINATION

OVERSHIELD: _____ POLYESTER FILM-ALUMINUM __ BRAID _ SERVED
_____ OTHER: _____
BRAID SHIELD: _____ TYPE STRANDS _____% COVERAGE _ TINNED
_____ BARE _ COPPER _____ ALUMINUM
OVERALL TYPE: _____ POLYESTER _____ PAPER ___ OTHER: ____

JACKET

TYPE: _____ POLYVINYL CHLORIDE _____ POLYETHYLENE
_____ HEAVY DUTY NEOPRENE _____ CHLOROSULFONATED POLYETHYLENE
_____ NYLON _____ OTHER: _____

ITEM NO. _____

DATA SHEET 3 of 4

JACKET (Cont)

THICKNESS (MILS OR MM) _____
COLOR: _____ BLACK _____ OTHER: _____
SPECIAL REQUIREMENTS: _____

ARMORING

TYPE: _____ INTERLOCKED (POSITIVE) OTHER: _____
MATERIAL: _____ GALVANIZED STEEL _____ ALUMINUM _____
_____ OTHER: _____
COVERING: _____ POLYVINYL CHLORIDE _____ OTHER: _____
COLOR: _____ BLACK _____ OTHER: _____
SPECIAL REQUIREMENTS: _____

MARKING

CONDUCTOR IDENTIFICATION

SINGLE-CONDUCTOR: _____
MULTI-CONDUCTOR: _____

CABLE MARKING

REQUIRED: _____ MANUFACTURER _____ CONDUCTOR SIZE
_____ NO. OF CONDUCTORS _____ VOLTAGE RATING
_____ UL LABEL _____ NEC TYPE
_____ TEMPERATURE RATING _____ MONTH/YEAR OF MANUFACTURE
_____ OTHER: _____

FACTORY TESTING/DOCUMENTATION

_____ PHYSICAL _____ _____ FLAME TESTS (SPECIFY STANDARDS) _____
_____ ELECTRICAL _____ OTHER TESTS: _____
_____ MEGGER
_____ OTHER: _____ _____
_____ _____
_____ _____
_____ _____

QUALITY ASSURANCE

_____ NO ADDITIONAL REQUIREMENTS _____ ATTACHED SPECIFICATION _____

PACKAGING

_____ DOMESTIC _____ EXPORT

SHIPPING

REEL TYPE: ___ RETURNABLE _ NON-RETURNABLE _____ LENGTH PER REEL _____
ADDITIONAL REQUIREMENTS: _____

ITEM NO. _____

INSTRUMENTATION CABLE

DATA SHEET 4 of 4

[ ] **MANUFACTURER DATA**

CABLE DIMENSION (O.D. IN.) _____ SHIPPING TIME _____
CABLE CROSS-SECTIONAL AREA _____ OTHER _____
CABLE WEIGHT (LBS/FT) _____
CABLE MIN BENDING RADIUS _____
TENSILE STRENGTH _____
GROSS WEIGHT/REEL (LBS) _____
TOTAL CUBIC FEET/REEL _____
SHORT CIRCUIT WITHSTAND CURVES _____
CABLE TESTING REQUIREMENTS _____

NOTES

ITEM NO. _____

Section 16131

DEVICE, PULL AND JUNCTION BOXES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for device, pull, and junction boxes.

1.02 REFERENCES

A. American National Standards Institute/National Electrical Manufacturers Association (ANSI/NEMA).

1. FB1 - Fittings and Support for Conduits and Cable Assemblies
2. 250 - Enclosures for Electrical Equipment (1000 volts maximum)

B. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), NFPA70 - National Electrical Code (NEC) - Article 314 - Outlet Device, Pull and Junction Boxes, Conduit Bodies and Fittings.

C. Underwriters Laboratories (UL):

1. 50 - Safety Cabinets and Boxes
2. 508 - Safety Industrial Control Equipment
3. 514B - Safety Fittings for Conduit and Outlet Boxes
4. 886 - Safety Outlet Boxes and Fittings for Use in Hazardous Areas

1.03 SUBMITTALS

A. Submit the following under provisions of Section 01330 – Submittal Procedures:

1. Manufacturer's cut sheets, catalog data
2. Instruction for handling and storage
3. Installation instructions
4. Dimensions and weights

1.04 DELIVERY, STORAGE AND HANDLING

A. Pack and crate boxes to permit ease of handling and to provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Sheet Metal Boxes

1. Hoffman Industrial Products
2. Pauluhn Electric Manufacturing Company
3. Hennessy
4. Tanco
5. Tejas
6. Circle A.W.

B. Cast Device Boxes

1. Appleton Electric Company
2. Crouse-Hinds, Division of Cooper Industries
3. Killark Electric Manufacturing Company

2.02 MATERIALS AND EQUIPMENT

A. Sheet Metal Boxes

1. Provide UL-approved junction boxes and pull boxes manufactured from stainless steel sheet metal and meeting requirements of NEMA 4X for corrosive and wet area, NEMA 250 and NEC Article 314.
2. Provide boxes with a stainless steel continuous hinge, closure hasps and all- stainless steel hardware. Junction boxes shall be mounted so the door opens to the right or to the left.
3. Furnish the door with neoprene gasket and provision for padlock.

B. Device Boxes

1. Provide UL-approved boxes designed and manufactured to house electrical devices like receptacles and switches, and in conformance with NEMA FB1 and NEC Article 314.

2. Supply boxes that are hot-dip galvanized on cast iron suitable for corrosive and wet atmosphere.

C. Hardware

1. Mounting Hardware: Stainless steel

2. Conduit Connectors: Watertight as manufactured by Myers Hubs, or equal.

PART 3 EXECUTION

3.01 PREPARATION

A. Review the drawings and determine how many boxes of each kind are required and check if supplied quantity is sufficient.

3.02 INSTALLATION

A. Boxes described in this specification shall be used both in dry and wet, corrosive areas, both inside and outside locations.

B. Install boxes in accordance with NEC Article 314 in locations indicated on the Drawings. Junction boxes shall be mounted so the door opens to the right or to the left.

C. Install junction and pull boxes in readily accessible places to facilitate wire pulls, maintenance and repair. Junction boxes shall be sized for the number and size of conduits that enter the junction box.

D. Plug unused conduit openings.

E. Make conduit connections to sheet metal boxes with watertight conduit connectors.

F. Label boxes with phenolic nameplates as required in Section 16195.

END OF SECTION

Section 16140

WIRING DEVICES

PART 1 G E N E R A L

1.01 SECTION INCLUDES

A. Specifications for wiring devices including:

1. Receptacles.

2. Wall switches.

3. Wall plates and cover plates.

1.02 REFERENCES

A. American National Standards Institute/National Electrical Manufacturers Association (ANSI/NEMA):

1. NEMA WD1 - General Purpose Wiring Devices.

2. NEMA WD6 - Dimensional Requirements.

B. Federal Specifications (WC-596F).

C. American National Standards Institute/National Fire Protection Association (NFPA):

1. NFPA No. 70 - National Electrical Code (NEC), Articles 210 Branch Circuits, 250 Grounding and 410, Paragraphs 56, 57 and 58.

1.03 SUBMITTALS

A. Submit the following under provisions of Section 01330 – Submittal Procedures:

1. Product Data: Manufacturer's product literature and specifications including dimensions, weights, certifications and instructions for handling, storage and installation.

1.04 DELIVERY, STORAGE AND HANDLING

A. Pack and crate devices to permit ease of handling and protect from

damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Bryant Electric

B. Crouse-Hinds, Arrow Hart Division

C. Hubbel Inc. Wiring Devices Division

D. Leviton Manufacturing Company

E. Pass & Seymour/Legrand.

2.02 MATERIALS AND EQUIPMENT

A. Standards: Conform to NEMA WD1 for general requirements and NEMA WD6 for dimensional requirements.

B. Manufacture devices to heavy-duty industrial specification grade with brown nylon bodies (orange for isolated-ground receptacles) back and side wiring provisions and green-colored grounding screws.

C. Receptacles:

1. Duplex-type receptacles: Rated 20 amps at 120 volts.

2. Contacts: Brass or phosphor bronze.

3. Receptacle grounding system: Extend to the mounting strap unless isolated ground is indicated or required.

4. GFI or GFCI (ground fault circuit interrupter) receptacles: Provide feed-through type with test and reset button.

D. Wall Switches:

1. Toggle switches: Rated 20 amps at 120/277 volts AC rated for both resistive and inductive loads.

2. Contacts: Silver cadmium oxide construction to prevent sticking, welding and excessive pitting.

E. Cover Plates:

1. In outdoor, corrosive and wet areas, provide cover plates of heavy duty plastic, gasketed with hinged covers that remain waterproof while still in use and stainless steel hardware.

2. All other plates: Type 302 stainless steel.

PART 3 EXECUTION

3.01 PREPARATION

A. Verify that device boxes are correctly placed.

B. Verify that the correct quantity, size and type of wires are pulled to each device box.

C. Verify that wiring has been checked at both ends.

D. Prepare wire ends for connection to devices.

E. Inspect each wiring device for defects.

3.02 INSTALLATION

A. Install products in accordance with manufacturer's instructions.

B. Install devices plumb and level.

C. Install switches with OFF position down.

D. Install receptacles with grounding pole on top.

E. Connect wiring device grounding terminal to outlet box with bonding jumper.

F. Connect wiring devices by wrapping conductors clockwise around screw terminals.

G. Install cover plates on switch, receptacle and blank outlets in finished areas.

H. Energize and test devices for proper operation.

END OF SECTION

Section 16160

CABINETS AND ENCLOSURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for cabinets and enclosures for housing of control panels and motor controls.

1.02 REFERENCES

A. National Electrical Manufacturers Association (NEMA).

1. 250 - Enclosures for Electrical Equipment (1000 volts maximum).

a. NEMA 3 - Enclosures for outdoor use primarily to provide a degree of protection against wind-blown dust, rain, and sleet; undamaged by formation of ice on the enclosure.

b. NEMA 12 - Enclosures for indoor use primarily to provide a degree of protection against dust, falling dirt, and dripping non-corrosive liquids.

B. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), NFPA 70 - National Electrical Code (NEC), Article 312 - Cabinets, Cutout Box, and Meter Socket Enclosures.

C. Underwriters Laboratories (UL), UL 50 - Safety for Cabinets and Boxes.

1.03 SUBMITTALS

A. Submit the following under provisions of Section 01330 – Submittal Procedures:

1. Manufacturer's cut sheets and catalog data

2. Instruction for handling and storage

3. Installation instructions

4. Dimensions and weights

1.04 DELIVERY, STORAGE AND HANDLING

A. Have cabinets and enclosures packed and crated to permit ease of handling and to provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. The EMF Company

B. Hennessey Products, Inc.

C. Hoffman Industrial Products

D. Pauluhn Electric Manufacturing Company

E. Weigman Company

F. Rose Enclosure

G. N.E.M.A. Enclosure Mfg. Co.

H. Rittal

2.02 MATERIALS AND EQUIPMENT

A. Sheet Metal Boxes

1. Provide enclosures manufactured in accordance with NEMA 250 and NEC Article 312. Fabricate outdoor NEMA 3 panels from 0.125- inch thick type 5052 H32 aluminum or 14 gauge, 316 stainless steel for installation in areas that are not air conditioned. NEMA 12 indoor panels for installation in air conditioned areas shall be painted steel.

2. Dimensions and special features are shown on the Drawings.

3. Construct outdoor enclosures with continuously welded seams ground smooth.

4. Additional material thickness and bracing requirements shall be determined by the manufacturer to provide the strength required by the standard listed. The bracing shall be provided in such a

way as to minimize the protrusion into the wiring and the equipment spaces.

5. Install the door with a stainless steel continuous hinge, stainless steel padlock handle with gasket and stainless steel hardware. Junction boxes shall be mounted so the door opens to the right or to the left.

6. Furnish the door with oil-resistant neoprene gasket attached with oil-resistant adhesive and held in place with aluminum retaining strips.

7. Use a single, 3/4-inch minimum, door handle that provides a 3-point latching through latch rods with rollers. Provide rollers with at least 3/4-inch diameter.

8. Gasketed overlapping doors may be used instead of a center post.

9. Provide heavy duty lifting eyes of suitable material.

10. Fabricate the enclosure with a stud-mounted panel inside. Make panels from 12-gauge steel painted with white enamel finish.

11. Equip both NEMA 12 and NEMA 3 enclosures with thermostatically controlled space heaters and corrosion inhibitors. Provide heaters rated for 240V for 120V operation.

12. Weld mounting feet to the enclosure if called for on the Drawing.

13. Include a high impact plastic data pocket in the enclosure.

14. Provide ground connections on the enclosures to enable grounding of the enclosure with a No. 2 AWG conductor.

15. Equip free-standing outdoor cabinets with inner and outer door restraint bars to prevent door swing during windy conditions.

16. Supply indoor enclosures with filtered passive air intake and exhaust openings, 4-inch square in the side near the top and near the bottom of the adjacent side panel.

B. Hardware

1. Mounting Hardware: Stainless steel

2. Conduit Connectors: Watertight as manufactured by Myers Hubs, or equal.

2.03 TESTING

A. Test cabinets and enclosures in accordance with UL 50 so unit qualifies for a UL label.

PART 3 EXECUTION

3.01 PREPARATION

A. Review Drawings and determine how many enclosures of each kind are required and check if supplied quantity is sufficient.

B. Check the mounting pads or foundations for proper mounting dimensions and features, including grounding conductor stub-up.

3.02 INSTALLATION

A. Use enclosures described in this specification only above grade.

B. Install enclosures in accordance with NEC Article 312 in locations as indicated on the Drawings.

C. Install enclosures in readily accessible locations to facilitate general operations, wire pulls, maintenance and repair.

D. Plug unused conduit openings.

E. Make conduit connections to the enclosures with watertight conduit connectors.

F. Identify all components in cabinets with phenolic nameplates as required in Section 16195.

G. Use pre-printed tubular heat-shrink type wire and cable markers to label each end of all conductors.

END OF SECTION

Section 16161

PANELBOARDS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for panelboards.

1.02 REFERENCES

A. American National Standards Institute/National Electrical Manufacturers Association (ANSI/NEMA)

1. NEMA AB1: Molded Case Circuit Breakers
2. NEMA PB1: Panelboards
3. NEMA PB1.1: Instruction for Safe Installation Operation and Maintenance of Panelboards rated 600 volts or less.
4. NEMA PB1.2: Application Guide for Ground-fault Protective Devices for Equipment
5. UL 67: Panelboards
6. UL 50: Cabinets and Boxes
7. Fed. Spec W-P-115C

B. Federal Specifications, FS W-C-375A: Circuit Breakers, Molded Case, Branch Circuit and Service.

C. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), NFPA No. 70 - National Electrical Code (NEC), Article 408 - Switchboards and Panelboards.

D. Underwriters Laboratory

1. UL 67: Panelboards
2. UL 50: Cabinets and Boxes

1.03 SUBMITTALS

A. Submit the following under provisions of Section 01330 – Submittal Procedures:

1. Manufacturer's cut sheets and catalog data
2. Breaker arrangement
3. Breaker characteristic curves
4. Instruction for handling and storage
5. Installation instructions
6. Dimensions and weights

1.04 DELIVERY, STORAGE AND HANDLING

A. Have panelboards packed and crated to permit ease of handling and to provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Sheet Metal Boxes

1. Eaton Cutler Hammer
2. General Electric
3. Siemens
4. Schneider Electric

2.02 MATERIALS AND EQUIPMENT

A. Basic Requirements

1. Use panelboards manufactured and tested in accordance with NEMA PB 1.
2. Provide circuit breakers of industrial grade, manufactured and tested in accordance with NEMA AB 1 and Federal Specification FS W-C-375.

3. Do not exceed 42 available single pole branch circuits in any one panelboard.

4. Perform a load analysis to assure the panel rating is not overloaded when new loads are added to existing panels.

B. Rating

1. Voltage rating, current rating, number of phases, number of wires and number of poles are indicated on Drawings.

2. Branch circuit breaker interrupting capacity shall be minimum 10,000 ampere RMS symmetrical for 208V; 25,000 ampere RMS symmetrical for 480V.

C. Circuit Breakers: Molded case, bolt-on thermal magnetic type with number of poles and trip ratings as shown on the Drawings. Provide ground fault interrupters with trip rating where shown on the Drawings.

D. Bus System

1. Bus Bars: 98 percent conductivity copper. Provide a solid neutral bar in 4-wire panelboards. Include ground bus in all panels. Provide split-bus panels where shown on Drawings.

2. Main: Circuit breaker or main lugs only as indicated on the Drawings or as required to meet the current interrupting ratings.

E. Box and Trim

1. Construction: Code grade steel, ample gutter space, flush door, flush snap latch and lock.

2. Trim: Surface or flush as required. Enclose panelboards located outdoors, in other wet and corrosive areas, or in non-air conditioned areas in NEMA 4X weatherproof stainless steel enclosures. Enclose indoor panelboards installed in air conditioned areas in a NEMA 1 enclosure with manufacturer's standard gray enamel finish.

3. Directory: Typed card, with glass cover in frame on back of door giving the circuit numbers and the area or equipment served.

F. Conduit Connectors: Watertight as manufactured by Myers Hubs, or equal.

PART 3 EXECUTION

3.01 PREPARATION

A. Review Drawings to verify that panelboards are correct for the application.

3.02 INSTALLATION

A. Install the panelboard in accordance with NEMA PB 1.1 and NEC Article 408.

B. Mount panelboards 6'-0" (to top of cabinet) above finished floor or grade. In wet and corrosive areas, including outdoor locations, install panel enclosures on spacers to provide approximately 1/4-inch between back of cabinet and mounting surface. Mounting hardware shall be type 316 stainless steel.

C. In wet and corrosive areas, including outdoor locations, connect conduit to the bottom of enclosure and to the lower 30 percent of the sides using watertight connectors.

END OF SECTION

Section 16165

DISCONNECT SWITCHES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for disconnect switches including:

1. Fusible disconnect switches
2. Non-fusible disconnect switches
3. Circuit breaker type disconnect switches
4. Fuses
5. Circuit breakers

1.02 REFERENCES

A. American National Standards Institute/National Electrical Manufacturers Association (ANSI/NEMA)

1. NEMA AB1: Molded Case Circuit Breakers
2. NEMA KS1: Enclosed Switches

B. Underwriters Laboratories (UL)

1. UL 98: Standard for safety enclosed switches and Dead Front Switches
2. UL 198C: High Interrupting Capacity Fuses, Current Limiting type
3. UL 198E: Class R Fuses

C. American National Standards Institute/National Fire Protection Association (ANSI/NFPA), NFPA No. 70 - National Electrical Code (NEC), Chapter 4.

1.03 SUBMITTALS

A. Submit the following under provisions of Section 01330 – Submittal Procedures:

1. Manufacturer's cut sheets and catalog data
2. Switch internal arrangement
3. Breaker or fuse characteristic curves
4. Instructions for handling and storage
5. Installation instructions
6. Dimensions and weights

1.04 DELIVERY, STORAGE AND HANDLING

A. Have disconnect switches packed and crated to permit ease of handling and to provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Disconnect Switches and Circuit Breakers:

1. Eaton/ Cutler Hammer
2. General Electric
3. Siemens Energy and Automation
4. Schneider Electric

B. Fuses

1. Bussman Division, Eaton/ Cooper Industries
2. Gould Shawmut
3. Littlefuse Incorporated

2.02 MATERIALS AND EQUIPMENT

A. Disconnect Switches

1. Characteristics: Horsepower rated, 600-volt, heavy-duty type with an interlocked door, positive quick-make, quick-break mechanism and visible blades.

2. Use switches and components designed, manufactured and tested in accordance with NEMA AB1, NEMA KS1, UL 98, and NEC Chapter 4.

3. Enclose switch in a NEMA 12 type enclosure for indoor, air-conditioned applications and NEMA 4X (type 316 stainless steel) in outdoor locations, non-air-conditioned areas, or other wet or corrosive areas.

4. Provide switches with provisions for padlocking the operating lever in OFF position and door in closed position.

5. Select switches having the number of poles and general size conforming to the Drawings.

6. Conform to fusible, non-fusible or circuit breaker type switch requirements as shown on Drawings and required by the NEC, or one-line diagrams.

7. Provide an auxiliary contact, shown on the Drawings.

8. Select fuses or circuit breakers with current interrupting duty as calculated for the points of switch application or as indicated on the Drawings or one-line diagrams.

B. Fuses. Unless otherwise noted on Drawings, for fuses used in disconnect switches, provide the dual-element, time-delay type with the maximum interrupting rating of 200,000 amperes, conforming to the NEC.

C. Circuit Breakers. When circuit breakers are used in disconnect switches, provide the thermal-magnetic type with current interruption ratings as required at the point of application.

D. Conduit Connectors: Watertight as manufactured by Myers Hubs, or equal.

PART 3 EXECUTION

3.01 PREPARATION

A. Review the Drawings and verify that the disconnect switches are correct for the applications.

B. Make sure that the correct fuses or breakers are being used regarding size and short circuit interrupting capability.

C. Prepare adhesive labels on the inside door of each switch indicating UL fuse class and size or breaker type and size for replacement.

3.02 INSTALLATION

A. Install the disconnect switches in accordance with and NEC Chapter 4. Disconnect switches shall be mounted in sight of or within 25' of motors and rotating equipment.

B. Mount switches 6'-6" (to top of cabinet) above finished floor or grade.

C. In wet and corrosive areas, including outdoor locations, install switches on spacers to provide a space of approximate 1/4-inch between the back of cabinet and the mounting surface.

D. In wet and corrosive areas, including outdoor locations, connect conduit to the bottom of enclosure and to the lower 30 percent of the sides using watertight connectors.

E. Disconnect shall be labeled as required in Section 16195.

END OF SECTION

Section 16170

GROUNDING AND BONDING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Grounding electrodes and conductors

B. Equipment grounding conductors

C. Bonding

D. Power system grounding

E. Communication system grounding

F. Electrical equipment and raceway grounding and bonding

G. Control equipment grounding

1.02 REFERENCES

A. American Society for Testing and Materials (ASTM)

1. ASTM B3: Soft or Annealed Copper Wires

2. ASTM B8: Concentric-Lay-Stranded Copper Conductors, Hard, Medium Hard, Soft

3. ASTM B33: Tinned Soft or Annealed Copper Wire for Electrical Purposes

B. Institute of Electrical and Electronics Engineers (IEEE)

1. IEEE 142-82: Recommended Practice for Grounding of Industrial and Commercial Power Systems

2. IEEE 383-2.5: IEEE Standard for Type Test of Class IE Electric Cables, Field Splices, and Connections for Nuclear Power Generating Stations.

C. Underwriters' Laboratories (UL)

1. UL 83: Thermoplastic Insulated Wire and Cables

2. UL 467: Grounding and Bonding Equipment

D. National Fire Protection Association (NFPA), NFPA No. 70 - National Electrical Code (NEC), Article No. 250 - Grounding.

1.03 SUBMITTALS

A. Submit the following under the provisions of Section 01330 – Submittal Procedures:

1. Manufacturer's cut sheets and catalog data

2. Installation, terminating and splicing procedure

3. Instruction for handling and storage

4. Dimensions and weight

1.04 QUALITY ASSURANCE

A. Tests

1. Use insulated cable conforming to requirements of the vertical tray flame test as described in IEEE 383-2.5.

2. Test grounding system in the field in accordance with procedures outlined in Part 3 - Execution.

1.05 DELIVERY, STORAGE AND HANDLING

A. Ship grounding cable on manufacturer's standard reel sizes unless otherwise specified. Where cut lengths are specified, mark reel footage accordingly. Each reel shall contain one continuous length of cable. Provide impact protection by wood lagging or suitable barrier across the traverse of the reel. Pack and crate other materials specified to withstand normal abuse during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Cable

1. American Insulated Wire Company
2. Cablec Continental Cables Company
3. General Cable Company
4. Okonite Company
5. Pirelli Cable Corporation
6. Rome Cable Corporation
7. Triangle Wire and Cable, Inc.

B. Ground Rods and Connectors:

1. Blackburn
2. Copperweld
3. Thomas & Betts

C. Exothermic Connections:

1. Burndy Corporation (Therm-O-Weld)
2. Erico Products (Cadweld)

D. Grounding Connectors:

1. Burndy Corporation
2. O.Z. Gedney
3. Thomas & Betts

2.02 MATERIALS AND EQUIPMENT

A. Design. Provide grounding cable and materials with the following characteristics:

1. Use a grounding system designed in accordance with NEC Article No. 250 - Grounding, and the IEEE 142-82 - Recommended Practice for Grounding of Industrial and Commercial Power Systems.

B. Materials

1. Use grounding conductors, bare or insulated, which are manufactured and tested in accordance with applicable standards ASTM B3, ASTM B8 and ASTM B33.

2. Provide a main ground loop of No. 4/0 AWG, Class C stranded, bare copper cable. Small groups of isolated equipment may be grounded by a No. 2 AWG minimum insulated conductor connected to the main loop. Generally, taps shall be sized as follows:

   a. Main ground loop or grid #4/0 minimum

   b. Switchgear, motor control centers and power transformers #4/0

   c. Motors 200 hp and above #4/0

   d. Power panels - AC and DC #2/0

   e. Control panels and consoles #2

   f. Building columns #4/0

   g. Fencing posts #2/0

3. Where single conductor insulated grounding conductors are called for, use 600-volt insulation. Use ground conductors identified with green insulation or green tape marking.

4. Supply identifying ribbon which is PVC tape, 3 inches wide, red color, permanently imprinted with "CAUTION BURIED ELECTRIC LINE BELOW" in black letters as specified in Section 16195, Electrical Identification.

5. Utilize flexible copper braid across hinged chain link or fence gates to bond the movable portion to the grounded fence post.

PART 3 EXECUTION

3.01 PREPARATION

A. Complete site preparation and soil compaction before trenching and driving ground rods for the underground grid.

B. Verify from Drawings the exact location of stub-up points for grounding of equipment, fences and building or steel structures.

3.02 CONSTRUCTION CRITERIA

A. The main ground loop at a depth of at least 30 inches below earth surface. Connect the ground loop to ground rods and to tap connections to form a complete system as indicated on the electrical Drawings. The Contractor shall give special attention to the grounding of service equipment, structures and fences to comply with the NEC, local authorities and the serving utility company.

B. Electrical equipment, buildings, tanks, and other structures and equipment shall be grounded as indicated on the Drawings. Where ground rods are required, the rods shall be 10 feet long, 3/4 inch diameter, copper-clad steel ground rods. Rods shall be driven vertically, and the top of the rods shall be a minimum of 18 inches below finished grade, or as specified on the Drawings. Ground wells will be provided for all driven rods.

C. Local pushbutton and selector switch stations, two-wire control devices, disconnect switches, lighting transformers, panelboards, operator panels, benchboards, and the enclosures of other electrical apparatus shall be grounded through and equipment grounding conductor run with the power supply or control circuit conductors or shall be grounded as shown on the Drawings.

D. Ground medium voltage motors, in addition to the grounding conductors in the motor feeder cable, with a separate No. 4/0 AWG cable to motor frame.

E. Motors having power supplied by multiconductor cable shall be grounded by a separate grounding conductor in the cable and where supplied by single conductor cable in conduit by a grounding conductor pulled in the conduit. Connect ground conductors to the ground bus in the motor control center and to the ground terminal provided in the motor conduit box.

F. Do not ground the insulated bearing pedestals of large motors.

G. Connect ladder-type cable trays to the grounding electrode system.

H. Install a warning ribbon approximately 12 inches below finished grade directly above the ground grid.

I. Connect fence posts of chain link and metal fences to the main ground loop at least every 50 feet. Install bonding straps to gates.

3.03 INSTALLATION

A. Equipment Grounding

1. Make grounding connections to surfaces which are dry and cleaned of paint, rust, oxides, scales, grease and dirt to ensure good conductivity. Clean copper and galvanized steel to remove oxide before making welds or connections.

2. Use the exothermic welding process for below-grade grounding connections, except at ground rods. Use mechanical connectors or thermal connections for above-grade grounding connections as shown on the Drawings.

3. Make grounding connections to electrical equipment, vessels, mechanical equipment and ground rods in accordance with the Drawings.

4. Ground tanks and vessels by making connections to integral structural supports or to existing grounding lugs or pads, and not to the body of the tank or vessel.

5. Leave ground connections to equipment visible for inspection. Protect them with PVC non-metallic conduit as indicated on the Drawings.

6. Make connections to motor frames and ground buses with lugs attached to the equipment by means of bolts. Do not use motor anchor bolts or equipment housing for fastening lugs of grounding cable.

7. Where the wiring for lighting systems consists of single conductor cables in conduit, provide each conduit with an equipment grounding conductor. Use a grounding conductor with green colored insulation and ground equipment in the lighting system.

B. Raceway and Support Systems Grounding

1. Install raceway, cable rack or tray and conduit so that it is bonded together and permanently grounded to the equipment ground bus, according to the Drawings. Connection to conduit may be grounding bushing or ground clamp.

2. Install raceway at low voltage motor control centers or other low voltage control equipment so that it is bonded and grounded, except that any conduit which is effectively grounded to the sheet metal enclosure by bonding bushing or hubs need not be otherwise bonded.

3. Where a grounding conductor is run in or on a cable tray, bonds the grounding conductor to each section of cable tray with a cable tray ground clamp.

4. Where only grounding conductor is installed in a metal conduit, bond both ends of the conduit to the grounding conductor.

5. Provide flexible "jumpers" around raceway expansion joints. Use copper bonding straps for steel conduit. Install jumpers across cable tray joints which have been parted to allow for expansion and any hinged cable tray connections.

C. Fences and Gates. Ground fences, fence posts and gates to the underground grid as shown on the Drawings.

D. Power System Grounding

1. Solidly ground the secondary neutral of the main power supply transformer either to the ground grid or through an impedance. See Drawings for details.

2. Solidly ground the neutral of lighting, instrument and control transformers.

E. Cable Armor and Shields

1. For shielded control cable, terminate and ground the shield at one end only, preferably at the control panel end for instrument and communication cable and at the supply end for electronic power cables. Maintain shield continuity by jumpering the ground shield across connection point where it is broken at junction boxes, or other splice points. Insulate these points from ground.

2. Connect the ground wire in power cable assemblies at each terminal point to a ground bus, if available, or to the equipment enclosure. Do not carry these ground wires through a "doughnut" current transformer (CT) used for ground fault relaying; do carry ground leads from stress cones through CTs. Ground power cable armor and shield at each terminal point.

F. Test Wells

1. Provide access (test wells) for testing the ground grid system at one or several ground rod locations. Make test wells of a pipe surrounding the

rod and connections with a cover placed on top at grade level. See Drawings for details.

2. Install a test well at the service entrance pole to serve as the service entrance grounding electrode.

G. Test

1. Perform ground resistance tests after underground installation and connections to building steel are complete, unless otherwise noted on applicable Drawings.

2. Make tests at each ground test well using a "fall of potential" test method. Each ground test well shall not exceed a maximum resistance of 5 ohms. Where measured values exceed this figure, install additional ground rods as required to reduce the resistance to the specified limit.

H. Inspection. Inspection of the grounding system by the Project Manager and the local Code Inspector must take place before the grid trenches are backfilled.

END OF SECTION

Section 16195

ELECTRICAL IDENTIFICATION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specification for electrical identification including:

1. Nameplates and labels
2. Wire and cable markers
3. Conduit markers
4. Cable tray markers
5. Underground warning tape
6. Warning labels

1.02 REFERENCES

A. American National Standards Institute/National Fire Protection Association (ANSI/NFPA)

1. No. 70 - National Electrical Code (NEC)

a. Article 110 - Requirements for Electrical Installation

b. Article 430 - Transformers and Transformer Vaults

B. City of Houston Building Code

C. Other applicable Codes and Standards as referenced in other Sections.

D. Underwriters Laboratories. U.L. Standards No. 224 - Extruded Insulated Tubing

1.03 SUBMITTALS

A. Submit the following under the provisions of Section 01330 Submittal Procedure:

Manufacturer's cut sheets and catalog data

Description of materials used

Label or nameplate dimensions

Engraving or imprint legends

Instruction for handling and storage

Installation instructions

1.04 DELIVERY, STORAGE AND HANDLING

A. Pack materials to permit ease of handling and to provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Almetek Industries Incorporated

B. Brady U.S.A. Incorporated

C. Ideal Electric Company

D. Raychem Corporation

E. 3M Electrical Products Division

F. Thomas & Bett

G. Tyton Corporation

2.02 MATERIALS AND EQUIPMENT

A. Nameplates and Labels

1. Provide an identification tag for each item of electrical and instrumentation equipment showing its item number and service or application. Use the description shown on the electrical Drawings.

2. For nameplates, use 3-ply phenolic material engraved to show black lettering on a white background. Size the nameplates approximately 1 inch wide and 3 inches long for 3 lines of 3/16 inch - 16 letters with a 0.8 condensed factor.

3. Generally, provide large pieces of equipment with engraved nameplates; provide additional nameplates at pushbuttons and other local devices; as detailed. Provide identification for all other electrical and instrumentation equipment, devices, or enclosures, such as MCC's, panelboards, disconnect switches, capacitors, relays, and dedicated receptacles not furnished with readily noticeable tag, nameplates, or other means of identification.

4. Install nameplates on the front cover of transformers stating the transformer service location number or identification number, the panelboard or device served, and main breaker feeding the transformer (MCC No. and compartment), and the drawing number on which the transformer schematic is shown.

5. Furnish equipment, such as motor starters, safety switches, welding receptacles and circuit breakers, with 1" x 3" plastic nameplates stating description of item served.

6. Provide nameplates for motors giving the driven equipment description, the service location number, and the MCC number with compartment number when applicable. Nameplates will normally be mounted adjacent to the motor at the motor pushbutton when one is furnished.

7. Install nameplates on the outside and inside of doors to circuit breaker panelboards (i.e., lighting, instrument or receptacle panels). State the panelboard name, the drawing number on which the panelboard schedule shows, and the main breaker feeding the panel (MCC No. and compartment).

8. Type panelboard directories and insert them inside the panelboard doors.

9. Place a large nameplate no less than 3"x5" on control panels, relay panels, junction boxes, or enclosures with electrical devices mounted inside or on the outside of the enclosure indicating the purpose of the cabinet.

10. Provide a nameplate on MCC motor starter doors duplicating motor nameplate data.

B. Wire and Cable Markers

1. Use pre-printed tubular heat-shrink type wire and cable markers at each end of all conductors.

2. Select markers manufactured so that the heat-shrink process makes the imprint permanent and solvent-resistant.

3. Use markers that are self-extinguishing, conforming to U.L. Standard No. 224 for print performance, heat shock, and flammability.

4. Provide marker material that is flexible, radiation cross-linked polyolefin with 3 to 1 shrink ratio, rated 600 volts, and white in color.

C. Conduit Markers

1. Provide conduit markers made of stainless steel tags approximately 2 inches x 1 inch x 19 gage.

2. Stamp the caption on the tag and have it black filled.

3. Punch tags for tie fasteners. Fasten tags to the conduits with stainless steel braided wire.

D. Cable Tray Markers

1. For high visibility and contrast, use cable tray markers that are yellow with black legend.

2. Use markers made of vinyl impregnated cloth, suitable for exposure to corrosive, wet, and abrasive environment.

3. Make markers of pre-cut individual letters or numbers with pressure sensitive adhesive backing.

4. Size legend characters to 4 inches high on a total marker height of approximately 5 inches, suitable for applying to 6-inch side rails of a cable tray.

E. Underground Warning Tape

1. Provide warning tape made of 4 mil thick polyolefin film, 3 inches wide, suitable for direct burial and resistant to alkalis, acids, and other common soil substances.

2. Use red tape with black legend printed in permanent ink.

F. Warning Labels

1. Place OSHA safety labels on enclosures and boxes 100 cubic

inches or more containing electrical equipment or terminations.

2. Provide OSHA color codes for the labels. Use labels made from 4 mil vinyl with pressure sensitive adhesive backing.

3. The warning label caption is DANGER - 480 VOLTS or as indicated on the drawings

4. Size labels either 5 inches x 3-1/2 inches or 10 inches x 7 inches, as indicated on the Drawings.

PART 3 EXECUTION

3.01 PREPARATION

A. Degrease and clean surfaces where adhesive labels will be applied.

B. Drill holes for nameplates to be fastened with stainless screws.

C. Prepare the cable ends for termination and conductor markings.

D. Identify conduits at terminating points and select tags accordingly.

3.02 INSTALLATION

A. Install nameplates and labels in accordance with the manufacturer's instructions and the Drawings.

B. Apply wire and cable markers in accordance with manufacturer's instructions using a heat gun with properly sized nozzle for the application. Tag the wires at both ends with the same notation.

C. Tag conduits at junction boxes, pull boxes, and at other termination points.

D. Identify cable trays at the time of installation with the alphanumeric number shown on the Drawings. Label cable trays on the outside rail. Place the tray identifier at each point where the tray designation changes and at 200 foot intervals in between, but not less than two per run.

E. Identify underground conduits, cables, or duct banks using the underground warning tape. The underground grounding grid, including the laterals. Also use underground warning tape. Install one tape per trench at 12 inches below grade or as indicated on the Drawings. For wide trenches or duct banks, install one warning tape per 24 inch width.

F. Apply the 5 inches by 3-1/2 inches warning labels to disconnect switches, panelboards, terminal boxes, and similar devices in accordance with manufacturer's instruction and the Drawings. Apply the 10 inches x 7 inches warning labels to larger control panel enclosures, motor control centers, and to entrance doors to buildings containing electrical power and control equipment.

END OF SECTION

SECTION 16290

SURGE PROTECTION DEVICES

PART 1 GENERAL

1.1 SCOPE OF WORK

A. Scope:
1. CONTRACTOR shall provide all labor, materials, equipment and incidentals as shown, specified and required to furnish and install surge protective devices (SPDs) in the control panels and field devices.
2. Provide surge protection devices to protect field instruments and equipment from the effects of transient surges caused by lightning and other electrical sources.

****
NTS: EDIT 1.1.A.3 AS APPROPRIATE FOR THE PROJECT.
****

3. SPDs shall be installed at the following locations:
   a. On 120 VAC, 60Hz power connections to control panels.
   b. On all analog signals at the control panel. Include surge protection at 24 VDC loop powered field instruments for wiring distances greater than 75 feet from the control panel. Include surge protection on all four-wire, 120 VAC field instruments.
   c. On all discrete signals that have portions of interconnecting wiring located outside of protected buildings.
   d. On all copper data lines that have portions of interconnecting wiring located outside of protected buildings

B. Related Sections:
1. Section 17320: Control Panels and Enclosures.
2. Division 16: Electrical.

1.2 QUALITY ASSURANCE

A. Standards, Codes and Regulations:
1. Surge protective devices and the installation and interconnection of the devices shall comply with applicable provisions of the following standards, codes and regulations:
   a. National Fire Protection Association 79, Annex "D" Standards, (NFPA).
   b. National Electrical Code, (NEC).
   c. National Electrical Manufacturer's Association Standards, (NEMA).
   d. UL 1449 Third Edition, Standard for Safety Surge Protective Devices (SPDs).
   e. UL 497B, Protectors for Data Communications and Fire-Alarm circuits.

f. International Electrotechnical Commission (IEC).
g. Institute of Electrical and Electronics Engineers (IEEE).
h. State and Local code requirements.
i. Where any conflict arises between codes or standards, the more stringent requirement shall apply.

PART 2 PRODUCTS

2.1 SPD - GENERAL

A. Connect and ground in accordance with surge protection device manufacturers instructions. SPDs shall use a separate path to building ground; the equipment safety ground is not to be used as a transient ground path.

B. SPDs shall be installed as close as practical to the protected equipment, panel, or switchboards to minimize connecting wire lead lengths.

C. All control panel SPDs shall be DIN-rail mountable and capable of being monitored by direct visual means and have remote indication for fault indication to a local monitoring and control system.

D. All control panel SPDs shall be pluggable for easy removal to facilitate testing to ensure proper protection levels. Removal shall not disrupt operation of protected circuits.

E. MOV based suppression products rated for use above 110 VAC, 60Hz, 95 percent humidity, shall incorporate a thermally sensitive device to remove the metal oxide varistor (MOV) from service should the event of severe overheating occur.

F. The surge protection devices shall be used as the interface terminal blocks when applicable.

****
NTS: CHOOSE THE APPROPRIATE SPDS TO FIT THE PROJECT APPLICATION
****

2.2 SPD - 480 VAC POWER

A. General: Provide surge protection for 3-phase 480 VAC wye power connections. Include circuit breaker in series with each device to facilitate device removal and testing.

B. Features:
1. Suppression: Metal oxide varistors (MOVs) and gas-filled surge arresters.
2. Protection level U_p (core-neutral): ≤ 1.6 kV.

3. Protection level U_p (core-ground): ≤ 1.75 kV.
4. Protection level U_p (neutral-ground): ≤1.5 kV.
5. Nominal discharge surge current (8/20 µs): 20 kA.
6. Maximum discharge surge current (8/20 µs): 40 kA.
7. Response time (core-neutral): ≤ 25 ns.
8. Response time (core-ground): ≤ 100 ns.
9. Operating temperature of -40 °C to 80 °C.

C. Product and manufacturer:
1. Phoenix Contact, VAL-MS 320/3+1.
2. Erico, TDS350TT277
3. Dehn, DG MU 3PY 480 4W+G
4. Or approved equal.

2.3 SPD - 120 VAC POWER

A. General: Provide modular, pluggable surge protective device of the incoming power feed to the control panel.

B. Features:
1. Suppression: Metal oxide varistors (MOVs) and gas-filled surge arresters.
2. Maximum Continuous Operating Voltage: 150V.
3. Nominal load current I_n: 26 A.
4. Protection level U_p (L-N): 620 V.
5. Protection level U_p (L-PE): 850 V.
6. Protection level U_p (N-PE): 850 V.
7. Nominal discharge surge current (8/20 µs): 2.5 kA.
8. Response time: < 25 ns (L-N)
9. Operating temperature of -40 °C to 85 °C.

C. Product and manufacturer:
1. Phoenix Contact, MAINS-PLUGTRAB PT 2-PE/S-120AC-ST.
2. Erico, TDS1301TR150
3. Dehn, DR M 2P 150
4. Or approved equal.

****

NTS: INCLUDE 2.4.B.11 AND 2.4.C FOR MONITORING OF ANALOG SPDS TO CONTROL SYSTEM

****

2.4 SPD – 24 VDC ANALOG – CONTROL PANEL

A. General: Surge protection device (SPD) at the control panel for 24 VDC power connections to field instruments. SPD shall be pluggable, modular and able to be tested.

B. Features:
1. Suppression: Gas-filled surge arrester and silicon avalanche diode.
2. Maximum Continuous Operating Voltage: 28 VDC.
3. Nominal current I_n: 450 mA.
4. Protection level U_p (core-core): ≤ 70 V (1 kV/500 A).
5. Protection level U_p (core-ground): ≤ 450 V (1 kV/5 kA).
6. Resistance per path: 2.2 ohms.
7. Nominal discharge surge current (8/20 µs): 10 kA.
8. Total surge current (8/20 µs): 20 kA.
9. Response time (core-core): ≤ 1 ns
10. Response time (core-ground): ≤ 100 ns
11. Capable of being monitored by head-end module and LED indicators for status.
12. Operating temperature of -40 °C to 85 °C.

C. Monitoring Module Features:
1. Communicate status and provide power to SPD LEDs via TBUS connector on DIN rail.
2. Nominal Operating Voltage: 28 VDC (20 VDC – 30 VDC).
3. Provide two NC contacts for status of overload and performance limit reached of connected SPDs.
4. Capable of monitoring status of 28 SPDs.
5. Provide ON/OFF switch for SPD LED lights.

D. Product and manufacturer:
1. Phoenix Contact, MCR-PLUGTRAB PT 1x2-24DC-ST.
2. Erico, UTB30SP
3. Dehn, BXT ML4 BE 24
4. Or approved equal.

****

NTS: INCLUDE 2.5.B.10 AND 2.5.C FOR MONITORING OF DISCRETE SPDS TO CONTROL SYSTEM

****

2.5 SPD – DISCRETE SURGE PROTECTION – 24 VDC

A. General: Surge protection at the control panel for 24 VDC discrete signal connections. SPD shall be pluggable, modular and able to be tested.

B. Features:
1. Suppression: Gas-filled surge arrester and silicon avalanche diode.
2. Maximum Continuous Operating Voltage: 28 VDC.
3. Nominal current I_n: 300 mA.
4. Protection level U_p (core-ground): ≤ 60 V (1 kV/500 A)

5. Resistance in series: 4.7 ohms.
6. Nominal discharge surge current (8/20 µs): 10 kA.
7. Total surge current (8/20 µs): 20 kA.
8. Response time (core-ground): ≤ 1 ns
9. Operating temperature of -40 °C to 85 °C.
10. Capable of being monitored by head-end module and LED indicators for status.

C. Monitoring Module Features:
1. Communicate status and provide power to SPD LEDs via TBUS connector on DIN rail.
2. Nominal Operating Voltage: 28 VDC (20 VDC – 30 VDC).
3. Provide two NC contacts for status of overload and performance limit reached of connected SPDs.
4. Capable of monitoring status of 28 SPDs.
5. Provide ON/OFF switch for SPD LED lights.

D. Product and manufacturer:
1. Phoenix Contact, MCR-PLUGTRAB PT 2x1-24DC-ST
2. Erico, UTB30SP
3. Dehn, BXT ML4 BD 24
4. Or approved equal.

2.6 SPD – DISCRETE SURGE PROTECTION – 120 VAC

A. General: Surge protection at the control panel for 120 VAC discrete signal connections. SPD shall be pluggable, modular and able to be tested.

B. Features:
1. Suppression: Metal oxide varistors.
2. Maximum Continuous Operating Voltage: 150 VAC.
3. Nominal current I_n: 26 amps.
4. Protection level U_p (Core-ground): ≤ 550 V.
5. Nominal discharge surge current (8/20 µs): 2.5 kA.
6. Total surge current (8/20 µs): 5 kA.
7. Response time (core-ground): ≤ 25 ns
8. Operating temperature of -40 °C to 85 °C.

C. Product and manufacturer:
1. Phoenix Contact, MCR-PLUGTRAB PT 2x1VA-120AC-ST.
2. Erico, UTB110DP
3. Dehn, BXT ML4 BE 180
4. Or approved equal.

2.7 SPD – 24 VDC POWER/ANALOG – FIELD DEVICE

A. General: Surge protection at the field device for 24 VDC power connections.

B. Features:
1. Suppression: Gas-filled surge arrester and silicon avalanche diode.
2. Maximum Continuous Operating Voltage: 36 VDC.
3. Nominal current I_n: 450 mA.
4. Protection level U_p (core-core): ≤65 V.
5. Protection level U_p (core-ground): ≤ 1.2 kV (C2- 10 kV/5 kA).
6. Nominal discharge surge current (8/20 µs) (core-ground): 10 kA.
7. Total surge current (8/20 µs): 20 kA.
8. Core to core response time: < 1 ns.
9. Core to ground response time: < 100 ns
10. Operating temperature of -25 °C to 80 °C.
11. Material and mounting: High grade steel with ½ inch NPT.

C. Product and manufacturer:
1. Phoenix Contact, SURGETRAB, S-PT-EX-24DC.
2. Erico, RTP3034
3. Dehn, BXT ML4 BE 36
4. Or approved equal.

2.8 SPD – 120 VAC POWER/24 VDC SIGNAL – FIELD DEVICE

A. General: Surge protection at the field device to protect the 120 VAC power and 24 VDC analog signal. Surge protection to be provided in a NEMA 4X enclosure.

B. 120 VAC Power Surge Features:
1. Suppression: Metal oxide varistors (MOVs) and gas-filled surge arresters.
2. Maximum Continuous Operating Voltage: 150V.
3. Nominal load current I_n: 26 A.
4. Protection level U_p (L-N): 620 V.
5. Protection level U_p (L-PE): 850 V.
6. Protection level U_p (N-PE): 850 V.
7. Nominal discharge surge current (8/20 µs): 2.5 kA.
8. Response time: < 25 ns (L-N)
9. Operating temperature of -40 °C to 85 °C.

C. 24 VDC Signal Surge Features:
1. Suppression: Gas-filled surge arrester and silicon avalanche diode.
2. Maximum Continuous Operating Voltage: 28 VDC.
3. Nominal current I_n: 450 mA.
4. Protection level U_p (core-core): ≤ 70 V.
5. Protection level U_p (core-ground): ≤ 450 V.
6. Resistance per path: 2.2 ohms.
7. Nominal discharge surge current (8/20 µs): 10 kA.
8. Total surge current (8/20 µs): 20 kA.

9. Response time (core-core): ≤1 ns
10. Response time (core-ground): ≤ 100 ns
11. Operating temperature of -40 °C to 85 °C.

D. Product and manufacturer:
1. Phoenix Contact, BOXTRAB – BXT-N4X 4-WIRE.
2. Erico, MWE and TDS1301TR150
3. Dehn, 999.990-01
4. Or approved equal.

2.9 SPD – DATA SURGE PROTECTION - ETHERNET

A. General: Surge protection to protect CAT-5/6 Ethernet data signal. Provide attachment plug for DIN-rail mounting. Connection method to device by RJ45 plug.

B. Features:
1. Suppression: Gas-filled surge arrester and diodes.
2. Maximum Continuous Operating Voltage (core-ground): ≤ 180 VDC.
3. Nominal current I_n: ≤ 1.5 A.
4. Protection level U_p (core-core): ≤ 9 V (1 kV/25A)
5. Protection level U_p (core-core): ≤ 100 V (1 kV/25A - PoE)
6. Protection level U_p (core-earth): ≤ 600 V.
7. Nominal discharge surge current (8/20 µs) (core-ground): 2 kA, per signal pair.
8. Total surge current (8/20 µs): 10 kA.
9. Response time (core-core): ≤ 1 ns.
10. Response time (core-ground): ≤ 100 ns
11. Operating temperature of -40 °C to 70 °C.

C. Product and manufacturer:
1. Phoenix Contact, DT-LAN-CAT.6.
2. Erico, LANRJ45C6
3. Dehn, DPA M CLE RJ45B 48
4. Or approved equal.

2.10 SPD – DATA SURGE PROTECTION – RS-485

A. General: Surge protection to protect RS-485 connection. Provide attachment plug for DIN-rail mounting. Connection method to device by 9-position D-SUB connector.

B. Features:
1. Suppression: Gas-filled surge arrester and diodes.
2. Maximum Continuous Operating Voltage: 12 VDC.
3. Nominal current I_n: ≤ 380 mA.
4. Protection level U_p (core-core): ≤ 40 V (5 kA)
5. Protection level U_p (core-ground): ≤ 750 V (5 kA).
6. Resistance in series: 3.3 ohms.

7. Nominal discharge surge current (8/20 µs) (core-ground): ≤ 5 kA.
8. Total surge current (8/20 µs): 10 kA.
9. Response time (core-core): ≤ 100 ns.
10. Response time (core-ground): ≤ 100 ns
11. Operating temperature of -40 °C to 85 °C.

C. Product and manufacturer:
   1. Phoenix Contact, DT-UFB-485/BS.
   2. Erico, DEPRS42299D
   3. Dehn, BXT ML4 BD HF 5
   4. Or approved equal.

2.11 SPD – DEVICE TESTER

A. General: Provide device tester for pluggable surge protective devices in convenient carrying case.

B. Features:
   1. Barcode scanner or keypad for entering information on SPD.
   2. Operating Voltage: 100 – 240 VAC.
   3. Provide all test sockets for SPDs used on the project.
   4. Provides documentation of test results.

C. Product and manufacturer:
   1. Phoenix Contact, CHECKMASTER.
   2. Erico, MGA TESTER
   3. Dehn, DRC LC M3+
   2. Or approved equal.

2.12 SPARE PARTS

A. Provide the following control system network component spare parts:

   1. One per five of each type of surge protective device; minimum of one of each type of surge protective device.

PART 3 EXECUTION

3.1 INSTALLATION

A. The installation shall follow the SPD manufacturer's recommended installation practices and comply with all applicable codes.

B. Coordinate the installation of the surge protection device with the installation of the equipment being protected. The surge protection device shall be installed as close as practical to or within the equipment being protected.

C. Conductor length between suppressor and connection point shall be as short and as straight as possible.

D. Upon completion of installation, provide the services of a factory-certified local service technician to perform start-up testing. Record test results and compare to factory testing to confirm proper operation of equipment. Submit test results with operation and maintenance manuals.

END OF SECTION

Section 16402

UNDERGROUND DUCT BANKS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Underground electrical duct banks.

1.02 REFERENCES

A. National Fire Protection Association (NFPA): No. 70 - National Electrical Code (NEC) Appendix B.

1.03 SUBMITTALS

A. Catalog cut sheets of the ducts and spacers.

1.04 DELIVERY, STORAGE AND HANDLING

A. Have duct spacers and associated hardware packed and crated to avoid damage during shipment and handling.

B. Clearly mark packages or crates stating that the material is for electrical duct banks only.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

A. Thomas and Betts.

B. Underground Devices Inc.

C. Walker Division, Butler Manufacturing Company.

2.02 MATERIALS AND EQUIPMENT

A. Conduit. Construct ducts using schedule 80 rigid PVC conduit. Refer to Section 16111 - Conduit, Fittings and Bodies.

B. Spacers. Secure conduit with non-magnetic, universal, interlocking-type spacers for both horizontal and vertical duct arrangements.

C. Concrete. Use steel reinforced, red concrete as duct encasement. Refer to Section 03100 Concrete Formwork.

PART 3 EXECUTION

3.01 PREPARATION

A. Verify from Drawings and field survey that the location of ductbanks does not interfere with any existing or new underground facilities.

B. Verify that materials are on site in proper condition and that sufficient quantity is on hand for the work.

C. Verify that trenches are in the correct places and prepared with sufficient depth and width to accommodate the duct banks, reinforcing rod, and concrete.

D. Be prepared for inspection of the duct banks before reinforcing rod is installed.

E. Before pouring concrete, verify that the ducts are free of debris and properly installed in the support and spacer systems and that the ducts are properly fitted together and firmly held in place by the hold down hardware.

F. Provide 24-hour notice to Project Manager, Wastewater Inspectors and the Local Code Inspector for cover-up inspection before pouring electrical conduit ductbanks.

3.02 INSTALLATION

A. Use the size and types of conduit as indicated on the Drawings for the various duct banks required for the project.

B. Make duct bank installations and penetrations through foundation walls watertight.

C. Assemble duct banks using non-magnetic saddles, spacers and separators. Position separators to provide 2-inch minimum concrete separation between the outer surfaces of the conduits.

D. Provide a 3-inch minimum concrete covering on both sides, top and bottom of concrete envelopes around conduits. Add red dye at the rate of 10 pounds per cubic yard to concrete used for envelopes for easy identification during subsequent excavation.

E. Firmly fix ducts in place during pouring of concrete. Carefully spade and vibrate the concrete to ensure filling of spaces between ducts.

F. Make bends with sweeps of radius not less than 6 times the smallest diameter of the raceway.

G. Make a transition from non-metallic to pvc-coated metallic rigid conduit where duct banks enter structures or turn upward for continuation above grade.

H. Make bends of 30 degrees or more using rigid galvanized steel.

I. Reinforce duct banks throughout, where indicated on the Drawings.

1. Unless otherwise noted on the Drawings, reinforce with No. 5 longitudinal steel bars placed at each corner and along each face at a maximum parallel spacing of 12 inches on centers, and No. 5 tie-bars transversely placed at 18-inch maximum longitudinal intervals.

2. Maintain a maximum clearance of 2 inches from bars to the edge of the concrete encasement.

J. Where ducts enter structures such as handholes, manholes, pullboxes, or buildings, terminate the ducts in suitable end bells, insulated L-bushings, Meyers hubs or couplings on steel conduits. Tag conduit entering pull boxes with stamped, stainless steel tags. Identify as designated in cable and conduit schedule.

K. Do not backfill with material containing large rock, paving materials, cinders, large or sharply angular substances, corrosive material, or other materials which can damage or contribute to corrosion of ducts or prevent adequate compaction of fill.

L. Install a bare stranded copper duct bank ground in each duct bank envelope. Make ground electrically continuous throughout the entire duct bank system. Connect ground to switchgear and MCC ground buses and to steel conduit extensions of the underground duct system.

M. After completion of the duct bank and prior to pulling cable, pull a mandrel, not less than 12 inches long and with a cross section approximately one-fourth inch less than the inside cross section of the duct, through each duct. Then pull a rag swab or sponge through to remove any particles of earth, sand or gravel that may have been left in the duct. Repull the rag or sponge swab until the swab emerges clean.

N. Use hemp rope to pull conductors into PVC conduit. Do not use nylon or wire cable for this purpose.

O. Install a warning ribbon approximately 12 inches below finished grade over underground duct banks. Refer to Section 16195 - Electrical Identification.

P. For manholes and pull boxes below grade, install wire racks to support cables properly around the perimeter and keep them dry.

Q. For manholes and pull boxes below grade, construct a french drain, or other drainage as detailed on the Drawings.

END OF SECTION

Section 16410

LOW VOLTAGE POWER FACTOR CORRECTION CAPACITORS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for low voltage power factor correction capacitors.

1.02 REFERENCES

A. American National Standards Institute/National Electrical Manufacturers Association (ANSI/NEMA)

1. NEMA CP-1: Shunt Capacitors

2. NEMA ICS-2: Industrial Control Devices, Controllers and Assemblies

B. American National Standards Institute/National Fire Protection Association (ANSI/NFPA): NFPA No. 70 - National Electrical Code (NEC) Article 460 - Capacitors.

C. American National Standards Institute/Institute of Electrical and Electronic Engineers (ANSI/IEEE): Standard No. 18 - Standard for Shunt Power Capacitors.

D. Underwriters Laboratories, Inc. (UL): UL 810 - Capacitors.

E. Power factor correction system shall comply with Centerpoint standard for harmonic distortion.

1.03 SUBMITTALS

A. Submit the following under provisions of Section 01330 – Submittal Procedures:

1. Mounting dimensions and instructions

2. Equipment weights

3. Catalog data

4. Electrical schematics and wiring diagrams for control devices

5. Operating instructions for controls

1.04 QUALITY ASSURANCE

A. Tests

1. Perform tests in accordance with ANSI/NEMA CP-1. Each capacitor shall be subjected to manufacturing testing as described in ANSI/UL 810. Have test or inspections performed and evaluated by qualified personnel. Document deficiencies observed during the testing process and correct them prior to shipment.

2. Tests required include: short-time over voltage test, capacitance test, leak test and dissipation factor test.

3. Run a functional test on factory assembled automatic units.

1.05 DELIVERY, STORAGE AND HANDLING

A. Have capacitors packed and crated to permit ease of handling and to provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. ABB Power T&D Company, Inc.

B. ASC Industries

C. Eaton/ Cutler Hammer.

D. General Electric Company

E. Schneider Electric

2.02 MATERIALS AND EQUIPMENT

A. Capacitor Requirements

1. The capacitors shall provide power factor correction for individual motors 15 horsepower and above in the system by connecting each capacitor to the load side of the respective motor starter, or automatically switching capacitor banks on and off in accordance with the need for reactive power. See Drawings and one-line diagrams for details.

2. Use capacitors meeting the requirements stipulated in NEMA CP-1 and IEEE Standard No. 18.

3. The capacitor total losses shall not exceed 0.5 W per kVAR.

4. Select capacitors with permanently connected discharge resistors in full compliance with NEC Article 460-6(a) and (b).
5. Use capacitors which are the fused, fixed-type with multiple cells with dry-type dielectric enclosed in an anti-corrsion unpainted enclosure.

6. When individual motor circuits are equipped with power factor correction capacitors, connect the capacitors to the circuit between the contactor and the overload relay so as not to affect the true value of the motor current going through the overload relay heater coils.

7. Provide necessary anti-corrosion mounting brackets and hardware with the capacitors.

8. When called for on the one-line diagrams, provide the power factor correction by an automatic capacitor bank.

9. Connect the capacitor bank to the main power supply bus immediately down-stream from the ammeter and voltmeter in the motor control center.

10. Select individual capacitors as described for the individual motor power factor correction capacitor.

11. Use a capacitor bank with a modular design to allow for expansion by adding capacitor units and control devices.

12. Mount capacitors and control system in an enclosure suitable for the environment and as specified in Section 16160 - Cabinets and Enclosures.

    a. If installed outside, provide a NEMA 3 gasketed enclosure.

    b. If installed inside a building, provide a NEMA 12 enclosure.

    c. Mount capacitors on wall above indoor motor control centers.

    d. If a motor control center is part of the plant design, install controls for the automatic power factor correction capacitors in a motor control center section.

B. Automatic Power Factor Control: Where specified, provide controls to permit an operator to select a target power factor adjustable to any value between 0.95 leading and 0.80 lagging. The controls continuously sense the power factor on the circuit being corrected and, when it differs from the target setting for more than 10 seconds, operate a contactor to switch a capacitor bank into or out of the circuit. Contactors are opened or closed as required to bring the corrected circuit power factor closer to the target setting. Only one capacitor bank is switched at a time.

C. Controls. The controls for the automatic power factor correction shall comply with NEMA ICS-2 with quantities, ratings, mounting provisions and sensing, and power connections as shown on the one-line diagrams. System features and components shall include:

1. Basic control system: solid-state microprocessor-based.

2. Three-pole 600-volt rated contactors for repetitive high-inrush-switching duty presented by capacitor loading.

3. Fuses or circuit breakers for protection of wiring, contactors and capacitors.

4. Air-core-type inductors mechanically braced to withstand the maximum fault current available at the point of application may be installed in the capacitor circuit to limit switching surges to within contactor ratings.

5. Indicating lights designating energized capacitor banks.

6. The power bus, when required, shall be tin plated copper and braced for available fault current.

7. Interlock enclosure doors to de-energize capacitors when doors are opened.

8. A switchboard type power factor meter with 0.5 lagging to 0.5 leading and plus or minus one percent accuracy.

9. A main circuit breaker operable from outside the enclosure which can de-energize the entire system inside the enclosure. Arrange breaker for pad-locking.

10. Capacitor failure alarm relay with one form C contact for connection by City.

PART 3 EXECUTION

3.01 PREPARATION

A. Factory Assembled Unit. Verify dimensions of the housekeeping pad and the embedded leveling channels and conduit stub-ups if applicable.

B. Individual Capacitor for Each Motor. Verify dimensions of the capacitor mounting rack to ensure proper fit and accessibility for wiring and maintenance.

C. Controls in Motor Control Center - Capacitors separately mounted. Verify content of Motor Control Center section to ensure correct power and control devices and wiring.

3.02 INSTALLATION

A. Install equipment and wire up in accordance with the manufacturer's published instructions.

B. Torque bus bar bolts and cable connections to manufacturer's recommendations and tighten nuts and bolts on steel enclosures to ensure structural integrity.

C. Locate capacitors to allow adequate ventilation around the enclosures.

END OF SECTION

Section 16461

DRY-TYPE TRANSFORMERS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specifications for dry-type transformers for the following applications:

1. Motor drive isolation
2. Shielded isolation
3. Non-linear loads
4. General purpose

1.02 REFERENCES

A. American National Standards Institute/National Electrical Manufacturers Association (ANSI/NEMA)

1. ANSI No. C89.2: Transformers
2. NEMA ST 1: Specialty Transformers
3. NEMA ST-20: Dry-Type Transformers for General Applications

B. Underwriters Laboratories (UL): UL 506 - Standard for Safety Specialty Transformers.

C. American National Standards Institute/National Fire Protection Association ANSI/NFPA): NFPA No. 70 -National Electrical Code (NEC); Article 450 - Transformers and Transformer Vaults.

1.03 SUBMITTALS

A. Submit the following under provisions of Section 01330 – Submittal Procedures:

1. Outline dimensions, support points and unit weight.
2. Electrical characteristics, including impedance and tap configuration.

3. Insulation type, rated temperature rise, and total insulation system.

4. Test reports are required for equivalent of supplied transformers 300 KVA and above, indicating losses at 25, 50, 75 and 100 percent rated load and sound levels.

5. Connection diagrams.

6. Catalog data.

7. Operation and maintenance data.

1.04 QUALITY ASSURANCE

A. Tests. Run manufacturer's test on transformers in accordance with Underwriters Laboratories (U.L.) Standard No. UL-506.

1.05 DELIVERY, STORAGE AND HANDLING

A. Have transformers individually packed and crated to permit ease of handling and to provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. ACME Transformer

B. Eaton/ Cutler Hammer

C. General Electric

D. Hevi-Duty

E. Schneider Electric

2.02 MATERIALS AND EQUIPMENT

A. Use dry-type transformers for lighting system or other general purpose applications, motor drive isolation, shielded isolation and non-linear load requirements.

B. Provide transformers with copper windings.

C. Select transformers designed and constructed in accordance with NEMA ST-1, NEMA ST-20 and the NEC Article 450.

D. For applications up to 30 KVA, use transformers that are encapsulated, non-ventilated type with 115 degree C temperature rise and 185 degree C insulation class.

E. Provide transformers with full capacity winding taps a minimum of two 2-1/2 percent above and two 2-1/2 percent below normal voltage.

F. For applications of 30KVA and above use transformers that are the drip-proof ventilated type for indoor mounting only.

G. Use transformers with sound levels in accordance with NEMA ST-20.

H. Basic impulse level (BIL) shall be 10KV for transformers less than 300 KVA, 30KV for transformers 300KVA and larger.

I. Ground core and coil assembly to enclosure by means of a visible flexible copper strap.

J. Provide transformers with lifting eye bolts or brackets.

K. Provide transformer nameplates of stainless steel, marked in accordance with NEC Article 450-11. Fasten nameplate to the transformers with stainless steel screws or rivets.

L. Refer to the one-line diagram or the Drawings for transformer size, volt and wire configuration.

M. Special purpose transformers shall be as follows:

1. Motor drive isolation transformers: designed for 3-phase SCR controlled, variable speed motor voltages with bracing to withstand stresses associated with motor drives.

2. Shielded isolation transformers shall be designed for power inputs to microprocessors and computers that require additional protection from electrical disturbances with the use of grounded electrostatic shielding.

3. Non-linear transformers shall be designed to withstand the heating effects caused by harmonics resulting from non-linear, non-sinusoidal loads. Use K-rated transformers for non-linear loads.

PART 3 EXECUTION

3.01 PREPARATION

A. Verify dimensions of housekeeping pads or other support structures to ensure proper fit.

B. Verify raceway and wiring drawings that are prepared for the transformers and check them against the manufacturer's information.

C. Verify that the protective devices planned for the transformers are in accordance with NEC Article 450.

3.02 INSTALLATION

A. Install transformers plumb and level and in accordance with manufacturer's instructions and the NEC Article 450.

B. Use flexible conduit for connection to transformer case. Make conduit connections to side panel of enclosure.

C. Mount transformers on isolation pads as required to isolate transformer noise from the buildings structure.

D. Wire transformer primary and secondary in accordance with the nameplate instructions and the designated voltages as shown on the one-line diagram.

END OF SECTION

Section 16480

MOTOR CONTROL CENTER

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specification for low voltage motor control center (MCC).

1.02 REFERENCES

A. American National Standards Institute/National Electrical Manufacturers Association (ANSI/NEMA)

1. ICS 1: General Standards for Industrial Control and Systems
2. ICS 2: Industrial Control Devices, Controllers and Assemblies
3. ICS 4: Terminal Blocks for Industrial Use

B. American National Standards Institute/Underwriters Laboratories, Inc. (ANSI/UL)

1. 467: UL Standard for Safety, Grounding and Bonding Equipment
2. 489: UL Standard for Safety, Molded-Case Circuit Breakers and Circuit-Breaker Enclosures
3. 506: UL Standard for Safety, Specialty Transformers
4. 845: UL Standard for Safety, Motor Control Centers

C. American National Standards Institute/National Fire Protection Association (ANSI/NFPA): 70 National Electrical Code (NEC).

1.03 SUBMITTALS

A. Submit the following under the provisions of Section 01330 – Submittal Procedures:

1. Outline drawings with elevations
2. Equipment arrangement drawings

3. Anchor bolt location drawings

4. Electrical schematics and wiring diagrams

5. Current, potential, and power transformer curves

6. Electrical fuse/circuit breaker characteristic

7. Equipment performance curves and data

8. Bill of installation/assembly materials

9. Equipment weights

10. Completed manufacturer's data sheets

11. Catalog data

12. Assembly/disassembly sizes and weights

13. Nameplate data

14. Performance/acceptance test report

15. Operation and maintenance data

1.04 QUALITY ASSURANCE

A. Tests. Perform tests in accordance with ANSI/NEMA ICS 2-322.22. Test each MCC as described in ANSI/UL 845. Make available upon request certified temperature and short-circuit test data, and a certificate of circuit breaker conformance with ANSI C37.16. Have tests and inspections performed and evaluated by qualified personnel. Document and correct deficiencies observed during the testing process prior to shipment.

1.05 DELIVERY, STORAGE AND HANDLING

A. Upon completion of the manufacture and assembly of the MCC and before crating for shipment, have parts that are disassembled match marked to facilitate installation in the field. Pack and crate parts in such a way to permit ease of handling.

B. Equip MCC shipping sections with lifting facilities so that may be easily unloaded and handled, either by crane or forklift.

C. Do not exceed 120 inches in length for shipping sections. Have equipment packed, crated, and rigidly braced to protect it from damage

during shipment, handling, and outdoor storage. Make provision to energize the space heater of each shipping section during storage at the jobsite. Make a connection point readily available without uncrating the equipment and clearly tag each shipping section to locate the connection and identify the electrical service required.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Allen-Bradley

B. Eaton/ Cutler Hammer

C. General Electric

D. Powell Electrical

E. Manufacturing Company

F. Siemens

G. Schneider Electric

H.

2.02 MATERIALS AND EQUIPMENT

A. Design. Provide an MCC with the following design characteristics:

1. The MCC construction and wiring shall be NEMA Class I, Type B as specified in ANSI/NEMA ICS-2-322.08 and ICS-2-322.10. Provide an MCC designed for 3-phase, 60 Hz, 480-Volt service with main horizontal and vertical bus ampacities and short circuit bracing as specified on the one-line diagram. Provide NEMA Class IIB wiring for interconnection wiring as specified on drawings.
2. Furnish an MCC designed to operate in service conditions described in NEMA ICS 1 and as shown on the one-line diagram.
3. Supply motor starters suitable for full voltage starting unless otherwise noted on the one-line diagram.

4. Construct the MCC of one or more vertical sections bolted together to form a free standing assembly, designed to permit future additions, changes, or regrouping of units.

5. Provide motor control units of the combination type, consisting of a motor circuit protector (MCP), a magnetic starter and a control power transformer. Size the MCP and starter in accordance with manufacturer's recommendation for the starter and motor size indicated on the one-line diagram.

6. When power factor correction capacitor is called for, connect its wiring to the line side of the overload relay with a set of fuses, a circuit breaker, or other acceptable means to serve as overload protection for the wiring and capacitor.

7. Manufacture main breaker (if used) and feeder breakers of the molded case, thermal-magnetic type to be mounted and wired in accordance with ANSI/UL 489.

8. If called for on the one-line-diagram, locate the lighting panelboard, transformer and transformer feeder breaker in the same vertical section. Supply a transformer with 115 degrees C temperature rise, installed in accordance with ANSI/UL 506.

B. Construction. Construct the MCC of self-supporting and fully enclosed metal clad section for mounting of motor starters, circuit breakers and necessary accessories including bus bars, control transformers, control switches, ground bus, and control wiring, as specified in this section and shown on the one-line diagram.

C. Enclosures

1. Construct each MCC enclosure to be fully metal enclosed, dead front, free standing, and NEMA 12 suitable for indoor service as defined in ANSI/UL 845 or NEMA 3R suitable for outdoor installation when indicated on the one-line diagram. Fabricate enclosure of sheet steel not less than 14 gauge with rear and end covers not less than 16 gauge; with adequate strength to withstand stresses imposed by short circuit current, shipping, handling, installation, and operation, without distortion or damage.
2. Construct frames of the enclosure structure with continuous steel barriers, extending from the front to the rear of each compartment for the controller units, buses and power cables.

3. Provide enclosures of suitable size for reduced voltage starting auto transformers and associated wiring, if required.

D. Vertical Sections

1. Make the structure 20 inches deep. Nominal vertical section dimensions are 20 inches wide by 90 inches high. Design each vertical section to accommodate not more than six NEMA Size 1 combination motor control units mounted one above the other in front-mounted arrangement.

2. Provided horizontal wiring space at the top and the bottom of each vertical section, which will line up with adjacent sections to form continuous raceways through the entire length of the MCC. In addition, in standard sections include vertical wireways with hinged doors for unit wiring. Provide grommets at points wiring must cross cut-outs.

3. Use section structure designed for top or bottom cable entry as indicated on the one-line diagram. Provide adequate ventilation and heating facilities for each section to keep the maximum temperature rise and humidity within the acceptable limits.

E. Incoming Feed

1. Terminate incoming feeder cables in a main breaker or main lugs. Use top feed to main breakers whether either top or bottom MCC cable entry is specified.

2. The MCC will be fed from one 480V source, unless otherwise stated. Provide the necessary space for adequate bending radius and spreading room to properly train and terminate the cables specified on the Drawings. Where large (350 MCM and above) or parallel cables are used as feeders, provide a separate termination compartment along side the main breaker for cable entry.

3. Provide a separate compartment with a hinged front access door and suitable space for terminations for incoming cables. Provide compression type lugs in the quantity shown on the diagram. Allow space for a cable bending radius not less than ten times the diameter of the cable. The cable size is shown on the one-line diagram. Install current transformers and phase monitor coils in this compartment on fixed horizontal mounting brackets. Do not loosely place coils around feeder cables.

4. Furnish surge protection devices as specified in Section 16290 - Primary Instrumentation Devices, located downstream from the

main breaker or lugs. Mount surge arresters in an isolated, completely enclosed cubicle.

5. When shown on the one-line diagram, install a voltmeter and an ampere-meter with switches in the incoming feed section. Provide meters of the switchboard type with one percent accuracy, 4-1/2 inch diameter face with a minimum of 240 degree direct reading scale. A single electronic meter may be used in lieu of electro-mechancial meters.

F. Combination Starter Unit

1. Provide a standard combination motor starter unit which consists of a motor circuit protector (MCP), a magnetic motor starter, and an overload relay. Install starter and circuit protective device and control power transformer in a plug-in unit. The ratings of the components are shown on the one-line diagram.

2. Provide motor starters conforming to NEMA standards for the horsepower of the motors with which they are to be used and which are suitable for full voltage, across-the-line starting. Select starters with pickup and dropout voltages of not greater than 85 percent and 60 percent of rated voltage, respectively. Do not use a starter smaller than NEMA Size 1.

3. For NEMA size 4 and larger, provide vacuum-type contactors.

4. Select overload relays designed so that any attempt for reset immediately after operation cannot result in damage to the unit. Provide running protection for the motor and all other series components, based upon the tripping characteristics of the overload relay.

5. Utilize motor management relays of the solid state type with adjustable overload, phase unbalance and phase failure sensitivity. Refer to speciation 16662.

6. Starters shall have a minimum of one NC and one NO auxiliary contacts in addition to the seal-in contact.

7. Have reversing contactors and 2-speed starters both mechanically and electrically interlocked to prevent both contactors from being engaged at one time.

8. Provide an MCP of the magnetic type with a fault interrupting capability suitable for the complete starter unit.

9. Provide each combination starter unit with its own control power transformer with Class B insulation and 120 volt secondary.
10. Place fuses on the secondary side of control power transformers with one dual element fuse. Have control transformers separately fused on the primary side with two dual element fuses.

11. Unless otherwise called for on the one-line diagram, the minimum rating of the control power transformer shall have the capacity to operate all connected loads including motor space heaters. The minimum for the various sizes of starters, shall be as follows:

NEMA Size 1	100 VA
NEMA Size 2	150 VA
NEMA Size 3	250 VA
NEMA Size 4	500 VA

12. Connect the control power transformer so that it is de-energized when the circuit breaker is opened.

G. Reduced Voltage Starters

1. If reduced voltage starters are specified, provide the closed transition auto-transformer type.

2. Construct each reduced voltage auto-transformer starter unit with a molded-case circuit breaker in combination with a closed transition type auto-transformer starter with 50 percent, 65 percent, and 80 percent taps. Set the starter on the 65 percent tap. The starter shall have three phase overload relays and shall be ambient temperature compensated with manual reset. Include a thermal switch wired to protect the auto-transformer from overheating. Control timing of the starting period by an adjustable accelerating relay.

3. Provide heavy duty, NEMA type, autotransformers sized for a minimum of 125 percent of the motor load.

H. Terminal Blocks

1. Provide terminal blocks conforming to NEMA/ANSI ICS 4 type rated 600 volts, with screw type terminals to accommodate non-insulated ring tongue wire lugs for No. 18 through No. 10 size wire for field connection.

2. Use a sufficient number of terminal blocks so circuits for 480-volt and 120-volt service can be wired to a separate group of terminal blocks, making power and control circuit readily identified for safety during maintenance.

3. Wire all auxiliary contacts to terminal blocks.

I. Units

1. Equip each unit compartment with barriers to isolate it from adjacent devices in the control center and prevent communication of faults from one compartment to another.

2. All full voltage starter units through NEMA Size 5 and all feeder breakers through 400 Amp shall be of the draw-out push in/ pull out type. Draw-out provisions shall include a positive guide rail system and stab shrouds to absolutely ensure alignment of stabs with the vertical bus. Draw-out units shall have a tin-plated stab assembly for connection to the vertical bus. No wiring to these stabs shall extend outside of the draw-out unit.

3. Install an individual front door on each unit compartment. Make each door interlocking with the circuit disconnect so that the door may not be opened while the circuit disconnect is in a closed position. Provide a means for overriding this interlock.

4. Use padlocking arrangements that permit locking circuit disconnect in the open position with a minimum of three padlocks when the door is closed.

5. Arrange components so that removal of a starter or breaker unit does not require removal of its door, or the removal of an adjacent unit.

6. Place unit wiring diagrams in the print pocket on the inside of each unit door.

7. Furnish units designated as future or spare complete with guide rails, separator bars, doors, and operating hardware required to permit completion of the unit by the addition of a combination starter or feeder breaker unit.

8. For any unused space that is not suitable for the addition of a plug-in unit, fabricate and install a plain bolted sheet metal cover.

9. Identify electrical components, such as relays, breakers, terminal strips, and starters, with laminated nameplates as required in Section 16195.

J. Buses and Connections

1. Extend the main horizontal copper bus across the assembly to form a complete continuous bus. Support it in at least two places in each vertical section using glass-reinforced, polyester-type insulators which are impervious to moisture and adverse atmospheric conditions.

2. Fabricate buses from tin plated copper bars. Use buses designed to operate at individual rate full load current without exceeding a 50 degrees C temperature rise at 40 degrees C ambient temperature as defined in ANSI/UL 845. The continuous current rating of the main and branch buses shall be as stated on the one-line diagram.

3. Bolt connections to main and branch buses. Make joints and contact surfaces free of burrs and irregularities.

4. Provide tin-plated, compression-type cable connectors (NEMA 2-hole) for each bus bar in the main feed cubicle. Select connectors of adequate size and quantity for the feeder cables.

5. Make provision for extension in both directions for future sections.

6. Install both main and branch buses so they are phased in the order A-B-C from front-to-rear, top-to-bottom, and left-to-right as viewed from the front of the MCC.

7. Have a copper ground bus extend the full length of the MCC near the bottom, with provision for extension into future sections. It shall be amp rated at a minimum of 25 percent of horizontal power bus. Provide compression lugs on each end of the ground bus for connection of the grounding copper conductor. Permanently ground the non-current carrying metal parts of equipment within each MCC through the ground bus in accordance with ANSI/UL 467. Terminate ground cables to the ground bus by means of the connectors.

8. The vertical bus shall be completely isolated and insulated by means of a labyrinth design barrier. It shall effectively isolate the vertical buses to prevent any fault-generated gases to pass from one phase to another. The vertical bus shall include a shutter mechanism that will allow the unit stabs to engage the vertical bus every 6 inches and provide complete isolation of the vertical bus when a unit is removed. Provide one shutter mechanism for all future spaces and covers for the balance of openings.

K. Wireways

1. Provide each section with horizontal wiring space at both the top and bottom. Make wiring spaces line up with adjacent sections to form a continuous wireway for the entire length of the MCC.

2. In addition, provide each section with a wireway space at least 4 inches wide between the units and side unit wiring. Secure the wireway with a tight fitting hinged access door of formed sheet metal. Furnish wire straps in the vertical wireway to group individual conductors. Tie wires securely in place for a neat, orderly installation.

3. Completely enclose both horizontal and vertical wireways and isolate them from exposure to any live parts.

4. Use control wiring that is a minimum No. 14-AWG copper, 600 volts, tin plated, Type TA, TBS or SIS as defined in ANSI C37.30.6.
5. For current transformer wiring, use No. 10 AWG copper which is otherwise, the same as control wiring.

6. Power and control cables may enter the MCC only at bottom. Provide suitable opening in bottom of MCC for cable entry. Collect power and control cables neatly in separate bundles.

7. Make wires continuous between terminals and other connections, without splices.

8. Identify wiring at both ends with same number, machine printed on heat shrink type sleeves as specified in Section 16195 - Electrical Identification.

L. Control Devices

1. Provide heavy duty oil tight pushbuttons, selector switches and indicating lights as specified on drawings.

2. Provide indicating lights which are push-to-test LED type with transformer and 100,000 hour lamp life.

M. Space Heaters: Install thermostat controlled electric space heaters to prevent condensation of moisture in the control centers. The rated voltage of these heaters shall be double the voltage applied. Make thermostats adjustable, and set to cut out when the temperature rises to an ambient of 30 degrees C (240 volt rated space heaters operated on 120 volt which power is derived from a local panelboard).

N. Nameplates

1. Use engraved phenolic with black lettering and white background for nameplates on individual units as well as the main nameplate for the assembly.

2. Make MCC compartment nameplates 1" x 3" with approximately 1/4 inch hig lettering. Make MCC main nameplates 8" x 2" with 1 inch high lettering. Secure nameplates with self tapping stainless steel metal screws.

3. Provide a blank nameplate for spare compartments.

4. Word nameplate captions as indicated on the one-line diagram.

5. Label all components in the MCC with phenolic nameplates as required in Section 16195.

O. Finish

1. Thoroughly clean the inside and outside of the MCC of foreign matter, excessive oxide, scale, weld spatter, and flux. Repair fabricating scars and rough edges by welding and grinding before painting, followed by heat treatment, if required by the governing code or standard.

2. Give a finish coat of manufacturer's standard enamel for compartment doors, cover plates, and structural parts of the MCC. Do not apply paint or filler until repairs, tests, and final shop inspection are completed. Epoxy based powder coat is acceptable.

PART 3 EXECUTION

3.01 PREPARATION

A. Verify dimension of the housekeeping pad and the embedded leveling channels and conduit stub-ups.

3.02 INSTALLATION

A. Install the motor control center in accordance with the manufacturer's published instructions.

B. Torque bus bar bolts to manufacturer's recommendations and tighten nuts and bolts on the steel structure to ensure structural integrity.

C. Adjust the magnetic setting on motor circuit protectors in accordance with motor inrush currents (nameplate data).

D. Select and install motor starter overload relay heater coils based on motor nameplate data.

E. Touch up scratches and verify data on nameplates.

F. Install warning labels on Motor Control Centers as required in Section 16195, 2.02, F.

END OF SECTION

Section 16481

MEDIUM VOLTAGE MOTOR CONTROL CENTER

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specification for medium voltage motor control center (MCC).

1.02 REFERENCES

A. American National Standards Institute/Institute of Electrical and Electronics Engineers (ANSI/IEEE): C62.11 - Metal-Oxide Surge Arresters for AC Power Circuits.

B. American National Standards Institute/National Electrical Manufacturers Association (ANSI/NEMA): ICS-3- 1993 (R2000)

C. American National Standards Institute/Underwriters Laboratories, Inc. (ANSI/UL)

1. 467: UL Standard for Safety, Grounding and Bonding Equipment

347 or equivalent CSA C22.2 No.14

D. Institute of Electrical and Electronics Engineers (IEEE).

1.03 SUBMITTALS

A. Submit the following under the provisions of Section 01330 – Submittal Procedures:

1. Outline drawings with elevations
2. Equipment arrangement drawings
3. Anchor bolt location drawings
4. Electrical schematics and wiring diagrams
5. Current, potential, and power transformer curves
6. Electrical fuse/circuit breaker characteristic

isolation switch, current limiting fuses, contactor, safety interlocks and specified instrument transformers, protective relays, meters and related components. The design, rating and testing shall be in accordance with ANSI standard C37.2 and C37.20.3.

2. Furnish an MCC assembly and accessories designed for the environmental conditions specified in the design guidelines.

3. Supply motor starters suitable for full voltage starting unless otherwise noted on the one-line diagram.

B. Construction

1. Enclosures shall be rigid, free standing steel. Steel panels and doors shall be of NEMA standard thickness and built according to ANSI/NEMA standards, No. ICS 2.

2. Construct the MCC of one or more vertical sections bolted together to form a rigid, free standing assembly, designed to permit future additions, changes, or regrouping of units.

3. Construct each unit with adequate strength to withstand stresses imposed by the specified short circuit current, shipping, handling, installation, and operation, without distortion or damage.

4. Provide lifting eyes on top of each structure.

5. Each vertical section shall accept one starter high or two high as specified on the arrangement and layout drawings. Use a maximum of two starters in any one vertical section. If manufacturers' standard design incorporates three high constructions, reserve the top space for either future use only or for auxiliary control devices, as specified.

6. Build enclosures with separate low voltage and high voltage.

7. Compartments. Arrange compartments so that the low voltage compartment can be entered with the controller energized without exposure of personnel to high voltage.

8. Construct starter unit assemblies to allow access from the front only unless one-line diagram specifies otherwise.

9. Make panels removable which are enclosing devices or fixtures that are normally inspected, maintained or replaced.

10. Provide adequate space in each controller unit for entrance and termination of power cables, control wiring, and raceways. The type, size, number, and location of these wires and conduits, as well as any special fittings, is given on the one-line diagram.

11. Provide panel positioners on hinged panels so panels will be able to clear the floor level. by at least one inch. Where the standard MCC design does not permit this clearance, supply a suitable raised platform for raising the MCC to the desired level. Design the platform for welding and bolting to the floor and with bolted fasteners for the MCC.

12. Design the enclosure ventilation system to prevent venting of hot gases or arcing toward an operator during circuit interruption. In addition, provide enclosures with proper ventilation to minimize temperature rise due to heat given off by fuses and contactors during normal operation.

C. Enclosures

1. Indoor Enclosures.

2. When a separate building is planned to house control equipment, use a NEMA type 12 enclosure for indoor, nonhazardous installations for mounting in an environmentally controlled location. Ventilation openings shall be filtered (1-inch fiberglass) and screened with stainless steel hardware, arranged to prevent the entrance of snakes, rodents, and insects. Screen exhaust openings. Select control devices for proper operation in the designated atmosphere without further protection.

3. Provide door and panel hardware that is captive. Use screws, fasteners and unpainted components that are plated.

4. Outdoor Enclosures

   a. When a separate building is not planned the assembly enclosure for indoor, nonhazardous installations shall be NEMA 3R. The enclosure may be either walk-in or non-walk-in design as specified on the data sheets. Use an enclosure that is dust-resistant, raintight, rodent proof and equipped with adequate lighting, heating and ventilation suitable for the specified environmental conditions.

   b. Seal, weld joints in the outer steel housing for the entire length, bolted and neoprene gasketed, or otherwise designed and

fabricated to preclude the entry of rain, snow, and dust. Gaskets shall be held in metal retainers (channel or other similar device). [I have not seen metal retainers for door gaskets before. Do people do this?] Slope the roof to provide drainage.

c. For the enclosure, provide structural members that raise the enclosure a minimum of 3 inches above the foundation or fabricate it suitable for direct mounting on structural members in the foundation if specified. Coat the underside of the enclosure with mastic or other equally effective coating material to prevent rust.

d. Provide enclosures with louvered ventilation openings at the top and bottom unless designed to be unventilated. Equip such openings with replaceable filter elements. Make filter elements accessible for replacement while the equipment is in normal service.

e. When specified, provide thermostatically controlled ventilation fans where required to maintain an acceptable temperature within the enclosures.

f. Provide an outer door of 28 inches minimum width at each end of walk-in (protected aisle) type enclosures. Conventional outdoor (aisleless) enclosures shall have individual outer doors of 24 inches minimum width, or a double door for each section. Position doors to allow full access to individual motor starters and to allow withdrawal of starters. Design outer doors to have formed and gasketed weatherproof joints which prevent entrance of dust and moisture. Gaskets shall be held in metal retainers (channel or other similar devices).

g. Provide door stops to hold doors in the open position. Provide a stop release no higher than 6 feet above the floor. Design door latches to engage the steel frame at three points (top, bottom, and middle) to latch the doors closed, with a rolling or smooth sliding action when engaging the frame to aid in operating the latches on doors at each end of walk-in enclosures include flush, cylinder type locks and inside quick release latch mechanisms. Make provisions for locking doors on conventional outdoor enclosures.

h. Secure removable panels with slotted or shaped head fasteners, machine screws, or machine bolts engaging captive nuts or tapped holes in structural members. Do not use self-tapping steel metal screws. Place warning signs saying "Danger High Voltage" on all high voltage access doors as required in Section 16195.

D. Finish

1. Thoroughly clean MCC steel work of foreign matter, excessive oxide, scale, weld spatter, and flux. Repair fabricating scars and rough edges by welding and grinding, followed by heat treatment as necessary, before painting.

2. Give a finish coat of manufacturer's standard enamel to compartment doors, cover plates, and structural parts of the MCC. Expoy powder coat is acceptab;le. Coat the bottom of each structure with a corrosion resistant compound. Do not apply paint or filler until repairs, tests, and final shop inspection are completed.

3. Plate unpainted parts for resistance to corrosion.

4. Obtain from the manufacturer, paint suitable for spray application, matching each color used, for field touch up after installation of the equipment. Supply two 1-pint cans of each color used for each lineup shipped. Aerosol cans are not acceptable.

E. Power Bus

1. Arrange the main bus structure for future extension on both ends. Include in end cubicles predrilled bus bars and a removable plate for bus extension.

2. Tighten bus joints with appropriate nuts, bolts, spring-type washers, torqued to maintain vendor's recommended pressure for the service life of the equipment.

3. Fabricate busses from tin plated copper, including bus joints. Provide buses having the capacity as shown on the one-line diagram. Brace buses for short circuit current as shown on the one-line diagram.

4. Support the power bus with track resistant, flame retardant, high impact strength porcelain bus supports. Provide supports with maximum creepage and air clearance distances. Isolate bus work to avoid accidental contact by means of removable insulating barriers of flame retardant, track resistant material. Use non-hygroscopic materials bus supports.

F. Ground Bus

1. Have a continuous copper ground bus extend for the entire length of the assembly, allowing connections in each vertical section. Provide the ground bus with copper compression lugs at each end of the

assembly suitable for connecting to copper cable at each end. Size lugs as shown on the one-line diagram. Arrange the ground bus for future extensions on both ends.

2. The ground bus shall have a capacity of at least 25 percent of the nominal main power bus capacity but shall be minimum 1/4 inch x 2 inch copper.

3. Bond non-current carrying metal parts in the MCC to the ground bus in accordance with ANSI/UL 467.

G. Isolation Device

1. Provide each starter unit with an externally operated, interlocked, primary disconnect means. Design this disconnect switch operating to open the secondary of the control power transformer, withdraw the line stabs and close the isolating shutters over the power connectors. Make the state of the switch clearly visible.

2. Provide interlocks to prevent inadvertent operation of the isolating mechanism under load and opening of the high voltage compartment before the controller is isolated and grounded.

3. Use mechanical interference type interlocks. Provide a means for gaining entry to the enclosure in case the contactor should become welded in the closed positions.

4. Make provision for padlocking the isolating switch in the open position.

5. Make provision to operate the controller from a separate control power source for testing, but only with the main isolating switch and control transformer secondary open.

H. Controller

1. Provide NEMA Class E2, high interrupting capacity controllers employing current limiting power fuses, vacuum type contactors, and having a minimum short circuit interrupting rating and voltage as indicated on the one-line diagram.

2. Integrate power fuses, contactor and contactor accessories on a single drawout carriage. Use a carriage design with line side and load side disconnects of the stab-on type so that the carriage can be removed from the compartment without physically disconnecting high voltage cables. Make low voltage connections to the carriage with a design with quick disconnect plug or with stab-on disconnects.

3. Use bus stabs designed to tighten under faults. Select a design with line site bus stab openings that are automatically shuttered when the carriage is withdrawn from the connected position.

4. Provide each controller with means for connection to ground for providing a positive grounding of the controller when the isolating means is opened. Connect positive grounding to the ground bus.

5. Include a detent inspection position to allow inspection or maintenance without complete removal of the carriage from the compartment.

6. Have each door interlocked with the associated circuit disconnect means so that the door may not be opened while the circuit disconnect device is in the closed position and so that the disconnecting device cannot be operated with the door open. Provide a means to prevent withdrawing the carriage from the connected position unless the contactor is deenergized and its contacts are open.

I. Current Limiting Power Fuses

1. Provide self-protecting type or R-rated motor starting type power fuses with visible fuse condition indicators. Locate fuses so they can easily inspected or replaced without starter disassembly.

2. Size power fuses for continuous rating and symmetrical short circuit interrupting capacity indicated on the data sheets. Use fuses that will not expel gases or foreign matter during fault conditions.

3. The fuses shall incorporate special time/current characteristics for motor service allowing proper coordination with the contactor and overload relay for maximum motor protection. This coordination shall be such that under a low-fault condition the interrupting rating and dropout time of the contactor shall be properly coordinated with all possible fuse sizes to eliminate contactor racing.

J. Contactor

1. Use contactors that are rollout or drawout, 3-pole, air break or vacuum, a-c or d-c, and magnetically operated. Provide contactors that are completely interchangeable with other contactors of the same continuous current rating.

2. Make connections to low voltage contactor through a quick-disconnect plug.

3. Equip contactor units with control, protection and monitoring devices of the type and quantity indicated on the data sheets. Supply additional devices required for proper operation of the specified load.

4. Design contactor to operate electrically under full rated voltage.

5. Supply contactors with a quantity of additional normally open and normally closed auxiliary contacts as specified on the one-line diagram. Wire spare contacts to an accessible terminal block.

K. Metering and Control Equipment

1. Current Transformers. Provide each current transformer with a 5-ampere secondary and a primary rating as shown on the one-line diagram. Verify that accuracy, class, and burden rating in accordance with ANSI/IEEE C37.20.2 for the metering and relay application specified. Design current transformers for the maximum fault current and BIL rating for which the starters are designed. For secondary circuit of each current transformer locate accessible short circuiting type terminal blocks remotely from the high voltage compartment.

2. Potential Transformers: Protect potential transformers with secondary fuses in the ungrounded phases and current limiting primary fuses mounted on pull out, range type fuse holders. Design potential transformers to withstand the basic impulse level of the MCC. Label fuse holders permanently to indicate the size and type of fuse required and to identify their associated transformers (e.g., phase, amperes, volts). Verify that each transformer has a 240/120V secondary and an ANSI accuracy classification meeting the requirements of the application shown on the one-line diagram.

L. Control Power Transformer

1. Provide a separate dry-type control power transformer for each starter. Control power voltage is specified on the one-line diagram.

2. Install fuses for both primary legs and one of the secondary. Ground the other secondary leg to the MCC ground bus.

3. Configure each control power transformer so it will automatically disconnect from the high voltage when the controller carriage is withdrawn or the isolating switch is opened. Size the control power transformer for at least 150 percent of the capacity needed for the control devices.

M. Induction Motor Protection

1. Provide starters for induction motors with three ambient compensated thermal overload relays for phase overcurrent protection.

2. Provide one sensitive instantaneous ground fault relay to pick up at no less than 5 amperes. Include a zero sequence current transformer for this relay.

3. Provide three front-accessible, current limiting power fuses for motor branch short circuit protection. Provide anti-single phase protection to open the main contactor when any power fuse operates.\

4. Provide each motor controller with an undervoltage trip device. Include with this device an adjustable time delay feature which is adjustable from zero to 5 seconds. Make this feature removable in the field by changing the wiring at a terminal block.

5. When specified on the data sheets, provide one time delay, overcurrent relay to protect against damaging locked rotor currents.

6. A solid state motor protector may replace the overcurrent, locked rotor, and ground fault relays when specified on the one-line diagram. A solid state motor protector is a multifunction device which incorporates all motor protection functions into a device.

N. Metering

1. Required metering is shown on the one-line diagram.

2. Supply indicating meters of the switchboard type, flush or semi-flush mounted, one percent accuracy, shock resistant, 4-1/2 inch diameter with a minimum 250-degree scale. An electronic meter version is an acceptable alternative.

3. When specified, equip kilowatt-hour meters with an indicating demand register for the specified time interval shown on the one-line diagram. Also indicate pulse initiators for remote metering, as required.

O. Control Wiring

1. Have wiring permanently marked with the same designation at both ends, with preprinted heatshrink tubing as required in Section 16195 to agree with the wiring diagrams. Adhesive type wire labels are not acceptable. Provide control wiring which is flame retardant tin plated type SIS, minimum No. 14 AWG. Provide throughout with insulated, compression type, ring tongue terminals.

2. Current transformer wiring shall be No. 10 AWG copper, unless otherwise noted. Furnish current transformer circuits with short circuiting terminal blocks.

3. Neatly bundle wiring and secure it with wire ties. Use terminal blocks rated 600V with cadmium-plated screw terminals identified to correspond with the wiring and schematic diagrams. Supply these terminals blocks for grouping external connections for relays, meters, interlocks, and alarms. Provide a minimum of 20 percent spare, unwired terminal points.

4. Bring connections to external circuits to conveniently located terminal blocks having marking strips, terminal screws and divider strips between points. Clearly show wiring to be installed by Contractor, including wiring between shipping sections.

P. Nameplates

1. Provide engraved nameplates on individual units, including a main nameplate for the assembly as detailed on the nameplate schedule. Provide permanent nameplates to identify each instrument, switch, meter, relay, control switch, indicating light, circuit breaker compartment, potential transformer compartment, auxiliary compartment and other like items. Include nameplates for items inside the doors and panels of the equipment as well as outside as required in Section 16195.

2. Engrave nameplates on satin finish white with black core and beveled edges.

3. Make MCC compartment nameplates 2-1/2 inch x 1 inch with 3/16 inch high lettering; MCC main nameplates 8 inch x 2 inch with 1 inch high lettering.

4. Secure nameplates with corrosion-resistant screws.

5. Include on nameplates, the ANSI device function number where applicable.

6. Put a blank nameplate on spare compartments.

7. Use nameplate captions indicated on the one-line diagram.

Q. Accessories

1. Provide the following equipment that will be turned over to the City of

Houston:

a. Provide an elevating table type lifting device for installing and removing starter units as specified on the one-line diagram.

b. Provide one insulated fuse puller for power and control fuses for each MCC.

c. Provide test plugs and cables for drawout watt-hour meters and switchboard class relays, when specified.

d. Provide a portable test set for testing of the solid state trip device.

e. Provide a manual closing device for contactors with each MCC.

f. Provide seamless, compression type cable lugs for incoming and outgoing circuits shown on the one-line diagrams. Use lugs suitable for the conductor material shown on the one-line diagram.

R. Space Heaters

1. Supply thermostatically controlled, electric space heaters, when specified, to prevent condensation of moisture in the motor control centers. Use heaters with a rated voltage of 240 VAC, which shall operate effectively on 120 VAC. Arrange each space heater to be powered from an external source.

2. Supply power for motor space heaters, when specified on the one-line diagram, from an external source. If required, power motor space heaters from the control power transformer. Include adequate transformer capacity to serve this load.

3. Provide motor space heaters with an AC ammeter for monitoring the state of the heaters. Control the motor space heater by a normally closed auxiliary contact for the respective motor starter. Supply terminal blocks for wiring the motor space heater.

S. Incoming Feeder. For incoming cables, provide a separate compartment with a hinged, front access door and suitable space for terminations as described on the one-line diagram. Provide compression type lugs of the size and quantity shown. Allow space for a cable bending radius not less than 10 times the diameter of the cable.

T. Surge Arresters/Surge Capacitors. Install three station class or intermediate class surge arresters and surge capacitors on the incoming line compartment as specified on the one-line diagram and in accordance with IEEE C62.1 or ANSI/IEEE C62.11. Furnish surge arresters complete with all fittings and brackets and mounted in an isolated and completely separate cubicle.

U. Auxiliary Devices. Furnish auxiliary control devices as indicated on the one-line diagram. Use pushbuttons, selector switches, and indicating lights that are the oil-tight type, mounted on the unit door, and shielded or recessed rear terminals to minimize the possibility of contact with live contact surfaces. Make pushbuttons color coded and of shrouded construction. Provide indicating lights L.E.D. push-to-test type with transformer and 100,000 hour lamp life.

PART 3 EXECUTION

3.01 PREPARATION

A. Verify dimension of the housekeeping pad and the embedded leveling channels and conduit stub-ups.

3.02 INSTALLATION

A. Install the motor control center in accordance with the manufacturer's published instructions.

B. Torque bus bar bolts to manufacturer's recommendations and tighten nuts and bolts on the steel structure to ensure structural integrity.

C. Adjust the settings on motor circuit protective relays in accordance with motor data and the relay instructions.

D. Before energizing the motor control center, perform a high potential test on the bus system with the contactors engaged and conduit MCC functional demonstration. Have the test and demonstration witnessed by the Project Manager.

E. Touch up scratches and check caption on nameplates.

END OF SECTION

Section 16510

LIGHTING FIXTURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Specification for:

1. Fluorescent lighting fixtures
2. High intensity discharge (HID) lighting fixtures
3. Emergency lighting fixtures
4. Exit fixtures
5. Incandescent lighting fixtures
6. Photo cells

1.02 REFERENCES

A. American National Standards Institute/National Fire Protection Association (ANSI/NFPA)

1. No. 70 - National Electrical Code (NEC)
   a. Article 410 - Lighting Fixtures, Lampholders, Lamps and Receptacles
   b. Article 500 - Hazardous (classified) locations
   c. Article 700 - Emergency Systems
2. No. 101 - Life Safety Code

B. American National Standards Institute (ANSI)

1. C78.379 - Electric Lamps - Incandescent and High Intensity discharge Reflector Lamps - Classification of Beam Patterns.
2. C82.1 - Ballasts for Fluorescent Lamps - Specifications.
3. C82.4 - Ballasts for High-Intensity-Discharge and Low-Pressure Sodium Lamps (Multiple-Supply Type).

C. American National Standards Institute/Illuminating Engineering Society (ANSI/IES): The IES Handbook shall be used as a basis for design and construction of lighting systems.

D. American Society of Heating, Refrigeration and Air-Conditioning Engineers, Inc./Illuminating Engineering Society (ASHRAE/IES): ASHRAE/IES 90.1 - 1989 - Energy Efficient Design of new Buildings Except Low-Rise Residential Buildings.

E. American National Standards Institute/Underwriters Laboratories (ANSI/UL).

1. UL1570 - Fluorescent Lighting Fixtures.

2. UL1571 - Incandescent Lighting Fixtures.

3. UL1572 - High Intensity Discharge Lighting Fixtures.

4. UL844 - Fixtures for Hazardous Areas.

1.03 SUBMITTALS

A. Submit the following under the provisions of Section 01330 – Submittal Procedures:

1. Outline dimensions, support points and unit weight.

2. Operation and maintenance data.

3. Complete test report with photometric curves.

4. Storage, handling, and installation recommendation.

5. Connection diagrams.

6. Catalog data.

1.04 QUALITY ASSURANCE

A. Tests. Run manufacturer's tests on lighting fixtures in accordance with applicable Underwriters Laboratories (U.L.) Standards 1570, 1571 and 1572.

1.05 DELIVERY, STORAGE AND HANDLING

A. Have lighting fixtures individually packed to permit ease of handling and to provide protection from damage during shipping, handling and storage.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

A. Benjamin Div., Thomas Industries

B. Crouse-Hinds, Div. of Cooper Industries

C. G.E. Lighting System

D. Guth Lighting

E. Holophane Company, Inc.

F. Hubbell Lighting, Inc.

G. Killark Electric Mfg. Company

H. Lithonia Lighting

I. Pauluhn Electric

J. Wide-Lite Corporation

K. Dual-Lite Company

2.02 REQUIREMENTS

A. Provide lighting fixtures in accordance with the lighting plan Drawings, Lighting Fixture Schedules and this specification.

B. Fluorescent Lighting Fixtures

1. Fixtures

a. Select fixtures designed for operation on rapid start ballast circuit with medium bipin T8 bases.

b. Use ballasts with high power factor rapid start electromagnetic type in accordance with ANSI C82.1.

c. Use fixtures tested and approved under UL 1570 for damp locations as a minimum.

d. Provide heavy duty industrial type fixtures with baked white finish, spring loaded metal clad lamp holders and heavy duty apertured reflector, unless indicated otherwise on the Drawings.

2. Ballasts

   a. Ballasts shall be UL listed with a Class P thermal rating, a Class A sound rating conforming to Part 18 of CRF 47 of the Federal Communications Commission Rules and Regulations.

   b. Ballasts shall comply with ANSI C62.1-1984 (IEEE 587) for line transients and ANSI C78-1 for maximum starting voltage for each type of fluorescent lamp.

   c. Ballasts shall be for minimum starting temperature of 0 degree F, unless otherwise specified and shall have a power factor greater than 0.90 and shall not contain PCB (Polychlorinated biphenyls).

   d. Ballasts shall maintain constant light output for line voltage fluctuations of plus or minus 10 percent and be able to operate properly with plus or minus 15 percent voltage fluctuations.

   e. Ballast factor: Ballasts shall comply with ANSI C82.1 and shall have a high ballast factor (.88 or greater) when firing the number of lamps wired to the ballast.

   f. Crest factor: Ballasts shall have a lamp current crest factor, CCF, of 1.65 or less, and shall be furnished by the manufacturer.

   g. Electronic ballasts shall have an output frequency of 20 Khz or higher with less than 2 percent lamp flicker. The average ballast life shall be rated at 60,000 hours or greater based on 3 hour average burn cycles. Total Harmonic Distortion (THD) shall not exceed 10 percent and third Harmonic Distortion shall be less than 6 percent.

   h. For lamp types for which none of the acceptable manufacturers produces an electronic ballast, the ballast shall be energy-saving magnetic type.

   i. Ballast and T8-lamp compatibility: Ballasts for use with T8 lamps shall be compatible with T8 lamps only. The ballast shall not adjust current if T12 lamps are inserted.

   j. Ballast and T12-lamp compatibility: Electronic ballasts for use with T12 lamps shall be T12 compatible only.

   k. Ballast for Compact Fluorescent Lamps: Ballasts shall be High Power Factor (HFP) type.

l. Warranty: Ballast shall carry a manufacturer's warranty against failure due to defects in material or workmanship for 5 years.

3. Lamps

a. Fluorescent lamps shall meet the following specifications unless otherwise specified for a particular lamp.

b. Lamp Type: Lamps shall be T8 tri-phosphor type.

c. Lamp Correlated Color Temperature, CCT: Lamps shall have a manufacturer's Correlated Color Temperature, CCT, of 4100K.

d. Lamp Color Rendering Index, CRI: Lamps shall have a Color Rendering Index, CRI, of greater than 75.

e. 4-foot Fluorescent Lamp type: Lamps shall be 4-foot Phillips F32T8/TL741, or equal. Initial lumen output shall be 2850 lumens or greater with a design lumen output of 2600 lumens or greater at 40 percent of rated lamp life. Lamps shall have an average rated life at 20,000 hours or greater, based on 3-hour burn cycles.

f. 8-foot Fluorescent Lamp type: Lamps shall be 8-foot Phillips F96T8/TL741, or equal. Initial lumen output shall be 4500 lumens or greater with a design lumen output of 4050 lumens or greater at 40 percent of rated lamp life. Lamps shall have an average rated life at 15,000 hours or greater, based on 3-hour burn cycles.

g. U-lamp type: U-lamps shall be Phillips FB31T8/TL741, or equal. Initial lumen output shall be 2600 lumens or greater with a design lumen output of 2370 lumens or greater at 40 percent of rated lamp life. Lamps shall have an average rated life at 20,000 hours or greater, based on 3-hour burn cycles.

h. Compact Fluorescent Lamps Short: Lamps shall be Phillips PL-S 13W/41, or equal. Initial lumen output shall be 900 lumens or greater. Lamps shall have an average rated life at 10,000 hours or greater, based on 3-hour burn cycles.

i. Compact Fluorescent Lamps Long; Lamps shall be Phillips PL-L 40W/2G11/RS/41, or equal. Initial lumen output shall be 3150 lumens or greater with a design lumen output of 2835 lumens or

greater at 40 percent of rated lamp life. Lamps shall have an average rated life at 20,000 hours or greater, based on 3-hour burn cycles.

C. High-Intensity Discharge (HID) Fixtures

1. Provide fixtures that are High Pressure Sodium (HPS) type.

2. Select fixtures which are enclosed and gasketed with mogul base porcelain lamp socket.

3. Use ballast high power factor type with taps for 120V, 208V and 277V input voltage, conforming to ANSI Standard C82.4.

4. Refer to Drawings or fixture schedules specific types, sizes and mounting hardware.

D. Emergency Fixtures / Exit Fixtures

1. In working areas such as dry wells, or valve vaults with two or more levels, rooms which do not exit directly outside, or rooms with multiple means of egress, exit signs and lighting are required for safe evacuation of workers.

2. Provide Dual Light AS-160-BCI wall-mounted, sealed beam, battery powered packs with dual heads where emergency illumination is required.

3. In areas where exit signs and emergency lighting is needed, utilize Dual Light ESRWW-RGI packs to provide both.

E. Incandescent Lighting Fixtures

1. Provide incandescent lighting fixtures with a maximum 150W design and vandal-proof construction.

2. Fixtures shall be made for wall, ceiling or pendant mount in accordance with the Drawings or fixture schedules.
3. Fixtures shall be designed for single incandescent lamp, medium base for maximum 150 watts with cast aluminum base and vandal-resistant polycarbonate lens or globe.

4. For outdoor application the fixtures shall be of vaporproof NEMA 4X construction with globe, guard and stainless steel hardware.

5. In hazardous areas the fixtures shall be approved under standard UL844 for Class 1, Division 1, Group D environment and shall be equipped with globe, guard and stainless steel hardware.

F. Photo Cells

1. Provide a photo cell to control outdoor fixtures unless otherwise indicated on the lighting plans.

2. Use a photo cell that is either the plug-in twist-locking type or the wire-in swivel-top type, both with similar features and operating characteristics.

3. Provide a photo cell that is enclosed in a UV-resistant rain-tight polypropylene housing with the cell being a 0.75 square inch cadmium sulfide surface passivated and a single pole, single throw normally closed bi-metallic switch.

PART 3 EXECUTION

3.01 PREPARATION

A. Check the types and quantity of fixtures to be mounted in the area to be illuminated and verify that materials are on hand.

B. Pick out the correct bulbs for the fixtures along with the necessary accessories and mounting hardware.

3.02 INSTALLATION

A. Install fixtures in accordance with manufacturer's instructions, NEC Articles 410, 500 and 700 as applicable, and the Drawings.

B. Wire up fixtures in accordance with the Drawings and ensure proper switching, circuiting and balanced loads.

C. Make sure proper grounding and bonding are provided for fixtures and raceways.

D. Install specified lamps in each fixture.

E. When applicable, aim and adjust fixtures in accordance with directions as indicated on the Drawings.

F. Energize and test fixtures for proper operation.

G. Check the illumination level with a light meter and ensure that sufficient light is reaching areas where tasks are performed and that egress paths are properly illuminated during emergency situations.

END OF SECTION

SECTION 16640

CATHODIC PROTECTION FOR PIPELINES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Requirements for impressed current cathodic protection systems on water and sewer pipelines using rectifiers and deep anodes.

B. Requirements for sacrificial anode cathodic protection on water and sewer pipelines using prepackaged, magnesium anodes.

1.02 RELATED SECTIONS

A. Section 15640 - Joint Bonding and Electrical Isolation.

B. Section 15641 - Corrosion Control Test Stations.

1.03 UNIT PRICES

A. This item will be measured and paid for as a lump sum item for the job.

B. Payment will be full compensation for all labor, equipment, materials and supervision for the installation of the cathodic protection system, complete in place including rectifier systems with deep anode groundbed and junction boxes, sacrificial anodes, power feed hookups, and all excavation, backfill, field welding, connections, adjustments, testing, cleanup, and other related work necessary for construction as shown on the drawings and specified herein.

1.04 REFERENCES

A. ASTM C94 - Ready Mixed Concrete

B. ASTM D-1248 - Polyethylene Plastics Molding and Extrusion Material

C. AWWA M9 Manual - Concrete Pressure Pipe

D. NEC 70 - National Electrical Code

E. CSA – Canadian Standards Association, Standard C22.2, No. 66 and No. 107

F. City of Houston Electrical Code

G. NACE RP-0169 - Recommended Practice, Control of External Corrosion on Underground or Submerged Metallic Piping Systems.

H. NACE RP-0572 - Recommended Practice for Design, Installation, Operation and Maintenance of Impressed Current Deep Groundbeds.

I. NEMA TC6 - PVC and ABS Plastic Utilities Duct for Underground Installation.

J. NEMA TC9 - Fittings for ABS and PVC Plastic Utilities Duct for Underground Installation.

K. NEMA 4 - TYPE 3R ENCLOSURES

L. UL 83 - Thermoplastic-Insulated Wires

M. UL 467 - Bonding and Grounding Equipment

N. UL 486A - Wire Connectors and Soldering Lugs for Use with Copper Conductors

1.05 SUBMITTALS

A. General: Submittals shall conform to the requirements of Section 01330 – Submittal Procedures.

B. Design Drawings and Computations: All computations and drawings shall be prepared by or under the direct supervision of a Professional Engineer, registered in the State of Texas with a minimum of ten years experience in cathodic protection design.

C. Catalog Cuts: Manufacturer's catalog cuts shall be submitted for each item. The catalog cuts shall include the manufacturer's name and shall provide sufficient information to show that the materials meet the requirements of the drawings and specifications. Where more than one item or catalog number appears on a catalog cut, clearly identify the item proposed.

D. Logs: The City of Houston representative shall be given a minimum of 48 hours notice prior to drilling the anode bore. Copies of detailed geological and resistance logs of each deep anode bore shall be typed by Contractor and submitted to the City of Houston representative.

E. Rectifier Operation and Maintenance Manual: The rectifier manufacturer shall include a complete operation and maintenance manual with each rectifier shipped to the job site. In addition to operating instructions, the manual shall include a circuit diagram and spare parts list. The rectifier shall be operated under full load conditions at the factory and shall be thoroughly inspected and tested by the manufacturer prior to delivery to the job site. Results of this testing shall be reported on a manufacturer's quality control form and shall be included in the operation manual. The rectifier manufacturer shall reference each operating manual by rectifier model number and individual serial number.

F. Report: Submit six (6) operating, monitoring and maintenance reports for the cathodic protection systems. Included shall be all test data as required by Section 3.07, paragraph D. The manuals shall include operating instructions, maintenance data, product data and test procedures.

G. Drawings: As-built drawings of the cathodic protection installation shall be maintained by the Contractor during installation and construction. Drawings

shall be revised to show exact locations of all rectifiers, anodes, wiring, connections and terminal boxes. All items of equipment and material shall be properly identified. The original as-built drawings shall be submitted to the City of Houston representative.

1.06 QUALITY CONTROL

A. Provide manufacturer's certification that all components of the cathodic protection system meet the requirements of the drawings and specifications. The certification shall reference the applicable section of the specifications and the applicable standard detail.

B. All materials, fabrication and installations are subject to inspection and testing by the City of Houston or its designated representative.

C. The drawings for the cathodic protection system are diagrammatic and shall not be scaled for exact locations unless scales are explicitly stated on the specific drawing. Field conditions, non-interference with other utilities or mechanical and structural features shall determine exact locations. Contractor shall note other existing utilities in the area and shall not damage these utilities during excavation. Any damaged utilities shall be repaired to the satisfaction of the City of Houston at the Contractor's expense.

PART 2 A N O D E S

2.01 SACRIFICIAL ANODES - MAGNESIUM

A. Magnesium Anodes: High potential magnesium anodes shall be used. The metallurgical composition of the magnesium anodes shall be as follows:

Element	Percent Composition
Aluminum	0.01 Maximum
Manganese	0.50 to 1.3
Copper	0.02 Maximum
Nickel	0.001 Maximum
Iron	0.03 Maximum
Other - (each)	0.05 Maximum
Other - (total)	0.30 Maximum
Magnesium	Balance

B. Magnesium Anode Current Capacity: Magnesium anodes shall have a current capacity of no less than 500 amp-hours per pound of magnesium.

C. Anode Backfill Material: Use chemical backfill material around all galvanic anodes. Backfill provides a reduced contact resistance to earth, provides a uniform environment surrounding the anode, retains moisture around the anode, and prevents passivation of the anode.

1. All galvanic anodes shall come prepacked in a backfill material conforming to the following composition:

a. Ground hydrated gypsum: 75 percent

b. Powdered bentonite: 20 percent

c. Anhydrous sodium sulfate: 5 percent.

2. The backfill shall have a grain size such that 100 percent is capable of passing through a 20 mesh screen and 50 percent is retained by a 100 mesh screen.

3. The backfill mixture shall completely surround the anode within a cotton bag.

4. For standard cast magnesium ingots, the weight of backfill required shall be as follows:

Anode Weight (Pounds)	Backfill Weight (Pounds)	Total Weight (Pounds)
9	15	24
17	25	42
20	50	70
32	38	70
48	48	96

D. Anode Lead Wires:

1. Standard lead wires for a galvanic anode shall be a 20-foot length of No. 12 AWG solid copper wire equipped with TW or THW insulation.

2. All anode lead wires shall be color coded green when terminated in test stations.

E. Lead Wire Connection to Magnesium Anode:

1. Magnesium anodes shall be cast with a galvanized steel core with the weight of the core not to exceed 0.10 pounds per linear foot.

2. One end of the anode shall be recessed to expose the core for the lead wire connection.

3. The lead wire shall be silver-soldered to the core and the connection fully insulated by filling the recess with an electrical potting compound.

2.02 SACRIFICIAL ANODES - ZINC

A. Zinc Anodes: Use high purity zinc anodes. The metallurgical composition of the zinc anodes shall be conformed to ASTM B-418, Type II and the following:

	Element	Percent Composition
a.	Aluminum	0.005 Maximum
b.	Cadmium	0.003 Maximum
c.	Iron	0.0014 Maximum
d.	Lead	0.003 Maximum
e.	Zinc	Balance

B. Zinc Anode Current Capacity: Zinc anodes shall have a current capacity of no less than 335 amp-hours per pound of zinc.

C. Anode Backfill Material: Use chemical backfill material around all galvanic anodes. Backfill provides a reduced contact resistance to earth, provides a uniform environment surrounding the anode, retains moisture around the anode, and prevents passivation of the anode.

1. All galvanic anodes shall come prepackaged in a backfill material conforming to the following composition:

   a. Ground hydrated gypsum: 75 percent

   b. Powdered bentonite: 20 percent

   c. Anhydrous sodium sulfate: 5 percent.

2. The backfill shall have grain a size such that 100 percent is capable of passing through a 20 mesh screen and 50 percent is retained by a 100 mesh screen.

3. The backfill mixture shall completely surround the anode within a cotton bag.

4. For standard cast zinc ingots, the weight of backfill required shall be as follows:

Anode Weight (Pounds)	Backfill Weight (Pounds)	Total Weight (Pounds)
30	40	70
45	55	100
60	70	130

D. Anode Lead Wires: The lead wire for the zinc anodes shall be a 20-foot length of No. 12 AWG solid copper wire equipped with TW of THW insulation.

E. Lead Wire Connection to Zinc Anode:

1. Zinc anodes shall be cast with a 1/4-inch diameter galvanized steel core.

2. One end of the core shall extend beyond the anode for the lead wire connection.

3. The lead wire shall be silver-soldered to the core and the connection fully insulated.

2.03 IMPRESSED CURRENT ANODES

A. Description: Use high silicon-chromium-iron anode centrifugally cast in tubular form in accordance with the following specifications.

1. Anode Alloy: The anode shall consist of Durichlor 51, high silicon, chromium iron. This alloy shall be made in accordance with ASTM A518-86, Grade 3 with nominal percentages as follows:

Chemical Composition

Element	Composition, Weight %
Carbon	0.70 - 1.10
Maganese	1.50, max
Silicon	14.20 - 14.75
Chromium	3.25 - 5.00
Molybdenum	.20, max
Copper	0.50, max

2. Casting Method: Centrifugally cast anodes in tubular form with a hollow, straight walled design. Bowing and malformation tolerances shall be no greater than 1/4" over the seven foot anode length. Anode designs which include enlargement of the outside diameter, at the center or elsewhere, or constrictions of a venturi type of the inside wall shall not be allowed.

The anode body shall have solid walls of a uniform thickness with an open cylindrical interior. Static casting methods, such as sand, die or metal mold techniques, shall not be allowed in order to avoid the risk of shrink cavities and internal stresses caused by non-uniform wall thickness.

Use of extraneous materials such as chaplets, spacers or chills to center the anode mold shall not be permitted. Any slag deficiencies shall be restricted to one end of the casting only allowing for simple inspection techniques to ascertain metal density and absence of slag inclusions.

3. Mechanical and Physical Properties: The mechanical and physical properties of the anode shall be as follows:

1. Tensile Strength (1/2" dia. bar) psi. 15,000
2. Compressive Strength, psi..... 100,000
3. Hardness, Brinell 520
4. Density, gr/ml..... 7.0
5. Melting Point, °F 2300
6. Specific Resistance, micro-ohms-cm (20°C) 72
7. Coefficient of expansion, 32° to 212° F .....7.33 X 10^6

4. Size: Anode castings shall conform to the following sizes:

Weight Type	O.D. (pounds)	Length (inches)	(feet)
TA-2	46	2.19	7
TA-3	63	2.66	7
TA-4	85	3.75	7
TA-5	110	4.75	7

Anodes shall be TA-2 unless otherwise noted on the drawings.

B. Anode Lead Wire Connection:

2. The lead wire for an impressed current anode shall be a No. 8 AWG seven stranded copper conductor equipped with a fluorinated polymer insulation. The lead wire shall be of sufficient length to reach the anode terminal box without splicing additional wire.

3. The anode lead wire shall be attached at the center of the anode. The center connection shall have minimum pull-out strength of one and one-half times the breaking strength of the No. 8 AWG lead wire or 788 pounds.

4. The electrical contact resistance as measured across the lead wire-to-connector junction shall not exceed 0.004 ohms.

C. Impressed Current Anode Backfill: Calcined fluid petroleum coke shall be used to backfill impressed current anodes. Anode backfill shall conform to the following:

2. Typical Chemical Analysis:

Component	Percent Composition
Carbon	91.77
Sulfur	5.85
Ash	2.23
Silicon	0.26
Iron	0.02
Volatiles	0.07
Moisture	0.00

2. Physical Properties.

Bulk Density, pounds/cubic foot	74
Specific Gravity	2.00
Porosity, percent	40.8

3. Particle Analysis.

Sieve	Percent Retained
16 mesh	0.0
28 mesh	7.15
35 mesh	86.40
80 mesh	2.30
100 mesh	3.30

2.04 MISCELLANEOUS DEEP ANODE GROUNDBED HARDWARE

Miscellaneous components of a deep anode groundbed shall include the following:

A. Surface Casing: Equip the deep anode bed with an 8-inch diameter, 10 foot long PVC surface casing.

B. Anode Bed Cover: Cap the casing. Set cover assembly in a 3-foot-square by 6-inch-thick Portland cement concrete slab.

C. Venting Facilities:

1. Use plastic vent pipe from the bottom anode to the surface for dissipating gases to the atmosphere.

2. The plastic vent pipe shall be 1-inch diameter with 1/8-inch holes drilled on 6-inch centers in the area of the anodes. Do not drill holes in the vent pipe above the anodes.

3. Extend the plastic vent pipe above grade, screen the vent outlet, and install in an inverted manner.

2.05 RECTIFIERS

Cathodic protection rectifiers shall be air cooled, tap adjust Super Custom model as manufactured by Good-All Electric or approved equal conforming to NEMA MR-20-1958 and listed in CSA File No. 45382.

A. D-C Output Ratings: Rate rectifiers as shown on the drawings. Rectifiers shall be capable of supplying continuous, full rated output at an ambient temperature of 45° C, in full sunlight with an expected life in excess of 10 years.

B. A-C Input Ratings: Full rated d-c output shall be obtained, with an input voltage ±10 percent of the nominal rated input.

C. Cooling: Cooling shall be by natural air convection. Cabinets shall be vented for natural air convection and shall be screened against insects.

D. Voltage Adjustments: The output voltage shall be adjustable by means of not less than 25 approximately equal steps of secondary taps from 5 percent of rated voltage to full-rated voltage.

E. Rectifying Elements: Rectifying elements shall be silicon diodes sized as follows:

1. Diode voltage shall be rated at 400 volts minimum for rectifier outputs up to 100 VDC, and 800 volts minimum for rectifiers with outputs from 100 to 200 VDC.

2. Diodes shall be configured into a full-wave bridge assembly. Diodes shall be sized to carry a minimum average current of one half of rated rectifier output.

3. Heat sinks shall be sized to keep diode junction temperatures less than 100° C at rated output and maximum ambient temperature.

4. Diodes shall be overload protected by means of semiconductor fuses, located in the transformer secondary leg to the diode bridge assembly.

5. Diodes shall be equipped with supplemental Metal Oxide Varistor (M.O.V.) surge arrestors at the diode bridge assembly sized to provide protection against secondary over-voltage surges.

F. A-C Circuit Breakers: Input overload and short circuit protection shall be provided by magnetic trip circuit breakers. The circuit breaker shall be sized to hold 100 percent of rated load. It may trip between 101 percent and 125 percent of rated load and must trip at 125 percent and above.

G. Surge Protection: Separate AC and DC surge protection shall be provided by means of high energy Metal Oxide Varistors rated at 500 joules on D.C. output and 750 joules on the A.C. output.

H. Electrical Panels: Electrical panels shall be minimum thickness of 1/4" NEMA "XX" laminated phenolic, rated for Class "B" operation (105° C maximum). Rectifiers rated at 100 amperes D.C. or higher shall be equipped with panels constructed from a minimum sheet thickness of 1/4" "UTR" fiberglass reinforced laminate rated for Class "F" operation (155° C). Rectifier front panel identifications shall be permanently silk-screened onto the panel.

I. Connection Hardware: All electrical hardware shall be copper or high conductivity brass, suitably sized, and finished in electroless nickel plating for superior corrosion resistance. All connections shall be tightly secured with lock washers and nuts torqued to manufacturer's recommended specifications.

J. Enclosures:

1. Enclosures shall be constructed from a minimum 12 gauge wiped coat mill galvanized steel, finished in 3 - 5 mils polyester fusion bonded powder coating.

2. Hinges and cabinet assembly bolts shall be of stainless steel.

3. Enclosures shall be equipped with a pad-lockable draw latch. Latch shall be manufactured from 12 gauge steel, finished in zinc-dichromate plating. Draw latch shall accommodate a 3/8 inch shackle padlock.

4. Enclosures (or rectifier frame) shall be equipped with a grounding lug sized to accommodate up to a No. 6 AWG conductor.

5. Separate conduit knockouts shall be provided for AC and DC; conveniently located and adequately sized for input and output conduit connectors.

6. Cabinet shall be furnished with suitable channel brackets for wall or pole mounting. Optionally available floor stands shall be available upon request.

7. Rectifier shall be equipped with slide-out frame and hinged door for access to the front and a minimum of one side of the cabinet.

K. Rectifier Instrumentation.

1. Rectifier shall be equipped with separate analog ammeter and voltmeter.

2. Meters shall be a minimum of 3-1/2" size, with a minimum scale length of 2-7/8".

3. Meters shall be 0 - 50 millivolts full scale deflection, taut-band movement with four-to-one swamping (i.e. internal meter resistance comprised of 25% winding resistance and 75% fully temperature compensated dropping resistor for wide temperature range performance).

4. Meter accuracy shall be $\pm$ 2% full scale deflection at 25° C., temperature compensated to 0.085% per degree C.

5. Rectifier meters shall be scaled to have rated output no less than 70%, or greater than 85% of full scale deflection.

6. Meter shunts shall be panel-mounted Holloway type "SW" style, with an accuracy of $\pm$0.25%.

L. Transformers: Transformers shall meet UL 506, Specialty Transformers and the following:

1. Transformer designed as full isolation with separate isolated primary and secondary windings with a minimum efficiency of 95%.

2. Transformer secondary shall be equipped with a minimum of 25 steps of secondary voltage adjustment (5-COARSE, 5-FINE). Tap adjustment shall be by means of tap bars.

3. Transformer materials and construction shall be rated for Class "H" operation (180° C). Insulation materials shall be further enhanced by dipping in thermosetting varnish and baking.

4. Transformer shall be rated for a minimum dielectric strength of 2250 volts applied for one minute between the windings, and the core.

M. Potential Monitoring Connections: Two, five-way binding posts shall be provided on the front of the rectifier instrument panel. One will be labeled "Reference" and one will be labeled "Structure".

N. Miscellaneous:

1. All rectifiers shall be capable of operating on either 115 or 230 volt, single phase, 60 hertz A.C. input.

2. Cathodic Protection Rectifier shall be 100% quality control tested as outlined in this specification.

3. During manufacture, the rectifier shall be subjected to frequent visual and performance testing to insure a high degree of quality acceptance level.

4. Rectifiers shall be subjected to 100% testing of the following rectifier electrical parameters:

   a. A.C. input voltage, current, apparent power and true power.

   b. D.C. output current, voltage and power.

   c. A.C. power factor.

   d. A.C. to D.C. conversion efficiency.

   e. Output ripple.

   f. Correct operation of optional features such as interrupters, filters, etc.

5. A final overall visual inspection shall be given each rectifier prior to packaging.

2.06 JUNCTION BOX

A. Enclosure: The anode junction box shall be a NEMA 4X fiberglass enclosure with multiple positive terminals, 0.01 ohm type RS Holloway shunts, and a

minimum 3/16" thick, NEMA Grade "XX" phenolic panel. For size and terminal configurations, see Drawings.

B. Positive Cable: Positive cable from the junction box to the transformer-rectifier shall be single conductor, seven strand copper with medium density, high molecular weight polyethylene (HMW/PE) insulation. The polyethylene shall conform to ASTM D 1248, Type I, Class C, Grade 5.

2.07 NEGATIVE CABLES

A. Cables: Rectifier negative cables shall be single conductor, seven-strand copper with medium density, HMW/PE insulation. The polyethylene shall conform to ASTM D 1248, Type I, Class C. Grade.

B. Test Lead: The test lead shall be No. 12 AWG, solid copper wire with white, TW or THW insulation and shall be of sufficient length to extend from the protected structure to the rectifier without splicing.

2.08 PERMANENT REFERENCE ELECTRODE

A. The electrode shall be equipped with No. 14 AWG stranded copper wire with blue HMW/PE insulation of suitable length to extend from the pipeline to the rectifier without splicing.

B. The reference electrode shall be copper/copper sulfate, Permacell Plus, double membrane, ceramic cell in a geomembrane package as manufactured by Corrpro Companies, Inc.

2.09 THERMITE WELD EQUIPMENT

A. Charges and Molds: Cadweld molds and charges shall be used. Charges and mold size shall be as specified by Erico for the specific surface configuration.

B. Limitation: For high strength steel pipelines, use only 15 gram Cadweld charges.

C. Weld Coating: Coating for welds shall be Kop-Coat as manufactured by Carboline.

D. Weld Cap: The coated weld shall be covered with a plastic weld cap.

2.10 AC POWER SERVICE

A. Products: All AC power components shall meet local power company requirements.

B. Meter Base: Meter base shall be 120/240-volt, single phase, 100-ampere.

C. Disconnect Swith: Disconnect switch shall be a heavy-duty, two-pole, NEMA 3, rain tight, rated at 120/240 volts, 30 amperes. Supply with circuit breakers sized for 100 to 135 percent of the AC current flow at maximum rectifier output.

D. Ground Rod: Ground rod shall conform to the requirements of the utility company having jurisdiction.

E. Ground Wire and Clamp: Ground wire shall be bare, No. 6 AWG solid copper wire. Use a bronze, bolt-on ground rod clamp.

F. Service Pole: Service pole for rectifier shall be a 25-foot, Class 5, treated wood pole.

PART 3 CATHODIC PROTECTION SYSTEM INSTALLATION

3.01 INSTALLATION OF SACRIFICIAL ANODES

A. Location: Install sacrificial anodes at locations where the anodes will operate at maximum effectiveness.

B. Placement: Install anodes in native soil, in a vertically augured hole as shown on the drawings. If a vertical installation of the anodes is not feasible, the anodes may be installed horizontally.

C. Augured Hole: The hole diameter shall easily accommodate the anode.

D. Backfilling: After the hole is augured, lower the packaged anode into the hole and firmly tamp the soil around the package so that it is in intimate contact with the package.

E. Lead Wire: Run lead wires from the anodes underground at a minimum depth of 36 inches. Connect the wires through a test station as indicated on the drawings.

F. Handling: Handle galvanic anodes carefully to avoid damaging anode materials and wire connections.

3.02 INSTALLATION OF DEEP ANODE GROUNDBEDS

A. Permits: The drilling and installation of the deep anode systems shall only be accomplished by a qualified well driller who is recognized as a fully experienced specialist in the installation of deep anode cathodic protection systems. The deep anode system installer shall have a minimum of 5 years experience installing deep anode systems with a minimum of 10 successful deep well anode installations. The Contractor is required to obtain and submit all applications for well drilling permits required by any City, County or State agency.

B. Field Location: Verification of actual field conditions, location of underground structures, and physical separation from other structures or utilities shall be the responsibility of the Contractor. Location of the anode wells are approximate. Exact placement shall be determined and verified in the field by the Contractor and the representative of the City of Houston.

C. Anode Hole Drilling: The anode hole shall be 8 inches diameter by 200 feet deep. Perform drilling with rotary bit equipment designed specifically for this purpose. Use standard techniques (i.e. trough and vacuum truck) to capture

and contain the drilling fluids, mud and cuttings at the top of the hole. Select the type and consistency of drilling fluids to be consistent with soil characteristics. Level the drilling rig to provide a round, straight and plumb anode hole.

D. Temporary Well Casing: Drilling of the holes may require the installation of temporary well casings. Remove all temporary casings by the end of the job.

E. Anode Hole Geological Logs: As the hole is drilled, maintain a record describing the depth and type of the geological formations encountered. Submit typed copies of the log as required by Section 1.05.C.

F. Anode Hole Resistance Log: An electric log of the hole shall be recorded using one of the anodes. The anode lead wire shall have been previously marked in five foot increments. The anode lead wire shall be marked for a distance equaling or exceeding the maximum anticipated depth of the hole. As the anode is lowered into the hole, a resistance log shall be performed by impressing a minimum 12 volt DC current between the anode and a very well grounded structure such as the local AC power neutral network. Nilsson type soil resistance meters shall not be used to perform this test. A recommended 12 volt DC power source is a heavy duty lead acid automobile battery. Lower the anode into the hole at ten foot increments, hold in place, and measure the voltage and current output of the DC current source. Record the data, type and submit as required under Section 1.05.C.

G. Vent Pipe Installation: Install the vent pipe in the hole with the first anode. Cap the bottom of the vent pipe. Cap the top of the vent pipe throughout the anode and coke breeze backfill installation procedure to prevent intrusion of foreign material. Do not allow drilling mud to enter in the vent pipe.

H. Anode Installation: The anode well shall contain ten (10) tubular cast iron anodes spaced at 10 foot intervals on centers. Center the anodes in the hole using anode centralizers. Install the anodes by lowering them individually into the hole by the lead wire. Mark the lead wires for the nominal anode depth. Record the final depth with the first anode in the hole (i.e. the bottom anode) identified as anode number one (1). Do not damage the anode lead during handling or lowering into the hole. Under no circumstances shall the anode lead wires be clamped or pinched around another object while lowering the anodes into the hole. If the insulation for any anode lead wires are cut, broken, or nicked during this operation or at any other time, the complete anode shall be rejected and shall be removed from the job site immediately. Contractor shall replace all damaged anodes at no additional expense to the City of Houston.

I. Anode Column Coke Backfill: The coke backfill shall be slurried above-grade and then pumped into the hole after the anodes are installed. Pump the coke from the bottom of the hole up using a pipe that is the length of the anode hole. Do not use the vent pipe to pump the coke. Raise the pipe as the anode column is filled with coke. Remove the pipe from the hole after the coke installation operation is completed. Use a sufficient amount of backfill such that the coke breeze column extends a minimum of five feet above the top of the uppermost anode. Install the coke backfill uniformly with no voids around the anodes.

J. Vent Pipe: Terminate the 1-inch diameter internal vent pipe with a gooseneck fitting. Leave the top end of the vent pipe open to allow gases from the anode hole to exit.

K. Precautions: Take all necessary precautions to avoid entrance of foreign matter into the hole, movement of soil strata, or collapsing of the hole during the progress of the work. Should movement of soil strata or collapse of the drilled hole interfere with proper completion of the anode groundbed, recover the wires, anodes and vent pipe and ream or redrill the hole at no cost to the City.

L. Mud And Cuttings: Dispose of drilling mud, cuttings and other waste in accordance with the methods and procedures of the best recognized practices and comply with the rules and regulations of the State, City and County.

3.03 INSTALLATION OF CATHODIC PROTECTION RECTIFIERS

A. Codes: The installation shall conform to National Electrical Codes (NEC) and be in compliance with all City of Houston and Houston Lighting and Power codes and standards.

B. Mounting: Pole mount cathodic protection rectifiers. The pole may be omitted and the rectifier mounted on a building wall or other available permanent structure, if approved by the Engineer. Install rectifiers at a minimum height of 4 feet above final grade.

C. Identification: Equip rectifiers with permanent engraved nameplates to identify the units as "Cathodic Protection Rectifier, Property of City of Houston, In Case of Emergency Call 713-748-4461."

D. Conduit: Enclose all wiring to the rectifier shall be contained in rigid galvanized steel conduit when run above grade.

1. Use insulating bushings at the ends of all conduits.

2. Extend steel conduit 12 inches below grade.

E. Electrical Service: Provide AC electrical service for each rectifier unit. The Contractor is responsible for furnishing and installing the necessary wiring, conduits, wires, meter sockets, splice boxes and equipment to the service connection as required by Houston Lighting and Power.

F. Completion: The installation shall not be considered complete until the AC and DC wiring is complete and the rectifier is capable of operating at full rated load. Install AC power such that the rectifier can be activated for test purposes. Leave the power off after test.

3.04 INSTALLATION OF WIRE AND CABLE

A. Depth: Install all underground wires and cables at a minimum of 36 inches below final grade with a minimum separation of 6 inches from other underground structures.

B. Conduit: Enclose all positive and negative cables, and anode lead wires in rigid galvanized steel conduit when above-grade.

2. Use insulating bushings at the ends of all conduits.

2. Extend conduit 12 inches below grade.

3.05 INSTALLATION OF ANODE LEAD JUNCTION BOXES

A. Location: Install anode lead junction boxes immediately adjacent to the rectifier with the bottom of the boxes at a minimum height of 2 feet above grade.

B. Concrete Pad: Set junction anode lead box supports (post or unistrut) in a Portland cement concrete anchor. The concrete anchor shall be a minimum of 12 inches in diameter and no less than 24 inches deep. Extend the concrete surface approximately 3 inches above grade.

C. Conduit: Enclose all cathodic protection wiring between the junction box and the rectifier in rigid, galvanized steel conduit. Use insulating bushings at the ends of all conduits to prevent damage to wire insulation.

3.06 NEGATIVE CABLE AND TEST LEAD ATTACHMENT

A. Attach negative cables and test lead to the pipe by thermite welding.

B. Clean and dry the pipe to which the negative cables and test lead are to be attached.

C. Use a grinding wheel to remove all coating, mill scale, oxide, grease and dirt from the pipe over an area approximately 3 inches square. Clean the surface to bright metal.

D. The wires to be thermite welded to the pipe shall have approximately 1 inch of insulation removed from each end, exposing clean, oxide-free copper for welding.

E. Using the proper size thermite weld mold as recommended by the manufacturer, place the wire between the graphite mold and the prepared metal surface. All wires No. 12 AWG size shall use a copper sleeve crimped over the wire.

F. Place the metal disk in the bottom of the mold.

G. Remove the cap from the weld charge container. Pour the contents into the mold. Squeeze the bottom of the weld charge container and spread ignition powder over the charge.

H. Close the mold cover and ignite the starting powder with a flint gun. Hold the mold firmly in place until all of the charge has burned and the weld has cooled slightly.

I. Remove the thermite weld mold and gently strike the weld with a hammer to remove the weld slag. Pull on the wire to assure a secure connection. If the weld is not secure or the wire breaks, repeat the procedure.

J. If the weld is secure, coat all bare metal and weld metal with Kop-Coat. Cover the coated weld with a plastic weld cap.

3.07 PERMANENT REFERENCE CELL

A. Location: When not shown on the Drawings, locate the permanent reference cell near the negative structure connection.

B. Placement: Remove the permanent reference cell from the shipping package and place below the springline and one foot away from the pipeline. Make certain that the reference electrode is completely surrounded by the special backfill material in the geomembrane package.

C. Backfill the reference electrode with six inches of select native soil and compact by hand. Moisten the soil, if necessary, for good compaction.

D. Wiring: Run continuous lengths of the blue reference cell wiring, and the white test lead to the rectifier unit in the same trench as the negative cable. Do not nick or otherwise damage the wire insulation.

3.08 POST INSTALLATION TESTING OF THE CATHODIC PROTECTION SYSTEMS

A. General: Inspect, energize, and adjust the cathodic protection as soon as possible after the equipment has been installed.

B. Energization: The energizing of the cathodic protection system shall be performed by a Corrosion Engineer hired by the Contractor to achieve compliance with the referenced corrosion control standards set forth by NACE and/or AWWA.

C. Notice: Prior to native state and polarized potential testing, the Contractor shall give a minimum of 48 hours notice to the City of Houston to facilitate observation of the tests by a City Representative.

Contact: City of Houston
Graphics and Engineering Management Section
306 McGowen
Houston, TX 77006

Mr. Wayne Dessens, P.E. or
Mrs. Tiffany Pham, P.E.

Telephone: (713) 525-9928

D. Method: The Corrosion Engineer shall:

1. Measure native state pipe-to-soil potentials at all test stations, permanent reference cells, electrical isolation devices, and locations of exposed pipe prior to energizing the cathodic protection system

2. Measure casing-to-soil potentials and foreign line potentials, prior to energizing the cathodic protection system.

3. Energize the cathodic protection system and adjust the DC current output such that the pipe-to-soil potentials near the cathodic protection current source (either transformer-rectifier or sacrificial anodes) is approximately -1000 millivolts to a copper sulfate electrode (CSE). Record the DC voltage and current of the power supply.

4. Allow sufficient time for the pipeline to polarize.

5. Using a current interrupter, cycle the power supply "On" and "Off".

6. Record "On" and "Instant Off" potentials at all water pipeline test stations, permanent reference cells, electrical isolation devices, locations of exposed pipe, casings and foreign pipelines.

7. For steel and ductile iron pipe, adjust the cathodic protection power supplies to satisfy the criteria of a minimum 100 millivolts of polarization or an "Instant Off" potential at least as negative as -850 millivolts CSE.

8. For concrete cylinder pipe, adjust the cathodic protection power supplies to achieve a minimum 100 millivolt of polarization without any "Instant Off" potentials more negative than -1000 millivolts CSE.

9. Record all final adjustments of the DC power supplies.

10. Verify that all electrical isolation devices are operating properly including flange isolators, and casing spacers.

11. Verify that interference does not exist with foreign pipelines. Perform joint tests and mitigate any interference detected.

E. After initial energization and after rectifiers have been adjusted as necessary for compliance with NACE RPO169-92, perform a walk-through inspection

with Project Manager to verify that all corrosion control components have been installed in accordance with project drawings and specifications.

F. A punch list of outstanding work identified during walk-through inspection shall be made. Once Contractor has completed all work on punchlist, pipeline will be allowed to polarize for 30 days before final testing. Final testing and adjustment shall be performed after 30-day polarization period. Deficiencies discovered during final testing shall be repaired at Contractor's expense and at no additional cost to City of Houston. Should additional testing be required after final testing, cost of additional testing shall be paid by Contractor and will be charged at a rate of $1,500.00 per day.

G. Equipment: All cathodic protection testing instruments shall be in proper working order and calibrated according to factory specifications.

H. Report: A written report shall be submitted in accordance with Section 1.05, Submittals. Included shall be all test data, resistance and geologic logs, the rectifier O&M Manual and the As-Built Drawings.

END OF SECTION

SECTION 16662

MOTOR MANAGEMENT RELAY

PART 1 GENERAL

1.01 CONDITIONS

A. This specification is issued for this specific project only. Reproduction of this document for any other purpose is prohibited.

B. Contractor shall comply with Section 3.07, A, 3 of this specification before bidding.

1.02 SUMMARY

A. Section Includes:

1. Motor Management Relay (MMR) and related devices commonly used with them.

2. Programming Requirements.

1.03 REFERENCES

A. National Fire Protection Association (NFPA): NFPA 70-90 - National Electrical Code (NEC).

1.04 DEFINITIONS

A. Motor Management Relay (MMR): Primary protective function shall be the thermal model consisting of four key elements:

1. Overload curves

2. Negative sequence unbalance/single phase bias

3. RTD Biasing (hot/cold motor compensation)

4. Motor cooling time constants.

1.05 SUBMITTALS

A. Shop Drawings:

1. Motor Management Relay showing dimensions and features including installation details.

2. Current and potential transformers showing dimensions and features including installation details.

B. Product Data:

1. Product data for motor management relay, C.T's, P.T.'s and accessories specified in this Section, including descriptive data and C.T. ratios.

2. Include parts list.

C. Test Results: Certified reports of field tests and observations.

D. With each submittal, include a copy of the applicable specification(s) page(s) for the item submitted and mark "Complies" or "Non-Compliance" or "Exception" adjacent to the applicable paragraph. Identify applicable drawing sheet number and specification section on front of each submittal cover.

1.06 QUALITY ASSURANCE

A. Items provided under this section shall be listed and labeled by UL or other Nationally Recognized Testing Laboratory (NRTL).

1. Term "NRTL" shall be as defined in OSHA Regulation 1910.7.

2. Terms "listed" and "labeled" shall be as defined in National Electrical Code, Article 100.

B. Regulatory Requirements:

1. Components and Installation:

a. NFPA 70 "National Electrical Code (NEC)."

b. Local codes and ordinances.

C. Single-Source Responsibility: Not Applicable.

1.07 MAINTENANCE

A. Extra Materials:

1. Maintenance Stock, Spare Parts: As recommended by Manufacturer.

PART 2 PRODUCTS

2.01 MOTOR MANAGEMENT RELAY (MMR)

A. General: Provide MMR in indicated type, as integral components of panelboards, switchboards, and motor control centers; and also as individually enclosed and mounted single units. Provide externally mounted 48 hour UPS for MMR 120 volt source.

B. Enclosures: Manufacturers draw-out construction to facilitate testing and maintenance.

C. Features: The motor management relay shall include complete power metering. An events recorder shall store the last 40 events. Sixteen cycles of waveform data shall be stored each time a trip occurs. A simulation feature shall be available for testing the relay. The user interfaces shall include:

1. A 40 character illuminated vacuum fluorescent display and associated keypad to provide access to actual values and set points.

2. A front RS232 serial port for set point programming.

3. An RS485 serial port which shall use an open protocol with baud rates selectable up to 19,200 bps.

4. An independent auxiliary RS485 port shall be available for added security or for use by maintenance personnel.

5. Interface software shall be provided in a Windows format.

D. The stator protective thermal model shall combine inputs from positive and negative sequence currents and RTD winding feedback. The protection shall also include:

1. Stall

2. Jam

3. 12 RTD inputs

4. Ground Overcurrent

5. Short Circuit

6. Differential protection using CT inputs; (6) from both sides of the machine winding.

7. Voltage transformer inputs which shall be used to provide over-voltage, under-voltage, voltage phase reversal, over-frequency and under-frequency functions.

8. MMR shall store up to 40 time and date stamped events, including the pre-tip data. For each trip, the MMR shall store a trace of 8 cycles pre-trip and 8 cycles post-trip for all measured AC quantities.

E. Manufacturer: G.E. Multilin

F. Model: SR 469-P5-HI-A20 with door mounted draw-out case.

2.02 CURRENT TRANSFORMER (CT)

A. Phase current CT's shall be provided for all three phase legs. In addition, a ground CT shall be provided. CT size and rating to be determined by MMR manufacturer and shall be furnished as part of the MMR equipment package. Include mounting brackets and all appurtenances.

2.03 POTENTIAL TRANSFORMER (PT)

A. A three phase PT shall be provided for voltage measurements of all three phase legs. Provide Flex-Core Part No. 2VT 460-480 FF, size and rating shall be determined by MMR manufacturer and shall be provided as part of the MMR equipment package. Include mounting bracket and all appurtenances.

2.04 SOFTWARE

A. Manufacturers programming, operation, maintenance and data analysis software shall be included in MMR equipment package. Complete instructions and any special equipment required for installation, setup, programming, operation, maintenance and data analysis shall be provided as part of the MMR equipment package. Special cables, plugs and adaptors for loading and downloading data to a computer shall be included.

B. All programming and startup shall be done by Double E Engineering.

C. All programming will be coordinated with Motor Manufacturers and shall conform to their standards.

2.05 UNINTERRUPTIBLE POWER SUPPLY – (NOT APPLICABLE)

PART 3 EXECUTION

3.01 INSTALLATION

A. MMR

1. Install MMR as shown on plans or as described in specifications.

2. Installation shall be done according to manufacturers recommendations and shall be done in a neat and professional manner.

3. Locate as indicated and install in accordance with manufacturer's written installation instructions.

4. Provide devices and connections to MMR as shown on plans.

B. Current and Potential Transformers: CT's and PT's shall be rated for electrical system voltage and current parameters and shall be installed according to the manufacturer's recommendations with hardware intended for mounting PT's and CT's.

3.02 IDENTIFICATION

A. Identify components and wiring in accordance with Section 16195 – "Electrical Identification".

3.03 CONTROL WIRING INSTALLATION

A. Wiring to CT's shall be installed according to related NEMA and NEC standards and codes. All wiring to be rated for application and shall be neatly bundled and secured with clamps. All wires are to be terminated with proper lugs. C.T. lugs shall be ring type only.

3.04 CONNECTIONS

A. Check connectors, terminals, bus joints, and mountings for tightness.

B. Tighten field-connected connectors and terminals, including screws

and bolts, in accordance with equipment manufacturer's published torque tightening values. Where manufacturer's torqueing requirements are not indicated, tighten connectors and terminals to comply with tightening torques specified in UL 486A and UL 486B.

3.05 GROUNDING

A. Provide equipment grounding connections for individually mounted Overcurrent Protective Devices (OCPD) units as indicated and as required by NEC. Tighten connectors to comply with tightening torques specified in UL Standard 486A to assure permanent and effective grounding.

3.06 COORDINATION STUDY

A. Where coordination study recommends changes in types, classes, features or ratings of equipment or devices indicated, make written request for instructions. Obtain instructions from Engineer before ordering equipment or devices recommended to be changed.

3.07 FIELD QUALITY CONTROL

A. Manufacturer's Field Services:

1. Supplier's or manufacturer's technician for equipment specified herein shall be present at job site or classroom designated by Owner for minimum of 1 workday, travel time excluded, for assistance during plant construction, plant startup, equipment adjustment, and training of Owner's personnel for plant operation. Include minimum of:

   a. one manday for Instructional Services.

2. Supplier or manufacturer shall direct services to specific system and equipment operation, maintenance, and troubleshooting.

3. Programming of the motor management relay alarm and trip set points and all testing shall be performed by Double E Engineering. No Exceptions.

4. All of the motor data available from the manufacturer, including overload curves and thermal characteristics, and all motor circuit information must be furnished by the Contractor to the Engineer a minimum of two weeks prior to programming of Multilin unit.

B. Testing:

1. Reports: Prepare certified written reports on tests and observations. Report defective materials and workmanship and unsatisfactory test results. Include complete records of repairs and adjustments made.

2. Labeling: Upon satisfactory completion of tests and related effort, apply label to tested components indicating test results, date, and responsible person.

3. Schedule visual and mechanical inspections and electrical tests with at least 1 week's advance notification.

4. Pre-testing: Upon completing installation of system, perform following preparations for tests:

   a. Make insulation resistance tests of OCPD buses, components, and connecting supply, feeder, and control circuits.

   b. Make continuity tests of circuits.

   c. Include full updating on final system configuration and parameters where they supplement or differ from those indicated in original Contract Documents.

   d. Comply with manufacturer's instructions for installation and testing of OCPDs.

5. Visual and mechanical inspection: Include following inspections and related work.

   a. Overcurrent-Protective-Device Ratings and Settings: Verify indicated ratings and settings to be appropriate for final system arrangement and parameters. Where discrepancies are found, test organization shall recommend final protective device ratings and settings. Use accepted revised ratings or settings to make final system adjustments.

6. Retest: Correct deficiencies identified by tests and observations and retest. Verify by system tests that specified requirements are met.

3.08 CLEANING

A. Upon completion of installation, inspect MMR. Remove paint splatter sand other spots, dirt, and debris. Touch up scratches and mars of finish to match original finish.

4.01 MOTOR PROTECTION RELAY (MPR)

A. General: Provide MPR in indicated type, as integral components of motor control centers; and also as individually enclosed and mounted single units.

B. Designed to monitor and protect any 3-phase, 200-480VAC motor drawing 1-800 full load amps (external CTs are required for motor above 9 FLA).

C. A 3-digit LED display that is used for programming, real-time operational information and displaying diagnostic codes and aid in troubleshooting a fault condition.

D. Features protection 3-phase motors from:

1. Voltage single-phase/phase loss
2. Phase reversal
3. Low voltage
4. High voltage
5. Voltage unbalance
6. Rapid cycling
7. Undercurrent
8. Overcurrent
9. Current unbalance
10. Curent single-phase/phase loss
11. Low control voltage
12. Ground fault
13. Contact failure

14. Low power

15. High power

E. Communication Capabilities:

1. Modbus RTU

2. Modbus TCP

3. DeviceNet

4. Profibus

F. The Equipment interface shall have the capability of connecting to the following systems:

1. HMI (Human-Machine Interface)

2. SCADA (supervisory Control and Data Acquisition)

3. DCS (Distributed Control System)

4. PLC (Programmable Logic Controllers)

5. SymCom Model RM-1000 Modbus remote display

6. SymCom Model Rm-2000 Modbus remote display

G. Manufacturer: SymCom

H. Model: 777-LR-P2 Surface or DIN rail mount

4.02 CURRENT TRANSFORMER (CT)

A. Motor 9 amp and above, phase current CT's shall be provided for all three phase legs. CT rating shall be determined based on the size of manufacturer's motor FLA.

4.03 INSTALLATION

A. MPR

1. Install MPR as shown on plans or as described in specifications.

2. Installation shall be done according to manufacturer's recommendations.

3. Locate as indicated and install in accordance with manufacturer's written installation instructions.

4. Provide devices and connections to MPR as shown on plans.

B. Current Transformer: CT's shall be rated for current parameters and shall be installed according to the manufacturer's recommendations with hardware intended for mounting CT's.

END OF SECTION

Section 16670

LIGHTNING PROTECTION SYSTEM

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Lightning protection system, including design, installation and materials.

1.02 REFERENCES

A. American National Standards Institute/National Fire Protection Association (ANSI/NFPA)

1. NFPA No: 780 - Lightning Protection Code
2. NFPA No: 70 - National Electrical Code
   a. Section 250-46 - Spacing from Lightning Rods
   b. Section 250-86 - Use of Lightning Rods

B. American National Standards Institute/Underwriters Laboratories (ANSI/UL)

1. UL 96 - Lightning Protection Components
2. UL 96A - Safety Installation Requirements for Lightning Protection System
3. Lightning Protection Institute (LPI) - LPI 175 - Installation Standards

1.03 SUBMITTALS

A. The following Section 01330 - Submittal Procedures.

1. Outline dimensions and weights
2. Installation and maintenance manual
3. Catalog data
4. Complete design and construction drawings
5. Underwriters Laboratories, Inc. Master Label Certification

6. Lightning protection institute certified system certification.

1.04 QUALITY ASSURANCE

A. See Part 3.02 – INSTALLATION

1.05 PREPARATION FOR SHIPPING

A. Pack and crate materials to permit ease of handling and provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Advanced Lightning Technology

B. East Coast Lightning Equipment

C. Harger Lightning Protection

D. Thompson Lightning Protection

2.02 DESIGN, CONSTRUCTION AND MATERIALS

A. System Design: Provide a functional and unobtrusive lightning protection system. Departures from the Drawings or submittals shall be submitted to the City Engineer for approval.

B. Lightning Protection Equipment: Materials shall be copper and bronze and of the size, weight, and construction to suit the application and used in accordance with PLI, UL, and NFPA code requirements. Use bolt type connectors and splicers Class I and Class II structures. Pressure squeeze clamps are not acceptable. Use stainless steel mounting hardware to prevent corrosion.

C. Aluminum Components: Aluminum materials may not be used except on roofs that utilize aluminum roofing components. On aluminum roofs or where aluminum parapet caps are used, utilize aluminum components for roof lightning protection equipment to ensure compatibility. However, use copper down leads and grounding with the bimetal transition occurring at the through roof assembly with an approved bimetal through roof assembly.

D. Use equipment which is UL listed and properly UL labeled. Equipment shall be new, and of a design and construction to suit the application in accordance with accepted industry standards and LPI, UL, NFPA, and NEC code requirements.

PART 3 EXECUTION

3.01 PREPARATION

A. The Contractor is responsible for the following coordination with the building contractors:

1. The lightning protection installer shall install a correct, neat and unobtrusive installation in cooperation with other trades.

2. The roofing contractor shall seal and flash protection roof lightning penetrations conforming to the roof manufacturer's recommendations. However, the lightning protection contractor shall designate locations of through roofs and submit details of through roof penetrations, as required.

3. Should the roofing manufacturer require any special walk pads, membrane patches or pavers under the components of the lightning protection system, the lightning protection installer shall install such items with the roofing materials (patches, pads, pavers, adhesive) supplied by the roofing manufacturer at no additional cost to the lightning protection installer.

4. The roofing contractor shall instruct the lightning protection installer of the proper installation procedures of the roof pads, patches, and pavers, if required.

3.02 INSTALLATION

A. Have the system installed by an experienced installation company that is UL listed, a member of the Lightning Protection Institute and an employer of Certified Master Installers of lightning protection systems.

B. A Certified Master Installer shall directly supervise the work. Provide and stall a complete conductor network at the roof and include air terminals, connectors, splicers, bonds, copper down leads, and proper ground terminals.

C. Use copper down lead conductors even when aluminum is required on the roof. Do not bring down lead conductors in conduit directly through the roof. Use through roof assemblies with solid brass or stainless steel rods for this purpose. Structural steel may be utilized in the installation as outlined by UL, NFPA, and LPI.

D. Upon completion of the installation, the lightning protection installer shall secure and deliver to the Contractor for submittal to the City

Engineer, the Underwriters Laboratories, Inc., Master Label certification and the Lightning Protection Institute Certified System certification. The system will not be accepted without the UL Master Label plate and the LPI certification certificate.

END OF SECTION

Section 16910

MANUAL TRANSFER SWITCH

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Manual transfer switches for the manual transfer of power between normal source power from CenterPoint Energy and portable generators and vice versa.

1.02 REFERENCES

A. Underwriters Laboratories (UL)

1. UL 1008
2. UL 489
3. UL 991
4. NFPA 99 – Essential Electrical Systems of Health Care Facilities
5. NFPA 110 – Emergency and Standby Power Systems
6. NEMA ICS 10 – AC Transfer Switch Equipment
7. IEEE 446 – Recommended Practice for Emergency and Standby Power Systems
8. Compliant with FCC Part 15, Subpart B, Class A.

1.03 SUBMITTALS

A. Submittals shall be prepared and submitted based on the requirements of Section 01330 - Submittal Procedures.

1. Outline dimensions and weights
2. Installation and maintenance manual
3. Catalog data

1.04 QUALITY ASSURANCE

A. See Part 3.02 – INSTALLATION

1.05 PREPARATION FOR SHIPPING

A. Pack and crate materials to permit ease of handling and provide protection from damage during shipping, handling and storage.

PART 2 P R O D U C T S

2.01 ACCEPTABLE MANUFACTURERS

A. Eaton Corporation

B. Schneider Electric

C. Siemens

D. General Electric

2.02 DESIGN, CONSTRUCTION AND MATERIALS

A. Design: Furnish and install a 600 volt rated manual transfer switch (MTS) with the appropriate ampacity rating as indicated on the Device Rating Schedules on the drawings. This MTS shall be provided in a NEMA 4X enclosure constructed of 316 stainless steel. The enclosure shall be dead front in its construction. It shall be possible to padlock the switch in either the normal source or the emergency source position.

B. The MTS shall provide a minimum withstand of 3 cycles, closing and interrupting rating of 65 KAIC.

C. The manual transfer switches shall be fully rated for all types of loads, inductive and resistive, without over-sizing, either open or enclosed.

D. The transfer switch shall be 100% equipment rated for continuous duty

E. The MTS buss and cable terminals shall be copper.

F. The switching mechanism shall consist of molded case switches for the power contact assemblies.

G. On-Automatic Transfer Switch (NATS) shall be electrically operated by integrally mounted pushbuttons. The transfer switch shall consist of completely enclosed contact assemblies. Control power for electrical operation shall be derived from a control power transformer connected to the line side of the source to which the load is being transferred. Transfer switch shall have pilot lights that indicate the following:

1. NORMAL Source connected {12C}
2. EMERGENCY Source connected {12D}
3. NORMAL Source available {12G}
4. EMERGENCY Source available {12H}

H. Main contacts shall be designed to withstand multiple fault currents and shall meet UL 489 and/or UL 1087 requirements.

I. The transfer switch shall be mechanically interlocked to prevent cross connection of sources when operated.

J. Transfer switches shall be capable of being operated manually under full rated load conditions. Removable manual operating handles are not acceptable. Manual operators requiring source or load disconnection prior to manual operation are not acceptable.

K. On transfer switches requiring a fourth pole for switching the neutral, the neutral shall be fully rated with equal withstand, closing and interrupting ratings to the power poles. Switched neutral poles which are add-on or overlap, or that are not capable of breaking full rated load current are not acceptable.

L. The MTS shall provide positive mechanical interlocking to assure an open transition functionality in accordance with the requirements of CenterPoint Energy.

M. The MTS shall have a permanently affixed manual operating handle.

N. ALL MTS units shall be UL listed and properly UL labeled. Equipment shall be new, and of a design and construction to suit the application in accordance with accepted industry standards and LPI, UL, NFPA, and NEC code requirements.

PART 3 EXECUTION

3.01 INSTALLATION

A. Have the MTS unit installed by a licensed electrician.

B. The MTS shall be mounted outdoors on a welded structural steel rack as indicated on the Drawings. This rack shall be hot dip galvanized after fabrication.